

TOWN of BROOKLINE

Massachusetts

BUILDING DEPARTMENT

Daniel Bennett Building Commissioner

TO: Selectboard/ School Committee

FROM: Ray Masak, PE Project Manager

SUBJECT: High School Expansion Project – Construction Management @ Risk (CM@R) Skanska Change Order –Guaranteed Maximum Price (GMP) Amendment/PCCO No.7

DATE: July 17, 2020

On the Calendar this week, the Building Department has submitted a request for Change Order/ Amendment Approval for the construction management firm Skanska to perform the following services in the amount of \$ 22,213,702:

- GMP Amendment- \$21,149,068; Final Procurement of Project
- PCCO No. 7-\$1,064,634; Schedule Update/ Extension – STEM Wing Unforeseen conditions; COVID Delay

The HS expansion project was awarded to the contractor Skanska which was based on their qualifications. Bid packages were prepared by the architect, William Rawn Associates and based on these documents, Skanska submitted pricing packages (18) which the Town approved. This package represents the final procurement of the project including a schedule extension. Refer to the Hill memo dated July 13, 2020 for further explanation of these services.

The Building Department will be available to answer any questions you may have. Thank you for your consideration.

HILL Hill International

Hill International, Inc. 75 Second Avenue, Suite 300 Needham, MA 02494 Tel: 617-778-0900 Fax: 617-778-0999 www.hillintl.com

July 13, 2020

Mr. Ray Masak, P.E. Project Manager Town of Brookline Building Department 333 Washington Street Brookline, MA 02445

RE: Recommendation to approve Skanska GMP Amendment

Dear Mr. Masak:

Under separate cover, Skanska USA Building Inc. is submitting original copies of FINAL GMP Amendment dated July 9, 2020 for the Expansion of Brookline High School Project for acceptance by the Town of Brookline. As of the end of February 2020, WRA, Hill, and the ToB received from Skanska various remaining Requests to Award (RTA) Subcontractor bid packages for review and comment or review and acceptance. Hill and WRA had reviewed each RTA package and provided coordinated comments as needed and were transmitted to Skanska for response. Specific attention and feedback was given regarding monies being ear-marked as HOLDs and ALLOWANCES in these RTA packages in order to better manage the overall project cost. Furthermore, RTA review meetings were held in March 2020 between WRA, Hill, and Skanska to discuss RTA's in much more detail. Skanska provided responses thereafter as well as bridge documentation as requested. Some of the RTAs were partially released in Pre-GMP Amendment #17r1. The balance of RTAs are now reflected in this FINAL GMP, including a few allowances for certain RTAs that were rejected and are being rebid or further negotiated down in pricing; to be reconciled in the near future post-GMP.

Following is a timeline recap of the process between the original GMP and the Final GMP:

- <u>March 13, 2020</u> Skanska submitted a GMP document for STEM, 22 Tappan (aka Cypress), MBTA Improvements, and Elevator Modernization projects. Hill considered it to be a draft because it was the first submission of a complete document for review. This GMP value was \$145,666,105 and represented Substantial Completion dates of April 27, 2021 for STEM, October 8, 2021 for Cypress and October 28, 2021 for MBTA Station Platform. However, this GMP did <u>not</u> include any costs or schedule impacts associated with COVID-19 because it was submitted just before the severity of the Pandemic became evident and the "Stay-at-Home" Government Orders began.
- <u>April 10, 2020</u> After extensive review by Hill and WRA, including some ToB's input, we returned the GMP with 200+ comments/questions for Skanska to address. Skanska included approximately (78) Assumptions and Qualifications (A&Qs) in the GMP, some of which we commented that they were not acceptable as they attempted to further modify and change terms already agreed to in the Owner-CM agreement. We provided extensive comments on the General Conditions (GCs) and General Requirements (GRs) in the GMP which were significantly higher than their previous 60% estimate.

<u>Between April thru June 2020</u> - Skanska responded incrementally (by GMP Exhibit Section comments) and Hill/WRA continued to review and correspond to each iteration during this period. The GMP sections that took the longest to reach agreement on are as follows:

- <u>GC/GRs</u> Skanska finally agreed on May 28, 2020 to a \$1.5M reduction in this section of the GMP.
- <u>A&Qs</u> in the Final GMP, Skanska agreed to completely delete 18 of the 78 original A&Qs, and reworded several others in order to be reasonable and acceptable.
- O <u>COVID-19 Impacts qualification</u> Simultaneous to this GMP negotiation, Skanska had reached an agreement with neighboring Town of Belmont for specific COVID-19 related qualifications/allowance on their project. Skanska provided the same language for ToB review and consideration on this project/GMP. Hill reviewed the language with ToB on June 19th and appeared to be reasonable and acceptable approach to accounting separately for those costs. Skanska's projection of \$616K was received on June 26th, which included additional costs for safety compliance protocols mandated by Government plus extended GCs for 22 Tappan St only for the schedule impact due to the MBTA's suspension of operational support for diversions needed for the overbuild. Upon further review with ToB, Hill made a recommendation to defer COVID-19 related impact specifically relating to GCs until Fall 2020, ahead of November Town Meeting. A \$150K allowance for known ongoing extra safety costs related to the Pandemic is included in the FINAL GMP.
- <u>Specification Division 1</u> Skanska objected to certain terms in Division 1 as they said certain sections were not project-specific, included conflicting requirements (some didn't align with the Owner-CM Agreement), etc. Therefore, Hill, WRA and Skanska went thru Skanska's Division 1 comments over multiple meetings in order to agree to a modified Division 1 which Skanska attached as Exhibit K in the FINAL GMP.
- <u>FINAL GMP Schedule</u> the March 13th GMP submission had reflected Substantial Completion dates <u>prior to</u> COVID-19 impacts to 22 Tappan St and MBTA Station Platform. STEM experienced concurrent delays primarily from continued demolition and structural unforeseen conditions related to the Robert's Wing final demo and underpinning requirements adjacent to the Cafeteria. The schedule impacts therefore pushed several exterior façade activities into the 2020-2021 winter season which were originally expected to occur during warmer months. After several iterations, included within this FINAL GMP Amendment Skanska has included PCCO #7 for mostly projected costs with additional GRs related to winter tarping and heat (use of propane tanks) on both projects, as well as some partial GCs related to STEM only:

	Skan	ska's Substantial Comp	oletion Dates
6	3/13/20 GMP	7/9/20 FINAL GMP	Cause
STEM	4/27/2021	7/7/2021	10-weeks; Unforeseen
22 Tappan St.	10/8/2021	11/15/2021	5-weeks; COVID-19
MBTA Station	10/28/2021	12/10/2021	6-weeks; COVID-19

 July 9, 2020 – Skanska's revised FINAL GMP was received after nearly 4 months of negotiations during a prolonged, unpredictable and complicated situation related to COVID-19 and only after gaining some schedule impact clarity (specifically related to MBTA operational support that resumed in June 2020). The following table provides a financial recap comparison between the March GMP and the Final GMP:

	3	3/13/20 GMP	7/	9/20 FINAL GMP	Variance	Notes
Direct Cost	\$	117,495,136	\$	117,328,428	\$ (166,708)	
GR	\$	7,485,663	\$	6,803,638	\$ (682,025)	
2.5% CM contingency	\$	2,843,025	\$	2,821,807	\$ (21,218)	
GC	\$	9,916,882	\$	9,154,000	\$ (762,882)	
other mark-ups	\$	7,925,399	\$	7,888,010	\$ (37,389)	
BASE GMP TOTAL	\$	145,666,105	\$	143,995,883	\$ (1,670,222)	
Precon	\$	476,928	\$	476,928		
MBTA Precon	\$	70,512	\$	70,512		
Owner Pandemic Allowance	\$	-	\$	150,000	1	
TOTAL	\$	146,213,545	\$	144,693,323	\$ (1,520,222)	
CHANGE ORDERS						
PCCOs 1-6 (ARs)	\$	527,009	\$	527,009		(see Pre-GMPs 12b, 13b, 14b, 15b, 17b & 18b)
PCCO 7 schedule adjustment	\$	_	\$	1,064,634		
TOTAL	\$	146,740,554	\$	146,284,966	\$ (455,588)	*FINAL GMP Amendment
GMP CO 1/PCCO 8 (ARs)	\$	710,394	\$	710,394		
TOTAL	\$	147,450,948	\$	146,995,360	\$ (455,588)	

Based on the above, we recommend approval of this GMP Amendment.

Very truly yours,

Quely tely

Andy Felix, MCPPO Project Director

TOWN OF BROOKLINE

333 Washington Street, Brookline, Massachusetts 02445

PURCHASE ORDER CHANGE FORM

	то:		SA Building Inc t Boulevard, Suite 2	200		Purchase Order Number 21911639
		Boston MA				Vendor Number 55399
					and the second se	PAYMENT AMOUNT
100.001.1		FUND	ORGANIZATION	ACTIVITY	OBJECT	
GET 120,391,4		10110	2594C204		6C0002	\$22,213,702.00

FOR: Brookline High School Expansion

Amendment	Date		AMOUNT
	7/10/2020	GMPAmendment/PCCO No. 007 - Schedule Update	\$22,213,702.00
L			

aber

AIA[°] Document G701[™] - 2017

Change Order

PROJECT: (Name and address) Expansion of Brookline High School, (Project A and Project B)	CONTRACT INFORMATION: Contract For: Construction	CHANGE ORDER INFORMATION: Change Order Number: GMP Amendment
Brookline, MA 02445	Date: July 24, 2018	Date: July 10, 2020
OWNER: (<i>Name and address</i>) Town of Brookline, Massachusetts, by and through the Board of Selectmen of Brookline	ARCHITECT: (Name and address) William Rawn Associates Architects Inc.	CONTRACTOR: (Name and address) Skanska USA Building Inc.
333 Washington Street, Brookline, MA 02445	10 Post Office Square, Suite 1010, Boston, Massachusetts 02109	101 Seaport Boulevard, Suite 200, Boston, MA 02210

THE CONTRACT IS CHANGED AS FOLLOWS:

(Insert a detailed description of the change and, if applicable, attach or reference specific exhibits. Also include agreedupon adjustments attributable to executed Construction Change Directives.)

GMP Amendment: \$21,149,068

PCCO No. 007 - Schedule Update: \$1,064,634

This Change Order includes adjusted Contract Time and General Conditions / General Requirements costs only as outlined below:

STEM Wing Addition ("Stem")

Revised interim completion date as described in enclosed Exhibit D ("Stem Interim Completion Date").

General Conditions and General Requirements costs for the 10 week extension from April _____ through July 7, 2021 in the amount of \$1,016,524.00.

Excludes any Subcontractor costs or claims associated with the Stem Interim Completion Date, as those will be handled separately and on a case by case basis.

Excludes any costs (General Conditions, General Requirements, Subcontractor or other costs) associated with COVID-19 or other pandemics.

111 Cypress St

Revised Substantial Completion Date as described in enclosed Exhibit D.

Excludes Subcontractor costs or claims associated with the revised Substantial Completion Date, as those will be handled separately and on a case by case basis.

Excludes any costs (General Conditions, General Requirements, Subcontractor or other costs) in connection with the Revised Substantial Completion Date or with COVID-19 or other pandemics. The GMP includes an Owner's Pandemic Allowance for those costs.

MBTA

Revised interim completion date as described in enclosed Exhibit D ("MBTA Interim Completion Date"). Excludes Subcontractor costs or claims associated with the MBTA Interim Completion Date, as those will be handled separately and on a case by case basis.

Excludes any costs (General Conditions, General Requirements, Subcontractor or other costs) associated with COVID-19 or other pandemics. The GMP includes an Owner's Pandemic Allowance for those costs.

Neither the adjustments to the Contract Price nor the Contract Time upon which this AR, CO, PCCO is based contemplates any project delays, suspensions, disruptions, cost escalations or other impacts caused, directly or indirectly, by the Pandemic (as defined in the GMP), as such cost adjustment to the Contract Sum and GMP shall be reconciled in accordance with the Owner Pandemic Allowance. Skanska further reserves all rights to request adjustment of the Contract Time as a result of the Pandemic Standards and in connection with this AR, CO, PCCO. Skanska will make every reasonable effort to provide the required documentation and notice in accordance with this Contract, however, Skanska may not be able to meet the contractual deadlines due to circumstances outside of Skanska's control.

The original Contract Sum was	\$ 476,928.00
The net change by previously authorized Change Orders	\$ 123,594,336.00
The Contract Sum prior to this Change Order was	\$ 124,071,264.00
The Contract Sum will be increased by this Change Order in the amount of	\$ 22,213,702.00
The new Contract Sum including this Change Order will be	\$ 146,284,966.00
The Constant Time will be used if ad here () down	

The Contract Time will be modified by: The new date of Substantial Completion will be

_____ () days November 15, 2021, Refer to Enclosed Exhibit D

NOTE: This Change Order does not include adjustments to the Contract Sum or Guaranteed Maximum Price, or the Contract Time, that have been authorized by Construction Change Directive until the cost and time have been agreed upon by both the Owner and Contractor, in which case a Change Order is executed to supersede the Construction Change Directive.

NOT VALID UNTIL SIGNED BY THE ARCHITECT, CONTRACTOR AND OWNER.

William Rawn Associates Architects Inc. ARCHITECT (Firm name)

SIGNATURE

Andrew Jonic AIA, Senior Associate

PRINTED NAME AND TITLE July 13, 2020

July 13,

DATE

Skanska USA Building Inc.

CONTRACTOR (Finm name) SIGNATURE

Daniel P. Lanneville, Sr. VP PRINTED NAME AND TITLE July 14, 2020

DATE

Town of Brookline

OWNER (Firm name)

SIGNATURE

PRINTED NAME AND TITLE

DATE

APPROVAL OF OWNER: TOWN OF BROOKLINE

Building Commission	Selectboard
Janet Fierman, Chairman	Bernard W. Greene, Chair
George Cole, Member	Benjamin J. Franco, Member
Kenneth Kaplan, Member	Nancy S. Heller, Member
Karen Breslawski, Member	Heather Hamilton, Member
Nathan E. Peck, Member	Raul Fernandez, Member
School Committee	
Helen Charlupski, Member	Julie Schreiner-Oldham, Chair
Suzanne Federspiel, Member	Susan Wolf Ditkoff, Member
Jennifer Monopoli, Member	Michael Glover, Member
Barbara Scotto, Member	David Pearlman, Member
	Sharon Abramowitz, Member
Confirmation of Availability of Funds:	

Town Comptroller

Town of Brookline Brookline High

Brookline High School Expansion Project | Project A and B



Guaranteed Maximum Price Submission

Submitted Date: March 13, 2020

Revision Number: 001

Date: July 10, 2020



 Skanska USA Building

 101 Seaport Blvd., Suite 200

 Boston, MA 02210

 Phone
 617-574-1400

 Fax
 617-574-1399

 Web
 www.usa.skanska.com

 Date
 Reference

 JULY 10, 2020
 Skanska Project No. 1318014 – Exapnsion & Renovation of Brookline High

 School (Project A and Projejct B) – Guaranteed Maximum Price Submission –

 Revision 001

Mr. Raymond Masak, Project Manager **TOWN OF BROOKLINE BUILDING DEPARTMENT** 333 Washington Street, 3rd Floor Brookline, MA 02445

Dear Mr. Masak:

Skanska USA Building Inc. presents to you the attached Guaranteed Maximum Price Submission, Revision 001, for the construction of the Brookline High School Expansion Projects A and B as outlined in the enclosed documents and Exhibits. We recognize the challenge associated with the projected cost vs budget and current economic conditions, and we are pleased to offer this revision inclusive of significant reductions in the Construction Contingency, General Requirements and General Conditions.

Since our initial Guaranteed Maximum Price Submission on March 13, 2020 there have been both unforeseen and external impacts to the project schedule. Skanska has issued updates to the project schedule on a monthly basis since our initial submission forecasting revised completion dates. Following discussions and at the request of Hill International, we are resubmitting the GMP based on the construction schedules originally included in our March 13, 2020 submission. This will require that a Prime Contract Change Order for an adjustment to the Contract Schedule and Contract Price is approved concurrent with the GMP Amendment that is submitted by Skanska following approval of this Guaranteed Maximum Price by the Town.

Please do not hesitate to contact me with any questions.

Sincerely,

SKANSKA USA BUILDING INC.

IM CRAFT

Jim Craft Project Executive

CC: Dan Lanneville, Peter Roche, Rob Mulligan, (Skanska USB) Andy Felix (Hill International)

Town of Brookline Brookline High School Expansion Project | Project A and B TABLE OF CONTENTS / EXHIBITS TO THIS AMENDMENT:

Pursuant to Article 6.1.2 of the Owner – Construction Manager Agreement dated July 24, 2018 and Article VII of the General Conditions of the Contract between the Town of Brookline, Massachusetts, by and through the Board of Selectmen of Brookline (Owner) and Skanska USA Building Inc. (Construction Manager), for construction of the Expansion of Brookline High School, (Project A and Project B) (the Project), the Owner and Construction Manager herby establish the Guaranteed Maximum Price.

- 1. Cover Letter
- 2. Signature Pages
- 3. Exhibit A: Document List
- 4. Exhibit B: List of Allowances & Scope Holds
- 5. Exhibit C: Assumptions, Qualifications & Clarifications
- 6. Exhibit D: Contract Time
- 7. Exhibit E: Schedule of Values
- 8. Exhibit F: Schedule of Alternate Prices
- 9. Exhibit G: Schedule of Unit Prices
- 10.Exhibit H: Time Limit for Acceptance
- 11.Exhibit I: Owner Change Log Summary Out of Scope Only
- 12.Exhibit J: Approved Prime Contract Change Orders
- 13.Exhibit K: Division 01 Specification Modifications
- 14.Exhibit GC: Construction General Conditions
- 15.Exhibit GR: Construction Requirements

Town of Brookline Brookline High School Expansion Project | Project A and B SIGNATURE PAGES:

This agreement is made as of the <u>14th</u> day of <u>July</u> by and between the Town of Brookline and Skanska USA Building Inc.

SKANS	KA USA BUILDING INC.
By:	Doft
	0
Date:	July 14, 2020

Dan Lanneville, Senior Vice President / Account Manager

Town of Brookline Brookline High School Expansion Project | Project A and B SIGNATURE PAGES:

APPROVAL OF OWNER: TOWN OF BROOKLINE

Building Commission	Selectboard
Janet Fierman, Chairman	Bernard W. Greene, Chair
George Cole, Member	Benjamin J. Franco, Member
Kenneth Kaplan, Member	Nancy S. Heller, Member
Karen Breslawski, Member	Heather Hamilton, Member
Nathan E. Peck, Member School Committee	Raul Fernandez, Member
Helen Charlupski, Member	Julie Schreiner-Oldham, Chair
Suzanne Federspiel, Member	Susan Wolf Ditkoff, Member
Jennifer Monopoli, Member	Michael Glover, Member
Barbara Scotto, Member	David Pearlman, Member
	Sharon Abramowitz, Member

Confirmation of Availability of Funds:

Town Comptroller

Town of Brookline Brookline High School Expansion Project | Project A and B

EXHIBIT A: DOCUMENT LIST

Refer to Pre-GMP Amendments 1 to 18 for a comprehensive list of Drawings, Specifications and other Contract Documents that have previously been incorporated into the Owner – Construction Manager Agreement.

The enclosed Field Bulletin and Request For Information (RFI) Matrix identifies which bid package each Field Bulletin and RFI was incorporated into. All Field Bulletins and RFI's not listed on this matrix are not included in the GMP.

Town of Brookline Brookline High School Expansion Project | Project A and B

EXHIBIT A: DOCUMENT LIST

PROJECT A: 111 CYPRESS STREET BULLETIN AND RFI MATRIX

Brookline High School Expansion - Project A Cypress Field Bulletin and RFI Matrix

BID PACK NO.	SUB OR TRADE	DESCRIPTION	Early Package 01 01/04/19	Early Package 01 Addenda 1 01/15/19	Early Package 01 Addenda 2 01/22/19	Early Package 02 03/01/19	Early Package 02 Ad denda 1 03/15/19	Early Package 03 03/29/19	Early Package 04 05/01/19	Early Package 04 Ad denda 1 05/22/19	Early Package 04 Ad denda 2 05/28/19	Early Package 05 07/01/19	Early Package 05 Ad denda 1 07/03/19	Early Package 05 Ad denda 2 07/12/19	Early Package 05 Ad denda 3 07/17/19	Field Bulletin 006 07/26/19	Field Bulletin 007 07/31/19	Field Bulletin 008 08/12/19	Field Bulletin 009 100% CD Documents 08/30/19	Field Bullet in 009.1 Trade Bid Addenda 01 09/16/19	Field Bulletin 009.2 Trade Bid Addenda 02 09/27/19, Reissued 10/10/19	Field Bullet in 009.3 Trade Bid Addenda 03 10/10/19	Field Bullet in 009.4 Trade Bid Addenda 04 10/18/19	Field Bullet in 009.5 Trade Bid Addenda 05 10/18/19	Field Bullet in 009.6 Trade Bid Addenda 06 10/18/19	Field Bulletin 011 10/18/19	Field Bulletin 018 10/28/19	Field Bulletin 024 12/10/19	Field Bulletin 025 12/09/19	Field Bulletin 026 12/03/19	Field Bulletin 027 12/10/19	Field Bulletin 029 12/24/19	Field Bulletin 038 01/13/20
BP-01A	SUB	Precast Design Assist	х	x	х																												
BP-02A	SUB	Façade Design Assist	х	X	х																												
BP-03A	SUB	Demolition / Abatement				х	х																										
BP-04A	SUB	Façade Furnish, Deliver and Install							х	х	х																						
BP-05A	SUB	Support of Excavation				x	х	x																									·
BP-06A	SUB	Monitoring				X	х																										·
BP-07A	SUB	Elevators (New)							х	х	х																						<u> </u>
BP-08A	SUB	Structural Steel & Precast Erection				x	х	x	x	x	x					х	х	х															<u> </u>
BP-09A	SUB	Sitework and Deep Foundations							x	x	X																						
BP-10A	SUB	Concrete - Foundations & Flatwork							x	x	x					х	x	x															
BP-11A BP-12A	TRADE	Not Used Not Used																															
BP-12A BP-13A		UG Waterproofing										x	x	x	x																		
BP-13A BP-14A	SUB	Concrete - Site											~		^				x	x	x	x	x									x	x
BP-14A BP-15A	TRADE	Misc. and Ornamental Metals																	x	x	x	x	x	x	x								
BP-15A BP-16A		Electrical / FA / Tele-Com																	x	x	x	x	x	x	x								
BP-17A	TRADE	HVAC																	x	x	x	X	x	x	x								(
BP-18A		Plumbing																	X	X	x	X	x	x	x								
BP-19A	TRADE	Fire Protection																	x	x	x	x	x	X	x								
BP-20A	TRADE	Masonry																	х	х	x	х	х	х	x								
BP-21A	SUB	Architectural Millwork / Casework																	х	х	x	х	х									· · · · · ·	
BP-22A	SUB	Laboratory Casework / Fume Hoods																	х	х	x	х	х							х			
BP-23A	TRADE	Waterproofing / Joint Sealants																	х	х	х	х	х	х	х								
BP-24A	SUB	Fireproofing / Intumescent																	X	Х	х	X	х										
BP-25A	TRADE	Roofing / Flashing																	X	х	х	X	x	х	x								
BP-26A	SUB	Doors, Frames and Hardware																	X	х	x	х	x			х	х						
BP-27A	SUB	Overhead Doors and Fire Shutters																	х	х	x	х	х										
BP-28A	SUB	Theater Draperies																	X	х	х	X	x										·
BP-29A		Interior Glass and Glazing																	X	x	x	х	x	x	x								·
BP-30A		Drywall																	X	X	X	X	x			x	x						
BP-31A	TRADE	Tile																	х	х	х	х	x	х	x								<u> </u>
BP-32A BP-33A	TRADE	Terrazzo Acoustic Ceilings					-												X	x	x	x	x	x	x								
BP-33A BP-34A		Carpet					-												x	x	x	x	x		^								
BP-34A BP-35A	SUB	Not Used										_						_			^												
BP-36A		Resilient Floor and Base																	х	х	x	х	x	х	x								
BP-30A BP-37A	SUB	Resinous Flooring																	x	x	x	x	x	^	Ŷ							+	
BP-38A		Painting (Paint and Sealed Floors)																	x	x	x	x	x	x	x								
BP-39A	SUB	Signage																	X	X	x	X	x					х					
BP-40A		Building Specialties																	x	x	x	x	x										
BP-41A	SUB	Window Treatments																	X	x	x	X	x								х		
BP-42A		Kitchen / Food Service Equipment																	х	х	x	X	х									· · · · · ·	
BP-43A	SUB	Stage / Theater Equipment and Seating																	х	х	x	X	х										
BP-44A BP-45A	SUB	Not Used																															
BP-46A	SUB	Hardscape / Landscape																	х	х	х	х	х						х				x
BP-47A	SUB	Final Cleaning																	x	x	x	x	x										
BP-48A	SUB	Audio/Visual Systems		1	1		1												x	x	x	x	x										
BP-49A	SUB	Operable Partitions		1	1	1	1	1		1			1						x	x	x	x	x	1	1		1						

Town of Brookline Brookline High School Expansion Project | Project A and B

EXHIBIT A: DOCUMENT LIST

PROJECT C: ENABLING BULLETIN AND RFI MATRIX



Brookline High School Expansion - Project C STEM Enabling

Field Bulletin and RFI Matrix

BID PACK NO.	SUB OR TRADE	DESCRIPTION	Early Package 02 03/01/19	Early Package 02 Addenda 1 03/13/19	Early Package 02 Addenda 2 03/15/19	Early Package 02 Addenda 3 3/22/19	Early Package 02 Addenda 4 03/28/19	RFI Nos. 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 24, 26, 27, 29, 30 & 31
BP-04B	SUB	Temp. Scaffolding & OH Protection - Enabling	х	х	х	х	х	х
BP-05B	SUB	Concrete - Enabling	х	х	х	х	х	х
BP-06B	TRADE	Masonry - Enabling	х	х	Х	х	х	х
BP-07B	TRADE	Misc. Metals - Enabling	х	х	х	х	х	х
BP-08B	TRADE	Waterproofing - Enabling	х	х	Х	х	х	х
BP-09B	TRADE	Roofing - Enabling	х	х	Х	х	х	х
BP-10B	SUB	Doors / Frames / Hardware - Enabling	х	Х	Х	Х	Х	х
BP-11B	SUB	Gypsum Wall Board / Carpentry / ACT - Enabling	х	х	х	х	х	х
BP-12B	SUB	Flooring - Enabling	х	х	х	х	х	х
BP-13B	TRADE	Paint - Enabling	х	х	х	х	х	х
BP-14B	TRADE	Fire Protection - Enabling	х	х	х	х	х	х
BP-15B	TRADE	Plumbing - Enabling	х	х	х	х	х	х
BP-16B	TRADE	HVAC - Enabling	х	х	х	х	х	х
BP-17B	TRADE	Electrical - Enabling	х	х	х	х	х	х
BP-18B	SUB	Sitework - Enabling	х	х	х	х	х	 х

Town of Brookline Brookline High School Expansion Project | Project A and B

EXHIBIT A: DOCUMENT LIST

PROJECT C: STEM ADDITION BULLETIN AND RFI MATRIX

Brookline High School Expansion - Project C STEM Wing

Field Bulletin and RFI Matrix

BID PACK NO.	SUB OR TRADE	DESCRIPTION	Early Package 01 01/04/19	Early Package 01 Addendum 01/15/19	Early Package 01 Addendum 02 01/22/19	Early Package 02 03/01/19	Early Package 02 Addendum 01 03/13/19	Early Package 02 Addendum 02 03/15/19	Early Package 02 Addendum 03 03/22/19	Early Package 02 Addendum 04 03/28/19	Early Package 02 Addendum 05 04/18/19	Early Package 03 05/01/19	Early Package 03 Addendum 01 05/17/19	Early Package 03 Addendum 02 05/24/19	Bulletin 001 06/06/19	Bulletin 004 07/19/19	Bulletin 005 00% CD Documents 08/01/19	Bulletin 005.1 ade Bid Addenda 01 08/01/19	Bulletin 005.2 ade Bid Addenda 02 08/01/19	Bulletin 005.3 11/06/19	Bulletin 005.4 12/30/19	Bulletin 005.5 01/15/19	Bulletin 008 08/09/19	Bulletin 008.1 08/14/19	Bulletin 022 10/11/19	Bulletin 026 10/25/19	Bulletin 027 11/18/19	Bulletin 029 11/18/19	Bulletin 037 12/20/19	Bulletin 055 02/10/20	Bulletin 071 03/17/20	RFI 142 11/26/19
																	10	Tra	Tra													· · · ·
BP-01B		Precast Design Assist	х	х	х																											
BP-02B		Façade Design Assist	x	x	x																											'
BP-03B		Demolition / Abatement				x	x	x	x	x	x																					'
BP-19B	SUB	Elevators - NEW										x	х	x																		'
BP-20B	SUB	Façade Furnish, Deliver and Install										x			x																	'
BP-22B	SUB	Elevators - Modernization										х	х	x																		'
BP-23B	SUB	Structural Steel & Precast Erection										x	x	x																		'
BP-24B	SUB	Sitework and Deep Foundations										x	x	x																		'
BP-25B	SUB	Concrete - Foundations & Flatwork										x	x	x																		
BP-28B	TRADE	UG Waterproofing										x	x	x																		
BP-29B BP-30B	SUB TRADE	Concrete - Site Misc. and Ornamental Metals															x	x	x												+	
BP-30B BP-31B		Electrical / FA / Tele-Com															x	x	x													
BP-31B BP-32B		HVAC															x	x	x													
BP-32B BP-33B	TRADE	Plumbing															x	x	x													
BP-33B BP-34B	TRADE	Fire Protection															x	x	x													
BP-34B BP-35B	TRADE	Masonry															x	x	x													
BP-35B BP-36B	SUB	Architectural Millwork / Casework															x	x	x				x	x								
BP-37B		Laboratory Casework / Fume Hoods / Equipment															x	x	x				^	^					x			
BP-38B		Waterproofing / Joint Sealants															x	x	x										^			'
BP-39B	SUB	Fireproofing / Intumescent															x	x	x													
BP-40B		Roofing / Flashing															x	x	x													
BP-41B	SUB	Doors, Frames and Hardware															x	x	x													
BP-42B	SUB	Overhead Doors and Fire Shutters															x	x	x													
BP-43B	TRADE	Interior Glass and Glazing															x	x	x													
BP-44B		Drywall															x	x	x						x	x	x	х				x
BP-45B	TRADE	Tile		1	1												x	х	x			1	1									
BP-46B	TRADE	Terrazzo															х	х	х													
BP-47B	TRADE	Acoustic Ceilings															х	х	x													
BP-48B	SUB	Carpet															x	х	х													
BP-50B	TRADE	Resilient Floor and Base															x	х	х													
BP-51B	SUB	Resinous Flooring															х	х	x													
BP-52B	TRADE	Painting (Paint and Sealed Floors)															х	х	х													
BP-53B	SUB	Signage															x	х	x		х											
BP-54B		Building Specialties															х	x	х													
BP-55B		Window Treatments															х	x	х									х				
BP-56B		Kitchen / Food Service Equipment															x	x	x	x	х											
BP-58B		Hardscape / Landscape															х	х	x											x	x	
BP-59B	SUB	Final Cleaning															х	х	x													
BP-60B	SUB	Audio/Visual Systems															x	x	x		x	x										

Town of Brookline Brookline High School Expansion Project | Project A and B

EXHIBIT A: DOCUMENT LIST

PROJECT F: ELEVATOR MODERNIZATION BULLETIN AND RFI MATRIX



Brookline High School Expansion - Project F Defered Maintenance

Field Bulletin and RFI Matrix

BID PACK NO.	SUB OR TRADE	DESCRIPTION	Early Package 03 05/01/19	Early Package 03 Addendum 01 05/17/19	Early Package 03 Addendum 02 05/24/19
BP-22B	SUB	Elevators - Modernization	х	х	x

Town of Brookline Brookline High School Expansion Project | Project A and B


EXHIBIT A: DOCUMENT LIST

MBTA OCS AND PLATFORM BULLETIN AND RFI MATRIX



Brookline High School Expansion - MBTA

Field Bulletin and RFI Matrix



No Project H, MBTA, Field Bulletins are included in the GMP. Refer to change management reports for all Project H Field Bulletins

Town of Brookline Brookline High School Expansion Project | Project A and B

EXHIBIT B: LIST OF ALLOWANCES AND EXPOSURE HOLDS

Refer to Pre-GMP Amendments 1 to 18 for a comprehensive list of Owner Allowances and Exposure Holds that have previously been incorporated into the Owner – Construction Manager Agreement. The total value of previously approved Owner Allowances and Exposure Holds are as follows:

1. Project A: 111 Cypress St:	\$ 2,031,375
2. Project C: Enabling:	\$ 210,863
3. Project C: STEM Addition:	\$ 1,601,354
4. Project F: Elevator Modernization:	\$ 65,000
5. MBTA: OCS, Enabling and Platform:	\$ 515,300

The below list of Owner Allowances and Exposure Holds have yet to be incorporated via Pre-GMP Amendment and therefore are included in the GMP submission:

1. Owner Pandemic Allowance	\$ 150,000
2. General Conditions:	\$ 0
3. General Requirements:	\$ 1,275,075
4. Project A: 111 Cypress St:	\$ 1,265,184
5. Project C: STEM Addition:	\$ 570,600
6. MBTA: OCS, Enabling and Platform:	\$ 0

Total of All Exposure Holds and Allowances:

1.	Owner Pandemic Allowance	\$ 150,000
2.	General Conditions:	\$ 0
3.	General Requirements:	\$ 1,275,075
4.	Project A: 111 Cypress St:	\$ 3,296,559
5.	Project C: Enabling:	\$ 210,863
6.	Project C: STEM Addition:	\$ 2,171,954
7.	Project F: Elevator Modernization:	\$ 65,000
8.	MBTA: OCS, Enabling and Platform:	\$ 515,300

9. Grand Total: \$7,684,751

Town of Brookline Brookline High School Expansion Project | Project A and B

EXHIBIT B: LIST OF ALLOWANCES AND EXPOSURE HOLDS

Owner All	owances:	
Sub-Project	Description:	Amount:
General		
	Owner Pandemic Allowance	\$150,000
	This Pandemic Allowance is added below the line in this GMP, all appropriate	
	mark ups for insurance and bonding are included within the allowance amount	
	except for fee as per the Pandemic Allowance language.	
General Conditi	lons	
General Conum	None	
General Require	ements	
	Temporary and Permanent Utility Costs, consumptions, backcharges and	
	connection fees	\$450,000
	Progress Photos	\$9,000
	Police Details (Cypress, STEM)	\$574,950
	Cypress; Fire Impairment	\$9,900
	Cypress: MBTA Line Protection	\$54,000
	STEM; Fire Impairment	\$27,225
	Street Sweeping Temporary Humidification / De-humidification Allowance	\$100,000 \$50,000
	Temporary Humunication / De-humunication Attowance	\$50,000
Project A: 111 (
Hoject A. III (Bid Package 14A: Site Concrete	
	All Site Concrete Scope, Furnished and Installed	\$523,984
		4000/001
	Bid Package 21A: Millwork	
	Modifications to Casework for MEP's	\$18,000
	Bid Package 22A: Lab Casework	
	Mobile Teacher Stations (qty. 8)	\$18,500
	Bid Package 46A: Landscape	
	Irrigation System Furnish and Install	\$50,000
	install Irrigation Sleeves by Others	\$7,500
	Irrigation Plumbing Service and Connections	\$20,000 \$10,000
	Irrigation Electrical Service and Connections	\$10,000
	Bid Package 39A: Signage	
	Temporary Signage for AHJ Requests	\$2,500
	Evacuation Maps in Classrooms	\$10,000
	Ended don maps in class of its	\$10,000
	Bid Package 40A: Building Specialties	
	Installation of Ice Makers by Plumbers	\$3,000
	Bid Package 41A: Window Treatment	
	All window treatment scope, Furnished and Installed	\$158,200
	Bid Package 42A: Kitchen Equipment	
	Kitchen Equipment Signage	\$2,500
	MEP Connections	\$7,500
	Did Dadkaga 49A. Audia Visual	
	Bid Package 48A: Audio Visual Alternate Projector	\$15,000
	Alternate Hojector	\$13,000
	Bid Package 49A: Operable Partition	
	Modifications of Support Steel	\$5,000
Project C: STEN	Addition	
	Bid Package 29B: Site Concrete	
	All Site Concrete Scope, Furnished and Installed	\$369,000
	Bid Package 56B: Kitchen Equipment	
	Kitchen Equipment Signage	\$2,500
	Bid Package 58B: Landscape	A
	Irrigation System Furnish and Install	\$25,000
	Install Irrigation Sleeves by Others	\$2,500
	Irrigation Electrical Service & Connections by Others	\$10,000
Exposure H		
Exposure F Sub-Project Project A: 111 (Description:	Amount:

Town of Brookline Brookline High School Expansion Project | Project A and B

EXHIBIT B: LIST OF ALLOWANCES AND EXPOSURE HOLDS

Did D-	ala a 24 A Million de	
	:kage 21A: Millwork tection	\$50,000
	Hours Deliveries	\$60,000
	ck-up Room Support	\$20,000
	pr Flashing	\$50,000
110		\$30,000
Bid Pa	:kage 22A: Lab Casework	
	Intertop Protection	\$10,000
0	intertop i lotection	\$10,000
Rid Pa	:kage 24A: Fireproofing	
	M Patching - Cementitious and Intumescent	\$50,000
110	Whatehing - cementatious and intumescent	\$50,000
Bid Pa	kage 26A: Doors, Frames, HDW	
	or & Frame Protection and Touch Up	\$25,000
	nporary Doors and Frames	\$10,000
10	porary boots and traines	\$10,000
Bid Pa	kage 27A: Fireproofing	
	al Electrical Coordination	\$5,000
	t Applied Anchor for Dock Bumpers	\$2,500
10.		\$2,500
Bid Pa	kage 28A: Theatrical Draperies	
	tection of Finished Work	\$5,000
TIC		\$5,000
Rid Do	ckage 34A: Carpet	
	protection	\$7,500
	eling / Floor Preparation	\$7,500
Lev	cung/ noor reparation	00C, ۱ ډ
Pid Do	ckage 37A: Resinous Flooring	
	by Protection	¢E 000
		\$5,000
vei	Itilation	\$5,000
Pid Do	trace 10A. Ruilding Englishing	
	ckage 40A: Building Specialties	¢1.000
Rec	eipt and Installation of AED's	\$1,000
Did De	ckage 42A: Kitchen Equipment	
		\$18,000
	lk-in Cooler/Freezer Sub Floor Build Up lk-in Cooler/Freezer Slab Depression Infill	
	or Trough Mud-set Infill	\$10,000
FIU	or mough wide-set innit	\$4,000
Rid Pa	:kage 46A: Landscape	
		\$10,000
Re	air of Neighbor Planting/Fence	\$10,000
Pid Do	kage 47A: Final Cleaning	
		¢ F R 000
POS	t Punchlist Re-Cleaning	\$58,000
Due le et Cr. CTERA A delalité	-	
Project C: STEM Additic	n	
Did Da	la - 200: Cita Commeta	
	ckage 29B: Site Concrete	¢20.000
VVint	er Conditions	\$20,000
Did De	de a 500 final Classica	
	ckage 59B: Final Cleaning	£24.000
POSL	Punchlist Re-Cleaning	\$34,000
Did D-	den en DCD: Anal-Manada Milleranda	
	ckage 36B: Architectural Millwork	¢5.000
	our Deliveries	\$5,000
	ction	\$15,000
Inwa	ll Blocking, Drywall & Paint Touch up Bulletin 008 & 008.1	\$5,000
	da en 270. Let Communit	
	kage 37B: Lab Casework	
	ours Deliveries	\$15,000
	Flashing	\$10,000
	1 Lab 211 Mockup Support	\$20,000
	tertop Protection	\$7,500
Insta	l Rubber Base at Deleted Wood Toekick	\$4,100
	ckage 56B: Kitchen Equipment	
	lk-in Cooler & Freezer Sub Floor	\$9,000
Wa	lk-in Cooler & Freezer Slab Depression Concrete Infill	\$5,000
		¢2,000
Flo	or Trough Mudset Infill ective Premium Time	\$2,000

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT C: ASSUMPTIONS, QUALIFICATIONS & CLARIFICATIONS

Refer to Pre-GMP Amendments 1 to 18 for a comprehensive list of Assumptions, Qualifications & Clarifications that have previously been incorporated into the Owner – Construction Manager Agreement.

General Assumptions, Qualifications and Exclusions

- 1. This Guaranteed Maximum Price Submission (GMP) is proposed for Project A: 111 Cypress St, Project C: STEM Addition and MBTA OCS, Enabling and Platform Work, and portions of the Elevator Modernization as noted below in line item 2.
- 2. This GMP does not include any work associated with Project B: Tappan Gym, Project D: 3rd Floor Renovation, Project E: Streetscapes or Project F: Deferred Maintenance, with the exception of the elevator modernization work. We have included the value of RTA 24B for the elevator refurbishment Subcontract, but have not included the costs associated with other Trade Contract and Subcontract work required to perform the elevator refurbishment work. That scope was issued by the design team in Field Bulletin 057 and the projected cost for that work is carried in the change management value that is not included in the GMP.
- 3. Deleted
- 4. The GMP includes all items approved in Pre-GMP Amendments 1 thru 11 and 12a, 12b, 13a, 13b, 14a, 14b, 15a, 15b, 16a, 16b, 17a, 17b, 18a and 18b, including, but not limited to; document lists, bid package values, exposure holds, allowances, qualifications, alternates, unit prices, etc.
- 5. Division 01 Specifications
 - a. Refer to Exhibit K Division 01 Specification Modifications, redlined and prepared by Hill International for agreed upon modifications to the Division 01 specifications for both the Project C – STEM Wing Addition ("Stem") and Project A – Cypress Building ("Cypress") projects, based on a collaborative review and agreement by Hill, Skanska and WRA.
 - b. The agreed upon modifications to the Division 01 Specifications are based on the Project C
 – STEM Wing Addition Early Package # 2 specification book as modified and issued with
 Revision: FB-005 GMP Bid Set August 1, 2019.
 - c. The agreed upon modifications assumed that the Division 01 Specifications for Project C STEM Wing Addition GMP Bid Set are identical to the Division 01 Specifications for Project A Cypress Building Field Bulletin # 9 GMP Bid Set. In the case there are discrepancies between the two, the Project C STEM wing specifications shall prevail.
 - d. Cost and Manpower Loading has not been included. As agreed, a manpower resource curve will be provided if the team feels the onsite project manpower is insufficient to complete the project by substantial completion.
- 6. The GMP does not include costs associated with Town of Brookline building department fees and other building department fees.
- 7. This GMP includes, as set forth below, an initial allowance of \$150,000 for compensation to the Construction Manager ("CM") for certain costs the Construction Manager incurs as a result of the COVID-19 pandemic, future epidemics or pandemics (collectively, "Pandemic"), and governmental

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT C: ASSUMPTIONS, QUALIFICATIONS & CLARIFICATIONS

orders and potential governmental orders associated with the same related to costs due to resulting delays, suspension(s), and material or equipment delays or shortages as further described below ("Pandemic Allowance").

This Pandemic Allowance shall be utilized to compensate the Construction Manager for the below-described costs ("Pandemic Costs"), including appropriate markups for increased insurance and bonding (but excluding Fee, which shall not be applied to any Pandemic Costs); provided that, only Pandemic Costs reasonably necessary for compliance with recommended Pandemic safety practices for the Project issued by local, state or federal law, regulations, or Pandemic-specific safety guidelines, including guidelines issued by the CDC or WHO, or other guidelines, if any, that the Owner and Construction Manager agree are in the best interest of the safety of personnel in or around the Project ("Pandemic Standards").

Construction Manager shall timely identify and submit to Owner any updates to the Pandemic Standards after this GMP Amendment has been executed.

The parties agree that long-term forecasting of the costs and impacts of the COVID-19 Pandemic is speculative. Therefore, the Pandemic Allowance shall include Pandemic Costs incurred through the execution of the GMP and shall also be based on a cost projection for the three (3) months following the date of acceptance of the GMP. Should the parties not agree to mutually agreeable terms within the first two week review period or any subsequent two week review periods as needed, the Owner-CM Agreement shall be automatically terminated. The CM shall be paid for its termination costs in accordance with Article XVII Paragraph 2 of the General Conditions of the Agreement and the CM shall not be liable for any Damages that result from said termination.

The Pandemic Costs shall include:

- i) <u>General Requirements ("GR's")/Direct Costs</u>. Additional Direct Costs of complying with the requirements of applicable Pandemic Standards, such as cleaning and testing supplies for the necessary sanitizing of equipment, materials and the jobsite, Anti-microbial surface protection chemicals and associated testing procedures for micro-organisms; constructing additional access for social distancing; supplying PPE (including face masks, face covers or face shields); additional Portojohns and daily cleaning of the Portojohns as required by Pandemic Standards; hand washing stations (including hand sanitizers), Pandemic signage and banners, and no contact thermometers; additional tools or equipment required to perform the Work in compliance with Pandemic Standards; and related labor and carpentry work necessary to install, manage, and maintain these Pandemic Standards.
- ii) <u>General Conditions Costs</u>. Additional General Conditions costs for CM Staffing (project management and supervision), but only to the extent such staffing is required to manage and monitor Pandemic Standards (including enforcing and collecting Self Certification

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT C: ASSUMPTIONS, QUALIFICATIONS & CLARIFICATIONS

paperwork, Temperature Checking/Health Screening, Social Distancing monitoring, suspected/actual case tracking, revised logistics/sequencing planning, shift work supervision and planning, daily reporting and other similar management and supervision efforts as needed) (collectively "Additional Efforts"). The Construction Manager shall endeavor to utilize its current staffing for these Additional Efforts within normal operating hours if possible. The staffing needs and projections for these Additional Efforts shall be reviewed with all other additional costs for each forecast period pursuant to paragraph (e) below.

- iii) <u>Schedule Delay Costs</u>. The Contract Time shall be extended on a day-for-day basis for any schedule impacts attributable to the Pandemic as reasonably demonstrated by the Construction Manager ("Pandemic Delay"), less any Contract Time due to any concurrent impacts unrelated to the Pandemic. In addition, the Construction Manager shall be entitled to recover its extended General Requirements and General Conditions costs for a Pandemic Delay. Extended General Conditions costs shall be based on the staffing engaged during the period of Pandemic Delay. Extended General Requirements costs, such as general labor/cleaning/carpentry, office/storage trailer and equipment rentals, police details, portojohn rentals and other time dependent GR's, shall be based on an average monthly cost of the actual GR's utilized on site during the period of Pandemic Delay. As a condition of CM's right to recover, all such costs shall be reasonably substantiated in accordance with the requirements of the Contract Documents.
- iv) <u>Procedure for Payments</u>. In accordance with the currently established Allowance process, the tracking of costs, approvals and distribution of payments requested through the Pandemic Allowance shall include a weekly review of Pandemic Allowance costs to maintain alignment on scope performed as Work progresses. Owner approval of proposed Change Orders to reconcile Pandemic Allowance funds shall be performed monthly. The CM shall furnish the Owner with a written breakdown of all reimbursable Pandemic Cost items for which the CM is requesting a Change Order from the Pandemic Allowance. Disbursement of all payments requested from the Pandemic Allowance shall be in accordance with the Payment Application process, except as otherwise provided herein.
- v) <u>Subsequent Increased Pandemic Allowance (if Necessary)</u>. The Parties shall promptly and mutually agree to adjust the Pandemic Allowance based on a revised forecasted budget at the end of the three month period and subsequent time periods as follows: Two weeks prior to the end of the first three month Pandemic Allowance projection period, Owner and Construction Manager shall negotiate in good faith an updated Pandemic Allowance

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT C: ASSUMPTIONS, QUALIFICATIONS & CLARIFICATIONS

to be completed prior to the end of the current Pandemic Allowance period. The updated Pandemic Allowance shall be reconciled based on then current knowledge. The new time period projection shall be applicable to a subsequent three-month period (or other period of time as mutually agreed by the parties). In the event changes in circumstances related to the Pandemic (resulting in the relaxation or removal of Pandemic Standards or changes in impacts from the Pandemic), the parties may mutually agree to suspend the funding of the Pandemic Allowance for the next three month period. Due to the fluid nature of the Pandemic, however, and in anticipation that the Pandemic may wane and surge throughout the term of the Project, the parties agree that the Pandemic Allowance shall remain accessible and available as a means of impact recovery as set forth in this Paragraph 7 for the duration of the Project whether or not the Parties agree to fund it for a particular period.

- 8. Overrun or underrun of allowance values shall be added to or subtracted from the GMP by Change Order, subject to ToB or OPM's approval.
- 9. Overrun or underrun of Scope (Exposure) Hold values shall be added to or subtracted from the Construction Manager's Contingency. Exposure hold expenditure approvals are not required prior to performing the associated work. However, final cost reconciliation will be made available with weekly cost logs
- 10. The GMP is based on the attached project schedules with data dates of February 10, 2020. We understand the substantial completion date for Project A is not in alignment with the desires of the ToB. We will continue to work diligently and collaboratively over the coming months with the project team and subcontractors on additional options and opportunities in attempt to constructively accelerate the date for the ToB.
- 11. This GMP excludes LEED certification and Building Flush-Out and associated costs. Per ToB, the project will not be submitted to the USGBS for certification; instead, it will be designed as "certifiable".
- 12. This GMP assumes that compliance with all LEED requirements have been specifically included in the Contract Documents in the trade specific specification sections as required to obtain compliance. Should a product be listed in the trade specific specification section that conflicts with Division 01 Sustainable Design Requirements, we have included the product as identified in the trade specific specifications. Substitutions, if required to meet LEED criteria, are not included.
- 13. Deleted
- 14. Article V.1.A of the General Conditions of the Contract infers that costs associated with Designer and Owner inspection and verification of materials stored at off site locations for which progress payments will be requested shall be borne by the CM. We have assumed that photographic evidence provided by the subcontractor is acceptable in the place of travel to storage locations will be acceptable, and have not included any costs associated with Designer and Owner costs for inspections and verification unless specifically indicated per a specification section.
- 15. Deleted

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT C: ASSUMPTIONS, QUALIFICATIONS & CLARIFICATIONS

- 16. Deleted
- 17. Deleted.
- 18. Deleted
- 19. Pursuant to Article 4.4 of the Owner CM Agreement, we have assumed 1 GMP substantial completion (refer to exhibit D). . We will endeavor to achieve Final Completion in a diligent and expeditious manner and have included staffing in the LS GC's for 3 months after substantial completion.
- 20. Per Article VI Section 5 of the CM Agreement, we have included the definition of Substantial Completion as achieving a Temporary Certificate of Use and Occupancy for beneficial use. All remaining items shall be completed prior to Final Completion.
- 21. Deleted
- 22. Deleted
- 23. Article IV.19 of the General Conditions of the Contract states that the CM shall bear the cost of any sales tax that the CM incurs and the Owner shall not reimburse the CM for any such taxes. This article shall only apply to items that are in fact tax exempt that the CM does not obtain the benefit of such sales tax exemption and is not negligent in managing the process. The Owner acknowledges that the Department of Revenue Directive 02-16 requires that there are various goods that remain taxable even on a tax exempt project, and the Owner shall reimburse the CM for such taxes.
- 24. Per Article XVIII.10 "Notices"; we assume in the GMP that a formal letter attached to an email servers as notice to the ToB and it's OPM (Hill International) in lieu of a certified letter to the Town Hall.
- 25. Per Article, 5.12.2 the revised Organization Chart and updated General Conditions cost has been included in the GMP as Exhibit GC.
- 26. Deleted
- 27. Deleted
- 28. We have included a tracking list for tools and equipment purchased by the project for turnover at the completion of the Work if not consumed.
- 29. Deleted
- 30. This GMP is based upon Skanska providing General Liability and Workers Compensation coverage as a Contractor Controlled Insurance Program (CCIP) at 2.65% of the total project cost less fee, bond, and CCIP.
- 31. This GMP assumes that Construction Contingency can be used for the deductible on Builders Risk claims, if necessary.
- 32. This GMP assumes that Skanska will provide Subcontractor Default Insurance (SDI) coverage for Subcontractors at 1.35% of the Subcontract Value and individual P&P Bonds for each Trade Contract value.
- 33. Pursuant to Article VI 1 B we have not included 30 days of "float" in the schedule allocated exclusively for unanticipated delays and change order work. Additionally, the current float in the schedule is for the exclusive use of the CM.

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT C: ASSUMPTIONS, QUALIFICATIONS & CLARIFICATIONS

- 34. The GMP includes tracking MBE/WBE participation with a good faith efforts goal of 10.4%. We have not included an Equal Employment Opportunity (EEO) program, as it's our understanding this is not required.
- 35. Deleted.
- 36. All costs associated with labor, materials, resequencing, logistics, winter conditions, and GR's, will be funded from within the Owner Allowances when used.
- 37. It is assumed that the design will be code compliant, accepted by the appropriate agencies and other applicable parties including the Owner's lenders and insurers, and fit for the Owner's purpose.
- 38. Deleted
- 39. Deleted
- 40. Skanska schedule is predicated on proceeding with wiring in a temporary condition with a temporary roof and will be acceptable to the ToB.
- 41. Manned site security and temporary cameras are excluded.
- 42. Skanska reserves the right to seek ToB approval to work extended hours and weekends. It is presumed approval of these requests will not be unreasonably withheld.
- 43. This GMP includes an Owner Allowance for utility consumption and usage (i.e. electrical power, gas, chilled water, heating hot water, diesel fuel, kerosene, propane, etc.). Submeetering at the STEM to be provided for electrical, if required per the specification.
- 44. We have included moisture mitigation only where required per the specifications and as shown clearly on the drawings and plans.
- 45. We have not included a boiler watch for the use of permanent or temporary systems.
- 46. Factory Mutual criteria has not been considered or included in this GMP Proposal, it is our understanding this is not a project requirement.
- 47. We have included temporary offices only for the CM Staff only, as it's our understanding this is all that is required.
- 48. Vibration testing or deformation monitoring, etc. of abutting properties is excluded.
- 49. All Geotechnical monitoring services will be performed by the Owner's consultant for all Work.
- 50. Deleted
- 51. As agreed to with the Town of Brookline, third party, independent inspecting agency testing and inspection services are excluded. This GMP assumes all testing and inspections will be provided by the Owners testing agency.
- 52. As-builts will consist of WRA construction document architectural plans annotated to incorporate RFI's and Bulletin modifications in pdf format. MEPFp as-builts will include digital files and the coordination model in Navisworks by Skanska. Updating the project model for changes other than MEPFp shall be by others, if required. In addition, site utilities and spread footing as-builts will be provided in a pdf format by Skanska. As agreed, WRA will provide updated model at project completion.
- 53. Model asset management and systems O&M manuals added to the model have not been included in the GMP.

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT C: ASSUMPTIONS, QUALIFICATIONS & CLARIFICATIONS

- 54. We assume the building superstructure can accommodate the loads imposed by systems that fall under Design Delegation, Licensed Professional or Registered Engineer, that will need to be developed with the Subcontractor's. Any additional work required to reinforce the superstructure or further distribute or accommodate the loads shall be considered a change to the GMP. However, if the contract documents identify a specific (not generic) detail for a defined location for a kicker or stiffener, this would be included by the Subcontractor.
- 55. We exclude any special provisions for managing deflection or movement of the structures following erection, plumbing, bolt up and welding of the structures. Unless specifically noted otherwise in the Contract Documents, the CM will determine the construction sequence. It is presumed architectural tolerances of details as designed will allow for any anticipated movements or deflections that might occur as construction progresses and thereafter.
- 56. We have assumed loads imposed during construction for lifts, staging, etc. on the permanent structure will be provided by Skanska and reviewed by the EOR. We have not included an engineer for reviewing this.
- 57. We have assumed that Eversource will be able to provide power by 6/1/2020 for construction lighting, welders, pumps, mixers, heaters, etc. including building permanent systems to support equipment start-up dates for Cypress. Should temporary power be unavailable, the utility consumption allowance shall be used to rent a temporary generator.
- 58. Deleted
- 59. This GMP assumes unfettered access to working on the roofs, facades, canopies and interior work around the MBTA tracks without restrictions. As agreed, Skanska will provide Work Plans in a timely manner to the MBTA.
- 60. This GMP assumes the punchlist will be completed on a construction clean in lieu of a final clean. We have included final clean of the exterior curtain wall once prior to punchlist only. No additional cleaning of the exterior curtain wall is included.
- 61. The estimated costs for Skanska employed craft labor (Union Carpenters and Laborers) included in the General Requirements is based on an average hourly rate based on the current anticipated schedule for completion of the work. The actual rates invoiced will be based on the the labor rates that have been submitted to and approved by Hill International, and will be adjusted over time as the corresponding union wage agreements are adjusted.
- 62. The GMP is based upon temporary use of the permanent systems for temperature conditioning of spaces as required for interior construction and installation of finishes, if available. Temporary humidification or dehumidification of the buildings to meet product installation requirements has been included as an Owner Allowance.
- 63. We have not included building pressure testing (blower door test), as it is our understanding that it's not required.
- 64. We have included a 1-year warranty including any specified special warranties commencing at Substantial Completion. Skanska will provide a list of warranty contacts prior to Final Completion for the ToB to contact during this period for repairs and/or replacements.

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT C: ASSUMPTIONS, QUALIFICATIONS & CLARIFICATIONS

- 65. As directed during OAC meetings we have not included a bi-directional amplifier for the Cypress Building. All parties understand that execution of the Pre-GMP Amendments and GMP authorizes the CM to proceed with the work included
- 66. Deleted
- 67. This GMP does not include any design or estimating contingency.
- 68. This GMP does not include the furnishing, receiving, installing and/or protection of FF&E. Minor plastic covering for punchlist work is included.
- 69. Trade and Subcontractor parking is presumed to be in accordance with the ToB parking requirements. We have not included enforcement of any parking restrictions.
- 70. This GMP is based on Skanska trucking routes, logistics plans and fencing locations.
- 71. This GMP includes only the RFI's and Bulletins per the attached Exhibit.
- 72. As agreed, this GMP excludes all change orders, proposed change orders and cost events in the SKA change management system (except prior approved PCCO's)Refer to Exhibit I: Owner Change Log Summary Out of Scope Only.
- 73. This GMP assumes we can continue to use the space behind Tappan Gym for Staff parking.
- 74. We have assumed craft labor steward support for 15 weekend building MBTA diversions, no MBTA Platform work.
- 75. With the exception of the steel and precast MBTA overbuild at the tracks (Level 2), and the curtain wall installation on the west elevation above the tracks, this GMP has assumed all work can be performed during normal workdays and hours. The Platform requires work to be done on Early Access nights, Diversion Weekends and limited day shifts and has been included as such.
 - a. If the Division 01 Specifications require better quality or greater quantity, the Owner-CM Agreement shall take precedence unless expressly agreed to by the Parties.

MBTA Assumptions, Qualifications and Exclusions

- 1. Deleted
- 2. We have not included an MBTA easement survey, based on recent meetings it's our understanding this will be performed by others.
- 3. We have not included any Cypress project delays or impacts associated with or caused by the MBTA due to phasing, work plan approvals, or lack of flagger support, etc. As agreed, work plans will be submitted to the MBTA.
- 4. The GMP does not include any costs associated with MBTA Force Account or other charges or fees. It is assumed that all costs for such will be paid by the Owner.

Deferred Maintenance Assumptions, Qualifications and Exclusions

1. The GMP includes the scope associated with the elevator refurbishment work only and as outlined in specification sections 142400, 144200 and 145500. All work by other trades required to support this scope of work such as demolition, structure, drywall cut and patch, flooring, painting, electrical, fire alarm, communications and security, & Deferred Bulletin 57 is excluded.

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT C: ASSUMPTIONS, QUALIFICATIONS & CLARIFICATIONS

Bid Package Assumptions, Qualifications and Exclusions – Project A (Cypress)

The following Assumptions and Qualifications represent the basis for the GMP value for the remaining Bid Packages that have not been included in Amendments 1–18. Bid Package qualifications should be considered the same as GMP qualifications unless otherwise noted, i.e. if an item is located within another bid package. RFI's and Bulletins or CCD's, and ASI's are included only as noted within each bid package and it's respective scope. Full scope of each RFI, Bulletin, CCD, ASI are not included in their entirety for complete scopes and will be addressed through the change order process.

BP-14A Concrete - Site

As requested we have included this as an Owner Allowance and will rebid.

BP-21A Architectural Millwork / Casework

- 1. The basis of this BP is the 100% GMP set drawings, field bulletins 9, 9.1, 9.2, 9.3 and 9.4 dated 10/21/19, as issued by WRA. Scope applicable to this trade shown in other bulletins and changes will be priced as part of a future change order.
- 2. This BP includes an Owner Allowance of \$18,000 for modifications due to casework being built around the MEPFP raceway at the perimeter of the building.
- 3. This BP includes an exposure hold of \$75,000 for countertop and casework protection.
- 4. This BP includes an exposure hold of \$60,000 for casework deliveries outside of 7AM to 3:30 PM.
- 5. This BP includes an exposure hold of \$20,000 for support work associated with the Level 1 C-129 classroom mock-up. This is intended to be used at Skanska's discretion for scope related to supporting the mock-up installation such as temporary protection and expediting the advancement of the room to support the installation of casework.
- 6. This BP includes an exposure hold of \$50,000 for floor flashing at long runs of base cabinetry where concrete floor was placed within specified tolerances.
- 7. This BP includes marker trays routed end to end per 5/A9-02-A however does not include the steel support for this marker tray as this work will be deleted in a future bulletin.

BP-22A Laboratory Casework

- 1. The basis of this BP is the 100% GMP set drawings, field bulletins 9, 9.1, 9.2, 9.3 and 9.4 dated 10/21/19, as issued by WRA.
- 2. This BP includes Bulletin FB 026, dated 12/3/19. Scope applicable to this trade shown in other bulletins and changes will be priced as part of a future change order.
- 3. This BP includes furnish and installation of all lab casework in the Physics rooms and Prep rooms on levels 3 and 4, and in the science room on ground level constructed to SEFA standards. Lab casework is to be provided with epoxy tops per the original specifications ILO Corian.

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT C: ASSUMPTIONS, QUALIFICATIONS & CLARIFICATIONS

- 4. This BP includes full flush overlay cabinets, per scope review by Rawn architects, in lieu of inset.
- 5. This BP includes furnish and installation of all lab casework in the Physics rooms and Prep rooms on levels 3 and 4, and in the science room on ground level constructed to SEFA standards. Lab casework is to be provided with epoxy tops per the original specifications ILO Corian.
- 6. This BP includes an Owner Allowance of \$18,500 for the eight (8) Mobile Teacher Stations. Stations are noted in the specifications however; plans and/or elevations have not been provided.

BP-27A Overhead Doors and Dock Bumpers

- 1. The BP includes Field Bulletin #9, 9.1, 9.2, 9.3, and 9.4.
- 2. This BP includes an Exposure Hold of \$5,000 for the final electrical connections and controls to the powered overhead door.
- 3. This BP includes an Exposure Hold of \$2,500 to investigate reinforcing conflicts with post-applied anchors to the loading dock walls that receive the dock bumpers in lieu of cast-in-place as specified.

BP-28A Theatrical Draperies

- 1. The BP includes Field Bulletin #9, 9.1, 9.2, 9.3, and 9.4.
- 2. This BP includes an Exposure Hold for \$5,000 for in-wall blocking or supplemental support for the drapery system.

BP-34A Carpet

- 1. The BP includes Field Bulletin #9, 9.1, 9.2, 9.3, and 9.4.
- 2. The BP includes, per the Architects direction, entrance walk-off mats in Vestibule C-045 and C-100, products from "Shaw Contract Path 5T034, in color "Sterling".
- 3. This BP does not include moisture mitigation as the specified materials suggest it's not required.
- 4. This BP includes an exposure hold of \$7,500 for flooring protection.
- 5. This BP includes an exposure hold of \$7,500 for floor leveling, flashing and preparation

BP-37A Resinous Flooring

- 1. The BP includes Field Bulletin #9, 9.1, 9.2, 9.3, and 9.4.
- 2. This BP includes a vapor mitigation system that is integral to the resinous flooring application. As such, a stand-alone vapor mitigation coating as described in 096710-2.2 is not included and not required for the resinous flooring systems specified.

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT C: ASSUMPTIONS, QUALIFICATIONS & CLARIFICATIONS

- 3. This BP includes an exposure hold of \$5,000 for protection of the resinous flooring at the Garden level and the First Floor level.
- 4. This BP includes an exposure hold of \$5,000 for supplemental ventilation.
- 5. This BP includes alternates to the specified resinous flooring at the garden level and L1 servery. The Garden Level has been included as standard color urethane epoxy per RTA 042A alternate 19.1. Resinous flooring at the L1 servery has been included as Duraflex Quartz Frappe.

BP-39A Signage

- 1. The basis of this BP is the 100% IFE drawings, field bulletins 9, 9.1, 9.2, 9.3 and 9.4 dated 10/21/19, as issued by WRA.
- 2. This BP includes work from field bulletin #24, dated 12/10/19. Scope applicable to this trade shown in other bulletins and changes will be priced as part of a future change order.
- 3. This BP includes furnish and installation of three (3) exterior, handicap parking signs, post and sleeve.
- 4. This BP does not include any work with the exterior monument sign as this work is to be performed by the masonry trade contractor.
- 5. This BP excludes glass backers. These are not shown and were agreed not required per the descope meeting.
- 6. Sign Type 33 appears on the sign type list but is not shown on the drawings or identified on the schedule. As such, Sign Type 33 is excluded from this BP.
- 7. This BP includes a \$2,500 Owner Allowance for Skanska to provide and install temporary signage as a result of OCC and AHJ inspections.
- 8. This BP includes a \$10,000 Owner Allowance for Skanska to provide and install evacuation map signage in the classrooms.

BP-40A Building Specialties

- 1. The basis of this BP is the 100% GMP set drawings, field bulletins 9, 9.1, 9.2, 9.3 and 9.4 dated 10/21/19, as issued by WRA. Scope applicable to this trade shown in other bulletins and changes will be priced as part of a future change order.
- 2. This BP includes clarifications made in pre-bid RFI nos. 4.2, 4.3, 4.4, 4.5, 4.6, 4.11, 4.12, 4.61 and 4.62 and a copy of the responses is included as an attachment.
- 3. This BP includes furnish and installation of five (5) AED units per pre-bid RFI #4.2.
- 4. This BP includes an Owner Allowance of \$3,000 for installation of icemakers.
- 5. This BP includes an Exposure Hold of \$1,000 to receive and install the AEDs.

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT C: ASSUMPTIONS, QUALIFICATIONS & CLARIFICATIONS

BP-41A Window Treatments

This bid package in it's entirety is included as an Owner Allowance. The below qualifications form

the basis of the allowance.

- 1. This allowance includes work contained in Field Bulletin Nos. 9, 9.1, 9.2, 9.3, and 9.4.
- 2. This allowance includes added window treatment in the "White Box" contained in Field Bulletin 027.
- 3. Deleted
- 4. Deleted
- 5. Deleted
- 6. This allowance includes 5% attic stock based on 5% of the total number of shades.
- 7. Deleted
- 8. This allowance is based on the Flexshade / Flexshade 2 system which is an alternate product then what is specified.
- 9. This allowance includes a value, in addition to the Subcontractor bid, for electrical and/or tele-com connections not show on the base building contract drawings buy may be required for the Flexshade / Flexshade 2 system. The Flexshade / Flexshade 2 system is a significant savings from the specified systems and was required to have a constructable and warrantable system. The Contract Drawings will need to be coordinated with the Flexshade / Flexshade 2 requirements to ensure power and tele-data is being provided at all areas required by this system.

BP-42A Kitchen / Food Service Equipment

- 1. The BP includes Field Bulletin #9, 9.1, 9.2, 9.3, and 9.4.
- 2. This BP does not include installation or connections to Owner Furnished items.
- 3. This BP does not include appliances noted on A9-31-A and 11 31 00. These will be included within the Building Specialties package.
- 4. This BP includes an Owner Allowance of \$2,500 for additional signage that may be needed on, or around kitchen food service equipment being installed under this bid package.
- 5. This BP includes an Owner Allowance of \$7,500 to complete field connections with mechanical, electrical, plumbing and fire protection subcontractors related to kitchen food service equipment that haven't been accounted for in the Contract Documents.
- 6. This BP includes an Exposure Hold of \$18,000 to furnish and install a 2" sub-floor within the walkin coolers and freezers as an underlayment to the resinous flooring.
- 7. This BP includes an Exposure Hold of \$10,000 to furnish and install the concrete fill around the walk-in coolers and freezers to secure the units within the slab depressions.

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT C: ASSUMPTIONS, QUALIFICATIONS & CLARIFICATIONS

8. This BP includes an Exposure Hold of \$4,000 to furnish and install a mud-set infill around the floor trough.

BP-43A Stage / Theater Equipment and Seating

- 1. The basis of this BP is the 100% GMP set drawings, field bulletins 9, 9.1, 9.2, 9.3 and 9.4 dated 10/21/19, as issued by WRA.
- 2. This BP includes an initial installation of one seating configuration only. Additional seating configuration set ups, installations and mobilizations called for in the specifications are not included.
- 3. The BP does not include furnish or delivery of attic stock.

BP-46A Hardscape / Landscape

- 1. The basis of this BP is the 100% GMP set drawings, field bulletins 9, 9.1, 9.2, 9.3 and 9.4 dated 10/21/19, as issued by WRA.
- 2. This BP includes Field Bulletin no. 25, dated 12/9/19, and Field Bulletin no. 38, dated 1/13/20. Scope applicable to this trade shown in other bulletins and changes will be priced as part of a future change order.
- 3. This BP includes installation of the granite curb (and unreinforced concrete bed) beneath the Wood/Iron fence, only.
- 4. This BP includes the granite campus bench as detailed on 1/L-507-A. We have not included a wood top as noted on 1.9/L-101-A as none are detailed.
- 5. Per the 1/24/20 de-scope meeting with the Landscape Architect, the liquid biological amendments are not defined in the Contract Documents are will not be required. As such, this BP does not include liquid biological amendments for plantings.
- 6. This BP includes design services for the irrigation scope, and excludes furnish and install of the system. The furnish & install of the irrigation system has been included as a \$50,000 Owner Allowance as the contract documents identify Irrigation as a Design/Build package.
- 7. This BP includes a \$7,500 Owner Allowance for the installation of irrigation sleeves by the others
- 8. This BP includes a \$20,000 Owner Allowance for the relocation of existing plumbing equipment and for the installation of new plumbing equipment/materials to provide a fully functioning and coordinated Irrigation system that is not detailed on the contract documents.
- 9. This BP includes a \$10,000 Owner Allowance for Irrigation System electrical service and connections, as none are indicated on the Contract Drawings.
- 10. This BP includes an Exposure Hold of \$10,000 for repairs to the neighbor's plants / fence.

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT C: ASSUMPTIONS, QUALIFICATIONS & CLARIFICATIONS

BP-47A Final Cleaning

- 1. The BP includes Field Bulletin #9, 9.1, 9.2, 9.3, and 9.4.
- 2. This BP assumes final cleaning will occur prior to the installation of Owner furnished furniture and equipment and excludes cleaning of these items.
- 3. This BP includes cleaning of the floors only and excludes waxing, as none was specified.
- 4. This BP excludes cleaning of exterior stone and brick in this BP, this work is to be performed by the mason.
- 5. This BP includes an Exposure Hold of \$58,000 to provide final cleaning after the completion of the punch list throughout the building.

BP-48A Audio / Visual Systems

- 1. The basis of this BP is the 100% GMP set drawings, field bulletins 9, 9.1, 9.2, 9.3 and 9.4 dated 10/11/19, as issued by WRA.
- 2. This BP excludes modifications to Owner furniture to interface with AV system.
- 3. This BP includes scope clarifications per pre-bid RFI no. 1 (attached).
- 4. This BP includes furnish and installation of projection screens.
- 5. This BP assumes the Owners representatives will perform any Owner software uploading that may need to get loaded onto the equipment.
- 6. This BP assumes the electrical and AV drawings have been fully coordinated by the design team. As such, we exclude any additional work to synchronize the two systems to ensure functionality of completed installations.
- 7. This BP include an Owner Allowance of \$15,000 for procurement of the alternate model projector.

BP-49A Operable Partitions

- 1. The BP includes Field Bulletin #9, 9.1, 9.2, 9.3, and 9.4.
- 2. This BP includes an operable partition with the specified STC rating. The BP does not include modifications to adjacent construction and finishes to continue this STC rating. It is assumed that adjacent construction and finishes have been designed with the appropriate STC ratings.
- 3. This BP includes an Owner Allowance of \$5,000 for modifications of the misc. metal and cold formed metal framing system to accept the operable partition

Bid Package Assumptions, Qualifications and Exclusions – Project B (STEM)

The following A's&Q's represent the basis for the GMP value for the remaining Bid Packages that have not been included in Amendments 1–18. Bid Package qualifications should be considered the same as GMP

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT C: ASSUMPTIONS, QUALIFICATIONS & CLARIFICATIONS

qualifications unless otherwise noted, i.e. if an item is located within another bid package. RFI's and Bulletins or CCD's, and ASI's are included only as noted within each bid package and it's respective scope. Full scope of each RFI, Bulletin, CCD, ASI are not included in their entirety for complete scopes and will be addressed through the change order process.

BP-29B Concrete – Site

As requested we have included this as an Owner Allowance and will rebid.

BP-36B Millwork

- 1. This BP includes WRA Field Bulletins 005, 005.1, and 005.2 GMP Bid Set. Additionally, WRA Field Bulletins 008 and 008.1 have been included in this BP.
- 2. 2This BP includes Skanska Bid-Bulletins 01 which included a then-current copy of the PreBid RFI Matrix.
- 3. This BP excludes lab casework and Millwork counter scope on the Food Service drawings see BP-37B and BP-56B.
- 4. This BP excludes full scale burn tests and materials testing.
- 5. This BP assumes storage shelving found on detail 6/A7-33-C is Owner provided and has not been included as a part of any STEM Wing bid package.
- 6. This BP includes a \$5,000 Exposure Hold for off-hours deliveries that will not be able to be coordinated during the regular working hours day due to the size and logistics of the site.
- 7. This BP includes a \$15,000 Exposure Hold for the furnish and install of protection to the finish millwork installations.
- 8. This BP includes a \$5,000 Exposure Hold for in-wall blocking, drywall, and paint touch ups to support scope added in Bulletin 008 and 008.1.

BP-37B Laboratory Casework / Fume Hoods / Equipment

- 1. The BP included the following Bulletins and RFIs beyond Field Bulletins 005, 005.1, 005.2 as part of their base bid pricing:
 - 1.1 Pre-Bid RFI Matrix dated 10/09/2019 (Bid Bulletin No. 2)
 - 1.2 Bulletin #037: VE Items and MLB-2 lab bench with cabinet
- 2. The BP includes the acceptance of voluntary deduct alternates proposed by NEIS. These have been applied to the revised subcontract amount identified in the cover page and later in the Summary Section.

2.1 Provide hinged doors at all tall cabinets in lieu of the specified sliding hinged doors.

2.2 Delete the wood toe kick at base cabinets. Costs to install a rubber base by the resilient

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT C: ASSUMPTIONS, QUALIFICATIONS & CLARIFICATIONS

flooring contractor are captured in exposure hold #5.

- 3. This BP includes an exposure hold of \$15,000 for the premium time associated with deliveries outside normal working hours.
- 4. This BP includes an exposure hold of \$10,000 for floor flashing at casework where the concrete slab specifications are met but to achieve level cabinets and counters floor flashing will be placed under shimmed areas.
- 5. This BP includes an exposure hold of \$20,000 for support work associated with the Level 2 Chem Lab 211 mockup. This is intended to be used at Skanska's direction for scope related to supporting the installation of finish materials in a building without weather-tight conditions. Examples include temporary weather protection and waterproofing, expediting the advancement of the exterior enclosure in this room, expediting the advancement of interior framing, drywall and MEP/Fps in the room.
- 6. This BP previously included a \$15,000 Exposure Hold for countertop protection. Hill has asked that this exposure hold be reduced to \$7,500 to protect and maintain the protection of the countertops and lab casework after installation but prior to punch list.
- 7. As a result of accepting NEIS's voluntary deduct alternate to delete the wood toekick, this revised BP includes an exposure hold of \$4,100 for the flooring contractor to furnish and install rubber base where highlighted on the attached drawings A10-01-C, A10-02-C, A10-03-C and A9-10-C.

BP-55B Window Treatment

- 1. This BP includes WRA Field Bulletin 005, 005.1, and 005.2 GMP Bid Set. This BP also includes WRA Field Bulletin 029 which deleted all of the R2 Blackout Shades as well as some R1 Exterior Window Shades.
- 2. This BP includes the recommendation of Walker Specialties. During the bidding period, Walker advised that there is a large savings to furnish and install Rollease Acmeda shades in lieu of the specified Hunter Douglas or MechoShade products. Walker has provided the attached product data and comparison matrix to the specified shades which has been reviewed and confirmed by WRA and the Town of Brookline.
- 3. This BP includes window treatments above doors at transom glazing only.
- 4. This BP includes shade headboxes and fascia covers as shown and per the contract documents.
- 5. The contract specifications, drawings, and details related to scope of work do not specify shade lengths or seam locations/layout. Therefore, this BP includes lengths and layout as determined by the product manufacturer.

BP-56B Kitchen Equipment

1. This BP includes WRA Field Bulletins 005, 005.1, and 005.2 GMP Bid Set. Additionally, WRA Field Bulletins 005.3 and 005.4 have been included in this BP.

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT C: ASSUMPTIONS, QUALIFICATIONS & CLARIFICATIONS

- 2. This BP includes Skanska Bid-Bulletins 01 which adds additional work to the bidders Exhibit A scope as well as a then-current copy of the PreBid RFI Matrix.
- 3. This BP includes Skanska Post Bid Bulletin 02 which clarifies that all support from the metal deck above within the building requires the use of Revel Lok RL3.5 hangers in conjunction with the acoustic metal deck scheduled to be installed by others.
- 4. This BP includes equipment ST-77 as specified. Further clarification is needed regarding the Disposer make and model as projects documents conflict.
- 5. This BP does not include removal or relocation of any existing Kitchen Equipment owned or operated by the Town of Brookline.
- 6. This BP does not include the Skanska recommendation to include a \$5,000 Owner Allowance for MEP-FP connections not shown on the contract documents that was rejected by the Town of Brookline in the initial review of this BP. Any required connections not shown on the contract documents will be submitted to the Town as an out-of-scope change.
- 7. This BP includes an Owner Allowance of \$2,500 for additional signage that may be needed on or around kitchen foodservice equipment being installed under this bid package. WRA has advised that additional signage may be needed, but has not provided scope.
- 8. This BP includes an Exposure Hold of \$9,000 to furnish and install a 2" subfloor within the walk-in cooler and freezer as an underlayment to the resinous flooring per detail 2 on FS-102-C. The Resinous Flooring subcontractor has provided the attached literature for Dur-A-Flex FlexLine Mortar which a compatible underlayment product to the finish floor. Skanska has confirmed the use of this product will not limit the warranty of the finish floor.
- 9. This BP includes an Exposure Hold of \$5,000 to furnish and install concrete fill around the walk-in cooler and freezer to secure the units within the slab depression per detail 2 on FS-102-C.
- 10. This BP includes an Exposure Hold of \$2,000 to furnish and install a mud-set infill within the Ice Machine floor trough per detail 3 on FS-102-C using Laticrete Mortar per the attached product literature.
- 11. This BP includes an Exposure Hold of \$10,000 for selective off-hours premium time to meet the schedule requirements based on the install logistics and anticipated manpower of other trades working within the kitchen space.

BP-58B Landscaping

- 1. This RTA includes WRA Field Bulletin 005, 005.1, and 005.2 GMP Bid Set.
- 2. This BP includes Skanska Bid Bulletin 01 dated December 11, 2019 which includes a then-current copy of the Pre-Bid RFI Matrix.
- 3. This BP includes furnishing and installing a 1/2" native crushed stone for the drip strip. Exotic stones have been excluded.

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT C: ASSUMPTIONS, QUALIFICATIONS & CLARIFICATIONS

- 4. This BP includes a qualification that plant materials substitutions may be required due to industry wide shortages. If applicable, substitution request forms shall be completed as a result of a legitimate shortage during the tagging process with the design team.
- 5. This BP includes design services for the irrigation scope, and excludes furnish and install of the system. The furnish & install of the irrigation system has been included as a \$25,000 Owner Allowance as the contract documents identify Irrigation as a Design/Build package. Much of the required information to begin the design process shall be coordinated with the Town per the design teams' response to PreBid RFI 058B.5.
- 6. This BP includes a \$2,500 Owner Allowance for the installation of irrigation sleeves by the others.
- 7. This BP includes a \$10,000 Owner Allowance for Irrigation System electrical service and connections not shown on the contract documents.
- 8. This BP does not include the Skanska recommendation to include a \$10,000 Owner Allowance for the relocation of existing plumbing equipment and for the installation of new plumbing equipment/materials to provide a fully functioning and coordinated Irrigation system that is not shown on the contract documents. Hill has asked that this allowance be removed, and agreed that plumbing additions or relocations should be submitted as an Owner Change Order thru the AR process.
- 9. This BP does not include the Skanska recommendation to include a \$10,000 Exposure Hold for Weather Related Premium Time in the event that off-hours work is required to complete the project as a result of weather-related delays. Should weather-related delays impact the project, Hill has recommended these delays be submitted as an Owner Change Order thru the AR process.

BP-59B Final Cleaning

- 1. This BP includes bids that were created using WRA Field Bulletins 005, 005.1, and 005.2 GMP Bid Set.
- 2. This BP assumes final cleaning operations will be complete before installation of Owner-furnished furniture and equipment, and excludes cleaning these items.
- 3. This BP includes cleaning requirements found in specification 011400 Work Restrictions only as a Final Cleaning specification has not been included or provided per Skanska PreBid RFI 059B.2.
- 4. This BP includes washing of floors only and excludes waxing as none was specified.
- 5. This BP includes Skanska Bid Bulletin 01 dated December 11, 2019 which includes a then-current copy of the Pre-Bid RFI Matrix for inclusion in bidder's proposals.
- 6. This BP includes a \$34,000 Skanska Exposure Hold to provide final cleaning after completion of the punch list throughout the building.

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT C: ASSUMPTIONS, QUALIFICATIONS & CLARIFICATIONS

BP-60B Audio Visual

- 1. This BP includes bids that were created using WRA Field Bulletins 005, 005.1, and 005.2 GMP Bid Set.
- 2. This BP includes a recommendation from Adtech that the ceiling and wall-mounted projectors be powered on a dedicated circuit to prevent damage to equipment from circuit overload that would not be covered under the warranty.
- 3. This BP excludes provisions for an in-place mock up per language provided in specification 014330 Mock-Ups.
- 4. This BP excludes modifications to existing Owner furniture to interface with the new AV system.
- 5. This BP excludes loading Owner software of any kind onto existing AV equipment or equipment scheduled to be installed in this bid package.
- 6. This BP assumes the electrical and AV drawings have been fully coordinated and excludes any additional work to synchronize the two systems to ensure functionality of completed installs.
- 7. This BP includes Skanska Bid Bulletin 01 which includes a copy of a then-current PreBid RFI Matrix. This BP also includes Skanska Post Bid Bulletins 01 & 02, inclusive of updated PreBid RFI Matrix as well as WRA Field Bulletin 005.4 and 005.5 respectively.

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT D: CONTRACT TIME

The Date of Substantial Completion for the Project prior to this Amendment is:	None
This Amendment revises the Contract duration by (Calendar Days):	None
The revised Date of Substantial Completion is:	October 8, 2021*

*

- 1. The above Date of Substantial Completion is based on Project A: 111 Cypress St. The anticipated interim project completion dates for other subprojects are outline below, but do not represent Substantial Completion Dates as outlined in the Owner Construction Manager Agreement.
 - a. Project C STEM Wing: April 27, 2021
 - b. MBTA Platform: December 29, 2021
- 2. Refer to attached Project Schedules
 - a. Project A: 111 Cypress St. Data Date: 10-Feb-20 / Run Date: 19-Feb-20
 - b. Project C: STEM Addition. Data Date: 10-Feb-20 / Run Date: 12-Feb-20

ivity ID	nool - Project A - 10Feb20 R1 Schedule Update - 1318014-CR - B26 Activity Name	Remaining	Start	Finish	iled Schedule	l		Da	ta Date: 10-Feb-20 / Run Date: 09-Jul-20	0 03.00
	Activity Name	Duration	Start	FILIST	2020		021		2022	
					F Mar Apr M Jun Jul A S	Dct N D Jan F Mar Apr M Jun	Jul A S	Oct N D	Jan F Mar Apr M Jun Jul Aug S	S Oct N
Brookline H	High School - Project A - 10Feb20 R1 Schedule Update						1			
Executive S										
			0 / NA / / 0 A	40.14 00						
EXEC-1065	Bid Period	23	04-Mar-19 A	12-Mar-20	Bid Period					
EXEC-1070	Construction Project A - 111 Cypress Building	418	24-Jun-19 A	08-Oct-21				Constructi	n Project A - 111 Cypress Building	
Work Orde	r Milestones						1 1 1	1		
EXEC-1090	Last Day for MBTA Utility Pole Removal	0		09-Mar-20	♦ Last Day for MBTA Utility Pole F	emoval		·	1	
EXEC-1060	Last Day for Tappan & Cypress Temporary Power Line Relocation	0		10-Apr-20	◆ Last Day for Tappan & Cy	ress Temporary Power Line Relocation				
EXEC-1100	Last Day for Cypress Building Permanent Power	0		29-Jun-20	Last Day for	Sypress Building Permanent Power				
EXEC-1110	Last Day for Cypress Building New Gas Service	0		29-Jun-20	♦ Last Day for	Cypress Building New Gas Service				
EXEC-1150	Last Day for Cypress Building New Fire, Water & Sewer	0		29-Jun-20	♦ Last Day for	ypress Building New Fire, Water & Sewe	r			
EXEC-1140	Last Day for Cypress Building New Telecom Service	0		25-Aug-21			🔶 La	ist Day for Cypr	ess Building New Telecom Service	
BHS Acade	mic Calendar						1			
BHS-1020	December Break - 2019	0	22 Dec 10 A	01 lan 20 4	armhan Brack, 2010					
		5			cember Break - 2019					
BHS-1030	February Break - 2020	5	17-Feb-20*	21-Feb-20*	February Break - 2020					
BHS-1040	April Break - 2020	5	20-Apr-20*	24-Apr-20*	April Break - 2020	pool 2010/2020	- 			
BHS-1050	Last Day of School - 2019/2020	0		22-Jun-20*	◆ Last Day of Sp					
BHS-1060	First Day of School - 2020/2021	0		03-Sep-20*		t Day of School - 2020/2021	1			
BHS-1070	December Break - 2020	8	25-Dec-20*	01-Jan-21*		December Break - 2020				
BHS-1080	February Break - 2021	5	15-Feb-21*	19-Feb-21*		February Break - 2				
BHS-1090	April Break - 2021	5	19-Apr-21*	23-Apr-21*	<u> </u>	April Bre			<u> </u>	
BHS-1100	Last Day of School - 20202021	0		22-Jun-21*		•		School - 202020	1 1	
BHS-1110	First Day of School - 2021/2022	0		02-Sep-21*			♦ F	irst Day of Sch	ool - 2021/2022	
Design / Pr	econstruction Phase									
MBTA Des iqu	n Submissions						1			
Building										
MBTA -1 030	MBTA Reviews - Building - 100% Design Submission	5	03-Jul-19 A	14-Feb-20	MBTA Reviews - Building - 100% D	esian Submission			1	
MBTA Platfor										
MBTA -1130	MBTA Reviews - MBTA Platform - 100% Design Submission	5	02-Jul-19 A	14-Feb-20	MBTA Reviews - MBTA Platform -	100% Design Submission				
GMP							1		1	
PRE-1170	Prepare & Submit - GMP	14	03-Sen-19A	02-Mar-20	Prepare & Submit - GMP		1			1
PRE-1180	Review & Execute - GMP	15			Review & Execute - GMP	· · · · · · · · · · · · · · · · · · ·			1	
PRE-1190	Agreement Executed - GMP	0	00-1011-20	23-Mar-20	♦ Agreement Executed - GMP		1	1 1 1		
		0		23-Mai-20						
Schedule Ir	•									
OCS Foundat	tion Redesign						1			
IMP-1232	Impact - Review & Approve - Micro Piles	0	11-Dec-19 A	27-Dec-19 A	act - Review & Approve - Micro Piles					
IMP-1262	Impact - Prepare & Submit - Micro Pile Load Test	0	30-Dec-19 A	06-Jan-20 A	pact - Prepare & Submit - Micro Pile Lo	ad Test				
IMP-1272	Impact - Review & Approve - Micro Pile Load Test	0	07-Jan-20 A	10-Jan-20 A	npact - Review & Approve - Micro Pile L	oad Test				
IMP-1342	Impact - Perform - Micro Pile Load Test	0	13-Jan-20 A	16-Jan-20 A	mpact - Perform - Micro Pile Load Test					
IMP-1352	Impact - Review & Accept - Micro Pile Load Test	0	17-Jan-20 A	17-Jan-20 A	mpact - Review & Accept - Micro Pile L	pad Test	1 1			
17.2 Pile Cap	Conflict with Existing Granite Retaining Wall						1			
IMP-1312	Impact - Discover 17.2 Pile Cap Conflict with Existing Granite Retaining Wal	0	14-Dec-19A	14-Dec-19 A	t - Discover 17.2 Pile Cap Conflict with	Existing Granite Retaining Wal				
IMP-1322	Impact - Re-Design 17.2 Pile Cap	0			ct - Re-Design 17.2 Pile Cap		1 1 1			
IMP-1332	Impact - Procure Revised Piles	0			npact - Procure Revised Piles					
MRTA Platfo	m Lighting Removal									
IMP-1292	Impact - Request MBTA to Assist with Platform Light Removal	0	06-Dec-19A	09- Jan-20 A	npact - Request MBTA to Assist with Pla	tform Light Removal				
IMP-1292	Impact - Request MBTA to Assist with Platform	0	00-D60-19 K		npact - MBTA Requests Temp Light at F	· - - <u>-</u>	, 		·····	
IMP-1372	Impact - MBTARequests Temp Light at Platform	0	10-Jan-20 A		mpact - Prepare & Submit Temp Lightin	I I			1	
IMP-1392	Impact - Prepare & Submit Temp Lighting Plan at Platform	0			Impact - MBTA Approves Temp Lighting		1 1 1	1		1
IMP-1392 IMP-1402	Impact - Install Temp Lights at Platform	0			Impact - Install Temp Lights at Platform		1 1 1			1
IMP-1402 IMP-1302	Impact - Install Temp Lights at Platform Impact - Disconnect & Remove MBTA Platform Lights	0			Impact - Disconnect & Remove MBTA					
MBTA Walkw		U	10-Jan-20A	20-Jan-20 A			 			
	ay Delays									
_					1		1			
_	ng Level of Effort Remaining Work		Page 1 of	29	TASK filter: Uncompleted Activitie	s Two Months Prior.				
_			Page 1 of	29	TASK filter: Uncompleted Activitie	s Two Months Prior. © Oracle Corporati	on		SKANSKA	



· · ·	Project A - 10Feb20 R1 Schedule Update - 1318014-CR - B26				iled Schedule			Data Date: 10-F	eb-20 / Run Date: 09-Ju	ui-20 09:05
y ID Ad	ctivity Name	Remaining Duration	Start	Finish	2020		.021		2022	
		Duration				Oct N D Jan F Mar Apr M Ju		D Jan F Ma		S Oct
IMP-1362 Im	npact - Address Accessibility Issues & Open West Walkway	0	05-Dec-19 A	01-Feb-20 A	Impact - Address Accessibility Issues				· [· [· [· [· · · [· · · ·]· · · ·]·	
	nic Soil at North Area				·····, ·····, ·····, ·····, ·····,					
		0	25 Jan 20 A	26 Jan 20 A	Impact Weather Impact Start of OCE	Dila Cana		ĺ		
	npact - Weather Impact Start of OCS Pile Caps	0			Impact - Weather Impact Start of OCS					
	npact - Unforeseen Organic Soil at North Area	5	30-Jan-20 A		Impact - Unforeseen Organic Soil a					
IMP-1422 Im	npact - Install Added Mini Piles at North Area (Week end Work)	2	15-Feb-20	16-Feb-20	I Impact - Install Added Mini Piles at	North Area (Week end Work)				
IMP-1432 Im	npact - Detail / Prep Mini Piles at North Area	2	18-Feb-20	19-Feb-20	I Impact - Detail / Prep Mini Piles at	North Area		1		
FB-016 Curtain Wa	all Design Revision									
	npact - FB-016 Curtain Wall Design Revision	5	13-Jan-20 A	14-Feb-20	Impact - FB-016 Curtain Wall Desig	an Revision				
/IBTA Work			10 0011 2071							
Procurement										
MBTA Design Subr	mission									
State or Local Per	rmits									
MBTA Platform								I I		
	btain State or Local Permits for MBTA Platform Work	27	02-Jul-19 A	18-Mar-20	Obtain State or Local Permits	for MBTA Platform Work				1
Procurement			02 001 1071				- <mark> </mark>	l	- <mark>1</mark>	
	t - CWP - OCS & Power (MBTA-1150)	-								
	ubmit, Approve, Fab & Deliver - MBTA Work (Summary)	0	01-Mar-19 A	20-Dec-19 A	nit, Approve, Fab & Deliver - MBTA Wo	rk (Summary)				
Enabling & OCS P	Procurement							I		
Temporary Powe	er and Re-Feed Plan									
BLHA-720 Pr	Prepare & Submit - Temporary Power and Re-Feed Plan_R0	0	10-Jun-19A	12-Dec-19A	re & Submit - Temporary Power and Re	Feed Plan R0	·			
	Review & Approve - Temporary Power and Re-Feed Plan_R0	1	13-Dec-19 A		Review & Approve - Temporary Pow	—				
	Install Temporary Power & Refeed WP#21 (Weekend Work)	2	15-Feb-20	16-Feb-20	I Install Temporary Power & Refeed					
	versource De-energizes OH service to Pole	5	18-Feb-20	24-Feb-20	Eversource De-energizes OH se					
New OCS Found			1					 		
BLHA-0190 Pr	Prepare & Submit - Revised OCS Rebar	0	17-Dec-19 A	08-Jan-20 A	epare & Submit - Revised OCS Rebar					
BLHA-0200 Re	Review & Approve - Revised OCS Rebar	0	09-Jan-20 A	30-Jan-20 A	Review & Approve - Revised OCS Re	ebar		1		
BLHA-0310 Fa	ab & Deliver - Revised OCS Rebar	0	24-Jan-20 A	31-Jan-20 A	Fab & Deliver - Revised OCS Rebar					
OCS Supports &	Brackets		,					I I		
	ab & Deliver - OCS Supports & Brackets	0	15-Nov-19 A	20-Dec-19 A	& Deliver - OCS Supports & Brackets					
New OCS Suppo	••	0		20 800 10/1						
			47 Dec 40 4	00 1 00 4		-		1		
	Prepare & Submit - Revised OCS Supports	0			epare & Submit - Revised OCS Suppo					
	Review & Approve - Revised OCS Supports	0			Review & Approve - Revised OCS Supp					
BLHA-1090 Fa	ab & Deliver - Revised OCS Supports	6	16-Jan-20 A	18-Feb-20	Fab & Deliver - Revised OCS Sup	ports				
OCS Cables								I		i i
BLHA-0120 Fa	ab & Deliver - OCS Cables	5	30-Jul-19 A	14-Feb-20	Fab & Deliver - OCS Cables					
Bid and Award ME	BTA Platform		·					1		
MBTA Platform										
	repare and Submit RTA - MBTA Platform	0	02 Dec 10 4	12 Dec 10 A	re and Submit RTA - MBTA Platform			1		
		0								
	pprove RTA - MBTA Platform	0			ve RTA- MBTA Platform					
BLHA-0210 Su	ubmitted to TOB for Vote - MBTA Platform (Assume Meeting on December 19, 2019)	0	17-Dec-19 A	18-Dec-19 A	itted to TOB for Vote - MBTA Platform	Assume Meeting on December 19, 2019				
CWP MBTA Platfo	form							1		
MBTA-1280 Su	ubmit, Approve, Fab & Deliver - MBTA Platform	176	07-Nov-19A	20-Oct-20		Submit, Approve, Fab & Deliver - ME	TA Platform			
	Prepare & Submit - CWP MBTA Platform	5	27-Dec-19 A		Prepare & Submit - CWP MBTA P					
	Review & Approve - CWP MBTA Platform	45	25-Feb-20	28-Apr-20	Review & Approve - CV					
MBTA Platform			201 00-20	20 10-20					- <mark>1</mark>	
	IBTA Platform - Issue Subcontracts for Procurement	Α	10 Dec 10 4	13-Feb-20	MBTA Platform - Issue Subcontract	to for Producement		l l		
		4	19-Dec-19 A	13-Feb-20						
Tactile Warning S								1		
	Prepare & Submit - Tactile Warning Strip_R0	21	14-Feb-20	16-Mar-20	Prepare & Submit - Tactile Wa					
BLHA-880 R	Review & Approve - Tactile Warning Strip_R0	20	17-Mar-20	13-Apr-20	Review & Approve - Tactil	le Warning Strip_R0				
BLHA-890 Pr	Prepare & Submit - Tactile Warning Strip_R1	5	14-Apr-20	21-Apr-20	Prepare & Submit - Tacti	ile Warning Strip_R1				
	Review & Approve - Tactile Warning Strip_R1	20	22-Apr-20	19-May-20	Review & Approve -			l l		
	ab & Deliver - Tac tile Warning Strip	20	20-May-20	17-Jun-20	Fab & Deliver					
Helical Piles		20	20-1viay-20	11-001-20						
	Deview & Approve Helical Dile Desiza DO	0	00 Dec 40 4	24 Dec 40 4				1		
BLHA-0230 Re	Review & Approve - Helical Pile Design_R0	0	09-Dec-19 A	24-Dec-19A	ew & Approve - Helical Pile Design_R0					1
Remaining Lev	vel of Effort Remaining Work		Dect 0	: 20	TACK filters Lineares Later 1 Arth 10	a Two Monthe Drier		,		
•	-		Page 2 of	29	TASK filter: Uncompleted Activitie		.			
Actual Level of	f Effort Critical Remaining Work					© Oracle Corpora	ion	SKA	NSKA	
Actual Work	♦ Milestone			Page	e 45 of 377					

)	I - Project A - 10Feb20 R1 Schedule Update - 1318014-CR - B26 Activity Name	Remaining	Start	Deta Finish	
		Duration	Start	1111511	2020
					F [Mar[Apr[M [Jun] Jul] A [S [Oct[N D]Jan[F [Mar[Apr[]
BLHA-0232	Prepare & Submit - Helical Pile Design_R1	0	26-Dec-19 A	21-Jan-20 A	Prepare & Submit - Helical Pile Design_R1
BLHA-0234	Review & Approve - Helical Pile Design_R1	0	22-Jan-20 A	05-Feb-20 A	Review & Approve - Helical Pile Design_R1
BLHA-0240	Fab & Deliver - Helical Piles	20	24-Jun-20	22-Jul-20	Fab & Deliver - Helical Piles
Helical Pile Te	st Program		-	-	
BLHA-1040	Prepare & Submit - Helical Pile Test Program_R0	19	19-Dec-19 A	06-Mar-20	Prepare & Submit - Helical Pile Test Program R0
BLHA-1030	Review & Approve - Helical Pile Test Program_R0	20	09-Mar-20	03-Apr-20	Review & Approve - Helical Pile Test Program_R0
BLHA-1010	Prepare & Submit - Helical Pile Test Program_R1	5	06-Apr-20	10-Apr-20	Prepare & Submit - Helical Pile Test Program_R1
BLHA-1020	Review & Approve - Helical Pile Test Program_R1	20	13-Apr-20	11-May-20	Review & Approve - Helical Pile Test Program_R1
BLHA-1050	Fab & Deliver - Helical Pile Test Pile & Equipment	20	12-May-20	09-Jun-20	Fab & Deliver - Helical Pile Test Pile & Equipment
BLHA-1060	Complete Test Pile and Reports	10	10-Jun-20	23-Jun-20	Complete Test Pile and Reports
Canopy Struc	· ·				
BLHA-0250	Prepare & Submit - Canopy Structures_R0	21	14-Feb-20	16-Mar-20	Prepare & Submit - Canopy Structures_R0
BLHA-0250	Review & Approve - Canopy Structures_R0	20	17-Mar-20	13-Apr-20	Review & Approve - Canopy Structures_R0
BLHA-0262	Prepare & Submit - Canopy Structures_R1	5	14-Apr-20	21-Apr-20	Prepare & Submit - Canopy Structures_R1
BLHA-0264	Review & Approve - Canopy Structures_R1	20	22-Apr-20	19-May-20	Review & Approve - Canopy Structures_R1
BLHA-0270	Fab & Deliver - Canopy Structures	85	20-May-20	18-Sep-20	Fab & Deliver Canopy Structures
Misc Metal Ra			1		
BLHA-0280	Prepare & Submit - Misc Metal Railings_R0	21	14-Feb-20	16-Mar-20	Prepare & Submit - Misc Metal Railings_R0
BLHA-0290	Review & Approve - Misc Metal Railings_R0	20	17-Mar-20	13-Apr-20	Review & Approve - Misc Metal Railings_R0
BLHA-0292	Prepare & Submit - Misc Metal Railings_R1	5	14-Apr-20	21-Apr-20	Prepare & Submit - Misc Metal Railings_R1
BLHA-0294	Review & Approve - Misc Metal Railings_R1	20	22-Apr-20	19-May-20	Review & Approve - Misc Metal Railings_R1
BLHA-0300	Fab & Deliver - Misc Metal Railings	65	20-May-20	20-Aug-20	Fab & Deliver - Misc Metal Railings
Security Equi	pment				
BLHA-0340	Prepare & Submit - Security Equipment_R0	21	14-Feb-20	16-Mar-20	Prepare & Submit - Security Equipment_R0
BLHA-0350	Review & Approve - Security Equipment_R0	20	17-Mar-20	13-Apr-20	Review & Approve - Security Equipment_R0
BLHA-0352	Prepare & Submit - Security Equipment_R1	5	14-Apr-20	21-Apr-20	Prepare & Submit - Security Equipment_R1
BLHA-0354	Review & Approve - Security Equipment_R1	20	22-Apr-20	19-May-20	Review & Approve - Security Equipment_R1
BLHA-0360	Fab & Deliver - Security Equipment	65	20-May-20	20-Aug-20	Fab & Deliver - Security Equipment
PA/VMS Equip			20 may 20	20 / kug 20	
BLHA-0370	Prepare & Submit - PA/VMS Equipment_R0	21	14-Feb-20	16-Mar-20	Prepare & Submit - PA/VMS Equipment_R0
BLHA-0380	Review & Approve - PA/VMS Equipment_R0	20	17-Mar-20	13-Apr-20	Review & Approve - PA/VMS Equipment_R0
BLHA-0382	Prepare & Submit - PA/VMS Equipment_R1	5	14-Apr-20	21-Apr-20	Prepare & Submit - PA/VMS Equipment_R1
			22-Apr-20	· ·	
BLHA-0384	Review & Approve - PA/VMS Equipment_R1	20		19-May-20	Review & Approve - PA/VMS Equipment_R1
BLHA-0390	Fab & Deliver - PA/VMS Equipment	85	20-May-20	18-Sep-20	Fab & Deliver - PA/VMS Equipment
Slab Reinforc					· · · · · · · · · · · · · · · · · · ·
BLHA-0400	Prepare & Submit - Slab Reinforcement_R0	21	14-Feb-20	16-Mar-20	Prepare & Submit - Slab Reinforcement_R0
BLHA-0410	Review & Approve - Slab Reinforcement_R0	20	17-Mar-20	13-Apr-20	Review & Approve - Slab Reinforcement_R0
BLHA-0412	Prepare & Submit - Slab Reinforcement_R1	5	14-Apr-20	21-Apr-20	Prepare & Submit - Slab Reinforcement_R1
BLHA-0414	Review & Approve - Slab Reinforcement_R1	20	22-Apr-20	19-May-20	Review & Approve - Slab Reinforcement_R1
BLHA-0420	Fab & Deliver - Slab Reinforcement	45	20-May-20	23-Jul-20	Fab & Deliver - Slab Reinforcement
Lighting Equi	pment				
BLHA-0430	Prepare & Submit - Lighting Equipment_R0	21	14-Feb-20	16-Mar-20	Prepare & Submit - Lighting Equipment_R0
BLHA-0440	Review & Approve - Lighting Equipment_R0	20	17-Mar-20	13-Apr-20	Review & Approve - Lighting Equipment_R0
BLHA-0442	Prepare & Submit - Lighting Equipment_R1	5	14-Apr-20	21-Apr-20	Prepare & Submit - Lighting Equipment_R1
BLHA-0444	Review & Approve - Lighting Equipment_R1	20	22-Apr-20	19-May-20	Review & Approve - Lighting Equipment_R1
BLHA-0450	Fab & Deliver - Lighting Equipment	65	20-May-20	20-Aug-20	Fab & Deliver - Lighting Equipment
	Ibber Rail Crossing				
BLHA-920	Prepare & Submit - Permanent Rubber Rail Crossing_R0	21	14-Feb-20	16-Mar-20	Prepare & Submit - Permanent Rubber Rail Crossing_R0
BLHA-930	Review & Approve - Permanent Rubber Rail Crossing_R0	20	17-Mar-20	13-Apr-20	Review & Approve - Permanent Rubber Rail Crossing_R0
BLHA-950	Prepare & Submit - Permanent Rubber Rail Crossing_R1	5			Review & Approve - Permanent Rubbel Rail Crossing_R0
			14-Apr-20	21-Apr-20	• • • • • • • • • • • • • • • • • • • •
BLHA-960	Review & Approve - Permanent Rubber Rail Crossing_R1	20	22-Apr-20	19-May-20	Review & Approve - Permanent Rubber Rail Crossing
BLHA-940	Fab & Deliver - Permanent Rubber Rail Crossing	22	20-May-20	19-Jun-20	Fab & Deliver - Permanent Rubber Rail Crossing
Wayfinding Si		i	i .		
BLHA-0460	Prepare & Submit - Wayfinding Signage_R0	21	14-Feb-20	16-Mar-20	Prepare & Submit - Wayfinding Signage_R0
BLHA-0470	Review & Approve - Wayfinding Signage_R0	20	17-Mar-20	13-Apr-20	Review & Approve - Wayfinding Signage_R0
Remaining	Level of Effort Remaining Work		Page 3 of	f 29	TASK filter: Uncompleted Activities Two Months Prior.
			i age 5 0		
 Actual Leve 	el of Effort Critical Remaining Work				© Oracle Co

Data Date: 10-Feb-20 / Run Date: 09-Jul-20 09:05 21 2022 Jul A S Oct N D Jan F Mar Apr M Jun Jul Aug S Oct N Dec - - - - - - - - -----------



	Activity Nome	Domesiste	Chart	Cinia I.		
/ ID	Activity Name	Remaining Duration	Start	Finish	2020	202
		2 01 01.011			F [Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr	
BLHA-0610	Prepare & Submit - Wayfinding Signage_R1	5	14-Apr-20	21-Apr-20	Prepare & Submit - Wayfinding Signage_R1	
BLHA-0620	Review & Approve - Wayfinding Signage_R1	20	22-Apr-20	19-May-20	Review & Approve - Wayfinding Signage_R1	
BLHA-0760	Wayfinding Signage Mock-up	21	20-May-20	18-Jun-20	Wayfinding Signage Mock-up	1
BLHA-0480	Fab & Deliver - Wayfinding Signage	85	19-Jun-20	20-Oct-20	Fab & Deliver - Wayfinding S	gnage
onstruction						1
/IBTA -1190	Perform Phase 1 Work - Close Limits of Existing Platform/Temp Platform/Crossings/Reloca	29	25-Sep-19 A	20-Mar-20	Perform Phase 1 Work - Close Limits of Existing Platform/Tem) Platform/(
MBTA -1200	Perform Phase 2 Work - Modify OCS System (Weekend & Night Shutdowns)	24	18-Jan-20 A	13-Mar-20	Perform Phase 2 Work - Modify OCS System (Weekend & Nigh	
	Limits of Existing Platform/Temp Platform/Crossings/Relocation of Furnishings					
General						
BLHS-0010	Phase 1 - Install Service Duct Bank From Street and Complete Temp Work in School Lot	0	26-Sep-19 A	17-Dec-19A	e 1 - Install Service Duct Bank From Street and Complete Temp Work in	SchoolLot
BLHS-0030	Phase 1 - Install Buried Utilities in MBTA Parking Lot	0	26-Sep-19 A		hase 1 - Install Buried Utilities in MBTA Parking Lot	
BLHS-0020	Phase 1 - Install Electrical Service from Street (BY EVERSOURCE)	3	17-Dec-19 A		Phase 1 - Install Electrical Service from Street (BY EVERSOURCE)	
BLHS-0040	Phase 1 - Cut-Over Temp. Fare Vending	0	11-Jan-20 A		hase 1 - Cut-Over Temp. Fare Vending	
BLHS-0040		1	05-Feb-20 A	10-Feb-20		
	Phase 1 - Complete Duct Banks beneath Existing Walkway				Phase 1 - Complete Duct Banks beneath Existing Walkway	
BLHS-1010	Phase 1 - Refeed Existing Platform Systems	34	05-Feb-20 A	27-Mar-20	Phase 1 - Refeed Existing Platform Systems	
BLHS-3210	Phase 1 - Pave Platform & Center Walkway	1	10-Feb-20	10-Feb-20	Phase 1 - Pave Platform & Center Walkway	
BLHS-3220	Phase 1 - MBTA Approves Platform & Center Walk way	5	11-Feb-20	18-Feb-20	Phase 1 - MBTA Approves Platform & Center Walk way	
BLHS-3230	Phase 1 - Close East Walkway	1	19-Feb-20	19-Feb-20	I Phase 1 - Close East Walkway	
BLHS-0130	Phase 1 - Remove Existing Pole & Wiring (Eversource)	10	25-Feb-20	09-Mar-20	Phase 1 - Remove Existing Pole & Wiring (Εγersource)	
BLHS-0120	Phase 1 - Install Buried Ductbanks below New Building	10	03-Mar-20	16-Mar-20	Phase 1 - Install Buried Ductbanks below New Building	
BLHS-0065	Install Hi-rail Temporary Gate and Fencing	5	16-Mar-20*	20-Mar-20	Install Hi-rail Temporary Gate and Fencing	
BLHS-3240	Phase 1 - Pull Wire at Buried Ductbanks below New Building	5	17-Mar-20	23-Mar-20	Phase 1 - Pull Wire at Buried Ductbanks below New Building	
BLHS-0050	Phase 1 - Cut-Over Bungalows (Weekend)	2	28-Mar-20	29-Mar-20	Phase 1 - Cut-Over Bungalows (Weekend)	
BLHS-1020	Phase 1 - Demo Asphalt Platforms & Furnishings	5	30-Mar-20	03-Apr-20	Phase 1 - Demo Asphalt Platforms & Furhishings	
hase 2 - Modif	y OCS System (Weekend & Night Shutdowns)			, . .		
Construction						
BLHS-0110	Phase 2 - Install Micro Piles (Weekend 1)	0	18-Jan-20 A	19-Jan-20 A	Phase 2 - Install Micro Piles (Weekend 1)	
BLHS-3170	Phase 2 - Install Micro Piles (Weekend 2)	0	25-Jan-20 A	26-Jan-20 A	Phase 2 - Install Micro Piles (Weekend 2)	
		-			Phase 2 - Install CIP Concrete Caps & Pedestals	
BLHS-3180	Phase 2 - Install CIP Concrete Caps & Pedestals	5	03-Feb-20 A	20-Feb-20		
BLHS-3190	Phase 2 - Install OCS Supports (Weekend 1)	3	21-Feb-20	23-Feb-20	Phase 2 - Install OCS Supports (Weekend 1)	
BLHS-0100	MBTA Performs Interim Inspection of OCS/Enabling	0		23-Feb-20	◆ MBTA Performs Interim Inspection of OCS/Enabling	
BLHS-0080	Phase 2 - Relocate Existing OCS Cable Bundles (Weekend 2)	3	28-Feb-20	01-Mar-20	Phase 2 - Relocate Existing OCS Cable Bundles (Weekend 2)	
BLHS-3200	Phase 2 - Relocate Existing OCS Contact Wires (Weekend 3)	3	06-Mar-20	08-Mar-20	Phase 2 - Relocate Existing OCS Contact Wires (Weekend 3)	
BLHS-0090	Phase 2 - Remove Existing Portals & Foundations (Weekend 4)	3	13-Mar-20	15-Mar-20	Phase 2 - Remove Existing Portals & Foundations (Weekend 4	
Phase 3 - Build	New Platform East and Temporary Extension					
Construction						
BLHS-0075	Completion BHS Over-Build	0	26-May-20*		Completion BHS Over-Build	
BLHS-1030	Phase 3 - De-Energize/Remove Existing MBTA Systems	10	26-May-20*	08-Jun-20	Phase 3 - De-Energize/Remove Existing MBTA Sy	stems
BLHS-1060	Phase 3 - Demo Platform Furnishings	3	09-Jun-20	11-Jun-20	Phase 3 - Demo Platform Furmishings	
BLHS-1040	Phase 3 - Excavate and Rough Grade for Piles	5	12-Jun-20	18-Jun-20	Phase 3 - Excavate and Rough Grade for Piles	
BLHS-1045	Phase 3 - Install Helical Piles	20	23-Jul-20	19-Aug-20	Phase 3 - Install Helical Piles	
BLHS-1070	Phase 3 - Install CIP Knee Walls	10	20-Aug-20	02-Sep-20	Phase 3 - Install CIP Knee Walls	
BLHS-1070	Phase 3 - Backfill and Compact Platform Slab Base				Phase 3 - Backfill and Compact P	otform Cla
	•	10	03-Sep-20	17-Sep-20		
BLHS-1090	Phase 3 - Form/Reinforce CIP Platform Slabs w/Haunch	25	18-Sep-20	23-Oct-20	Phase 3 - Form/Reinforce C	
BLHS-1091	Phase 3 - Place CIP Platform Slabs w/Haunch (Primary) - Weekend	2	24-Oct-20	25-Oct-20	Phase 3 - Place CIP Platfor	
BLHS-1092	Phase 3 - Place CIP Platform Slabs w/Haunch (Secondary) - Weekend	2	31-Oct-20	01-Nov-20	Phase 3 - Place CIP Platfo	
BLHS-1130	Phase 3 - Pave Temporary Ramps at West Pedestrian Crossing	2	02-Nov-20	03-Nov-20	Phase β - Pave Temporar	
BLHS-1115	Phase 3 - Install Rubber Rail Tiles	5	02-Nov-20	06-Nov-20	Phase 3 - Install Rubber F	ail Tiles
BLHS-1100	Phase 3 - Install CIP Egress Ramp on Inbound Platform	10	02-Nov-20	16-Nov-20	Phase 3 - Install CIP Eg	ess Ramp
BLHS-1095	Phase 3 - F/R/P Light Pole and Sign Pedestals	15	02-Nov-20	23-Nov-20	Phase 3 - F/R/P Light F	ole and Sig
BLHS-1050	Phase 3 - Pave Platform Extension - Weekends	2	07-Nov-20	08-Nov-20	Phase 3 - Pave Platform	xtension -
BLHS-1120	Phase 3 - Install Tactile Warning Panels	15	09-Nov-20	02-Dec-20	Phase 3 - Install Tacti	1
BLHS-1105	Phase 3 - Establish Egress Path Through 111 Cypress Site (By Others)	5	17-Nov-20	23-Nov-20	Phase 3 - Establish Eg	1-
BLHS-1180	Phase 3 - Install Railing - South Egress Ramp	5	17-Nov-20	23-Nov-20	Phase 3 - Install Railing	
22110 1100		0	11 1107-20	201107-20		
-	Level of Effort Remaining Work		Page 4 of	29	TASK filter: Uncompleted Activities Two Months Prior.	
						·ornoration
Actual Leve	el of Effort Critical Remaining Work				© Oracle (orporation

Data Date: 10-Feb-20 / Run Date: 09-Jul-20 09:05 21 2022 Jul A S Oct N D Jan F Mar Apr M Jun Jul Aug S Oct N Dec h/Crossings/Relocate Fare Ticketing/Etc. vns) L - - - - - - - - - -- - - - - - - - - - - -. -----. - - - - - - - -ab Base n Slabs w/Haunch /Haunch (Primary) - Weekend w/Haunch (Secondary) - Weekend t West Pedestrian Crossing on Inbound Platform ign Pedestals Weekends g Panels Through 111 Cypress Site (By Others) gress Ramp



y ID	h School - Project A - 10Feb20 R1 Schedule Update - 1318014-CR - B26				ed Schedule	Data Date: 10-Feb-20 / Run Date: 09-Jul-2				
	Activity Name	Remaining Duration			2020	2021	2022			
		Duration				Jan F Mar Apr M Jun Jul A S Oct N D				
BLHS-1200	Phase 3 - Install Phase 4 Temporary Signage	10	24-Nov-20	09-Dec-20		ase 3 - Install Phase 4 Temporary Signage				
BLHS-1140	Phase 3 - Install Platform Furnishings	40	24-Nov-20	25-Jan-21		Phase 3 - Install Platform Furnishings				
BLHS-1170	Phase 3 - Install VMS, PA, Security System	40	24-Nov-20	25-Jan-21		Phase 3 - Install VMS, PA, Security System				
BLHS-1110	Phase 3 - Install Phase 3 Light Poles - Weekends	2	28-Nov-20	29-Nov-20	I Pha	se 3 - Install Phase 3 Light Poles - Weekends				
BLHS-1190	Phase 3 - Establish Pedestrian Access for Phase 3 Platform	5	19-Jan-21	25-Jan-21		Phase 3 - Establish Pedestrian Access for Phase	3 Platform			
BLHS-1205	Phase 3 - Testing, Commissioning and Inspections of Station Systems	10	26-Jan-21	08-Feb-21		Phase 3 - Testing, Commissioning and Inspection	ons of Station Systems			
BLHS-1210	Phase 3 - Platform Put in Service	1	09-Feb-21	09-Feb-21		Phase 3 - Platform Put in Service				
Phase 4 - Demo	Existing West Platform & Build New Platform West									
Demolition	, i i i i i i i i i i i i i i i i i i i									
BLHS-2000	Phase 4 - De-Energize/Remove Existing MBTA Systems	10	09-Feb-21	23-Feb-21		Phase 4 - De-Energize/Remove Existing MBT	A Svstems			
BLHS-2010	Phase 4 - Demo Platform Furnishings	3	24-Feb-21	26-Feb-21		Phase 4 - Demo Platform Furnishings				
Construction										
Station				_						
BLHS-2015	Phase 4 - Excavate and Rough Grade for Piles	5	01-Mar-21	05-Mar-21		Phase 4 - Excavate and Rough Grade for P	iles			
BLHS-2010	Phase 4 - Install Helical Piles	20	08-Mar-21	02-Apr-21		Phase 4 - Install Helical Piles				
				· ·		Phase 4 - Install Helical Piles	form Slob Passa			
BLHS-2050	Phase 4 - Backfill and Compact Platform Slab Base	15	05-Apr-21	26-Apr-21						
BLHS-2060	Phase 4 - Form/Reinforce CIP Platform Slabs w/Haunch	25	27-Apr-21	01-Jun-21		Phase 4 - Form/Reinforce CIF				
BLHS-2080	Phase 4 - Form/Reinforce CIP Ramps	10	02-Jun-21	15-Jun-21		Phase 4 - Form/Reinforce (
BLHS-2062	Phase 4 - Place CIP Platform Slabs w/Haunch (Primary) - Weekend	2	05-Jun-21	06-Jun-21			Slabs w/Haunch (Primary) - Weekend			
BLHS-2064	Phase 4 - Place CIP Platform Slabs w/Haunch (Secondary) - Weekend	2	12-Jun-21	13-Jun-21			n Slabs w/Haunch (Secondary) - Weekend			
BLHS-2066	Phase 4 - F/R/P Light Pole and Sign Pedestals	5	14-Jun-21	18-Jun-21	¦¦¦¦¦	Phase 4 - F/R/P Light Pole				
BLHS-2110	Phase 4 - Install Tactile Warning Panels	15	14-Jun-21	05-Jul-21		Phase 4 - Install Tactile \				
BLHS-2082	Phase 4 - Place CIP Ramps - Weekend	2	16-Jun-21	17-Jun-21		Phase 4 - Place CIP Ramp				
BLHS-2090	Phase 4 - Install Rubber Rail Tiles	5	16-Jun-21	22-Jun-21		Phase 4 - Install Rubber R				
BLHS-2085	Phase 4 - Install Permanent Grade Crossing - Weekend	2	18-Jun-21	21-Jun-21		Phase 4 - Install Permaner	nt Grade Crossing - Weekend			
BLHS-2070	Phase 4 - Install Stone Landscaping Beyond Platform	5	18-Jun-21	24-Jun-21		Phase 4 - Install Stone Lar	ndscaping Beyond Platform			
BLHS-2120	Phase 4 - Canopies - Weekend	6	19-Jun-21	04-Jul-21		Phase 4 - Canopies - Wo	eekend			
BLHS-2100	Phase 4 - Install Phase 4 Light Poles	2	21-Jun-21	22-Jun-21		Phase 4 - Install Phase 4 L	ight Poles			
BLHS-2180	Phase 4 - Install Permanent Wayfinding Signage	10	21-Jun-21	05-Jul-21		🔲 Phase 4 - Install Perman	ient Wayfinding Signage			
BLHS-2160	Phase 4 - Install VMS, PA, AFC, Security System	35	23-Jun-21	11-Aug-21			MS, PA, AFC, Security System			
BLHS-2125	Phase 4 - Canopy Roofs - Weekends	4	10-Jul-21	18-Jul-21		Phase 4 - Canopy Roc				
BLHS-2230	Phase 4 - Install VMS, PA, AFC, Security System on Canopy	3	19-Jul-21	21-Jul-21			PA, AFC, Security System on Canopy			
BLHS-2130	Phase 4 - Install Platform Furnishings	10	19-Jul-21	30-Jul-21		Phase 4 - Install Plat				
	Phase 4 - Testing, Commissioning and Inspections of Station Systems	10	12-Aug-21				g, Commissioning and Inspections of Station Systems			
	Phase 4 - Platform Put Into Service	1	26-Aug-21	-			m Put Into Service			
	Temp. Extension, Connect East & West Platforms		20-7/0g-21	20-Aug-21						
Demolition	remp. Extension, connect Last & West Flatforms					· · · · · · · · · · · · · · · · · · ·				
BLHS-3000	Phase 5 - Setup Stage 5	1	27 Aug 21	27-Aug-21		Phase 5 - Setup	Stage 5			
BLHS-3000	Phase 5 - Demo Temp Asphalt / Ramps / Crossings - Weekends	6	27-Aug-21				mo Temp Asphalt / Ramps / Crossings - Weekends			
	Phase 5 - Demo Temp Asphalt / Ramps / Crossings - Weekends	0	28-Aug-21	12-Sep-21		mase 5 - Del	mp temp Asphait / Ramps / Crossings - weekends			
Construction										
Station										
BLHS-3020	Phase 5 - Excavate & Expose Piles	5	30-Aug-21	03-Sep-21			avate & Expose Piles			
BLHS-3090	Phase 5 - Install Stone Landscaping Beyond Platform - Weekends	2	04-Sep-21	05-Sep-21			all Stone Landscaping Beyond Platform - Weekends			
BLHS-3030	Phase 5 - Install CIP Knee Walls	10	07-Sep-21	20-Sep-21			stall CIP Knee Walls			
BLHS-3040	Phase 5 - Backfill and Compact Platform Slab Base - Weekends	2	21-Sep-21	22-Sep-21			ackfill and Compact Platform Slab Base - Weekends			
BLHS-3050	Phase 5 - Form and Reinforce CIP Platform Slabs w/Haunch - Weekends (OD: 10 to 4)	4	25-Sep-21	03-Oct-21		Phase 5 -	Form and Reinforce CIP Platform Slabs w/Haunch - V			
BLHS-3060	Phase 5 - Place CIP Platform - Weekends	2	09-Oct-21	10-Oct-21		Phase 5	- Place CIP Platform - Weekends			
BLHS-3080	Phase 5 - Install Tactile Warning Panels	5	12-Oct-21	18-Oct-21		Phase 5	- Install Tactile Warning Panels			
BLHS-2170	Phase 5 - Install Railing - Outbound Knee Wall	12	12-Oct-21	27-Oct-21			5 - Install Railing - Outbound Knee Wall			
BLHS-3085	Phase 5 - Install Rubber Rail Tiles	5	19-Oct-21	25-Oct-21			5- Install Rubber Rail Tiles			
	Phase 5 - Entire Station Open	1	28-Oct-21	28-Oct-21			5 - Entire Station Open			
	truct West Parking Lot Following Demob									
Parking Lot	and there in any set of one any set of									
	Phase 6 Demo Evisting Parking Lat	10	20 Oct 21*	12 Nov 21			se 6 Demo Evisting Parking Lat			
	Phase 6 - Demo Existing Parking Lot	10	29-Oct-21*	12-Nov-21			se 6 - Demo Existing Parking Lot			
BLHS-2190	Phase 6 - Relocate BHS Dumpster & Electrical	10	15-Nov-21	30-Nov-21			Phase 6 - Relocate BHS Dumpster & Electrical			
BLHS-2190 BLHS-2200						1				
BLHS-2200	Level of Effort Remaining Work		Page 5 of	29	TASK filter: Uncompleted Activities Two Months	Prior.				
BLHS-2200	-		Page 5 of	29	TASK filter: Uncompleted Activities Two Months	Prior. © Oracle Corporation	SKANSKA			

	ool - Project A - 10Feb20 R1 Schedule Update - 1318014-CR - B26 Activity Name	Remaining	Start	Finish	illed Schedule				Dat	a Date: 10-Feb-20 / Run	Jaie. 09-Jui-20 09:00
U	Activity Name	Duration	Sidil	Fillisti	20			2021			022
				ļ	F Mar Apr M Jun	JulAS	Oct N D	Jan F Mar Apr M Jun Jul A			
BLHS-2220	Phase 6 - Adjust DMH & Replace Granite Curb	10	15-Nov-21	30-Nov-21				·		ase 6 - Adjust DMH & Repla	
BLHS-2240	Phase 6 - Grade / Pave / Paint Parking Lot	20	01-Dec-21	29-Dec-21						Phase 6 - Grade / Pave /	Paint Parking Lot
unchlist / Tes	sting & Balancing / Commissioning										
INSP-1040	MBTA Interim Completion Date	0		28-Oct-21*					MBTA In	terim Completion Date	
INSP-1050	MBTA Interim Final Completion Date	0		29-Dec-21*					•	MBTA Interim Final Comp	letion Date
rmitting											
uilding Permi	it										
ER-230	Town Building Department Reviews & Issues - Building Permit	0	04 Nov 19 A	13 Jan 20 A	own Building Departmer	t Poviows &	lecuce Buildir	nt Permit			
		0	04-N0V-19A	13-Jan-20 A		it inteviews a	 			1	
ocurement	lt										
esign Assist											
recast Design	n Assist										
PRO-6940	Review & Approve Shop Drawings - Precast (Round 2)	0	12-Dec-19A	02-Jan-20 A	view & Approve Shop D	rawings - Pre	edast (Round 2	2)			- +
PRO-1640	Release for Fabrication - Precast	0			lease for Fabrication - F	-	ì				
PRO-1650	Fab & Available for Delivery - Precast	19	03-Jan-20 A		Fab & Available 1		Precast				
urtain Wall De				1							
PRO-1420	Review & Approve Shop Drawings - Curtain Wall (Round 1)	0	09-Oct-19A	13-Jan-20 A	eview & Approve Shop	Drawings - C	: urtain Wall (Ro	ound 1)			
RO-1430	Prepare & Submit Shop Drawings - Curtain Wall (Round 2)	10	14-Jan-20 A		Prepare & Submit	7					
PRO-1440	Review & Approve Shop Drawings - Curtain Wall (Round 2)	15	18-Feb-20	09-Mar-20	Review & Appro		-				
PRO-1450	Release for Fabrication - Curtain Wall	0	10-1 00-20	09-Mar-20	♦ Release for Fat		-				
PRO-1450		80	10-Mar-20	09-Mai-20 01-Jul-20				ry - Curtain Wall			
	Fab & Available for Delivery - Curtain Wall	80	10-iviar-20	01-Jul-20		Fab & Avail		rý - Curtain Wat			
rly Bid Pack	(ages									·	· · · · · · · · · · · · · · · · · · ·
levators											
PRO-1910	Fab & Available for Delivery - Elevators	80	02-Mar-20*	23-Jun-20		Fab & Availa	ble for Delivery	y - Elevators			
tructural Stee	el										
PRO-1660	Subcontractor Issues Submittals - Structural Steel	0	21-Aug-19 A	26-Dec-19 A	contractor Issues Subn	nittals - Struct	tural Steel				
PRO-1260	Prepare & Submit - Structural Steel/Precast Final CWP	0	21-Aug-19 A	23-Jan-20 A	Prepare & Submit - Stru	ctural Steel/F	Precast Final C	WP			
PRO-1710	Execute Contract - Structural Steel	0	29-Aug-19 A	18-Dec-19 A	ute Contract - Structura	Steel				· · · · · · · · · · · · · · · · · · ·	
PRO-1670	A/E Review & Approve Submittals - Structural Steel	0	19-Sep-19 A	13-Jan-20 A	/E Review & Approve S	ubmittals - Str	ructural Steel		1		
PRO-1680	Fab & Available for Delivery - Structural Steel	19	14-Jan-20 A		Fab & Available 1						
PRO-1270	MBTA Reviews - Structural Steel/Precast Steel CW P	34	24-Jan-20 A		MBTA Review	•					
Below Grade W	Naterp roo fing (Trade Contractor)										
PRO-4580	A/E Review & Approve Submittals - Foundation Waterproofing & Dampproofing	0	05-Nov-19A	23-Jan-20 A		Submittals - F		aterproofing & Dampproofing		J 	- 1
PRO-4570	Fab & Available for Delivery - Foundation Waterproofing & Dampproofing	0			Fab & Available for De						
	ocurement Post CDs (Trade Contractors)	0	24-001-207	20-001-20A							
-	· · ·										
• •	de Contractor)	10	40 5 40 4			<u>.</u>					
PRO-4720	Subcontractor Issue Submittals - Plumbing Fixtures	10	19-Dec-19 A		Subcontractor Iss					· · · · · · · · · · · · · · · · · · ·	· · · · · · · · · · · · · · · · · · ·
PRO-4770	Subcontractor Issue Submittals - Plumbing Domestic Water Heater	10	19-Dec-19 A		Subcontractor Iss						
PRO-4710	A/E Review & Approve Submittals - Plumbing Fixtures	15	25-Feb-20	16-Mar-20	A/E Review & A	• •	1				
PRO-4760	A/E Review & Approve Submittals - Plumbing Domestic Water Heater	15	25-Feb-20	16-Mar-20		••	1	ing Domestic Water Heater	1		
PRO-4700	Fab/Deliver Equipment - Plumbing Fixtures	65	17-Mar-20	17-Jun-20				umbing Fixtures			
PRO-4750	Fab/Deliver Equipment - Plumbing Domestic Water Heater	65	17-Mar-20	17-Jun-20		Fab/Deliver E	Equipment - Plu	umbing Domestic Water Heater		 	
ire Protection	n (Trade Contractor)										
PRO-4650	Execute Contract - Fire Protection	0	22-Nov-19 A	13-Dec-19 A	te Contract - Fire Prote	ction					
PRO-4690	Subcontractor Issue Submittals - Fire Protection Piping	15	19-Dec-19 A		Subcontractor Is		ls [¦] - Fire Protec	tion Piping			
PRO-4680	A/E Review & Approve Submittals - Fire Protection Piping	15	03-Mar-20		A/E Review &		1				
IVAC (Trade C						11					
PRO-5130	Subcontractor Issue Submittals - HVAC Air Cooled Chiler	10	19-Dec-19 A	24-Feb-20	Subcontractor Iss	ue Submittals	s + HVAC Air Co	ooled Chiler			
PRO-4790	Subcontractor Issue Submittals - HVAC Ductwork	10	19-Dec-19 A		Subcontractor Iss		1	- I			
PRO-4790 PRO-4840	Subcontractor Issue Submittals - HVAC Exhaust Fans	10	19-Dec-19 A		Subcontractor Iss		1				
	Subcontractor Issue Submittals - HVAC Exhaust Fails	10	19-Dec-19 A		Subcontractor Iss						
PRO-4890 PRO-4940					Subcontractor Iss						
	Subcontractor Issue Submittals - HVAC VAVs	10	19-Dec-19 A					┣			
	Subcontractor Issue Submittals - HVAC FCUs	10	19-Dec-19 A		Subcontractor Iss		1				
PRO-4970		10	19-Dec-19 A	24-⊢eb-20	Subcontractor Iss	ue Submittals	s - HVAC AHUs	5			
	Subcontractor Issue Submittals - HVAC AHUs	10									
PRO-4970 PRO-5040		1					•	1			•
PRO-4970 PRO-5040	Subcontractor Issue Submittals - HVAC AHUs		Page 6 o		TASK filter: Uncon	pleted Activit	ties Two Month	hs Prior.			
PRO-4970 PRO-5040	g Level of Effort Remaining Work				TASK filter: Uncon	pleted Activit	ties Two Month	hs Prior. © Oracle Corporation		5KANSK	

Data Date: 10-Feb-20 / Run Date:	09-Jul-20 09:05



ID PRO-5060 PRO-4780 PRO-4830 PRO-4830 PRO-4930 PRO-4930 PRO-5030 PRO-5050 PRO-5050 PRO-5120 PRO-5120 PRO-4820 PRO-4920	Activity Name Subcontractor Issue Submittals - HVAC Boilers A/E Review & Approve Submittals - HVAC Ductwork A/E Review & Approve Submittals - HVAC Exhaust Fans A/E Review & Approve Submittals - HVAC Pumps A/E Review & Approve Submittals - HVAC VAVs A/E Review & Approve Submittals - HVAC FCUs A/E Review & Approve Submittals - HVAC FCUs	Remaining Duration 10 10 15 15 15 15	19-Dec-19 A 25-Feb-20	Finish 24-Feb-20	2020 F [Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Subcontractor Issue Submittals + HVAC Boilers
PRO-4780 PRO-4830 PRO-4830 PRO-4930 PRO-4960 PRO-5030 PRO-5050 PRO-5120 PRO-4820 PRO-4920	A/E Review & Approve Submittals - HVAC Ductwork A/E Review & Approve Submittals - HVAC Exhaust Fans A/E Review & Approve Submittals - HVAC Pumps A/E Review & Approve Submittals - HVAC VAVs A/E Review & Approve Submittals - HVAC FCUs	10 15 15	25-Feb-20		Subcontractor Issue Submittals - HVAC Boilers
PRO-4780 PRO-4830 PRO-4830 PRO-4930 PRO-4960 PRO-5030 PRO-5050 PRO-5120 PRO-4820 PRO-4920	A/E Review & Approve Submittals - HVAC Ductwork A/E Review & Approve Submittals - HVAC Exhaust Fans A/E Review & Approve Submittals - HVAC Pumps A/E Review & Approve Submittals - HVAC VAVs A/E Review & Approve Submittals - HVAC FCUs	10 15 15	25-Feb-20		
PRO-4830 PRO-4880 PRO-4930 PRO-5030 PRO-5050 PRO-5120 PRO-4820 PRO-4920	A/E Review & Approve Submittals - HVAC Exhaust Fans A/E Review & Approve Submittals - HVAC Pumps A/E Review & Approve Submittals - HVAC VAVs A/E Review & Approve Submittals - HVAC FCUs	15 15		00.11	
PRO-4880 PRO-4930 PRO-4960 PRO-5030 PRO-5050 PRO-5120 PRO-4820 PRO-4920	A/E Review & Approve Submittals - HVAC Pumps A/E Review & Approve Submittals - HVAC VAVs A/E Review & Approve Submittals - HVAC FCUs	15		09-Mar-20	A/E Review & Approve Submittals - HVAC Ductwork
PRO-4930 PRO-4960 PRO-5030 PRO-5050 PRO-5120 PRO-4820 PRO-4920	A/E Review & Approve Submittals - HVAC VAVs A/E Review & Approve Submittals - HVAC FCUs		25-Feb-20	16-Mar-20	A/E Review & Approve Submittals - HVAC Exhaust Fans
PRO-4960 PRO-5030 PRO-5050 PRO-5120 PRO-4820 PRO-4920	A/E Review & Approve Submittals - HVAC FCUs	15	25-Feb-20	16-Mar-20	A/E Review & Approve Submittals - HVAC Pumps
PRO-4960 PRO-5030 PRO-5050 PRO-5120 PRO-4820 PRO-4920	A/E Review & Approve Submittals - HVAC FCUs	10	25-Feb-20	16-Mar-20	A/E Review & Approve Submittals - HVAC VAVs
PRO-5030 PRO-5050 PRO-5120 PRO-4820 PRO-4920		15	25-Feb-20	16-Mar-20	A/E Review & Approve Submittals - HVAC FCUs
PRO-5050 PRO-5120 PRO-4820 PRO-4920	A/E Review & Approve Submittals - HVAC AHUs	15	25-Feb-20	16-Mar-20	A/E Review & Approve Submittals - HVAC AHUs
PRO-5120 PRO-4820 PRO-4920	A/E Review & Approve Submittals - HVAC Boilers	15	25-Feb-20	16-Mar-20	A/E Review & Approve Submittals - HVAC Boilers
PRO-4820 PRO-4920	A/E Review & Approve Submittals - HVAC Air Cooled Chiller	15	25-Feb-20	16-Mar-20	AVE Review & Approve Submittals - HVAC Air Cooled Chiller
PRO-4920		50	17-Mar-20	27-May-20	Fab/Deliver Equipment - HVAC Exhaust Fans
	Fab/Deliver Equipment - HVAC Exhaust Fans			-	
	Fab/Deliver Equipment - HVAC VAVs	50	17-Mar-20	27-May-20	Fab/Deliver Equipment - HVAC VAVs
PRO-4870	Fab/Deliver Equipment - HVAC Pumps	65	17-Mar-20	17-Jun-20	Fab/Deliver Equipment - HVAC Pumps
PRO-4950	Fab/Deliver Equipment - HVAC FCUs	65	17-Mar-20	17-Jun-20	Fab/Deliver Equipment - HVAC FCUs
PRO-2200	Fab/Deliver Equipment - HVAC AHUs	80	17-Mar-20	09-Jul-20	Fab/Deliver Equipment - HVAC AHUs
PRO-2210	Fab/Deliver Equipment - HVAC Boilers	80	17-Mar-20	09-Jul-20	Fab/Deliver Equipment - HVAC Boilers
PRO-2220	Fab/Deliver Equipment - HVAC Air Cooled Chiller	80	17-Mar-20	09-Jul-20	Fab/Deliver Equipment - HVAC Air Cooled Chille
Electrical & Cor	mmunications (Trade Contractor)				
PRO-2250	Execute Contract - Electrical	0	22-Nov-19 A	15-Jan-20 A	Execute Contract - Electrical
PRO-2260	Subcontractor Issue Submittals - Electrical Switchgear	5	22-Nov-19A	14-Feb-20	Subcontractor Issue Submittals - Electrical Switchgear
PRO-2280	Subcontractor Issue Submittals - Electrical Interior Lighting	5	22-Nov-19A	14-Feb-20	Subcontractor Issue Submittals - Electrical Interior Lighting
PRO-2290	A/E Review & Approve Submittals - Electrical Switchgear	15	18-Feb-20	09-Mar-20	AVE Review & Approve Submittals - Electrical Switchgear
PRO-2300	A/E Review & Approve Submittals - Electrical Interior Lighting	15	18-Feb-20	09-Mar-20	A/E Review & Approve Submittals - Electrical Interior Lighting
PRO-2320	Fab/Deliver Equipment - Interior Lighting	65	10-1 CD-20	10-Jun-20	Fab/Deliver Equipment - Interior Lighting
PRO-2340		80	10-Mar-20	01-Jul-20	
	Fab/Deliver Equipment - Electrical Switchgear	00	10-1011-20	01-Jul-20	Fab/Deliver Equipment - Electrical Switchgear
Masonry (Trade		-	40 5 40 4		
PRO-2160	Subcontractor Issue Submittals - Masonry (Brick/Stone Samples)	5	19-Dec-19 A	14-Feb-20	Subcontractor Issue Submittals - Masonry (Brick/Stone Samples)
PRO-1990	Subcontractor Issue Initial Shop Drawings - Masonry	10	19-Dec-19 A	24-Feb-20	Subcontractor Issue Initial Shop Drawings - Masonry
PRO-2170	A/E Review & Approve Submittals - Masonry (Brick/Stone Samples)	10	18-Feb-20	02-Mar-20	A/E Review & Approve Submittals - Masonry (Brick/Stone Samples)
PRO-2000	A/E Review & Approve Initial Shop Drawings - Masonry	15	25-Feb-20	16-Mar-20	A/E Review & Approve Initial Shop Drawings - Masonry
PRO-2010	Fab & Available for Delivery - Masonry (Brick/Stone)	80	03-Mar-20	24-Jun-20	Fab & Available for Delivery - Masonry (Brick/Stor
/liscellaneous l	Metals & Ornamental Iron (Trade Contractor)				
PRO-2360	Execute Contract - Misc. Metals	0	13-Dec-19 A	06-Jan-20 A	ecute Contract - Misc. Metals
PRO-2350	Award Contract - Misc. Metals	0	18-Dec-19 A	18-Dec-19 A	d Contract - Misc. Metals
PRO-6600	Town Building Commission Approves Contract - Misc. Metals	0	18-Dec-19 A	18-Dec-19 A	Building Commission Approves Contract - Misc. Metals
PRO-2370	Subcontractor Issue Submittals - Misc. Metals Lintels	15	07-Jan-20 A	02-Mar-20	Subcontractor Issue Submittals - Misc. Metals Lintels
PRO-2380	Subcontractor Issue Submittals - Misc. Metals Stair 1	25	10-Feb-20	16-Mar-20	Subcontractor Issue Submittals - Misc. Metals Stair 1
PRO-2410	Subcontractor Issue Submittals - Misc. Metals Stair 2	25	13-Feb-20	19-Mar-20	Subcontractor Issue Submittals - Misc. Metals Stair 2
PRO-2400	Subcontractor Issue Submittals - Misc. Metals Stair 3	25	19-Feb-20	24-Mar-20	Subcontractor Issue Submittals - Misc. Metals Stair 3
PRO-5600	Subcontractor Issue Submittals - Misc. Metals Stair 6	25	21-Feb-20	26-Mar-20	Subcontractor Issue Submittals - Misc. Metals Stair 6
PRO-5630	Subcontractor Issue Submittals - Misc. Metals Stair 7	25	21-Feb-20	26-Mar-20	Subcontractor Issue Submittals - Misc. Metals Stair 7
PRO-2420			03-Mar-20	20-Mar-20 23-Mar-20	
	A/E Review & Approve Submittals - Misc. Metals Lintels	15			
PRO-2430	A/E Review & Approve Submittals - Misc. Metals Stair 1	15	17-Mar-20	06-Apr-20	A/E Review & Approve Submittals - Misc. Metals Stair 1
PRO-2460	A/E Review & Approve Submittals - Misc. Metals Stair 2	15	20-Mar-20	09-Apr-20	A/E Review & Approve Submittals - Misc. Metals Stair 2
PRO-2450	A/E Review & Approve Submittals - Misc. Metals Stair 3	15	25-Mar-20	14-Apr-20	A/E Review & Approve Submittals - Misc. Metals Stair 3
PRO-5610	A/E Review & Approve Submittals - Misc. Metals Stair 6	15	27-Mar-20	16-Apr-20	A/E Review & Approve Submittals - Misc. Metals Stair 6
PRO-5640	A/E Review & Approve Submittals - Misc. Metals Stair 7	15	27-Mar-20	16-Apr-20	A/E Review & Approve Submittals - Misc. Metals Stair 7
PRO-2470	Fab & Available for Delivery - Misc. Metals Lintels	10	31-Mar-20	13-Apr-20	Fab & Available for Delivery - Misc. Metals Lintels
PRO-2480	Fab & Available for Delivery - Misc. Metals Stair 1	25	07-Apr-20	12-May-20	Fab & Available for Delivery - Misc. Metals Stair 1
PRO-2500	Fab & Available for Delivery - Misc. Metals Stair 2	25	10-Apr-20	15-May-20	Fab & Available for Delivery - Misc. Metals Stair 2
PRO-2510	Fab & Available for Delivery - Misc. Metals Stair 3	25	15-Apr-20	20-May-20	Fab & Available for Delivery - Misc. Metals Stair 3
PRO-5620	Fab & Available for Delivery - Misc. Metals Stair 6	25	17-Apr-20	22-May-20	Fab & Available for Delivery - Misc. Metals Stair 6
PRO-5650	Fab & Available for Delivery - Misc. Metals Stair 7	25	17-Apr-20	22-May-20	Fab'& Available for Delivery - Misc. Metals Stair 7
	Caulking (Trade Contractor)	20			
PRO-2520	Award Contract - Building AVB & Caulking	0	18-Dec-19 A	18-Dec 10.4	d Contract - Ruilding AV/R & Coullking
					d Contract - Building AVB & Caulking
PRO-6610	Town Building Commission Approves Contract - Building AVB & Caulking	0	18-Dec-19 A	18-Dec-19A	Building Commission Approves Contract - Building AVB & Caulking
Remaining	Level of Effort Remaining Work		Page 7 of	29	TASK filter: Uncompleted Activities Two Months Prior.
Actual Leve	el of Effort Critical Remaining Work		5		© Oracle Co
Actual Worl	-			Dog	e 50 of 377

Data Date: 10-Feb-20 / Run Date: 09-Jul-20 09:05 1 2022 Jul A S Oct N D Jan F Mar Apr M Jun Jul Aug S Oct N Dec ------------------ - - - - - - - -------

SKANSKA

D	ool - Project A - 10Feb20 R1 Schedule Update - 1318014-CR - B26 Activity Name	Remaining	Start	Finish	ailed Schedule
D	Activity Name	Duration	Start	FILIST	2020
					F [Mar Apr M Jun Jul A S [Oct N D Jan F [Mar Apr M
PRO-2530	Execute Contract - Building AVB & Cauking	0	19-Dec-19 A	23-Dec-19 A	ute Contract - Building AVB & Cauking
PRO-2540	Subcontractor Issue Submittals - Building AVB & Caulking	20	10-Feb-20	09-Mar-20	Subcontractor Issue Submittals - Building AVB & Caulking
PRO-2550	A/E Review & Approve Submittals - Building AVB & Caulking	15	10-Mar-20	30-Mar-20	A/E Review & Approve Submittals - Building AVB & Caulking
PRO-2560	Fab & Available for Delivery - Building AVB & Caulking	20	31-Mar-20	28-Apr-20	Fab & Available for Delivery - Building AVB & Caulking
oofing & Fla	shing (Trade Contractor)			, .	
PRO-2570	Award Contract - Roofing	0	18-Dec-19 A	18-Dec-19A	d Contract - Roofing
PRO-6620	Town Building Commission Approves Contract - Roofing	0	18-Dec-19A	18-Dec-19A	
PRO-2580	Execute Contract - Roofing	0	19-Dec-19 A		xecute Contract - Roofing
PRO-2590	Subcontractor Issue Submittals - Roofing Metal Flashing & Trim	20	10-Feb-20	09-Mar-20	Subcontractor Issue Submittals - Roofing Metal Flashing & Trim
PRO-2600	Subcontractor Issue Submittals - Membrane Roofing	20	10-Feb-20	09-Mar-20	Subcontractor Issue Submittals - Membrane Roofing
PRO-2610	A/E Review & Approve Submittals - Roofing Metal Flashing & Trim	15	10-Mar-20	30-Mar-20	A/E Review & Approve Submittals - Roofing Metal Flashing & Tri
PRO-2620	A/E Review & Approve Submittals - Membrane Roofing	15	10-Mar-20	30-Mar-20	A/E Review & Approve Submittals - Membrane Roofing
PRO-2630	Fab & Available for Delivery - Membrane Roofing	20	31-Mar-20	28-Apr-20	Fab & Available for Delivery - Membrane Roofing
PRO-2640	Fab & Available for Delivery - Roofing Metal Flashing & Trim	25	31-Mar-20	05-May-20	Fab & Available for Delivery - Roofing Metal Flashing & Trir
	& Glazing (Trade Contractor)				
PRO-2650	Award Contract - Interior Glass & Glazing	0	18-Dec-19 A		d Contract - Interior Glass & Glazing
PRO-6630	Town Building Commission Approves Contract - Interior Glass & Glazing	0	18-Dec-19 A	18-Dec-19 A	Building Commission Approves Contract - Interior Glass & Glazing
PRO-2660	Execute Contract - Interior Glass & Glazing	0	19-Dec-19 A	13-Jan-20 A	xecute Contract - Interior Glass & Glazing
PRO-2670	Subcontractor Issue Submittals - Interior Glass	20	10-Feb-20	09-Mar-20	Subcontractor Issue Submittals - Interior Glass
PRO-2680	Subcontractor Issue Submittals - Interior Glass Mirrors	20	10-Feb-20	09-Mar-20	Subcontractor Issue Submittals - Interior Glass Mirrors
PRO-2690	A/E Review & Approve Submittals - Interior Glass	15	10-Mar-20	30-Mar-20	A/E Review & Approve Submittals - Interior Glass
PRO-2700	A/E Review & Approve Submittals - Interior Glass Mirrors	15	10-Mar-20	30-Mar-20	A/E Review & Approve Submittals - Interior Glass Mirrors
PRO-2710	Fab & Available for Delivery - Interior Glass Mirrors	25	31-Mar-20	05-May-20	Fab & Available for Delivery - Interior Glass Mirrors
PRO-2720	Fab & Available for Delivery - Interior Glass	40	31-Mar-20	27-May-20	Fab & Available for Delivery - Interior Glass
ile (Trade Co	•		01-Ividi-20	27-10ay-20	
PRO-2730	Award Contract - Tile	0	19 Dec 10 4	19 Dec 10 A	d Contract - Tile
		0			
PRO-6640	Town Building Commission Approves Contract - Tile	0	18-Dec-19A		Building Commission Approves Contract - Tile
PRO-2740	Execute Contract - Tile	0	19-Dec-19 A		ecute Contract - Tile
PRO-2750	Subcontractor Issue Submittals - Ceramic Tile	20	10-Feb-20	09-Mar-20	Subcontractor Issue Submittals - Ceramic Tile
PRO-2760	A/E Review & Approve Submittals - Ceramic Tile	15	10-Mar-20	30-Mar-20	A/E Review & Approve Submittals - Ceramic Tile
PRO-2770	Fab & Available for Delivery - Ceramic Tile	50	31-Mar-20	10-Jun-20	Fab & Available for Delivery - Ceramic Tile
errazzo (Trad	le Contractor)				
PRO-5270	Award Contract - Terrazzo	0	18-Dec-19 A	18-Dec-19 A	d Contract - Terrazzo
PRO-6650	Town Building Commission Approves Contract - Terrazzo	0	18-Dec-19 A	18-Dec-19 A	Building Commission Approves Contract - Terrazzo
PRO-5280	Execute Contract - Terrazzo	0	19-Dec-19 A	19-Dec-19 A	ute Contract - Terrazzo
PRO-5290	Subcontractor Issue Submittals - Terrazzo	20	10-Feb-20	09-Mar-20	Subcontractor Issue Submittals - Terrazzo
PRO-5300	A/E Review & Approve Submittals - Terrazzo	15	10-Mar-20	30-Mar-20	A/E Review & Approve Submittals - Terrazzo
PRO-5310	Fab & Available for Delivery - Terrazzo	30	31-Mar-20	12-May-20	Fab & Available for Delivery - Terrazzo
coustical Ce	iling Tile (Trade Contractor)	1 1			
PRO-2780	Award Contract - Acoustical Ceiling Tile	0	18-Dec-19 A	18-Dec-19A	d Contract - Acoustical Ceiling Tile
PRO-6660	Town Building Commission Approves Contract - Tile	0	18-Dec-19 A		Building Commission Approves Contract - Tile
PRO-2790	Execute Contract - Acoustical Ceiling Tile	0	19-Dec-19 A		ute Contract - Acoustical Ceiling Tile
	-				
PRO-2800	Subcontractor Issue Submittals - ACT	20	10-Feb-20	09-Mar-20	Subcontractor Issue Submittals - ACT
PRO-2810	Subcontractor Issue Submittals - Acoustical Metal Panels	20	10-Feb-20	09-Mar-20	Subcontractor Issue Submittals - Acoustical Metal Panels
PRO-2820	A/E Review & Approve Submittals - ACT	15	10-Mar-20	30-Mar-20	A/E Review & Approve Submittals - ACT
PRO-2830	A/E Review & Approve Submittals - Acoustical Metal Panels	15	10-Mar-20	30-Mar-20	A/E Review & Approve Submittals - Acoustical Metal Panels
PRO-2840	Fab & Available for Delivery - ACT	15	31-Mar-20	21-Apr-20	Fab & Aviailable for Delivery - ACT
PRO-2850	Fab & Available for Delivery - Acoustical Metal Panels	50	31-Mar-20	10-Jun-20	Fab & Available for Delivery - Acoustica I Metal Panels
esilient Floo	ring (Trade Contractor)				
PRO-2860	Award Contract - Resilient Flooring	0	18-Dec-19 A	18-Dec-19 A	d Contract - Resilient Flooring
PRO-6670	Town Building Commission Approves Contract - Resilient Flooring	0	18-Dec-19 A		Building Commission Approves Contract - Resilient Flooring
PRO-2870	Execute Contract - Resilient Flooring	0	19-Dec-19 A		ecute Contract - Resilient Flooring
PRO-2880	Subcontractor Issue Submittals - Resilient Flooring	20	10-Feb-20	09-Mar-20	Subcontractor Issue Submittals - Resilient Flooring
PRO-2890	A/E Review & Approve Submittals - Resilient Flooring	15	10-Mar-20	30-Mar-20	A/E Review & Approve Submittals - Resilient Flooring
PRO-2900	Fab & Available for Delivery - Resilient Flooring	30	31-Mar-20	12-May-20	Fab & Available for Delivery - Resilient Flooring
	g Level of Effort Remaining Work				
	-		Page 8 of	29	TASK filter: Uncompleted Activities Two Months Prior.
• • • • •					
 Actual Lev Actual Wo 	ő				© Oracle Cor e 51 of 377

Data Date: 10-Feb-20 / Run Date: 09-Jul-20 09:05 1 2022 Jul A S Oct N D Jan F Mar Apr M Jun Jul Aug S Oct N Dec ------------------ - - - - - - - -------

SKANSKA

	ol - Project A - 10Feb20 R1 Schedule Update - 1318014-CR - B26	Domoinin	Otor!		ailed Schedule	Data Date: 10-Feb-20 / Run Date: 09-Jul-20	03.00
D	Activity Name	Remaining	Start	Finish	2020	2021 2022	
		Duration				Oct N D Jan F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul Aug S	Oct
ainting (Trade	e Contractor)						
PRO-2910	Award Contract - Painting	0			d Contract - Painting		
PRO-6680	Town Building Commission Approves Contract - Painting	0	18-Dec-19 A	18-Dec-19 A	Building Commission Approves Contra	ct - Painting	
PRO-2920	Execute Contract - Painting	0	19-Dec-19 A	19-Dec-19 A	ute Contract - Painting		
PRO-2930	Subcontractor Issue Submittals - Painting	20	10-Feb-20	09-Mar-20	Subcontractor Issue Submittals	- Painting	
PRO-2940	A/E Review & Approve Submittals - Painting	15	10-Mar-20	30-Mar-20	A/E Review & Approve Subr	nittals - Painting	
PRO-2950	Fab & Available for Delivery - Painting	10	31-Mar-20	13-Apr-20	🔲 Fab & Available for Delive	ry - Painting	
maining Pro	ocurement Post CDs (Subcontractors)						
RO-2970	Prepare Bid Packages - Wave 2 - Remaining Subcontractors	0	04-Sep-19A	20-Dec-19A	are Bid Packages - Waye 2 - Remainin	a Subcontractors	
RO-2980	Prepare Bid Packages - Wave 3 - Remaining Subcontractors	0			pare Bid Packages - Wave 3 - Remain		
RO-2990	Prepare Bid Packages - Wave 4 - Remaining Subcontractors	0			repare Bid Packages - Wave 4 - Rema		
RO-3000	Prepare Bid Packages - Wave 5 - Remaining Subcontractors	0	· ·		Prepare Bid Packages - Wave 5 - Rem		
arpentry & Di					gen a serie gen a serie gen a serie se		
PRO-3010	Bid, De-scope & RTA - Carpentry & Drywall	0	02-Dec-19A	23-Dec-19A	De-scope & RTA - Carpentry & Drywall		
PRO-3020	Owner Review/Approve RTA - Carpentry & Drywall	0			wner Review/Approve RTA - Carpentry	& Drywall	
PRO-6690	Town Building Commission Approves Contract - Carpentry & Drywall	0	14-Jan-20 A		own Building Commission Approves Co		
PRO-3030	Award Contract - Carpentry & Drywall	0	15-Jan-20 A		Award Contract - Carpentry & Drywall		
PRO-3040	Execute Contract - Carpentry & Drywall	5	17-Jan-20 A		Execute Contract - Carpentry & Dry	wall	
PRO-3050	Subcontractor Issue Submittals - Carpentry & Drywall Exterior Cold Formed Metal Framing	15	18-Feb-20	09-Mar-20		- Carpentry & Drywall Exterior Cold Formed Metal Framing	
PRO-3980	Subcontractor Issue Submittals - White Box Vibration/Sound Isolation	20	18-Feb-20	16-Mar-20		s - White Box Vibration/Sound Isolation	
PRO-3060	Subcontractor Issue Submittals - Carpentry & Drywall Non-Structural Metal Framing	25	18-Feb-20	23-Mar-20		als - Carpentry & Drywall Non-Structural Metal Framing	-
PRO-3070	A/E Review & Approve Submittals - Carpentry & Drywall Exterior Cold Formed Metal Framin	10	10-Mar-20	23-Mar-20		ittals - Carpentry & Drywall Exterior Cold Formed Metal Framing	
PRO-3990	A/E Review & Approve Submittals - White Box Vibration/Sound Isolation	15	17-Mar-20	06-Apr-20		mittals - White Box Vibration/Sound Isolation	
PRO-3080	Fab & Available for Delivery - Carpentry & Drywall Exterior Cold Formed Metal Framing	15	24-Mar-20	13-Apr-20		ry - Carpentry & Drywall Exterior Cold Formed Metal Framing	
PRO-3090	A/E Review & Approve Submittals - Carpentry & Drywall Non-Structural Metal Framing	15	24-Mar-20	13-Apr-20		bmittals - Carpentry & Drywall Non-Structural Metal Framing	
PRO-4000	Fab & Available for Delivery - White Box Vibration/Sound Isolation	40	07-Apr-20	03-Jun-20		r Delivery - White Box Vibration/Sound Isolation	
PRO-3100	Fab & Available for Delivery - Carpentry & Drywall Non-Structural Metal Framing	10	14-Apr-20	28-Apr-20		very - Carpentry & Drywall Non-Structural Metal Framing	}
pray Fireproo		10	14-Api-20	20-Api-20		very - Carpeniu y & Drywall Non-Structural Metal Franning	
PRO-3110	Bid, De-scope & RTA - Spray Fireproofing	0	19-Dec-19 A	04-Feb-20 A	Bid, De-scope & RTA - Spray Firepro	ofina	
PRO-3120	Owner Review/Approve RTA - Spray Fireproofing	1	05-Feb-20 A	10-Feb-20	 Owner Review/Approve RTA - Spray 		
PRO-6700	Town Building Commission Approves Contract - Spray Fireproofing	1	11-Feb-20	11-Feb-20	Town Building Commission Approve		
PRO-3130	Award Contract - Spray Fireproofing	2	12-Feb-20	13-Feb-20	Award Contract - Spray Fireproofin		
PRO-3140	Execute Contract - Spray Fireproofing	3	12-Feb-20 14-Feb-20	13-Feb-20 19-Feb-20	 Award Contract - Spray Fileproon Execute Contract - Spray Fileproon 		
PRO-3140	Subcontractor Issue Submittals - Spray Fireproofing	-	20-Feb-20	04-Mar-20	Subcontractor Issue Submittals		
PRO-3160		10	20-Feb-20 05-Mar-20	18-Mar-20	 A/E Review & Approve Submittais 		
PRO-3170	A/E Review & Approve Submittals - Spray Fireproofing	3	19-Mar-20	23-Mar-20	Fab & Available for Delivery -		-
	Fab & Available for Delivery - Spray Fireproofing	3	19-1011-20	23-10181-20		Spray Filepi Qolling	
	And Hard ware	5	10 Dec 10 A	11 Eab 20			
PRO-3180	Bid, De-scope & RTA - Doors, Frames & Hardware	5	19-Dec-19 A	14-Feb-20	Bid, De-scope & RTA - Doors, Fran		
PRO-3190	Owner Review/Approve RTA - Doors, Frames & Hardware	5	18-Feb-20	24-Feb-20	Owner Review/Approve RTA - Do		
PRO-6710	Town Building Commission Approves Contract - Doors, Frames & Hardware	1	10-Mar-20	10-Mar-20		roves Contract - Doors, Frames & Hardware	
PRO-3200	Award Contract - Doors, Frames & Hardware	2	11-Mar-20	12-Mar-20	Award Contract - Doors, Fram		1
PRO-3210	Execute Contract - Doors, Frames & Hardware	5	13-Mar-20	19-Mar-20	Execute Contract - Doors, Fr		
PRO-3220	Subcontractor Issue Submittals - Interior Wood Doors	20	20-Mar-20	16-Apr-20	Subcontractor Issue Sub		
PRO-3230	Subcontractor Issue Submittals - Door Hardware	20	20-Mar-20	16-Apr-20	Subcontractor Issue Sub		
PRO-3240	Subcontractor Issue Submittals - HM Door Frames	20	20-Mar-20	16-Apr-20	Subcontractor Issue Sub		
PRO-3250	Subcontractor Issue Submittals - HM Doors	20	20-Mar-20	16-Apr-20	Subcontractor Issue Sub		
PRO-3260	A/E Review & Approve Submittals - Interior Wood Doors	15	17-Apr-20	08-May-20		e Submittals - Interior Wood Doors	
PRO-3270	A/E Review & Approve Submittals - Door Hardware	15	17-Apr-20	08-May-20		e Submittals - Door Hardware	
PRO-3280	A/E Review & Approve Submittals - HM Door Frames	15	17-Apr-20	08-May-20		e Submittals - HM Door Frames	
PRO-3290	A/E Review & Approve Submittals - HM Doors	15	17-Apr-20	08-May-20	A/E Review & Approve		
PRO-3300	Fab & Available for Delivery - HM Door Frames	25	11-May-20	15-Jun-20		for Delivery - HM Door Frames	
PRO-3330	Fab & Available for Delivery - HM Doors	50	11-May-20	21-Jul-20		ilable for Delivery - HM Doors	
PRO-3310	Fab & Available for Delivery - Interior Wood Doors	65	11-May-20	11-Aug-20		Available for Delivery - Interior Wood Doors	
PRO-3320	Fab & Available for Delivery - Door Hardware	65	11-May-20	11-Aug-20	Fab &	Available for Delivery - Door Hardware	:
						· · · · · · · · · · · · · · · · · · ·	
Remaining	Level of Effort Remaining Work		Page 9 of	29	TASK filter: Uncompleted Activitie	s Two Months Prior.	
J	<u> </u>	1		-			
 Actual Lev 	el of Effort Critical Remaining Work					© Oracle Corporation	



Alilwork & Finish O PRO-3340 Bi PRO-3350 O PRO-6720 Ta PRO-3350 Ai PRO-3360 Ai PRO-3370 Ei PRO-3390 Si PRO-3400 Si PRO-3410 Si PRO-3420 Si PRO-3440 Ai PRO-3450 Ai PRO-3450 Ai PRO-3460 Ai PRO-3460 Fi PRO-3490 Fi PRO-3500 Fi PRO-3510 Fi	Activity Name Carpentry Bid, De-scope & RTA - Millwork & Finish Carpentry Dwner Review/Approve RTA- Millwork & Finish Carpentry Town Building Commission Approves Contract - Millwork & Finish Carpentry Award Contract - Millwork & Finish Carpentry Execute Contract - Millwork & Finish Carpentry Execute Contract - Millwork & Finish Carpentry Subcontractor Issue Submittals - Millwork Display Cases Subcontractor Issue Submittals - Millwork Wood Benches Subcontractor Issue Submittals - Millwork Wood Veneer Casework Subcontractor Issue Submittals - Millwork Plastic Laminate Casework Subcontractor Issue Submittals - Millwork Display Cases A/E Review & Approve Submittals - Millwork Display Cases A/E Review & Approve Submittals - Millwork Dod Benches A/E Review & Approve Submittals - Millwork Display Cases A/E Review & Approve Submittals - Millwork Display Cases A/E Review & Approve Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Vood Veneer Casework A/E Review & Approve Submittals - Millwork Vood Veneer Casework A/E Review & Approve Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Plastic Laminate Casework Eab & Available for Delivery - Millwork Wood Benches Eab & Available for Delivery - Millwork Wood Veneer Casework Eab & Available for Delivery - Millwork Wood Veneer Casework Eab & Available for Delivery - Millwork Wood Veneer Casework Eab & Available for Delivery - Millwork Wood Veneer Casework Eab & Available for Delivery - Millwork Wood Veneer Casework Eab & Available for Delivery - Millwork Wood Veneer Casework Eab & Available for Delivery - Millwork Wood Veneer Casework Eab & Available for Delivery - Millwork Countertops	Remaining Duration 5 1 2 5 2 5 25 25 25 25 25 25 25 15 15 15 35 35 25	23-Dec-19 A 18-Feb-20 10-Mar-20 11-Mar-20 20-Mar-20 20-Mar-20 20-Mar-20 20-Mar-20 20-Mar-20 20-Mar-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 18-May-20	Finish 14-Feb-20 24-Feb-20 10-Mar-20 12-Mar-20 24-Apr-20 24-Apr-20 24-Apr-20 24-Apr-20 24-Apr-20 24-Apr-20 15-May-20 15-May-20 15-May-20 15-May-20	2020 2021 F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul A S Oct Bid, De-scope & RTA - Millwork & Finish Carpentry Owher Review/Approve RTA- Millwork & Finish Carpentry Town Building Commission Approves Contract - Millwork & Finish Carpentry Town Building Commission Approves Contract - Millwork & Finish Carpentry Award Contract - Millwork & Finish Carpentry Execute Contract - Millwork & Finish Carpentry Subcontractor Issue Submittals - Millwork Display Cases Subcontractor Issue Submittals - Millwork Wood Benches Subcontractor Issue Submittals - Millwork Wood Veneer Casework Subcontractor Issue Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Veneer Casework	N D Jan F Mar Apr M Jun Jul Aug S
PRO-3340 Bi PRO-3350 O PRO-6720 Tr PRO-3360 Ar PRO-3370 Ei PRO-3370 Ei PRO-3370 Ei PRO-3370 Si PRO-3390 Si PRO-3400 Si PRO-3400 Si PRO-3410 Si PRO-3420 Si PRO-3420 Si PRO-3420 Si PRO-3420 Si PRO-3420 Si PRO-3420 Si PRO-3450 Ar PRO-3450 Ar PRO-3450 Ar PRO-3460 Fr PRO-3490 Fr PRO-3500 Fr PRO-3510 Fr	Bid, De-scope & RTA - Millwork & Finish Carpentry Dwner Review/Approve RTA- Millwork & Finish Carpentry Fown Building Commission Approves Contract - Millwork & Finish Carpentry Award Contract - Millwork & Finish Carpentry Execute Contract - Millwork & Finish Carpentry Subcontractor Issue Submittals - Millwork Display Cases Subcontractor Issue Submittals - Millwork Wood Benches Subcontractor Issue Submittals - Millwork Countertops Subcontractor Issue Submittals - Millwork Plastic Laminate Casework VE Review & Approve Submittals - Millwork Display Cases VE Review & Approve Submittals - Millwork Display Cases VE Review & Approve Submittals - Millwork Display Cases VE Review & Approve Submittals - Millwork Wood Benches VE Review & Approve Submittals - Millwork Nood Benches VE Review & Approve Submittals - Millwork Plastic Laminate Casework VE Review & Approve Submittals - Millwork Wood Veneer Casework VE Review & Approve Submittals - Millwork Plastic Laminate Casework VE Review & Approve Submittals - Millwork Display Cases Fab & Available for Delivery - Millwork Wood Benches Eab & Available for Delivery - Millwork Wood Benches Fab & Available for Delivery - Millwork Wood Benches Fab & Available for Delivery - Millwork Rod Benches Fab & Available for D	5 1 2 5 25 25 25 25 25 25 15 15 15 15 15 35 35 35 35	18-Feb-20 10-Mar-20 11-Mar-20 20-Mar-20 20-Mar-20 20-Mar-20 20-Mar-20 20-Mar-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 18-May-20	24-Feb-20 10-Mar-20 12-Mar-20 24-Apr-20 24-Apr-20 24-Apr-20 24-Apr-20 24-Apr-20 15-May-20 15-May-20 15-May-20 15-May-20	 Bid, De-scope & RTA - Millwork & Finish Carpentry Owher Review/Approve RTA- Millwork & Finish Carpentry I Town Building Commission Approves Contract - Millwork & Finish Carpentry Award Contract - Millwork & Finish Carpentry Execute Contract - Millwork & Finish Carpentry Execute Contract - Millwork & Finish Carpentry Subcontractor Issue Submittals - Millwork Display Cases Subcontractor Issue Submittals - Millwork Wood Benches Subcontractor Issue Submittals - Millwork Wood Veneer Casework Subcontractor Issue Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Veneer Casework 	N D Jan F Mar Apr M Jun Jul Aug S
PRO-3340 Bi PRO-3350 O PRO-6720 Tr PRO-3360 Ar PRO-3370 Ei PRO-3370 Ei PRO-3370 Ei PRO-3370 Si PRO-3390 Si PRO-3400 Si PRO-3400 Si PRO-3410 Si PRO-3420 Si PRO-3420 Si PRO-3420 Si PRO-3420 Si PRO-3420 Si PRO-3420 Si PRO-3450 Ar PRO-3450 Ar PRO-3450 Ar PRO-3460 Fr PRO-3490 Fr PRO-3500 Fr PRO-3510 Fr	Bid, De-scope & RTA - Millwork & Finish Carpentry Dwner Review/Approve RTA- Millwork & Finish Carpentry Fown Building Commission Approves Contract - Millwork & Finish Carpentry Award Contract - Millwork & Finish Carpentry Execute Contract - Millwork & Finish Carpentry Subcontractor Issue Submittals - Millwork Display Cases Subcontractor Issue Submittals - Millwork Wood Benches Subcontractor Issue Submittals - Millwork Countertops Subcontractor Issue Submittals - Millwork Plastic Laminate Casework VE Review & Approve Submittals - Millwork Display Cases VE Review & Approve Submittals - Millwork Display Cases VE Review & Approve Submittals - Millwork Display Cases VE Review & Approve Submittals - Millwork Wood Benches VE Review & Approve Submittals - Millwork Nood Benches VE Review & Approve Submittals - Millwork Plastic Laminate Casework VE Review & Approve Submittals - Millwork Wood Veneer Casework VE Review & Approve Submittals - Millwork Plastic Laminate Casework VE Review & Approve Submittals - Millwork Display Cases Fab & Available for Delivery - Millwork Wood Benches Eab & Available for Delivery - Millwork Wood Benches Fab & Available for Delivery - Millwork Wood Benches Fab & Available for Delivery - Millwork Rod Benches Fab & Available for D	5 1 2 5 25 25 25 25 25 25 15 15 15 15 15 35 35 35 35	18-Feb-20 10-Mar-20 11-Mar-20 20-Mar-20 20-Mar-20 20-Mar-20 20-Mar-20 20-Mar-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 18-May-20	24-Feb-20 10-Mar-20 12-Mar-20 24-Apr-20 24-Apr-20 24-Apr-20 24-Apr-20 24-Apr-20 15-May-20 15-May-20 15-May-20 15-May-20	 Owher Review/Approve RTA- Millwork & Finish Carpentry Town Building Commission Approves Contract - Millwork & Finish Carpentry Award Contract - Millwork & Finish Carpentry Execute Contract - Millwork & Finish Carpentry Execute Contract - Millwork & Finish Carpentry Subcontractor Issue Submittals - Millwork Display Cases Subcontractor Issue Submittals - Millwork Wood Benches Subcontractor Issue Submittals - Millwork Countertops Subcontractor Issue Submittals - Millwork Wood Veneer Casework Subcontractor Issue Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Display Cases A/E Review & Approve Submittals - Millwork Display Cases A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Veneer Casework 	
PRO-3350 O PRO-6720 Tr PRO-3360 Ar PRO-3370 Er PRO-3370 Er PRO-3370 Er PRO-3370 Sr PRO-3390 Sr PRO-3400 Sr PRO-3410 Sr PRO-3420 Sr PRO-3420 Sr PRO-3420 Ar PRO-3440 Ar PRO-3440 Ar PRO-3440 Ar PRO-3440 Ar PRO-3440 Ar PRO-3440 Fr PRO-3440 Fr PRO-3450 Fr PRO-3460 Fr PRO-3490 Fr PRO-3500 Fr PRO-3510 Fr	Dwner Review/Approve RTA- Millwork & Finish Carpentry Town Building Commission Approves Contract - Millwork & Finish Carpentry Award Contract - Millwork & Finish Carpentry Execute Contract - Millwork & Finish Carpentry Subcontractor Issue Submittals - Millwork Display Cases Subcontractor Issue Submittals - Millwork Wood Benches Subcontractor Issue Submittals - Millwork Countertops Subcontractor Issue Submittals - Millwork Vood Veneer Casework Subcontractor Issue Submittals - Millwork Plastic Laminate Casework AVE Review & Approve Submittals - Millwork Wood Benches AVE Review & Approve Submittals - Millwork Wood Benches AVE Review & Approve Submittals - Millwork Display Cases AVE Review & Approve Submittals - Millwork Wood Benches AVE Review & Approve Submittals - Millwork Wood Veneer Casework AVE Review & Approve Submittals - Millwork Wood Veneer Casework AVE Review & Approve Submittals - Millwork Wood Veneer Casework AVE Review & Approve Submittals - Millwork Wood Veneer Casework AVE Review & Approve Submittals - Millwork Wood Veneer Casework AVE Review & Approve Submittals - Millwork Display Cases Fab & Available for Delivery - Millwork Display Cases Fab & Available for Delivery - Millwork Wood Benches Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Plastic Laminate Casework Fab & Available for Delivery - Millwork Plastic Laminate Casework	5 1 2 5 25 25 25 25 25 25 15 15 15 15 15 35 35 35 35	18-Feb-20 10-Mar-20 11-Mar-20 20-Mar-20 20-Mar-20 20-Mar-20 20-Mar-20 20-Mar-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 18-May-20	24-Feb-20 10-Mar-20 12-Mar-20 24-Apr-20 24-Apr-20 24-Apr-20 24-Apr-20 24-Apr-20 15-May-20 15-May-20 15-May-20 15-May-20	 Owher Review/Approve RTA- Millwork & Finish Carpentry Town Building Commission Approves Contract - Millwork & Finish Carpentry Award Contract - Millwork & Finish Carpentry Execute Contract - Millwork & Finish Carpentry Execute Contract - Millwork & Finish Carpentry Subcontractor Issue Submittals - Millwork Display Cases Subcontractor Issue Submittals - Millwork Wood Benches Subcontractor Issue Submittals - Millwork Countertops Subcontractor Issue Submittals - Millwork Wood Veneer Casework Subcontractor Issue Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Display Cases A/E Review & Approve Submittals - Millwork Display Cases A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Veneer Casework 	
PRO-6720 Tr PRO-3360 A PRO-3360 E PRO-3370 E PRO-3370 E PRO-3380 Si PRO-3390 Si PRO-3400 Si PRO-3410 Si PRO-3420 Si PRO-3420 Si PRO-3420 Si PRO-3420 A PRO-3420 A PRO-3440 A PRO-3450 A PRO-3450 A PRO-3460 A PRO-3460 F PRO-3490 F PRO-3500 F PRO-3510 F	Town Building Commission Approves Contract - Millwork & Finish Carpentry Award Contract - Millwork & Finish Carpentry Execute Contract - Millwork & Finish Carpentry Subcontractor Issue Submittals - Millwork Display Cases Subcontractor Issue Submittals - Millwork Wood Benches Subcontractor Issue Submittals - Millwork Countertops Subcontractor Issue Submittals - Millwork Wood Veneer Casework Subcontractor Issue Submittals - Millwork Plastic Laminate Casework AVE Review & Approve Submittals - Millwork Wood Benches AVE Review & Approve Submittals - Millwork Wood Benches AVE Review & Approve Submittals - Millwork Wood Veneer Casework AVE Review & Approve Submittals - Millwork Display Cases AVE Review & Approve Submittals - Millwork Wood Veneer Casework AVE Review & Approve Submittals - Millwork Wood Veneer Casework AVE Review & Approve Submittals - Millwork Wood Veneer Casework AVE Review & Approve Submittals - Millwork Wood Veneer Casework AVE Review & Approve Submittals - Millwork Wood Veneer Casework AVE Review & Approve Submittals - Millwork Display Cases Fab & Available for Delivery - Millwork Wood Benches Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & A	1 2 5 25 25 25 25 25 25 25 25 15 15 15 15 15 15 35 35 35	10-Mar-20 11-Mar-20 20-Mar-20 20-Mar-20 20-Mar-20 20-Mar-20 20-Mar-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 18-May-20	10-Mar-20 12-Mar-20 24-Apr-20 24-Apr-20 24-Apr-20 24-Apr-20 24-Apr-20 24-Apr-20 15-May-20 15-May-20 15-May-20 15-May-20	 Town Building Commission Approves Contract - Millwork & Finish Carpentry Award Contract - Millwork & Finish Carpentry Execute Contract - Millwork & Finish Carpentry Subcontractor Issue Submittals - Millwork Display Cases Subcontractor Issue Submittals - Millwork Wood Benches Subcontractor Issue Submittals - Millwork Wood Veneer Casework Subcontractor Issue Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Countertops A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches 	
PRO-3360 Ai PRO-3370 Ei PRO-3370 Ei PRO-3370 Si PRO-3380 Si PRO-3400 Si PRO-3410 Si PRO-3420 Si PRO-3420 Si PRO-3430 Ai PRO-3430 Ai PRO-3440 Ai PRO-3450 Ai PRO-3460 Ai PRO-3460 Fi PRO-3460 Fi PRO-3490 Fi PRO-3490 Fi PRO-3500 Fi PRO-3510 Fi	Award Contract - Millwork & Finish Carpentry Execute Contract - Millwork & Finish Carpentry Subcontractor Issue Submittals - Millwork Display Cases Subcontractor Issue Submittals - Millwork Wood Benches Subcontractor Issue Submittals - Millwork Countertops Subcontractor Issue Submittals - Millwork Wood Veneer Casework Subcontractor Issue Submittals - Millwork Plastic Laminate Casework Subcontractor Issue Submittals - Millwork Plastic Laminate Casework AVE Review & Approve Submittals - Millwork Display Cases AVE Review & Approve Submittals - Millwork Wood Benches AVE Review & Approve Submittals - Millwork Countertops AVE Review & Approve Submittals - Millwork Wood Veneer Casework AVE Review & Approve Submittals - Millwork Plastic Laminate Casework AVE Review & Approve Submittals - Millwork Plastic Laminate Casework AVE Review & Approve Submittals - Millwork Plastic Laminate Casework AVE Review & Approve Submittals - Millwork Display Cases Fab & Available for Delivery - Millwork Plastic Laminate Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework	2 5 25 25 25 25 25 25 15 15 15 15 15 35 35 35 35	11-Mar-20 13-Mar-20 20-Mar-20 20-Mar-20 20-Mar-20 20-Mar-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 18-May-20	12-Mar-20 19-Mar-20 24-Apr-20 24-Apr-20 24-Apr-20 24-Apr-20 24-Apr-20 15-May-20 15-May-20 15-May-20 15-May-20	 Award Contract - Millwork & Finish Carpentry Execute Contract - Millwork & Finish Carpentry Subcontractor Issue Submittals - Millwork Display Cases Subcontractor Issue Submittals - Millwork Wood Benches Subcontractor Issue Submittals - Millwork Countertops Subcontractor Issue Submittals - Millwork Wood Veneer Casework Subcontractor Issue Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Countertops A/E Review & Approve Submittals - Millwork Display Cases A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Veneer Casework 	
PRO-3370 Ei PRO-3380 Si PRO-3390 Si PRO-3400 Si PRO-3410 Si PRO-3410 Si PRO-3420 Si PRO-3420 Si PRO-3420 Si PRO-3440 Ai PRO-3460 Ai PRO-3470 Ai PRO-3490 Fi PRO-3500 Fi PRO-3510 Fi	Execute Contract - Millwork & Finish Carpentry Subcontractor Issue Submittals - Millwork Display Cases Subcontractor Issue Submittals - Millwork Wood Benches Subcontractor Issue Submittals - Millwork Countertops Subcontractor Issue Submittals - Millwork Wood Veneer Casework Subcontractor Issue Submittals - Millwork Plastic Laminate Casework AVE Review & Approve Submittals - Millwork Display Cases AVE Review & Approve Submittals - Millwork Wood Benches AVE Review & Approve Submittals - Millwork Countertops AVE Review & Approve Submittals - Millwork Countertops AVE Review & Approve Submittals - Millwork Wood Veneer Casework AVE Review & Approve Submittals - Millwork Wood Veneer Casework AVE Review & Approve Submittals - Millwork Plastic Laminate Casework AVE Review & Approve Submittals - Millwork Display Cases Fab & Available for Delivery - Millwork Wood Benches Fab & Available for Delivery - Millwork Wood Benches Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework	5 25 25 25 25 25 15 15 15 15 15 35 35 35 35	13-Mar-20 20-Mar-20 20-Mar-20 20-Mar-20 20-Mar-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 18-May-20	19-Mar-20 24-Apr-20 24-Apr-20 24-Apr-20 24-Apr-20 24-Apr-20 15-May-20 15-May-20 15-May-20 15-May-20	 Execute Contract - Millwork & Finish Carpentry Subcontractor Issue Submittals - Millwork Display Cases Subcontractor Issue Submittals - Millwork Wood Benches Subcontractor Issue Submittals - Millwork Countertops Subcontractor Issue Submittals - Millwork Wood Veneer Casework Subcontractor Issue Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Countertops A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Veneer Casework 	
PRO-3380 Si PRO-3390 Si PRO-3400 Si PRO-3410 Si PRO-3410 Si PRO-3420 Si PRO-3420 Si PRO-3420 Si PRO-3420 Si PRO-3440 Ai PRO-3440 Ai PRO-3450 Ai PRO-3460 Ai PRO-3460 Fi PRO-3470 Ai PRO-3480 Fi PRO-3500 Fi PRO-3500 Fi PRO-3520 Fi	Subcontractor Issue Submittals - Millwork Display Cases Subcontractor Issue Submittals - Millwork Wood Benches Subcontractor Issue Submittals - Millwork Countertops Subcontractor Issue Submittals - Millwork Wood Veneer Casework Subcontractor Issue Submittals - Millwork Plastic Laminate Casework AVE Review & Approve Submittals - Millwork Display Cases AVE Review & Approve Submittals - Millwork Wood Benches AVE Review & Approve Submittals - Millwork Countertops AVE Review & Approve Submittals - Millwork Wood Veneer Casework AVE Review & Approve Submittals - Millwork Wood Veneer Casework AVE Review & Approve Submittals - Millwork Plastic Laminate Casework AVE Review & Approve Submittals - Millwork Plastic Laminate Casework AVE Review & Approve Submittals - Millwork Display Cases Fab & Available for Delivery - Millwork Wood Benches Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework	25 25 25 25 25 15 15 15 15 15 35 35 35 35	20-Mar-20 20-Mar-20 20-Mar-20 20-Mar-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 18-May-20	24-Apr-20 24-Apr-20 24-Apr-20 24-Apr-20 24-Apr-20 15-May-20 15-May-20 15-May-20 15-May-20	 Subcontractor Issue Submittals - Millwork Display Cases Subcontractor Issue Submittals - Millwork Wood Benches Subcontractor Issue Submittals - Millwork Countertops Subcontractor Issue Submittals - Millwork Wood Veneer Casework Subcontractor Issue Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Display Cases A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Countertops A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Wood Veneer Casework 	
PRO-3390 Si PRO-3400 Si PRO-3410 Si PRO-3420 Si PRO-3420 Si PRO-3420 Si PRO-3420 Si PRO-3440 Ai PRO-3440 Ai PRO-3450 Ai PRO-3460 Ai PRO-3460 Fi PRO-3470 Ai PRO-3480 Fi PRO-3490 Fi PRO-3500 Fi PRO-3510 Fi	Subcontractor Issue Submittals - Millwork Wood Benches Subcontractor Issue Submittals - Millwork Countertops Subcontractor Issue Submittals - Millwork Wood Veneer Casework Subcontractor Issue Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Display Cases A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Countertops A/E Review & Approve Submittals - Millwork Wood Veneer Casework A/E Review & Approve Submittals - Millwork Wood Veneer Casework A/E Review & Approve Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Display Cases Fab & Available for Delivery - Millwork Wood Benches Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework	25 25 25 25 15 15 15 15 15 35 35 35 35	20-Mar-20 20-Mar-20 20-Mar-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 18-May-20	24-Apr-20 24-Apr-20 24-Apr-20 24-Apr-20 15-May-20 15-May-20 15-May-20 15-May-20	Subcontractor Issue Submittals - Millwork Wood Benches Subcontractor Issue Submittals - Millwork Countertops Subcontractor Issue Submittals - Millwork Wood Veneer Casework Subcontractor Issue Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Display Cases A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Countertops A/E Review & Approve Submittals - Millwork Countertops A/E Review & Approve Submittals - Millwork Wood Veneer Casework	
PRO-3400 Si PRO-3410 Si PRO-3420 Si PRO-3420 Si PRO-3420 Ai PRO-3430 Ai PRO-3440 Ai PRO-3450 Ai PRO-3460 Ai PRO-3460 Fi PRO-3470 Ai PRO-3480 Fi PRO-3490 Fi PRO-3500 Fi PRO-3510 Fi	Subcontractor Issue Submittals - Millwork Countertops Subcontractor Issue Submittals - Millwork Wood Veneer Casework Subcontractor Issue Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Display Cases A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Countertops A/E Review & Approve Submittals - Millwork Wood Veneer Casework A/E Review & Approve Submittals - Millwork Wood Veneer Casework A/E Review & Approve Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Plastic Laminate Casework Fab & Available for Delivery - Millwork Wood Benches Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework	25 25 25 15 15 15 15 15 15 35 35 35 35	20-Mar-20 20-Mar-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 18-May-20	24-Apr-20 24-Apr-20 24-Apr-20 15-May-20 15-May-20 15-May-20 15-May-20	Subcontractor Issue Submittals - Millwork Countertops Subcontractor Issue Submittals - Millwork Wood Veneer Casework Subcontractor Issue Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Display Cases A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Countertops A/E Review & Approve Submittals - Millwork Wood Veneer Casework	
PRO-3410 Si PRO-3420 Si PRO-3430 A PRO-3440 A PRO-3450 A PRO-3450 A PRO-3460 A PRO-3460 Fi PRO-3460 Fi PRO-3460 Fi PRO-3460 Fi PRO-3480 Fi PRO-3500 Fi PRO-3510 Fi	Subcontractor Issue Submittals - Millwork Wood Veneer Casework Subcontractor Issue Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Display Cases A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Countertops A/E Review & Approve Submittals - Millwork Wood Veneer Casework A/E Review & Approve Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Plastic Laminate Casework Fab & Available for Delivery - Millwork Wood Benches Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Plastic Laminate Casework	25 25 15 15 15 15 15 15 35 35 35 35	20-Mar-20 20-Mar-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 18-May-20	24-Apr-20 24-Apr-20 15-May-20 15-May-20 15-May-20 15-May-20	Subcontractor Issue Submittals - Millwork Wood Veneer Casework Subcontractor Issue Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Display Cases A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Countertops A/E Review & Approve Submittals - Millwork Wood Veneer Casework	
PRO-3420 Si PRO-3430 A PRO-3440 A PRO-3450 A PRO-3450 A PRO-3460 A PRO-3460 A PRO-3470 A PRO-3480 Fi PRO-3490 Fi PRO-3500 Fi PRO-3510 Fi	Subcontractor Issue Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Display Cases A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Countertops A/E Review & Approve Submittals - Millwork Wood Veneer Casework A/E Review & Approve Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Plastic Laminate Casework Fab & Available for Delivery - Millwork Wood Benches Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Plastic Laminate Casework	25 15 15 15 15 15 15 35 35 35 35	20-Mar-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 18-May-20	24-Apr-20 15-May-20 15-May-20 15-May-20 15-May-20	Subcontractor Issue Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Display Cases A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Countertops A/E Review & Approve Submittals - Millwork Wood Veneer Casework	
PRO-3430 A PRO-3440 A PRO-3450 A PRO-3460 A PRO-3460 A PRO-3470 A PRO-3480 Fa PRO-3490 Fa PRO-3500 Fa PRO-3510 Fa PRO-3520 Fa	VE Review & Approve Submittals - Millwork Display Cases VE Review & Approve Submittals - Millwork Wood Benches VE Review & Approve Submittals - Millwork Countertops VE Review & Approve Submittals - Millwork Wood Veneer Casework VE Review & Approve Submittals - Millwork Plastic Laminate Casework A/E Review & Approve Submittals - Millwork Plastic Laminate Casework Fab & Available for Delivery - Millwork Display Cases Fab & Available for Delivery - Millwork Wood Benches Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Plastic Laminate Casework	15 15 15 15 15 15 35 35 35 35	27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 18-May-20	15-May-20 15-May-20 15-May-20 15-May-20	 A/E Review & Approve Submittals - Millwork Display Cases A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Countertops A/E Review & Approve Submittals - Millwork Wood Veneer Casework 	
PRO-3440 A PRO-3450 A PRO-3460 A PRO-3460 A PRO-3460 A PRO-3470 A PRO-3480 Fi PRO-3490 Fi PRO-3500 Fi PRO-3510 Fi	VE Review & Approve Submittals - Millwork Wood Benches VE Review & Approve Submittals - Millwork Countertops VE Review & Approve Submittals - Millwork Wood Veneer Casework VE Review & Approve Submittals - Millwork Plastic Laminate Casework Fab & Available for Delivery - Millwork Display Cases Fab & Available for Delivery - Millwork Wood Benches Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Plastic Laminate Casework	15 15 15 15 35 35 35 35	27-Apr-20 27-Apr-20 27-Apr-20 27-Apr-20 18-May-20	15-May-20 15-May-20 15-May-20	A/E Review & Approve Submittals - Millwork Wood Benches A/E Review & Approve Submittals - Millwork Countertops A/E Review & Approve Submittals - Millwork Wood Veneer Casework	
PRO-3450 A PRO-3460 A PRO-3460 A PRO-3470 A PRO-3480 Fi PRO-3490 Fi PRO-3500 Fi PRO-3510 Fi PRO-3520 Fi	VE Review & Approve Submittals - Millwork Countertops VE Review & Approve Submittals - Millwork Wood Veneer Casework VE Review & Approve Submittals - Millwork Plastic Laminate Casework Fab & Available for Delivery - Millwork Display Cases Fab & Available for Delivery - Millwork Wood Benches Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Plastic Laminate Casework	15 15 15 35 35 35 35	27-Apr-20 27-Apr-20 27-Apr-20 18-May-20	15-May-20 15-May-20	A/E Review & Approve Submittals / Millwork Countertops A/E Review & Approve Submittals - Millwork Wood Veneer Casework	
PRO-3460 A PRO-3470 A PRO-3480 Fi PRO-3490 Fi PRO-3500 Fi PRO-3510 Fi PRO-3520 Fi	VE Review & Approve Submittals - Millwork Wood Veneer Casework VE Review & Approve Submittals - Millwork Plastic Laminate Casework Fab & Available for Delivery - Millwork Display Cases Fab & Available for Delivery - Millwork Wood Benches Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Plastic Laminate Casework	15 15 35 35 35 35	27-Apr-20 27-Apr-20 18-May-20	15-May-20	A/E Review & Approve Submittals - Millwork Wood Veneer Casework	
PRO-3470 A PRO-3480 Fi PRO-3490 Fi PRO-3500 Fi PRO-3510 Fi PRO-3520 Fi	WE Review & Approve Submittals - Millwork Plastic Laminate Casework Fab & Available for Delivery - Millwork Display Cases Fab & Available for Delivery - Millwork Wood Benches Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Plastic Laminate Casework	15 35 35 35 35	27-Apr-20 18-May-20			· · · · · · · · · · · · · · · · · · ·
PRO-3470 A PRO-3480 Fa PRO-3490 Fa PRO-3500 Fa PRO-3510 Fa PRO-3520 Fa	WE Review & Approve Submittals - Millwork Plastic Laminate Casework Fab & Available for Delivery - Millwork Display Cases Fab & Available for Delivery - Millwork Wood Benches Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Plastic Laminate Casework	35 35 35	18-May-20			
PRO-3480 Fa PRO-3490 Fa PRO-3500 Fa PRO-3510 Fa PRO-3520 Fa	Fab & Available for Delivery - Millwork Display Cases Fab & Available for Delivery - Millwork Wood Benches Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Plastic Laminate Casework	35 35	18-May-20		A/E Review & Approve Submittals - Millwork Plastic Laminate Casework	
PRO-3490 Fa PRO-3500 Fa PRO-3510 Fa PRO-3520 Fa	Fab & Available for Delivery - Millwork Wood Benches Fab & Available for Delivery - Millwork Wood Veneer Casework Fab & Available for Delivery - Millwork Plastic Laminate Casework	35 35		07-Jul-20	Fab & Available for Delivery - Millwork Display Cases	
PRO-3500 Fa PRO-3510 Fa PRO-3520 Fa	ab & Available for Delivery - Millwork Wood Veneer Casework ab & Available for Delivery - Millwork Plastic Laminate Casework	35	18-May-20	07-Jul-20	Fab & Available for Delivery - Millwork Wood Benches	
PRO-3510 Fa	ab & Available for Delivery - Millwork Plastic Laminate Casework		18-May-20	07-Jul-20	Fab & Available for Delivery - Millwork Wood Veneer Casework	
PRO-3520 F		35	18-May-20	07-Jul-20	Fab & Available for Delivery - Millwork Plastic Laminate Casework	
	as a walk being being will were been being a second being be	40	18-May-20	14-Jul-20	Fab & Available for Delivery - Millwork Countertops	
Our Service Equi	inment	-10	To May 20	14 001 20		
PRO-3530 Bi	Bid, De-scope & RTA - Food Service Equipment	5	23-Dec-19 A	14-Feb-20	Bid, De-scope & RTA - Food Service Equipment	
		5	18-Feb-20	24-Feb-20	 Owner Review/Approve RTA - Food Service Equipment 	
	Dwner Review/Approve RTA - Food Service Equipment	5			*	
	Fown Building Commission Approves Contract - Food Service Equipment	1	10-Mar-20	10-Mar-20	I Town Building Commission Approves Contract - Food Service Equipment	
	Award Contract - Food Service Equipment	2	11-Mar-20	12-Mar-20	Award Contract - Food Service Equipment	
	Execute Contract - Food Service Equipment	5	13-Mar-20	19-Mar-20	Execute Contract - Food Service Equipment	
	Subcontractor Issue Submittals - Food Service Equipment	20	20-Mar-20	16-Apr-20	Subcontractor Issue Submittals - Food Service Equipment	
	Subcontractor Issue Submittals - Wak-In Cooler/Freezer	20	20-Mar-20	16-Apr-20	Subcontractor Issue Submittals - Walk+In Cooler/Freezer	
	Subcontractor Issue Submittals - Hood System (Make Up Air Exhaust)	20	20-Mar-20	16-Apr-20	Subcontractor Issue Submittals - Hood System (Make Up Air Exhaust)	
	VE Review & Approve Submittals - Food Service Equipment	15	17-Apr-20	08-May-20	A/E Review & Approve Submittals - Food Service Equipment	
	VE Review & Approve Submittals - Walk-In Cooler/Freezer	15	17-Apr-20	08-May-20	A/E Review & Approve Submittals - Walk-In Cooler/Freezer	
PRO-3620 A	VE Review & Approve Submittals - Hood System (Make Up Air Exhaust)	15	17-Apr-20	08-May-20	A/E Review & Approve Submittals - Hood System (Make Up Air Exhaust)	
PRO-3630 F	Fab & Available for Delivery - Hood System (Make Up Air Exhaust)	65	11-May-20	11-Aug-20	Fab & Available for Delivery - Hood System (Make Up Air Exhaust)	
PRO-3640 F	Fab & Available for Delivery - Food Service Equipment	65	11-May-20	11-Aug-20	Fab & Available for Delivery - Food Service Equipment	
PRO-3650 F	Fab & Available for Delivery - Walk-In Cooler/Freezer	65	11-May-20	11-Aug-20	Fab & Available for Delivery - Walk-In Cooler/Freezer	
Overhead Doors &	& Fire Shutters					
PRO-5450 B	Bid, De-scope & RTA - Overhead Doors & Fire Shutters	5	30-Dec-19 A	14-Feb-20	Bid, De-scope & RTA - Overhead Doors & Fire Shutters	
PRO-5410 0	Owner Review/Approve RTA - Overhead Doors & Fire Shutters	5	18-Feb-20	24-Feb-20	Owner Review/Approve RTA - Overhead Doors & Fire Shutters	
	Town Building Commission Approves Contract - Overhead Doors & Fire Shutters	1	10-Mar-20	10-Mar-20	I Town Building Commission Approves Contract - Overhead Doors & Fire Shutters	
	Award Contract - Overhead Doors & Fire Shutters	2	11-Mar-20	12-Mar-20	Award Contract - Overhead Doors & Fire Shutters	
	Execute Contract - Overhead Doors & Fire Shutters	5	13-Mar-20	19-Mar-20	Execute Contract - Overhead Doors & Fire Shutters	
	Subcontractor Issue Submittals - Loading Dock Equipment	20	20-Mar-20	16-Apr-20	Subcontractor Issue Submittals - Loading Dock Equipment	
	Subcontractor Issue Submittals - Overhead Doors & Fire Shutters	20	20-Mar-20	16-Apr-20	Subcontractor Issue Submittals - Overhead Doors & Fire Shutters	
	A/E Review & Approve Submittals - Loading Dock Equipment	15	17-Apr-20	08-May-20	A/E Review & Approve Submittals - Loading Dock Equipment	
	VE Review & Approve Submittals - Overhead Doors & Fire Shutters	15	17-Apr-20	08-May-20	A/E Review & Approve Submittals - Overhead Doors & Fire Shutters	
	Fab & Available for Delivery - Loading Dock Equipment	50	11-May-20	21-Jul-20	Fab & Available for Delivery - Loading Dock Equipment	
	Fab & Available for Delivery - Overhead Doors & Fire Shutters	65	11-May-20	11-Aug-20	Fab & Available for Delivery - Overhead Doors & Fire Shutters	
Nood Flooring			20 Dec 40.4	14 Eak 00		
	Bid, De-scope & RTA - Wood Flooring	5	30-Dec-19 A		Bid, De-scope & RTA - Wood Flooring	
	Dwner Review/Approve RTA - Wood Flooring	5	18-Feb-20	24-Feb-20	Owner Review/Approve RTA - Wood Flooring	
	Town Building Commission Approves Contract - Wood Flooring	1	10-Mar-20	10-Mar-20	I Town Building Commission Approves Contract - Wood Flooring	
	Award Contract - Wood Flooring	2	11-Mar-20	12-Mar-20	Award Contract - Wood Flooring	
	Execute Contract - Wood Flooring	5	13-Mar-20	19-Mar-20	Execute Contract - Wood Flooring	
PRO-3770 S	Subcontractor Issue Submittals - Wood Flooring	20	20-Mar-20	16-Apr-20	Subcontractor Issue Submittals - Wood Flooring	
Remaining Lev	vel of Effort Remaining Work		Page 10 of	f 29	TASK filter: Uncompleted Activities Two Months Prior.	
 Actual Level of 			rage 10 0	. 20	© Oracle Corporation	CIZANCIZA
Actual Level of Actual Work				_	e 58 of 377	SKANSKA

ID PRO-3780 PRO-3790 PRO-3800 PRO-3810 PRO-6810 PRO-3820 PRO-3830 PRO-3840 PRO-3850 PRO-3860 Carpet	Activity Name A/E Review & Approve Submittals - Wood Flooring Fab & Available for Delivery - Wood Flooring Bid, De-scope & RTA - Epoxy Flooring Owner Review/Approve RTA - Epoxy Flooring Town Building Commission Approves Contract - Epoxy Flooring Award Contract - Epoxy Flooring Execute Contract - Epoxy Flooring Subcontractor Issue Submittals - Epoxy Flooring A/E Review & Approve Submittals - Epoxy Flooring	Remaining Duration 15 30 5 5 1 2 5 1 2 5	Start 17-Apr-20 11-May-20 13-Jan-20 A	Finish 08-May-20 22-Jun-20	2020 F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr N A/E Review & Approve Submittals - Wood Flooring Fab & Available for Delivery - Wood Flooring
PRO-3790 poxy Flooring PRO-3800 PRO-3810 PRO-6810 PRO-3820 PRO-3830 PRO-3840 PRO-3850 PRO-3860	Fab & Available for Delivery - Wood Flooring Bid, De-scope & RTA - Epoxy Flooring Owner Review/Approve RTA - Epoxy Flooring Town Building Commission Approves Contract - Epoxy Flooring Award Contract - Epoxy Flooring Execute Contract - Epoxy Flooring Subcontractor Issue Submittals - Epoxy Flooring	15 30 5 5 1 2	11-May-20	•	F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr N A/E Review & Approve Submittals - Wood Flooring
PRO-3790 poxy Flooring PRO-3800 PRO-3810 PRO-6810 PRO-3820 PRO-3830 PRO-3840 PRO-3850 PRO-3860	Fab & Available for Delivery - Wood Flooring Bid, De-scope & RTA - Epoxy Flooring Owner Review/Approve RTA - Epoxy Flooring Town Building Commission Approves Contract - Epoxy Flooring Award Contract - Epoxy Flooring Execute Contract - Epoxy Flooring Subcontractor Issue Submittals - Epoxy Flooring	30 5 5 1 2	11-May-20	•	A/E Review & Approve Submittals - Wood Flooring
poxy Flooring PRO-3800 PRO-3810 PRO-6810 PRO-3820 PRO-3830 PRO-3840 PRO-3850 PRO-3860	Bid, De-scope & RTA - Epoxy Flooring Owner Review/Approve RTA - Epoxy Flooring Town Building Commission Approves Contract - Epoxy Flooring Award Contract - Epoxy Flooring Execute Contract - Epoxy Flooring Subcontractor Issue Submittals - Epoxy Flooring	5 5 1 2	_	22-Jun-20	Fab & Available for Delivery - Wood Flooring
PRO-3800 PRO-3810 PRO-6810 PRO-3820 PRO-3830 PRO-3840 PRO-3850 PRO-3860	Owner Review/Approve RTA - Epoxy Flooring Town Building Commission Approves Contract - Epoxy Flooring Award Contract - Epoxy Flooring Execute Contract - Epoxy Flooring Subcontractor Issue Submittals - Epoxy Flooring	5 1 2	13-Jan-20 A		
PRO-3800 PRO-3810 PRO-6810 PRO-3820 PRO-3830 PRO-3840 PRO-3850 PRO-3860	Owner Review/Approve RTA - Epoxy Flooring Town Building Commission Approves Contract - Epoxy Flooring Award Contract - Epoxy Flooring Execute Contract - Epoxy Flooring Subcontractor Issue Submittals - Epoxy Flooring	5 1 2	13-Jan-20 A		
PRO-3810 PRO-6810 PRO-3820 PRO-3830 PRO-3840 PRO-3850 PRO-3860	Owner Review/Approve RTA - Epoxy Flooring Town Building Commission Approves Contract - Epoxy Flooring Award Contract - Epoxy Flooring Execute Contract - Epoxy Flooring Subcontractor Issue Submittals - Epoxy Flooring	1 2		14-Feb-20	Bid, De-scope & RTA - Epoxy Flooring
PRO-6810 PRO-3820 PRO-3830 PRO-3840 PRO-3850 PRO-3860	Town Building Commission Approves Contract - Epoxy Flooring Award Contract - Epoxy Flooring Execute Contract - Epoxy Flooring Subcontractor Issue Submittals - Epoxy Flooring	1 2	18-Feb-20	24-Feb-20	Owner Review/Approve RTA - Epoxy Flooring
PRO-3820 PRO-3830 PRO-3840 PRO-3850 PRO-3860	Award Contract - Epoxy Flooring Execute Contract - Epoxy Flooring Subcontractor Issue Submittals - Epoxy Flooring	2	10-Mar-20	10-Mar-20	I Town Building Commission Approves Contract - Epoxy Flooring
PRO-3830 PRO-3840 PRO-3850 PRO-3860	Execute Contract - Epoxy Flooring Subcontractor Issue Submittals - Epoxy Flooring		11-Mar-20	12-Mar-20	Award Contract - Epoxy Flooring
PRO-3840 PRO-3850 PRO-3860	Subcontractor Issue Submittals - Epoxy Flooring	J	13-Mar-20	19-Mar-20	Execute Contract - Epoxy Hooring
PRO-3850 PRO-3860		20	20-Mar-20		Subcontractor Issue Submittals - Epoxy Flooring
PRO-3860				16-Apr-20	
		15	17-Apr-20	08-May-20	A/E Review & Approve Submittals - Epoxy Flooring
arpet	Fab & Available for Delivery - Epoxy Flooring	25	11-May-20	15-Jun-20	Fab & Available for Delivery - Epoxy Flooring
-					
PRO-3870	Bid, De-scope & RTA - Carpet	5	13-Jan-20 A	14-Feb-20	Bid, De-scope & RTA - Carpet
PRO-3880	Owner Review/Approve RTA - Carpet	5	18-Feb-20	24-Feb-20	Owner Review/Approve RTA - Carpet
PRO-6820	Town Building Commission Approves Contract - Carpet	1	10-Mar-20	10-Mar-20	I Town Building Commission Approves Contract - Carpet
PRO-3890	Award Contract - Carpet	2	11-Mar-20	12-Mar-20	Award Contract - Carpet
PRO-3900	Execute Contract - Carpet	5	13-Mar-20	19-Mar-20	Execute Contract - Carpet
PRO-3910	Subcontractor Issue Submittals - Carpet	20	20-Mar-20	16-Apr-20	Subcontractor Issue Submittals - Carpet
PRO-3920	A/E Review & Approve Submittals - Carpet	15	17-Apr-20	08-May-20	A/E Review & Approve Submittals - Carpet
PRO-3930	Fab & Available for Delivery - Carpet	25	11-May-20	15-Jun-20	Fab & Available for Delivery - Carpet
ite Concrete		20	11 11/120	10 0411 20	
PRO-5590	Bid, De-scope & RTA - Site Concrete	5	27-Jan-20 A	14-Feb-20	Bid, De-scope & RTA - Site Concrete
PRO-5550	Owner Review/Approve RTA - Site Concrete	5	18-Feb-20	24-Feb-20	Owher Review/Approve RTA - Site Concrete
PRO-6830	Town Building Commission Approves Contract - Site Concrete	1	10-Mar-20	10-Mar-20	I Town Building Commission Approves Contract - Site Concrete
PRO-5540	Award Contract - Site Concrete	2	11-Mar-20	12-Mar-20	Award Contract - Site Concrete
PRO-5530	Execute Contract - Site Concrete	5	13-Mar-20	19-Mar-20	Execute Contract - Site Concrete
PRO-5580	Subcontractor Issue Submittals - Site Concrete	15	20-Mar-20	09-Apr-20	Subcontractor Issue Submittals - Site Concrete
PRO-5570	A/E Review & Approve Submittals - Site Concrete	15	10-Apr-20	01-May-20	A/E Review & Approve Submittals - \$ite Concrete
PRO-5560	Fab & Available for Delivery - Site Concrete	20	04-May-20	01-Jun-20	Fab & Available for Delivery - Site Concrete
pecialties					
PRO-4080	Bid, De-scope & RTA - Specialties	5	14-Jan-20 A	14-Feb-20	Bid, De-scope & RTA - Specialties
PRO-4090	Owner Review/Approve RTA - Specialties	5	18-Feb-20	24-Feb-20	Owher Review/Approve RTA - Specialties
PRO-6840	Town Building Commission Approves Contract - Specialties	1	10-Mar-20	10-Mar-20	I Town Building Commission Approves Contract - Specialties
PRO-4100	Award Contract - Specialties	2	11-Mar-20	12-Mar-20	Award Contract - Specialties
PRO-4110	Execute Contract - Specialties	5	13-Mar-20	19-Mar-20	Execute Contract - Specialties
PRO-4120	Subcontractor Issue Submittals - Specialties	20	20-Mar-20	16-Apr-20	Subcontractor Issue Submittals - Specialities
PRO-4130	A/E Review & Approve Submittals - Specialties	15	17-Apr-20	08-May-20	A/E Review & Approve Submittals - Specialities
			· ·	-	
PRO-4140	Fab & Available for Delivery - Specialties	30	11-May-20	22-Jun-20	Fab & Available for Delivery - Specialties
Stage Equipmer		_			4
PRO-4220	Bid, De-scope & RTA - Stage Equipment	5	13-Jan-20 A	14-Feb-20	Bid, De-scope & RTA - Stage Equipment
PRO-4230	Owner Review/Approve RTA - Stage Equipment	5	18-Feb-20	24-Feb-20	Owner Review/Approve RTA - Stage Equipment
PRO-6850	Town Building Commission Approves Contract - Stage Equipment	1	10-Mar-20	10-Mar-20	I Town Building Commission Approves Contract - Stage Equipment
PRO-4240	Award Contract - Stage Equipment	2	11-Mar-20	12-Mar-20	Award Contract - Stage Equipment
PRO-4250	Execute Contract - Stage Equipment	5	13-Mar-20	19-Mar-20	Execute Contract - Stage Equipment
PRO-4260	Subcontractor Issue Submittals - Stage Equipment	20	20-Mar-20	16-Apr-20	Subcontractor Issue Submittals - Stage Equipment
PRO-4270	A/E Review & Approve Submittals - Stage Equipment	15	17-Apr-20	08-May-20	A/E Review & Approve Submittals - Stage Equipment
PRO-4280	Fab & Available for Delivery - Stage Equipment	65	11-May-20	11-Aug-20	Fab & Available for Delivery - Stage Equip
Vindow Treatmo					
PRO-4360	Bid, De-scope & RTA - Window Treatments	5	14-Jan-20 A	14-Feb-20	Bid, De-scope & RTA - Window Treatments
PRO-4370	Owner Review/Approve RTA - Window Treatments	5	18-Feb-20	24-Feb-20	Owner Review/Approve RTA - Window Treatments
PRO-6860	Town Building Commission Approves Contract - Window Treatments	1	10-Mar-20	10-Mar-20	I Town Building Commission Approves Contract - Window Treatmer
PRO-4380	Award Contract - Window Treatments	2	11-Mar-20	12-Mar-20	Award Contract - Window Treatments
PRO-4390	Execute Contract - Window Treatments	5	13-Mar-20	19-Mar-20	Execute Contract - Window Treatments
PRO-4400	Subcontractor Issue Submittals - Window Treatments	20	20-Mar-20	16-Apr-20	Subcontractor Issue Submittals - Window Treatments
PRO-4410	A/E Review & Approve Submittals - Window Treatments	15	17-Apr-20	08-May-20	A/E Review & Approve Submittals - Window Treatments
Remaining LActual Leve	evel of Effort Remaining Work		Page 11 o	129	TASK filter: Uncompleted Activities Two Months Prior. © Oracle Co
Actual Work				Pag	je 54 of 377

Data Date: 10-Feb-20 / Run Date: 09-Jul-20 09:05 21 2022 Jul A S Oct N D Jan F Mar Apr M Jun Jul Aug S Oct N Dec _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ ---------------



tivity ID	ol - Project A - 10Feb20 R1 Schedule Update - 1318014-CR - B26 Activity Name	Remaining	Start	Finish		
		Duration	C.C.T		2020	
DDO 4420	Fab 8 Available for Delivery - Window Treatments		11 May 20	00 lum 00	F Mar Apr M Jun Jul A S Oct N	
PRO-4420	Fab & Available for Delivery - Window Treatments	20	11-May-20	08-Jun-20	Fab & Available for Delive	ry - window Treatments
Signage	Did De seene & DTA Signage	E	06 Jan 20 A	14 Eab 20		
PRO-4430	Bid, De-scope & RTA - Signage	5	06-Jan-20 A	14-Feb-20	Bid, De-scope & RTA - Signage	
PRO-4440	Owner Review/Approve RTA - Signage	5	18-Feb-20	24-Feb-20	Owner Review/Approve RTA - Signage	
PRO-6880	Town Building Commission Approves Contract - Signage	1	10-Mar-20	10-Mar-20	I Town Building Commission Approves Co	ontract - Signage
PRO-4450	Award Contract - Signage	2	11-Mar-20	12-Mar-20	Award Contract - Signage	
PRO-4460	Execute Contract - Signage	5	13-Mar-20	19-Mar-20	Execute Contract - Signage	
PRO-4470	Subcontractor Issue Submittals - Signage	20	20-Mar-20	16-Apr-20	Subcontractor Issue Submittals - S	
PRO-4480	A/E Review & Approve Submittals - Signage	15	17-Apr-20	08-May-20	🔲 A/E Review & Approve Submitt	
PRO-4490	Fab & Available for Delivery - Signage	30	11-May-20	22-Jun-20	Fab & Available for Deli	very L Signage
Landscaping						
PRO-4010	Bid, De-scope & RTA - Landscaping	5	06-Jan-20 A	14-Feb-20	Bid, De-scope & RTA - Landscaping	
PRO-4020	Owner Review/Approve RTA - Landscaping	5	18-Feb-20	24-Feb-20	Owher Review/Approve RTA - Landscapir	g
PRO-6890	Town Building Commission Approves Contract - Landscaping	1	10-Mar-20	10-Mar-20	I Town Building Commission Approves Co	
PRO-4030	Award Contract - Landscaping	2	11-Mar-20	12-Mar-20	Award Contract - Landscaping	
PRO-4040	Execute Contract - Landscaping	5	13-Mar-20	19-Mar-20	Execute Contract - Landscaping	
PRO-4050	Subcontractor Issue Submittals - Landscaping	15	20-Mar-20	09-Apr-20	Subcontractor Issue Submittals - La	andscaning
PRO-4060	A/E Review & Approve Submittals - Landscaping	15	10-Apr-20	01-May-20	A/E Review & Approve Submitta	1
PRO-4000	Fab & Available for Delivery - Landscaping	50	04-May-20	14-Jul-20		Delivery - Landscaping
	Fab & Available for Delivery - Lanuscaping	50	04-1viay-20	14-Jul-20		
Final Cleaning		-	04 1 00 4	44 5 1 00		
PRO-4500	Bid, De-scope & RTA - Final Cleaning	5	21-Jan-20 A	14-Feb-20	Bid, De-scope & RTA - Final Cleaning	
PRO-4510	Owner Review/Approve RTA - Final Cleaning	5	18-Feb-20	24-Feb-20	Owner Review/Approve RTA - Final Clean	
PRO-6900	Town Building Commission Approves Contract - Signage	1	10-Mar-20	10-Mar-20	I Town Building Commission Approves Co	ontract - Signage
PRO-4520	Award Contract - Final Cleaning	2	11-Mar-20	12-Mar-20	Award Contract - Final Cleaning	
PRO-4530	Execute Contract - Final Cleaning	5	13-Mar-20	19-Mar-20	Execute Contract - Final Cleaning	
PRO-4540	Subcontractor Issue Submittals - Final Cleaning	20	20-Mar-20	16-Apr-20	Subcontractor Issue Submittals - I	inal Cleaning
PRO-4550	A/E Review & Approve Submittals - Final Cleaning	15	17-Apr-20	08-May-20	A/E Review & Approve Submitt	als - Final Cleaning
PRO-4560	Fab & Available for Delivery - Final Cleaning	10	11-May-20	22-May-20	Fab & Available for Delivery	- Final Cleaning
Construction	Summary					
SUM-1110	Summary - Demo 111 Cypress St Building	0	29-Aug-19 A	02 Jan 20 A	mmary - Demo 111 Cypress St Building	
SUM-1120	Summary - Temp Platform Work		25-Sep-19 A	20-Mar-20	Summary - Temp Platform Work	
		29				
SUM-1100	Summary - Sitework & Foundations at MBTA D Line Area	32	12-Oct-19A	25-Mar-20	Summary - Sitework & Foundations a	
SUM-1090	Summary - Sitework & Foundations at Cypress St Lot	20	25-Nov-19 A		Summary - Sitework & Foundations at C	ypress St Lot
SUM-1125	Summary - OCS Work	24	10-Feb-20	13-Mar-20	Summary - OCS Work	
SUM-1150	Summary - Overhead Catenary Work Complete to Begin Precast	0		13-Mar-20	Summary - Overhead Catenary Work C	
SUM-1040	Summary - Erect Steel & Precast Structure alongside & over MBTA D Line Tracks (Weeke	8	18-Apr-20	10-May-20	Summary - Erect Steel & Prec	-
SUM-1010	Summary - Erect Structural Steel	43	18-May-20	17-Jul-20	Summary - Erect S	ructural Steel
SUM-1020	Summary - Detail & Deck Structural Steel	55	26-May-20	11-Aug-20	Summary - Det	ail & Deck Structural Steel
SUM-1050	Summary - Lower Level Slab on Grade	35	30-Jun-20	18-Aug-20	Summary - Lo	wer µevel Slab on Ġrade
SUM-1030	Summary - Prep & Place Slabs on Deck	32	06-Jul-20	18-Aug-20	Summary - Pre	ep & Place Slabs on Deck
SUM-1060	Summary - Spray Fireproofing	21	11-Aug-20	09-Sep-20		Spray Fireproofing
SUM-1070	Summary - Exterior Facade	124	18-Aug-20	18-Feb-21		Summary - Exte
SUM-1080	Summary - MEP & Architectural Rough-in	107	01-Sep-20	08-Feb-21		Summary - MEP
INT-1080	Summary - Interior Drywall & Finishes	160	11-Feb-21	29-Sep-21		
INT-1110	Summary - Building Temp Tight	0		18-Feb-21	·	Summary - Build
INT-1090	Summary - Final Inspections & C of O	52	28-Jul-21	08-Oct-21		
INT-1150		10	23-Aug-21	03-Sep-21		
	Summary - Owner Install FF&E					
INT-1140	Summary - MEP Commissioning	60	26-Aug-21	22-Nov-21		
INT-1100	Summary - Substantial Completion - Project A: 111 Cypress Street	0		08-Oct-21		
MEP Coordir	nation					
Lower Level SI	ab on Grade					
MEP-3000	Coordinate MEPs - LL Underground	3	19-Dec-19 A	12-Feb-20	Coordinate MEPs - LL Underground	
MEP-3010	Review & Approve MEPs - LL Underground	5	13-Feb-20	20-Feb-20	Review & Approve MEPs - LL Underground	4
		5	13-1 60-20	20-1 60-20		
Lower Level						
Remaining	Level of Effort Remaining Work		Page 12 of	f 29	TASK filter: Uncompleted Activities Two M	onths Prior.
Actual Leve	-		- 37 - 0			© Oracle Corpor
Actual Wor	-			Pag	e 55 of 377	
				i ay		
		1				

						Da	ta Da	te: 1	I0-Fe	b-20	/ R	lun D	ate:	09-Jul	-20	09:05		
1		<u> </u>	0		N.			F	IN Arrow	A	N 4		22	14			N	
Jul		1	S	Oct	Ν	D	Jan	F	Mar	Apr	Μ	Jun	Jul	Aug	S	Oct	N	Dec
				 			 			1								1
				1 1 1						1 1 1								
				1 1 1														
				1 1 1 1			 									1		
				; ; ; ;														
				1 1 1														
				, , , ,			 			, , , ,								
				1 1 1			 											
				 			 									1		
																		1
				1 1 1			 			1 1 1						1		
				, , , ,												, , , , ,		
				 												1		
				 			' 									¦		
				1 1 1 1			 			1 1 1 1								1
				1 1 1			 			1 1 1						1		
				1 1 1 1						1 1 1						1		
				{ !			i 									 !		
ΓA	DL	ine	Tra	cks ('	Wee	ekend	ls)									1		
										1								
				1 1 1														
	cad			 			1 											1
chi	tect	ura	al Ro	ugh-i		m l	 	- D-		0	uio ho							
Tei	mp⊺	Гig	ht	Sur		ry - 1	nterio		ywaii	αгII	ISTIC							
	_	-					Final				Сс	of O						1
			S	umma	ry -		er Ins				issi	onina				1		
				🔶 Si	ımm									A: 111	Су	press	Str	eet
													-		-			
							1											
וו						(5	K	Δ	N	5	K						
- 1																		

	ool - Project A - 10Feb20 R1 Schedule Update - 1318014-CR - B26		011		iled Schedule	Data Date: 10-Feb-20 / Run Date: 09-Jul-20 09:05
ivity ID	Activity Name	Remaining Duration	Start	Finish	2020 2021	2022
		Duration			F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul A S	
MEP-3020	Coordinate MEPs - LL	18	23-Jan-20 A	05-Mar-20	Coordinate MEPs - LL	
MEP-3030	Review & Approve MEPs - LL	5	06-Mar-20	12-Mar-20	Review & Approve MEPs - LL	
MEP-3040	Fab & Deliver - Duct & Pipe - LL	15	24-Mar-20	13-Apr-20	Fab & Deliver - Duct & Pipe - LL	
Level 1						
MEP-3050	Coordinate MEPs - L1	20	13-Feb-20	12-Mar-20	Coordinate MEPs - L1	
MEP-3060	Review & Approve MEPs - L1	5	13-Mar-20	19-Mar-20	Review & Approve MEPs - L1	
MEP-3070	Fab & Deliver - Duct & Pipe - L1	15	24-Mar-20	13-Apr-20	🗖 Fab & Deliver - Duct & Pipe - L1	
Level 2						
MEP-3080	Coordinate MEPs - L2	20	28-Feb-20	26-Mar-20	Coordinate MEPs - L2	
MEP-3090	Review & Approve MEPs - L2	5	27-Mar-20	02-Apr-20	Review & Approve MEPs - L2	
MEP-3100	Fab & Deliver - Duct & Pipe - L2	15	03-Apr-20	· ·	₭ ┫╴╴╴╴╴╴╴┊╴╴╴╴╴╴╴╴╴╴╴╴╴┊╴╴╴╴╴╴╴╴╴╴╴╴╴╴╴	
	Pab & Deliver - Duct & Pipe - L2	10	03-Api-20	24-Apr-20	Fab & Deliver - Duct & Pipe - L2	
Level 3		i i				
MEP-3110	Coordinate MEPs - L3	20	13-Mar-20	09-Apr-20	Coordinate MEPs - L3	
MEP-3120	Review & Approve MEPs - L3	5	10-Apr-20	16-Apr-20	Review & Approve MEPs - L3	
MEP-3130	Fab & Deliver - Duct & Pipe - L3	15	17-Apr-20	08-May-20	Fab & Deliver - Duct & Pipe - L3	·····
Level 4						
MEP-3140	Coordinate MEPs - L4	20	27-Mar-20	24-Apr-20	Coordinate MEPs - L4	
MEP-3150	Review & Approve MEPs - L4	5	27-Apr-20	01-May-20	Review & Approve MEPs - L4	
MEP-3160	Fab & Deliver - Duct & Pipe - L4	15	04-May-20	22-May-20	🔲 Fab'& Deliver - Duct & Pipe - L4	
Constructio		,	,	, ,		
Enabling Site	work & Utility Relocations					
North (MBTA	D Line Area)					
ENAB-110	Overhead Catenary Line Work Complete - North (MBTAD Line Area)	0		16-Mar-20	 Overhead Catenary Line Work Complete - North (MBTAD Line Area) 	
Demolition						
South (111 Cy	ypress St Lot)					
	Demo Existing Tractor Building Foundations - South	0	19-Dec-19 A	03-Jan-20 A	mo Existing Tractor Building Foundations - South	
Sitework & Fo	oundations	/				
South (111 Cy						
	8 Excavate for Foorings & Foundations - South	14	25-Nov-19 A	28-Eeb-20	Excavate for Foorings & Foundations - South	
	0 Install Foundations - South	35	24-Dec-19A		Install Foundations - South	
	0 Cure & Backfill Foundations - South	21	18-Mar-20	15-Apr-20	Cure & Backfill Foundations - South	·
		21	10-1011-20	15-Api-20		
	Piles & Footings	0	00 Dec 10 A	01 Jan 00 A		
	55 Excavate & Cut Piles CL D - South	0		1	Excavate & Cut Piles CL D - South	
	30 FRP Pile Caps CLD	1	31-Jan-20 A	10-Feb-20	FRP Pile Caps CL D	
	Piles & Footings	-				·····
	0 Excavate & Cut Piles CL E - South	0			avate & Cut Piles CL E - South	
	20 FRP Pile Caps CL E - South	0	24-Dec-19 A	03-Jan-20 A	IP Pile Caps CL E - South	
Aggregate P						
FOUND-133	30 Cut Site - South	0		26-Dec-19 A		
FOUND-121	10 Install Aggregate Piers - South	0	30-Dec-19 A	13-Jan-20 A	nstall Aggregate Piers - South	
	ootingsat Elevator PitArea & East Elevation					
FOUND-122	20 Excavate for Footings - Elevator Pit Area & East Elevation	0	13-Jan-20 A	27-Jan-20 A	Excavate for Footings - Elevator Pit Area & East Elevation	
FOUND-184	40 Waterproof below Base Slab at Elevator Pit - Elevator Pit 2	0	14-Jan-20 A	14-Jan-20 A	Vaterproofbebw Base Slab at Elevator Pit-Elevator Pit2	
FOUND-185	50 FRP Base Slab at Elevator Pit - Elevator Pit 2	0	20-Jan-20 A	22-Jan-20 A	FRP Base Slab at Elevator Pit - Elevator Pit 2	
FOUND-124	40 FRP Perimeter Spread Footings - Elevator Pit Area & East Elevation	0	20-Jan-20 A	04-Feb-20 A	FRP Perimeter Spread Footings - Elevator Pit Area & East Elevation	
	60 FRP & Strip Walls at Elevator Pit - Elevator Pit 2	0			FRP & Strip Walls at Elevator Pit - Elevator Pit 2	
	30 FRP Perimeter Isolated Footings - Elevator Pit Area & East Elevation	10			FRP Perimeter Isolated Footings - Elevator Pit Area & East Elevation	
	potings at West Elevation					
	30 Excavate for Footings - West	5	13-Jan-20 A	14-Feb-20	Excavate for Footings - West	
	PO FRP Perimeter Isolated Footings - West	5		1	FRP Perimeter Isolated Footings - West	
	00 FRP Perimeter Spread Footings - West	5		1	FRP Perimeter Spread Footings - West	·
		C	15-Jan-20 A	21-Feb-20		
	botings at South Elevation	4		00 Eak 00	Evenuete for Eastings Courts	
FUUND-125	50 Excavate for Footings - South	4	20-F6D-20	20-160-20	Excavate for Footings - South	ii
Domainin	ng Level of Effort Remaining Work		D 40	£ 00	TACK filters Uncompleted Activities Two Marsters Drive	
			Page 13 o	129	TASK filter: Uncompleted Activities Two Months Prior.	
Actual Le	5				© Oracle Corporation	SKANSKA
	/ork ♦ ♦ Milestone	1		Pag	e 5β of 377	



Druch (m) Partner Display (L) Display (L) <thdisplay (l)<="" th=""> <thdisplay (l)<="" th=""> <thdi< th=""><th>117</th><th></th><th>Domaining</th><th>Start</th><th>L Linich</th><th colspan="5"></th></thdi<></thdisplay></thdisplay>	117		Domaining	Start	L Linich					
Fighter Fourier Indust Fooding - South Fighter Fooding - South Fighter Fooding - South Fighter Fooding - South FOUND-100 Term Private Indust Fooding - South 6 0.5 Auro 20 10 Mar 20 10 Fighter Fooding - South FOUND-100 Term Private Indust Fooding - South 5 15 Jaar 20A 10 Mar 20 Fighter Fooding - South FOUND-100 Term Private Indust Fooding - South 5 15 Jaar 20A 10 Mar 20 Fighter Fooding - South FOUND-100 Term Private Indust Fooding - South 5 15 Jaar 20A 10 Mar 20 Fighter Fooding - Vest FOUND-100 Term Private Indust Fooding - South 5 15 Jaar 20A 20 Mar 20 Fighter Fooding - Vest FOUND-100 Term Private Fooding - Vest 5 10 Fighter 20 Fighter Fooding - Vest FOUND-100 Term Private Fooding - Vest 5 11 Fighter 20 Fighter Fooding - Vest FOUND-100 Term Private Fooding - Vest 5 11 Fighter 20 Fighter Fooding - Vest FOUND-100 Term Private Fooding - Vest 5 11 Fighter 20 Fighter Fooding - Vest FOUND-100 Term Private Fooding - Vest 5 11 Fighter 20 Fighter Fooding - Vest FOUND-100 Term		Activity Name	Remaining Duration	Start	Finish	2020 20				
FOUND-1207 FOUND 1207 FOUND 1			Duration							
CUBLE CD FEE Thermatic Strate Coding - South 6 0 20-Mar 20 10-Mar 20 III. Part Network Strate Coding - South FOUND - FAST Decade for Inter Trading - East 5 13-Jar 20 14-Fd 20 Feed and the Strate Coding - South FOUND - FAST Feed and the Strate Coding - South 0 15-Jar 20 24-Fd 20 FeEd and the Strate Coding - South FOUND - FAST FEED and the Strate Coding - South 0 15-Jar 20 24-Fd 20 FEED and the Strate Coding - South FOUND - FAST FEED and the Strate Coding - South 0 15-Jar 20 74-Fd 20 FEED and the Strate Coding - South FOUND - FAST FEED and the Strate Coding - South 0 15-Jar 20 74-Fd 20 FEED and the Strate Coding - South FOUND - FAST FEED and the Strate Coding - South 0 15-Jar 20 74-Fd 20 FEED and the Strate Coding - South FOUND - FAST FEED and the Strate Coding - South 0 15-Jar 20 74-Fd 20 FEED and the Strate Coding - South FOUND - FAST FEED and the Strate Coding - South 5 15-Fd 20 74-Fd 20 FEED And 20 FEED And 20 FEED And 2	FOUND-1260	FRP Perimeter Isolated Footings - South	6	27-Feb-20	05-Mar-20					
Interior Fordings - East 6 13. No-20A 14-fb-20 Exclusion for fording - fordings - East FOUND-1470 Scale for fording - fordings - East 6 10. No-20A 14-fb-20 FOUND-1470 Scale for fording - fordings - fast 6 10. No-20A 14-fb-20 FOUND-100 PErformer Energy - Next 6 10. No-20A 14-fb-20 FOUND-100 PErformer Energy - Next 6 10. No-20A 24-fb-20 FOUND-100 PErformer Energy - Next 6 10. No-20A 24-fb-20 FOUND-100 PERformer Energy - Next 6 10. No-20A 24-fb-20 FOUND-100 PERformer Energy - Next 6 10. No-20A 14-fb-20 FOUND-100 PERformer Energy - Next 6 10. No-20A 14-fb-20 FOUND-100 PERformer Energy - Next 6 10. No-20A 14-fb-20 FOUND-100 PERformer Energy - Next 6 10. No-20A 14-fb-20 FOUND-100 PERformer Energy - Next 6 10. No-20A 14-fb-20 FOUND-1000 PERforman - No-20A			6			ERP Perimeter Spread Footings - South				
FOUND-140 Enclaration for internet Frances 6 11.3.m.20A 4.4.6.5.0.0 Enclaration for internet Frances 6 Internet Frances 6 11.3.m.20A 24.4.7.6.2.0 0 <td< td=""><td></td><td></td><td></td><td></td><td></td><td></td></td<>										
FOUND-1481 FOUND-1		7	5	13- Jan-20 A	14-Feb-20	Excavate for Interior Footings - Fast				
Interfor Fording - Vest FOUR-140 Each and for Interior Fooding - Vest Each and for Interior Fooding - Vest FOUR-140 Disk Fré Poul - Rur 1 0 24 Jan 20A PRI Histor Fooding - Vest FOUR-150 FRF Interior Fooding - Vest 0 24 Jan 20A PRI Histor Fooding - Vest FOUR-150 FRF Interior Fooding - Vest 0 24 Jan 20A PRI Histor Fooding - Vest FOUR-150 FRF Interior Fooding - Vest 0 24 Jan 20A PRI Histor Fooding - Vest FOUR-150 FRF Interior Fooding - Vest 0 24 Jan 20A PRI Histor Fooding - Vest FOUR-150 FRF Interior Fooding - Vest 0 24 Jan 20A PRI Histor Fooding - Vest FOUR-150 FRF Interior Fooding - Vest 0 24 Jan 20A PRI Histor Fooding - Vest FOUR-150 FRF Interior Fooding - Vest 0 24 Jan 20A PRI Histor Fooding - Vest FOUR-150 FRF Interior Fooding - Vest 0 24 Jan 20A PRI Histor Fooding - Vest FOUR-150 FRF Interior Fooding - Vest 1 PRI Histor Fooding - Vest PRI Histor Fooding - Vest FOUR-150		-								
CUMU-100 Pickerski for interior Footing - Vest 0 15 Jan-20A 24-bar-20A <		-	5	13-341-20A	02-10181-20					
FOUND-150 FPF Intern Facings - Weat FPF Intern Facings - Weat FPF Intern Facings - Weat FOUND-150 FPF Wai - Faur 1 0 24-38-20 24-38-20 24-38-20 24-38-20 24-38-20 FPF Wai - Faur 1 FPF Wai - Faur 1 FPF Wai - Faur 1 FPF Wai - Faur 3 FPF Wai - Faur 4 FPF Wai - Faur 4 FPF Wai - Faur 4 FPF Wai - Faur 5 FPF Wai - Faur 7 FPF Wai - Faur 7 </td <td></td> <td>7</td> <td>10</td> <td>12 Jon 20 A</td> <td>24 Eab 20</td> <td>Evenuete for Interior Excellinge Mont</td>		7	10	12 Jon 20 A	24 Eab 20	Evenuete for Interior Excellinge Mont				
Foundation Wais Foundation		-				· · · · · · · · · · · · · · · · · · ·				
CDUB-1030 FIP Wail-Part 0 24-Jan 2A FIP Wail-Part CDUB-1030 FIP Wail-Part 5 10-Fe-20 14-Fe-20 14-Fe-20 CDUB-1030 FIP Wail-Part 5 10-Fe-20 14-Fe-20 14-Fe-20 14-Fe-20 CDUB-1030 FIP Wail-Part 5 18-Fe-20 24-Fe-20 14-Fe-20			5	15-Jan-20 A	02-10181-20					
FOURD-1320 FIRE Weil - Pour2 S 10-Feb-200 1+RP Weil - Pour2 FOURD-1320 FRP Weil - Pour2 5 10-Feb-200 1+Feb-200 1+RP Weil - Pour2 FOURD-1320 FRP Weil - Pour2 5 10-Feb-200 1+Feb-200 1+RP Weil - Pour3 FOURD-1330 FRP Weil - Pour4 5 10-Feb-200 1+Feb-200 1+RP Weil - Pour5 FOURD-1330 FRP Weil - Pour4 5 10-Feb-200 1+RP Weil - Pour5 FOURD-1300 FRP Weil - Pour5 5 10-Feb-200 1+RP Weil - Pour7 FOURD-1400 FRP Weil - Pour6 5 0-Heb-200 1+RP Weil - Pour7 FOURD-1400 FRP Weil - Pour8 5 11-Har-20 1-Har-20 1-Har-20 FOURD-1707 Rack Fill Foundsin Wals - South 5 10-Har-20 1-Feb-20 1-Feb-20 1-Feb-20 FOURD-1707 Rack Fill Foundsin Wals - South 5 10-Har-20 1-Har-20 1-Har-20 1-Har-20 FOURD-1500 FRP Weil - Pour3 5 10-Feb-20 1-Feb-20 1-Feb-20 FOU			0	04 Jan 00 A	20. Jan 20. A					
FOUND-1320 FRF Wait - Pour 3 FRF Wait - Pour 3 FOUND-1320 FRF Wait - Pour 3 5 16 + Feb-200 24 + reac 20 FRF Wait - Pour 4 FOUND-1320 FRF Wait - Pour 5 6 16 + Feb-200 24 + reac 20 FRF Wait - Pour 4 FOUND-1320 FRF Wait - Pour 5 6 25 + Feb-200 24 - Feb-200 16 - FRF Wait - Pour 6 FOUND-1400 FRF Wait - Pour 7 6 25 - Feb-200 24 - Mar 20 FRF Wait - Pour 6 FOUND-1700 Wategroof Foundsim Wals - South 15 04 - Mar 20 FRF Wait - Pour 6 9 FOUND-1700 Wategroof Foundsim Wals - South 15 14 - Mar 20 FRF Wait - Pour 3 9 FOUND-1700 Wategroof Face Sign at Elevator Pt - Bavator Pt 18 - 3 10 + Feb-200 12 - Feb-20 12 - Feb-2										
FOURD-1300 FRP Wai - Pour 4 5 18 - Freb2.20 24 - Freb2.20 FRP Wai - Pour 6 FOURD-1300 FRP Wai - Pour 6 5 28 - Freb2.20 24 - Freb2										
FOUR-1300 FFP Wail - Pour 6 5 18 Feeb20 24 Feb20 IFFP Wail - Pour 6 FOUR-1300 FFP Wail - Pour 7 6 25 Feb20 02 Min-20 FFP Wail - Pour 6 FOUR-1400 FFP Wail - Pour 7 6 25 Feb20 02 Min-20 FFP Wail - Pour 6 FOUR-1400 FFP Wail - Pour 7 6 02 Min-20 94 Min-20 FFP Wail - Pour 6 FOUR-1400 FFP Wail - Pour 7 6 02 Min-20 94 Min-20 94 Min-20 FOUR-1770 Matter Contraction Wails - South 5 18 Min-20 17 Min-20 94 Min-20 FOUR-1500 FFP Wail - Pour 6 5 18 Min-20 24 Min-20 18 Min-20 19 Min-20 19 Min-20 Min-20 19 Min-20										
FOURD-1300 FRP Weil - Pour 0 5 2.5 Freb. 20 02.Mmr.20 FFP Weil - Pour 7 FOURD-1400 FRP Weil - Pour 3 5 0.5 Afler 20 02.Mmr.20 FFP Weil - Pour 7 FOURD-1400 FRP Weil - Pour 3 5 0.5 Afler 20 02.Mmr.20 FFP Weil - Pour 3 FOURD-1700 Weigrood Foundation Weils - South 5 11.Mar.20 31.Mmr.20 31.Mmr.20 FOURD-1700 Weigrood Foundation Weils - South 5 11.Mar.20 31.Mmr.20 31.Mmr.20 FOURD-1700 Weigrood Foundation Weils - South 5 11.Mar.20 31.Mmr.20 FFP Weil - Pour 5 FOURD-1500 Weigrood Foundation Weils - South 5 18.Mar.20 18.Feb 20										
FOUND-1400 FRP Wait-Pour 7 5 25 Feb 20 004mi-20 004mi-20 FOUND-1400 FRP Wait-Pour 7 004mi-20 004mi-20 004mi-20 004mi-20 FOUND-1700 Rep Wait-Pour 8 5 014mi-20 144mi-20 14min-20 FOUND-1700 Rep Wait-Pour 8 5 114mi-20 14min-20 14min-20 FOUND-1700 Rep Wait-Pour 9 5 314min-20 14min-20 14min-20 FOUND-1700 Rep Wait-Pour 9 5 314min-20 14min-20 14min-20 FOUND-1700 Rep Wait-Pour 9 18 16 14min-20 14min-20 FOUND-1500 Rep A Stry 4Minia Edubration PR - Elevator PR - Ele										
FOUD-1440 FRP Wai - Pour 9 6 0.3-Marco 2 0.4-Marco 2										
FOURD-1000 Waterpool & curvation Wale - South 15 0.4.Mar-20 24-Mar-20 FOURD-1000 FREP Wale Fourd 5 11.Mar-20 74-Mar-20 FEAP FOURD-1000 File Mare Pool & South 15 11.Mar-20 74-Mar-20 FEAP FOURD-1000 File Mare Pool & South 5 18.Mar-20 24-Mar-20 FEAP FOURD-1000 File Mare Pool & South & Eventor PH - Eventor PH 1 & A3 3 13-File 20 24-Mar-20 FOURD-1000 File PA Stry Wals & Elevator PH - Eventor PH 1 & A3 5 18-File 20 25-File 20 FOURD-1000 File PA Stry Wals & Elevator PH - Eventor PH 1 & A3 5 18-File 20 25-File 20 FOURD-1000 File PA Stry Wals & Elevator PL - Eventor PH 1 & A3 5 24-Mar-20 25-Mar-20 FOURD-1000 File PA Stry Wals & Elevator PL - Eventor PH 1 & A3 5 24-Mar-20 25-Mar-20 FOURD-1000 File PA Stry Wals & Elevator PL - Eventor PH 1 & A3 4 5 24-Mar-20 5-Mar-20 FOURD-1000 File PA Stry Wals & Elevator PL - Eventor PH 1 & A3 4 5 24-Mar-20 5-Mar-20 File PA Stry Wals & Elevator PH 1 & A3 5										
FOUND-1430 FPP Wall - Pour 8 FPP Wall - Pour 8 FOUND-1430 Final Cure Perimeter Wals 5 14.Mar-20 14.Mar-20 FOUND-1430 Final Cure Perimeter Wals 5 16.Mar-20 24.Mar-20 FOUND-1500 Waterproof Base Site at Elevator PI- Elevator PIs 1.8.3 3 10°-Fa.20 12°-Fa.20 14°-Fa.20 FOUND-1500 Waterproof Base Site at Elevator PI- Elevator PIs 1.8.3 3 10°-Fa.20 15°-Fa.20 15°-Fa.20 <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td></t<>										
FOUND-1770 Backet II Foundation Walk - South 15 11-Marc20 31-Marc20 Backet II Foundation Walk - South FOUND-130 FRP Base Slab at Elevator PR - Elevator PR 1 & 3 2 13-Feb-20 24-Marc20 FRP Course Slab at Elevator PR - Elevator PR 1 & 3 FOUND-150 FRP Base Slab at Elevator PR - Elevator PR 1 & 3 3 13-Feb-20 12-Feb-20 FRP Face Slab at Elevator PR - Elevator PR 1 & 3 FOUND-150 FRP Base Slab at Elevator PR - Elevator PR 1 & 3 5 19-Feb-20 25-Feb-20 FRP Interor Wals at Elevator PR 1 & 3 FRP Interor Wals at Elevator P				04-Mar-20						
FOUND.1490 Final Cure Perimeter Wals Final Cure Perimeter Wals FOUND.1500 Waterpool Save Sta at Elevator P1: Elevator P1s 1 & 3 3 10-Enc.20 12-Enc.20	FOUND-1430	FRP Wall - Pour 8	5	11-Mar-20	17-Mar-20					
Image Parts	FOUND-1770	Backfill Foundation Wals - South	15	11-Mar-20	31-Mar-20	Backfill Foundation Walls - South				
FOUND-1520 Wetergroof Base Sate at Elevator Pie 1.6.3 3 10 Feb-20 12 Feb-20 Wetergroof Base Sate at Elevator Pie 1.6.3 FOUND-1530 FRP Base Sate at Elevator Pie 1.6.3 3 10 Feb-20 12 Feb-20 FRP Base Sate at Elevator Pie 1.6.3 FOUND-1530 FRP & Strip Wale at Elevator Pie 1.6.3 5 10 Feb-20 25 Feb-20 FRP & Strip Wale at Elevator Pie 1.6.3 FOUND-1530 FRP & Strip Wale at Elevator Pie 1.6.3 5 10 Metergroof Wale at Elevator Pie 1.6.3 FRP & Strip Wale at Elevator Pie 1.6.3 FOUND-1560 Strip & Baschill Interior Wale 1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.	FOUND-1450	Final Cure Perimeter Wals	5	18-Mar-20	24-Mar-20	Final Cure Perimeter Walls				
FOUND-1507 FRP Base Slab at Elevator Pt - Elevator Pt 1 & 3 3 3 13 Feb-20 18 Feb-20 18 Feb-20 FRP Asstry Mala at Elevator Pt - Elevator Pt 1 & 3 FOUND-1530 FRP Asstry Mala at Elevator Pt - Elevator Pt 1 & 15 3 5 19 Feb-20 18 Feb-20 18 FRP Asstry Mala at Elevator Pt - Elevator Pt 1 & 3 FOUND-1530 Waterproof Wala at Elevator Pt 8 interior Wals - Interior Wals A Pts 5 17 / Mar.20 23 Mar.20 18 FRP Asstry Mala at Elevator Pt 8 interior Wals - Interior Wals A Pts FOUND-1530 Katerproof Wals at Elevator Pt 8 interior Wals - Interior Wals A Pts 5 24 / Mar.20 30 Mar.20 18 FRP Asstry Mala At Elevator Pt 8 interior Wals - Interior Wals A Pts FOUND-1530 Katerproof Wals at Elevator Pt 8 interior Wals - Interior Wals A Pts 5 24 / Mar.20 30 / Mar.20 18 freb Asstry Mala At Elevator Pt 8 interior Wals - Interior Wals A Pts FOUND-1530 Katerproof Wals at Elevator Pt 8 interior Wals - Interior Wals A Pts 11 / Mar.20 18 freb Asstry Mala At Elevator Pt 8 interior Wals - Interior Wals A Pts 18 freb Asstry Mala At Elevator Pt 8 interior Wals A Pts 18 freb Asstry Mala At Elevator Pt 8 interior Wals A Pts 18 freb Asstry Mala At Elevator Pt 8 interior Wals A Pts 18 freb Asstry Mala At Elevator Pt 8 interior Wals At Elevator Pt 8 interior Wals At Elevator Pt 8 interior Wals At Elevator Pt 8 interinterior Wals At Elevator Pt 8 interior Wals At	Interior Walls &	، Pits								
FOUND-1530 FRP & Strip Walls at Elevator Pt = Levator Pt 1 & 3 5 19-Feb-20 25-Feb-20 19-Feb-20 25-Feb-20 FPE Notice Walls at 11, 33 GG Lines - Interior Walls & Pt18 10 0.544ar-20 10-44ar-20 19-4bar-20 19-4bar-20 19-4bar-20 19-Feb-20 19-Feb-20 <td>FOUND-1520</td> <td>Waterproof Base Slab at Elevator Pit - Elevator Pits 1 & 3</td> <td>3</td> <td>10-Feb-20</td> <td>12-Feb-20</td> <td>Waterproof Base Slab at Elevator Pit - Elevator Pits 1 & 3</td>	FOUND-1520	Waterproof Base Slab at Elevator Pit - Elevator Pits 1 & 3	3	10-Feb-20	12-Feb-20	Waterproof Base Slab at Elevator Pit - Elevator Pits 1 & 3				
FOUND-1540 FRP Interior Wals at H. 13 & GG Lines - Interior Wals & Pts 10 0.5Mar-20 16-Mar-20 FOUND-1550 Strp & Backfill Interior Wals - Interior Wals & Pts 5 17-Mar-20 23-Mar-20 FOUND-1550 Strp & Backfill Interior Wals - Interior Wals & Pts 5 24-Mar-20 30-Mar-20 FOUND-1550 Strp & Backfill Interior Wals - Interior Wals & Pts 5 24-Mar-20 30-Mar-20 FOUND-1560 Install Support of Exavate (19 Ptes) (Weekend Work) - North 14-Dec-19A 15-Dec-19A Support of Exavate (19 Ptes) (Weekend Work) - North FOUND-1560 Install MiniPies (0) (Weekdq Work) - North 0 14-Ja-20 16-Ja-20 Install MiniPies (0) (Weekdq Work) / North FOUND-1560 FRP Pers. Spread Footings & Pte Cap (CL 10 3) - North 5 22-Feb-20 24-Feb-20 Interior Wals (Pur 1) - North FOUND-1505 FRP Foundation Wals (Pour 2) - North 5 05-Mar-20 Interior Wals (Pur 1) - North FOUND-1506 FRP Foundation Wals (Pour 2) - North 5 05-Mar-20 Interior Wals (Pur 1) - North FOUND-1506 FRP Foundation Wals (Pour 2) - North 5 12-Mar-20 Interior Wals (Pu	FOUND-1570	FRP Base Slab at Elevator Pit - Elevator Pits 1 & 3	3	13-Feb-20	18-Feb-20	FRP Base Slab at Elevator Pit - Elevator Pits 1 & 3				
FOUND-1540 FRP Interior Wals at H. 13 & GG Lines - Interior Wals & Pts 10 0.5Mar-20 16-Mar-20 FOUND-1550 Strp & Backfill Interior Wals - Interior Wals & Pts 5 17-Mar-20 23-Mar-20 FOUND-1550 Strp & Backfill Interior Wals - Interior Wals & Pts 5 24-Mar-20 30-Mar-20 FOUND-1550 Strp & Backfill Interior Wals - Interior Wals & Pts 5 24-Mar-20 30-Mar-20 FOUND-1560 Install Support of Exavate (19 Ptes) (Weekend Work) - North 14-Dec-19A 15-Dec-19A Support of Exavate (19 Ptes) (Weekend Work) - North FOUND-1560 Install MiniPies (0) (Weekdq Work) - North 0 14-Ja-20 16-Ja-20 Install MiniPies (0) (Weekdq Work) / North FOUND-1560 FRP Pers. Spread Footings & Pte Cap (CL 10 3) - North 5 22-Feb-20 24-Feb-20 Interior Wals (Pur 1) - North FOUND-1505 FRP Foundation Wals (Pour 2) - North 5 05-Mar-20 Interior Wals (Pur 1) - North FOUND-1506 FRP Foundation Wals (Pour 2) - North 5 05-Mar-20 Interior Wals (Pur 1) - North FOUND-1506 FRP Foundation Wals (Pour 2) - North 5 12-Mar-20 Interior Wals (Pu	FOUND-1530	FRP & Strip Walls at Elevator Pit - Elevator Pits 1 & 3	5	19-Feb-20	25-Feb-20	FRP & Strip Walls at Elevator Pit - Elevator Pits 1 & 3				
FOUND-1550 Waterpoord Wals at Elevator Pt & Interior Wals & Pts 5 17-Mar-20 23-Mar-20 III Waterpoord Wals at Elevator Pt & Interior Wals & Pts FOUND-1550 Strip & Backfill Interior Wals - Interior Wals & Pts 5 24-Mar-20 30-Mar-20 FOUND-1550 Strip & Backfill Interior Wals - Interior Wals & Pts Excavato (19 Pte) [Noth 5 24-Mar-20 III Waterpoord Wals at Elevator Pt & Interior Wals - Interior Wals & Pts FOUND-1500 Excavato (19 Pte) [Noth 3 23-Nor-19A 12-Feb-20 Excavato (12 Pte) [Noth) 5 24-Mar-20 III Waterpoord Wals at Elevator Pt & Interior Wals - Interior Wals & Pts FOUND-1500 Excavato (19 Pte) [Noth 0 14-Jan-20A III Waterpoord Wals (2a (Some Veekend Work) - North FOUND-1501 FRP Pers, Spread Footings & Pte Cap (CL 1 to 3) - North 5 20-Feb-20 04-Mar-20 III Mar-20 III FRP Pers, Spread Footings & Pte Cap (CL 1 to 3) - North FOUND-1501 FRP Foundation Wals (Pour 2) - North 5 12-Mar-20 11-Mar-20 III FRP Foundation Wals (Pour 2) - North FOUND-1500 FRP Foundation Wals (Pour 3) - North 5 12-Mar-20 11-Mar-20 IFRP Foundation Wals (Pour 3) - North FOUND-1500 FRP Foundation Wals (Pour 3) - North </td <td></td> <td></td> <td>10</td> <td>03-Mar-20</td> <td>16-Mar-20</td> <td></td>			10	03-Mar-20	16-Mar-20					
FOUND-1560 Strip & Backfill Interior Walls - Interior Walls & Pits 5 24-Mar-20 30-Mar-20 Strip & Backfill Interior Walls - Interior Walls & Pits FOUND-1030 Excavate & Lag for Foolings & Pile Cap (Some Weekend Work) - North 0 14-Dec-19A 12-Feb-20 Excavate & Lag for Foolings & Pile Cap (Some Weekend Work) - North FOUND-1030 Instal Support of Excavation (19 Piles) (Weekend Work) - North 0 14-Dec-19A 13-Dec-19A Support of Excavation (19 Piles) (Weekend Work) - North FOUND-1030 Instal Mini Piles ((Weeked) Work) - North 0 14-Ja-20A 14-Ja-20A Nation Piles (Weeked) Work) - North FOUND-1500 FRP Piers, Spread Foolings & Pile Cap (CL 1 to 3) - North 5 22-Feb-20 24-Mar-20 Pile Piles, Spread Foolings & Pile Cap (CL 1 to 3) - North FOUND-1505 FRP Foundation Wals (Pour 1) - North 5 25-Feb-20 04-Mar-20 FRP Foundation Wals (Pour 1) - North FOUND-1506 FRP Foundation Wals (Pour 3) - North 5 12-Mar-20 14-Mar-20 FRP Foundation Wals (Pour 3) - North FOUND-1700 FRP Foundation Wals (Pour 3) - North 5 12-Mar-20 14-Mar-20 FRP Foundation Wals (Pour 3) - North FOUND-1700 FRP Foundation Wals (Pour 3) - North 5 <td< td=""><td>FOUND-1550</td><td>Waterproof Walls at Elevator Pit & Interior Walls - Interior Walls & Pits</td><td>5</td><td>17-Mar-20</td><td>23-Mar-20</td><td>Waterproof Walls at Elevator Pit & Interior Walls - Interior Walls & Pits</td></td<>	FOUND-1550	Waterproof Walls at Elevator Pit & Interior Walls - Interior Walls & Pits	5	17-Mar-20	23-Mar-20	Waterproof Walls at Elevator Pit & Interior Walls - Interior Walls & Pits				
forth MBTA Area; FOUND-1030 Exavate & Layate & La			5							
FOUND-1030 Excavate & Lag for Footings & Pile Cap (Some Weekend Work) - North 3 25-Nov-19A 12-Feb-20 Excavate & Lag for Footings & Pile Cap (Casme Weekend Work) - North FOUND-1030 Instal Support of Excavation (19 Piles) (Weekend Work) - North 0 14-Dec-19A 15-Dec-19A Support of Excavation (19 Piles) (Weekend Work) - North FOUND-1030 FRP Piers, Spread Footings & Pile Cap (CL 3 to 17.2) - North 5 20-Feb-20 26-Feb-20 4FRP Piers, Spread Footings & Pile Cap (CL 3 to 17.2) - North FOUND-1030 FRP Piers, Spread Footings & Pile Cap (CL 3 to 17.2) - North 5 27-Feb-20 04-Mar-20 FRP Piers, Spread Footings & Pile Cap (CL 1 to 3) - North FOUND-1030 FRP Foundation Walls (Pour 1) - North 5 05-Mar-20 11-Mar-20 FRP Foundation Walls (Pour 2) - North FOUND-1030 FRP Foundation Walls (Pour 2) - North 5 12-Mar-20 18-Mar-20 18-FRP Foundation Walls (Pour 2) - North FOUND-1100 FRP Foundation Walls (Pour 3) - North 5 12-Mar-20 18-Mar-20 18-Mar-20 18-Mar-20 18-FRF Foundation Walls (Pour 2) - North FOUND-1120 WaterproofD amproof Foundation Walls (Pour 3) - North 10 12-Mar-20 18-Mar-20 <td></td> <td></td> <td></td> <td></td> <td>1</td> <td></td>					1					
FOUND-1800 Install Support of Excavation (19 Piles) (Weekend Work) - North 0 14-Dec-19A 15-Dec-19A Support of Excavation (19 Piles) (Weekend Work) - North FOUND-1085 Install Mini Piles (4) (Weekday Work) - North 0 14-Jan-20A 16-Jan-20A 16-Jan-20A <td>•</td> <td></td> <td>3</td> <td>23-Nov-19 A</td> <td>12-Feb-20</td> <td>Excavate & Lag for Footings & Pile Cap (Some Weekend Work) - North</td>	•		3	23-Nov-19 A	12-Feb-20	Excavate & Lag for Footings & Pile Cap (Some Weekend Work) - North				
FOUND-1085 Install Minr Piles (4) (Wreekday Work) - North 0 14-Jan-20A 16-Jan-20A FRP Piers. Spread Footings & Pile Cap (CL 3 to 17.2) - North FRP Piers. Spread Footings & Pile Cap (CL 1 to 3) - North FRP Piers. Spread Footings & Pile Cap (CL 1 to 3) - North FRP Piers. Spread Footings & Pile Cap (CL 1 to 3) - North FRP Piers. Spread Footings & Pile Cap (CL 1 to 3) - North FOUND-1050 FRP Foundation Wals (Pour 1) - North 5 0.7-Feb-20 0.4-Mar-20 1.5-Mar-20 1.5-Mar-20 <td></td> <td></td> <td>0</td> <td></td> <td></td> <td></td>			0							
FOUND-1590 FRP Piers, Spread Footings & Pile Cap (CL 3 to 17.2) - North 5 20-Feb-20 26-Feb-20 IFRP Piers, Spread Footings & Pile Cap (CL 1 to 3) - North FOUND-1080 FRP Foundation Walls (Pour 1) - North 5 27-Feb-20 04-Mar-20 IFRP Piers, Spread Footings & Pile Cap (CL 1 to 3) - North FOUND-1680 FRP Foundation Walls (Pour 2) - North 5 05-Mar-20 11-Mar-20 FOUND-1680 FRP Foundation Walls (Pour 2) - North 5 05-Mar-20 11-Mar-20 FOUND-1690 FRP Foundation Walls (Pour 2) - North 5 05-Mar-20 11-Mar-20 FOUND-1700 FRP Foundation Walls (Pour 3) - North 5 12-Mar-20 18-Mar-20 FOUND-1720 FRP Foundation Walls (Pour 5) - North 6 FRP Foundation Walls (Pour 6) - North FOUND-1720 WaterproofDamproof Foundation Walls - North 10 12-Mar-20 25-Mar-20 FOUND-1600 Cure Foundations - North 3 23-Mar-20 27-Mar-20 FOUND-1610 Complete FRP Grade Beam at CL B - North 3 23-Mar-20 27-Mar-20 FOUND-1610 Complete FRP Grade Beam at CL B - North 5 31-Mar-20 05-Mar-20 14-Mar-20 FOU			0							
FOUND-1810 FRP Piers, Spread Footings & Pile Cap (CL 1 to 3) - North 3 27-Feb-20 02-Mar-20 1 FRP Foundation Walis (Pour 1) - North 5 27-Feb-20 04-Mar-20 1 FRP Foundation Walis (Pour 2) - North 5 05-Mar-20 11-Mar-20 FRP Foundation Walis (Pour 2) - North FRP Foundation Walis (Pour 2) - North 5 05-Mar-20 11-Mar-20 FRP Foundation Walis (Pour 2) - North FRP Foundation Walis (Pour 3) - North FRP Foundation Walis (Po										
FOUND-1050 FRP Foundation Walls (Pour 1) - North 5 27. Feb-20 04-Mar-20 FOUND-1680 FRP Foundation Walls (Pour 2) - North 5 0.5-Mar-20 11-Mar-20 FOUND-1690 FRP Foundation Walls (Pour 3) - North 5 0.5-Mar-20 11-Mar-20 FOUND-1700 FRP Foundation Walls (Pour 3) - North 5 0.5-Mar-20 18-Mar-20 FOUND-1700 FRP Foundation Walls (Pour 3) - North 5 12-Mar-20 18-Mar-20 FOUND-1700 FRP Foundation Walls (Pour 4) - North 5 12-Mar-20 28-Mar-20 FOUND-1700 FRP Foundation Walls (Pour 4) - North 5 12-Mar-20 28-Mar-20 FOUND-1820 Excavate Elevator PIt & Orth 5 19-Mar-20 29-Mar-20 FOUND-1640 Waterproof Debw Base Slab at Elevator PIt - North 3 23-Mar-20 25-Mar-20 FOUND-1610 Complete FRP Grade Beam at CL B - North 5 32-Mar-20 29-Mar-20 12-Mar-20 FOUND-1610 Complete FRP Grade Beam at CL B - North 5 23-Mar-20 29-Mar-20 12-Mar-20 12-Mar-20 12-Mar-20 FOUND-1610 Complete FRP Grade Beam at CL B - North 5										
FQUND-1680 FRP Foundation Walls (Pour 2) - North 5 05-Mar-20 11-Mar-20 FQUND-1680 FRP Foundation Walls (Pour 3) - North 5 05-Mar-20 11-Mar-20 FQUND-1690 FRP Foundation Walls (Pour 3) - North 5 12-Mar-20 18-Mar-20 FQUND-1700 FRP Foundation Walls (Pour 3) - North 5 12-Mar-20 18-Mar-20 FQUND-1700 Waterproof/Damproof Foundation Walls (Pour 3) - North 5 12-Mar-20 28-Mar-20 FQUND-1720 Waterproof/Damproof Foundation Walls (Pour 3) - North 5 19-Mar-20 28-Mar-20 FQUND-1720 Waterproof/Damproof Foundation Walls (Pour 3) - North 5 19-Mar-20 28-Mar-20 FQUND-1600 Cure Foundation - North 5 19-Mar-20 28-Mar-20 19-Mar-20 FQUND-1640 Waterproof/Debw Base Stab at Elevator Pt - North 3 26-Mar-20 30-Mar-20 19-Mar-20 19-M										
FQUND-1690 FRP Foundation Walls (Pour 3) - North 5 05-Mar-20 11-Mar-20 II -Mar-20 <										
FOUND-1700 FRP Foundation Walls (Pour 4) - North 5 12-Mar-20 18-Mar-20 FRP Foundation Walls (Pour 4) - North FOUND-1710 FRP Foundation Walls (Pour 5) - North 5 12-Mar-20 18-Mar-20 FRP Foundation Walls (Pour 4) - North FOUND-1720 Waterproof/Damproof Foundation Walls - North 10 12-Mar-20 25-Mar-20 Waterproof/Damproof Foundation Walls - North FOUND-1820 Excavate Elevator Pit & CL B Area - North 5 19-Mar-20 25-Mar-20 Waterproof/Damproof Foundation Walls - North FOUND-1860 Cure Foundation S - North 5 19-Mar-20 25-Mar-20 Waterproof/Babw Base Stab at Elevator Pit - North FOUND-1660 Complete FRP Grade Beam at CL B - North 5 23-Mar-20 25-Mar-20 Complete FRP Grade Beam at CL B - North FOUND-1660 FRP Base Stab at Elevator Pit - North 5 31-Mar-20 06-Apr-20 Complete FRP Grade Beam at CL B - North FOUND-1660 FRP & Strip Walls at Elevator Pit Area - North 10 02-Apr-20 15-Apr-20 FRP Base Stab at Elevator Pit Area - North FOUND-1670 Waterproof/Walls at Elevator Pit Area - North 15 06-Apr-20 15-Apr-20 Backill Foundation Walls - North FO										
FOUND-1710 FRP Foundation Walls (Pour 5) - North 5 12-Mar-20 18-Mar-20 18-Mar-20 FOUND-1720 Waterproof/Damproof Foundation Walls - North 10 12-Mar-20 25-Mar-20 Waterproof/Damproof Foundation Walls - North FOUND-1820 Excavate Elevator Pit & CL B Area - North 5 16-Mar-20 25-Mar-20 Excavate Elevator Pit & CL B Area - North FOUND-1600 Cure Foundations - North 5 19-Mar-20 25-Mar-20 Waterproof/Damproof Foundation Walls - North FOUND-1600 Cure Foundations - North 3 23-Mar-20 25-Mar-20 Waterproof/Damproof Foundation Walls - North FOUND-1610 Complete FRP Grade Beam at CL B - North 3 23-Mar-20 25-Mar-20 Waterproof/Damproof Foundation Pit - North FOUND-1650 FRP Base Slab at Elevator Pit - North 5 31-Mar-20 30-Mar-20 15-Mar-20 16-Mar-20						*+++++++++++				
FOUND-1720 Waterproof/Damproof Foundation Walls - North 10 12-Mar-20 25-Mar-20 FOUND-1820 Excavate Elevator Pit & CL B Area - North 5 16-Mar-20 20-Mar-20 FOUND-1800 Cure Foundations - North 5 19-Mar-20 25-Mar-20 FOUND-1600 Waterproof/Damproof Foundation Walls - North 5 19-Mar-20 25-Mar-20 FOUND-1640 Waterproof/Damproof Foundation Walls - North 5 23-Mar-20 25-Mar-20 FOUND-1600 Cure Foundations - North 5 23-Mar-20 25-Mar-20 FOUND-1600 Complete FRP Grade Beam at CL B - North 5 23-Mar-20 27-Mar-20 FOUND-1600 FRP Base Slab at Elevator Pit Area - North 5 31-Mar-20 30-Mar-20 FOUND-1600 FRP & Strip Walls at Elevator Pit Area - North 5 07-Apr-20 15-Apr-20 FRP 8 strip Walls at Elevator Pit Area - North 10 02-Apr-20 15-Apr-20 15-Apr-20 FOUND-1700 FRP Stairs - North 15 26-Mar-20 15-Jun-20 16 FOUND-1700 FRP Stairs - North 15 26-Mar-20 15-Jun-20 16 FOUND-1700										
FOUND-1820 Excavate Elevator Pit & CL B Area - North 5 16-Mar-20 20-Mar-20 20-Mar-20 FOUND-1060 Cure Foundations - North 5 19-Mar-20 25-Mar-20 25-Mar-20 FOUND-1640 Waterproof bebw Base S ab at Elevator Pit - North 3 23-Mar-20 25-Mar-20 10-Mar-20 FOUND-1610 Complete FRP Grade Beam at CL B - North 5 23-Mar-20 25-Mar-20 10-Mar-20 FOUND-1650 FRP Base Slab at Elevator Pit - North 3 26-Mar-20 30-Mar-20 30-Mar-20 FOUND-1660 FRP Satif Elevator Pit Area - North 5 31-Mar-20 06-Apr-20 15-Apr-20 FOUND-1670 Waterproof Walls at Elevator Pit Area - North 5 07-Apr-20 13-Apr-20 16-Mar-20 FOUND-1670 Waterproof Walls at Elevator Pit Area - North 5 07-Apr-20 13-Apr-20 15-Apr-20 FOUND-1670 Waterproof Walls at Elevator Pit Area - North 5 07-Apr-20 13-Apr-20 15-Apr-20 FOUND-1670 FRP Stairs - North 15 26-Mar-20 15-Jun-20 16-Mar-20 16-Mar-20 FRP Stairs - North 15 26-Mar-20 15-A										
FOUND-1060 Cure Foundations - North 5 19-Mar-20 25-Mar-20 25-Mar-20 FOUND-1640 Waterproof bebw Bas e Slab at Elevator Pit - North 3 23-Mar-20 25-Mar-20 27-Mar-20 FOUND-1650 FRP Base Slab at Elevator Pit - North 5 23-Mar-20 27-Mar-20 27-Mar-20 27-Mar-20 FOUND-1650 FRP Base Slab at Elevator Pit - North 5 31-Mar-20 30-Mar-20 30-Mar-20 FOUND-1650 FRP Base Slab at Elevator Pit - North 5 31-Mar-20 06-Apr-20 15-Apr-20 FOUND-1670 Waterproof Walls at Elevator Pit Area - North 10 02-Apr-20 15-Apr-20 15-Apr-20 FOUND-1670 Waterproof Walls at Elevator Pit Area - North 15 26-Mar-20 15-Apr-20 18-Apr-20 Waterproof Walls at Elevator Pit Area - North FOUND-1670 Waterproof Walls at Elevator Pit Area - North 15 26-Mar-20 15-Apr-20 18-Apr-20 Waterproof Walls at Elevator Pit Area - North FOUND-1100 FRP Stairs - North 15 26-Mar-20 15-Jun-20 Waterproof Walls at Elevator Pit Area - North FUNCT-1270 Install Crane Mats & Mobilize Crane - North 15 09-Apr-20<										
FOUND-1640 Waterproof below Base Stab at Elevator Pit - North 3 23-Mar-20 25-Mar-20 1 Waterproof below Base Stab at Elevator Pit - North FOUND-1610 Complete FRP Grade Beam at CL B - North 5 23-Mar-20 27-Mar-20 30-Mar-20 30-Mar										
FOUND-1610 Complete FRP Grade Beam at CL B - North 5 23-Mar-20 27-Mar-20 FOUND-1650 FRP Base Slab at Elevator Pit - North 3 26-Mar-20 30-Mar-20 FOUND-1660 FRP & Strip Walls at Elevator Pit Area - North 5 31-Mar-20 06-Apr-20 FOUND-1730 Backfill Foundation Wals - North 10 02-Apr-20 15-Apr-20 FOUND-1670 Waterproof Walls at Elevator Pit Area - North 5 07-Apr-20 13-Apr-20 FOUND-1670 Waterproof Walls at Elevator Pit Area - North 5 07-Apr-20 13-Apr-20 FOUND-1670 Waterproof Walls at Elevator Pit Area - North 5 07-Apr-20 13-Apr-20 FOUND-1670 Waterproof Walls at Elevator Pit Area - North 5 07-Apr-20 13-Apr-20 FOUND-1670 Waterproof Walls at Elevator Pit Area - North 5 07-Apr-20 15-Jun-20 FUNCTION FRP Stairs - North 15 26-May-20 15-Jun-20 Waterproof Walls at Elevator Pit Area - North sevel 1						*+				
FOUND-1650 FRP Base Slab at Elevator Pit - North 3 26-Mar-20 30-Mar-20 FOUND-1660 FRP & Strip Walls at Elevator Pit Area - North 5 31-Mar-20 06-Apr-20 FOUND-1730 Backfill Foundation Wals - North 10 02-Apr-20 15-Apr-20 FOUND-1670 Waterproof Walls at Elevator Pit Area - North 5 07-Apr-20 13-Apr-20 FOUND-1670 Waterproof Walls at Elevator Pit Area - North 5 07-Apr-20 13-Apr-20 FOUND-1670 Waterproof Walls at Elevator Pit Area - North 5 07-Apr-20 15-Jun-20 FOUND-1100 FRP Stairs - North 15 26-May-20 15-Jun-20 I waterproof Walls at Elevator Pit Area - North ructure										
FOUND-1660 FRP & Strip Walls at Elevator Pit Area - North FOUND-1730 Backfill Foundation Wals - North FOUND-1730 Backfill Foundation Wals - North FOUND-1670 Waterproof Walls at Elevator Pit Area - North FOUND-1670 Waterproof Walls at Elevator Pit Area - North FOUND-1670 Waterproof Walls at Elevator Pit Area - North FOUND-1670 Waterproof Walls at Elevator Pit Area - North FOUND-1100 FRP Stairs - North FRP Stairs - North 15 ructure		•								
FOUND-1730 Backfill Foundation Walls - North 10 02-Apr-20 15-Apr-20 FOUND-1670 Waterproof Walls at Elevator Pit Area - North 5 07-Apr-20 13-Apr-20 FOUND-1100 FRP Stairs - North 15 26-May-20 15-Jun-20 ructure										
FOUND-1670 Waterproof Walls at Elevator Pit Area - North 5 07-Apr-20 13-Apr-20 FOUND-1100 FRP Stairs - North 15 26-May-20 15-Jun-20 FOUND-1100 FRP Stairs - North FOUND-1100 FRP Stairs - North FOUND-1100 FRP Stairs - North FOUND-1100 FRP Stairs - North FOUND-1100 FRP Stairs - North FRP Stairs - North Image Area - Morth FRP Stairs - North Image Area - Morth FRP Stairs - North Image Area - Morth Image Area - Morth </td <td>FOUND-1660</td> <td></td> <td></td> <td></td> <td></td> <td></td>	FOUND-1660									
FOUND-1100 FRP Stairs - North 15 26-May-20 15-Jun-20 ructure FRP Stairs - North FRP Stairs - North orth (MBTA D Line Area) Install Crane Area Install Crane Mats & Mobilize Crane - North evel 1 STRUCT-1270 Install Crane Mats & Mobilize Crane - North Install Crane Mats & Mobilize Crane - North STRUCT-1270 Install Crane Mats & Mobilize Crane - North (Weekend Work) 2 18-Apr-20 19-Apr-20 Install Crane Mats & Mobilize Crane - North STRUCT-1000 Erect Steel along Tracks Sequence 1 - North (Weekend Work) 2 18-Apr-20 19-Apr-20 Install Crane Mats & Mobilize Crane - North (Weekend Work) Remaining Work Page 14 of 29 TASK filter: Uncompleted Activities Two Months Prior.	FOUND-1730		10	02-Apr-20		Backfill Foundation Walls - North				
ructure orth (MBTA D Line Area) .evel 1 STRUCT-1270 Install Crane Mats & Mobilize Crane - North STRUCT-1270 Install Crane Mats & Mobilize Crane - North STRUCT-1000 Erect Steel along Tracks Sequence 1 - North (Weekend Work) 2 18-Apr-20 19-Apr-20 Image 14 of 29 TASK filter: Uncompleted Activities Two Months Prior.		•	5	07-Apr-20	13-Apr-20	Waterproof Walls at Elevator Pit Area - North				
orth (MBTA D Line Area) Level 1 STRUCT-1270 Install Crane Mats & Mobilize Crane - North STRUCT-1270 Install Crane Mats & Mobilize Crane - North STRUCT-1000 Erect Steel along Tracks Sequence 1 - North (Weekend Work) Page 14 of 29 TASK filter: Uncompleted Activities Two Months Prior.	FOUND-1100	FRP Stairs - North	15	26-May-20	15-Jun-20	FRP Stairs - North				
orth (MBTA D Line Area) wevel 1 STRUCT-1270 Install Crane Mats & Mobilize Crane - North STRUCT-1270 Install Crane Mats & Mobilize Crane - North 5 09-Apr-20 15-Apr-20 Install Crane Mats & Mobilize Crane - North STRUCT-1000 Erect Steel along Tracks Sequence 1 - North (Weekend Work) 2 18-Apr-20 19-Apr-20 I Erect Steel along Tracks Sequence 1 - North (Weekend Work) Page 14 of 29	ructure									
.evel 1 STRUCT-1270 Install Crane Mats & Mobilize Crane - North STRUCT-1000 Erect Steel along Tracks Sequence 1 - North (Weekend Work) 2 18-Apr-20 19-Apr-20 Install Crane Mats & Mobilize Crane - North I Erect Steel along Tracks Sequence 1 - North (Weekend Work) 2 Page 14 of 29 TASK filter: Uncompleted Activities Two Months Prior.										
STRUCT-1270 Install Crane Mats & Mobilize Crane - North 5 09-Apr-20 15-Apr-20 Install Crane Mats & Mobilize Crane - North STRUCT-1000 Erect Steel along Tracks Sequence 1 - North (Weekend Work) 2 18-Apr-20 19-Apr-20 I Erect Steel along Tracks Sequence 1 - North (Weekend Work) Remaining Level of Effort Remaining Work Page 14 of 29 TASK filter: Uncompleted Activities Two Months Prior.	-									
STRUCT-1000 Erect Steel along Tracks Sequence 1 - North (Weekend Work) 2 18-Apr-20 19-Apr-20 I Erect Steel along Tracks Sequence 1 - North (Weekend Work) Remaining Level of Effort Remaining Work Page 14 of 29 TASK filter: Uncompleted Activities Two Months Prior.					48.4					
Remaining Level of Effort Remaining Work Page 14 of 29 TASK filter: Uncompleted Activities Two Months Prior.										
	SIRUCT-1000	Erect Steel along Tracks Sequence 1 - North (Weekend Work)	2	18-Apr-20	19-Apr-20	I Erect Steel along Tracks Sequence 1 North (Weekend Work)				
	· · · ·									
Actual Level of Effort Critical Remaining Work © Oracle Corp.	-	-		Page 14 c	of 29					
	Actual Leve	l of Effort Critical Remaining Work				© Oracle Corporati				

	Da	ta Date: 10-Fe	b-20 / Run D	ate: 09-Jul-20	09:05
AS	Oct N D	Jan F Mar	20 Apr M Jun	22 Jul Aug S	Oct N Dec
		 		, , , , ,	
	1 1 1 1 1		1 1 1 1 1	1 1 1 1	
	1 1 1 1 1 1		1 1 1 1 1 1	1 1 1 1 1	
	1 		1 1 1 1		
	1 1 1 1 1		1 1 1 1 1	1 1 1 1 1	
	 	 	 	, , , ,	
	 		1 1 1 1 1		
	1 		1 1 1 1		
	 	 	, , , , , , ,		
		 	1 1 1 1 1	1 1 1 1	
	 		1 1 1 1 1 1		
	1 1 1 1 1	 	1 1 1 1		
	 	 1	 		
			1 1 1 1		
	 	 		•	
		 	1 1 1 1 1		
	, , , , , ,	 	, , , , , , , , , , , , , , , , , , , ,		
	1 1 1 1 1	 	1 1 1 1 1		
	1 1 1 1 1	 	1 1 1 1 1		
	, 1 1 1 1	 	, 1 1 1 1		
		 	1 1 1 1 1	1 1 1 1	

	ol - Project A - 10Feb20 R1 Schedule Update - 1318014-CR - B26	Domoining	Ctort		led Schedule Data Date: 10-Feb-20 / Run Date: 09-Jul-20 09:05
ID	Activity Name	Remaining	Start	Finish	2020 2021 2022
					F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul Aug S Oct N
STRUCT-1210	Detail, Bolt-up & Plumb Steel along Tracks Sequence 1 - North (Weekday)	5	21-Apr-20	27-Apr-20	Detail, Bolt-up & Plumb Steel along Tracks Sequence 1 - North (Weekday)
STRUCT-1200	Erect & Detail Precast over Tracks - L1 - North (Weekend Work)	2	02-May-20	03-May-20	Erect & Detail Precast over Tracks - L1 - North (Weekend Work)
	Erect & Detail Precast over Tracks - L1 - North (Weekend Work)	2	09-May-20	10-May-20	Erect & Detail Precast over Tracks - L1 - North (Weekend Work)
	FRP Perimter Curb - L1 - North	5	23-Jun-20	29-Jun-20	FRP Perimter Curb - L1 - North
	Prep & Place Topping Slab (Weekend Work) - L1 - North	2	04-Jul-20	05-Jul-20	Prep & Place Topping Slab (Weekend Work) - L1 - North
Level 3 to Roo			04 041 20	00 00 20	
	Erect Structural Steel over Tracks Sequence 2 - L3 & Canopy - North (Weekend Work)	2	16-May-20	17-May-20	Erect Structural Steel over Tracks Sequence 2 - L3 & Canopy - North (Weekend Work)
	Elect Structural Steel Over Track's Sequence 2 - LS & Canopy - North (Weekday Work)	5	18-May-20	22-May-20	 Erect Structural Steel Sequence 3 - L3 & Canopy - North (Weekday Work)
			-	-	
	Detail & Deck Structural Steel over Tracks Sequence 2 - L3 & Canopy - North (Weekend 1	2	23-May-20	24-May-20	Detail & Deck Structural Steel over Tracks Sequence 2 - L3 & Canopy - North (Weekend Work)
	Detail & Deck Structural Steel Sequence 3 - L3 & Canopy- North (Weekday Work)	20	26-May-20	22-Jun-20	Detail & Deck Structural Steel Sequence 3 - L3 & Canopy- North (Weekday Work)
outh (111 Cyp	press St Lot)				
Level 1					
STRUCT-1050	Erect Structural Steel - L1 - South	8	26-May-20	04-Jun-20	Erect Structural Steel - L1 - South
STRUCT-1060	Detail & Deck Steel - L1 - South	17	05-Jun-20	29-Jun-20	Detail & Deck Steel - L1 - South
STRUCT-1070	Prep & Place Slab on Deck - L1 - South	5	06-Jul-20	10-Jul-20	Prep & Place Slab on Deck - L1 - South
STRUCT-1250	FRP Perimeter Curbs - L1- South	5	13-Jul-20	17-Jul-20	FRP Perimeter Curbs - L1- South
Level 2					
STRUCT-1080	Erect Structural Steel - L2 - South	6	05-Jun-20	12-Jun-20	Erect Structural Steel - L2 - South
STRUCT-1090	Detail & Deck Steel - L2 - South	17	15-Jun-20	08-Jul-20	Detail & Deck Steel - L2 - South
	 Prep & Place Slab on Deck - L2 - South 	5	13-Jul-20	17-Jul-20	Prep & Place Slab on Deck - L2 - South
Level 3		U	10 001 20	11 001 20	
	Erect Structural Steel - L3 - South	13	15-Jun-20	01-Jul-20	Erect Structural Steel - L3 - South
					Detail & Deck Steel - L3 - South
	Detail & Deck Steel - L3 - South	17	02-Jul-20	27-Jul-20	
	Prep & Place Slab on Deck - L3 - South	5	28-Jul-20	03-Aug-20	Prep & Place Slab on Deck - L3 - South
Level 4					
	Erect Structural Steel - L4 - South	5	02-Jul-20	09-Jul-20	Erect Structural Steel - L4 - South
	Detail & Deck Steel - L4 - South	17	10-Jul-20	03-Aug-20	Detail & Deck Steel - L4 - South
STRUCT-1160	Prep & Place Slab on Deck - L4 - South	5	04-Aug-20	10-Aug-20	Prep & Place Slab on Deck - L4 - South
Roof					
STRUCT-1170	Erect Structural Steel - Roof - South	6	10-Jul-20	17-Jul-20	Erect Structural Steel - Roof - South
STRUCT-1180	Detail & Deck Steel - Roof - South	17	20-Jul-20	11-Aug-20	Detail & Deck Steel - Roof - South
STRUCT-1190	Prep & Place Slab on Deck - Roof - South	5	12-Aug-20	18-Aug-20	Prep & Place Slab on Deck - Roof - South
isc. Metal \$	Stairs				
		5	45 km 00	40 km 00	
TAIR-1000	Install - Stair 1	5	15-Jun-20	19-Jun-20	Install - Stair 1
TAIR-1010	Install - Stair 2	20	22-Jun-20	20-Jul-20	Install - Stair 2
TAIR-1020	Install - Stair 3	20	07-Jul-20	03-Aug-20	Install - Stair 3
TAIR-1030	Install - Stairs 6/7	20	21-Jul-20	17-Aug-20	Install - Stairs 6/7
TAIR-1040	Install - Stairs 4/5	5	18-Aug-20	24-Aug-20	Install - Stairs 4/5
ab on Grad	de				
ower Level					
SOG-1000	Excavate & Install Underslab Utilitites - Lower Level	25	20 1.00 20	04 4.00 20	Excavate & Install Underslab Utilitites - Lower Level
		25	30-Jun-20	04-Aug-20	
SOG-1010	Prep & Place Slab on Grade - Lower Level	10	05-Aug-20	18-Aug-20	Prep & Place Slab on Grade - Lower Level
ayout & Ins	stall Top Track				
1-3000	Layout & Install Top Track - L1	5	20-Jul-20	24-Jul-20	Layout & Install Top Track - L1
1-3010	Layout & Install Top Track - L2	5	04-Aug-20	10-Aug-20	Layout & Install Top Track - L2
1-3020	Layout & Install Top Track - L3	5	11-Aug-20	17-Aug-20	Layout & Install Top Track - L3
1-3030	Layout & Install Top Track - L4	5	19-Aug-20	25-Aug-20	Layout & Install Top Track - L4
1-3040	Layout & Install Top Track - Car Layout & Install Top Track - Garden Level	5	26-Aug-20	01-Sep-20	Layout & Install Top Track - Garden Level
		5	20-Aug-20	01-0ep-20	
pray Firepr			,		
PF-1000	Spray Fireproof - L1	5	04-Aug-20	10-Aug-20	Spray Fireproof - L1
PF-1010	Spray Fireproof - L2	5	11-Aug-20	17-Aug-20	Spray Fireproof - L2
PF-1020	Spray Fireproof - L3	5	18-Aug-20	24-Aug-20	■ Spray Fireproof - L3
PF-1030	Spray Fireproof - L4	5	26-Aug-20	01-Sep-20	Spray Fireproof - L4
		-			
Remaining	Level of Effort Remaining Work		Page 15 c	f 29	TASK filter: Uncompleted Activities Two Months Prior.
	rel of Effort Critical Remaining Work				© Oracle Corporation SKANSKA
Actual Lev					

-	hool - Project A - 10Feb20 R1 Schedule Update - 1318014-CR - B26	Demoiring	Start	Finish	iled Schedule	
vity ID	Activity Name	Remaining Duration	Start	Finish	2020	
						Oct N D Jan F Mar Apr M J
SPF-1040	Spray Fireproof - Garden Level	5	02-Sep-20	09-Sep-20		Spray Fireproof - Garden Level
Roofing						
RF-1000	Temp-in Roofs	15	19-Aug-20	09-Sep-20		Temp-in Roofs
RF-1010	Set & Connect Roof Top Equipment	20	19-Aug-20	16-Sep-20		Set & Connect Roof Top Equipment
RF-1020	Install Roof Screens	20	17-Sep-20	15-Oct-20		Install Roof Screens
RF-1030	Install Permanent Roof - Roof Level	15	16-Oct-20	05-Nov-20		Install Permanent Roof - Roof Le
RF-1040	Install Permanent Roof (Following Staging Removal) - L3	15	25-Mar-21	14-Apr-21		🔲 Install F
Exterior Fa	Icade					
EXT-1000	Frame Exterior Walls	70	18-Aug-20	30-Nov-20		Frame Exterior Walls
EXT-105	Sheath Exterior Walls	59	08-Sep-20	03-Dec-20		Sheath Exterior Walls
EXT-1010	AVB Exterior Walls	56	22-Sep-20	14-Dec-20		AVB Exterior Walls
EXT-1040	Install Curtain Wal	90	06-Oct-20	18-Feb-21		Install Curtain W
EXT-1020	Stage Exterior Walls	83	19-Nov-20	23-Mar-21		Stage Exte
EXT-1020	Install Stone & Brick / Washdown / Remove Staging	77	02-Dec-20	24-Mar-21		
EXT-1050	Building Temp Tight	0	02-000-20	18-Feb-21		 Building Temp T
	on (CL C.7 to PP)	0		10-1 60-21		
E-1000	Frame Exterior Walls & Canopy - East Elevation	24	18-Aug-20	21-Sep-20		Frame Exterior Walls & Canopy - East E
E-1000		15	_			Sheath Exterior Walls & Canopy - East
E-1010 E-1020	Sheath Exterior Walls & Canopy - East Elevation	10	08-Sep-20	28-Sep-20		Install AVB + East Elevation
			22-Sep-20	05-Oct-20		1 I
E-1030	Prep Openings for Curtain Wall - East Elevation	10	29-Sep-20	13-Oct-20		Prep Openings for Curtain Wall - Ea
E-1040	Install Curtain Wal - East Elevation	31	06-Oct-20	19-Nov-20		Install Curtain Wal - East Elevent
E-1050	Install Staging - East Elevation	20	29-Oct-20	30-Nov-20		Install Staging - East Elevat
E-1060	Install Stone - East Elevation	18	17-Nov-20	14-Dec-20		Install Stone - East Elevat
E-1070	Install Brick - East Elevation	24	02-Dec-20	06-Jan-21		Install Brick - East Ele
E-1080	Washdown Masonry - East Elevation	10	29-Dec-20	12-Jan-21		🔲 Washdown Masonry
E-1090	Remove Staging - East Elevation	10	06-Jan-21	20-Jan-21		Remove Staging - E
E-1100	Caulk Facade - East Elevation	11	21-Jan-21	04-Feb-21		│ 🗖 Caulk Facade - E
	tion (CL 10 to 18)				_	
S-1000	Frame Exterior Walls - South Elevation	17	11-Sep-20	05-Oct-20		Frame Exterior Walls - South Elevation
S-1010	Sheath Exterior Walls - South Elevation	10	29-Sep-20	13-Oct-20		Sheath Exterior Walls - South Eleva
S-1020	Install AVB - South Elevation	6	13-Oct-20	20-Oct-20		■ Install AVB - South Elevation
S-1030	Prep Openings for Curtain Wall - South Elevation	5	21-Oct-20	27-Oct-20		Prep Openings for Curtain Wall-
S-1040	Install Curtain Wal - South Elevation	8	20-Nov-20	03-Dec-20		Install Curtain Wal - South
S-1050	Install Staging - South Elevation	5	04-Dec-20	10-Dec-20		Install Staging - South Elev
S-1060	Install Stone - South Elevation	15	15-Dec-20	06-Jan-21		Install Stone - South E
S-1070	Install Brick - South Elevation	20	30-Dec-20	28-Jan-21		Install Brick - Sout
S-1080	Washdown Masonry - South Elevation	5	28-Jan-21	03-Feb-21		Washdown Maso
S-1090	Remove Staging - South Elevation	3	04-Feb-21	08-Feb-21		Remove Staging
S-1100	Caulk Facade - South Elevation	7	09-Feb-21	18-Feb-21		🔲 Caulk Facade
West Elevation	ion (CL C.7 to P)				[]	
W-1000	Frame Exterior Walls - West Elevation	36	25-Sep-20	17-Nov-20		Frame Exterior Walls - West I
W-1010	Sheath Exterior Walls - West Elevation	17	30-Oct-20	24-Nov-20		Sheath Exterior Walls - Wes
W-1020	Install AVB - West Elevation	19	06-Nov-20	07-Dec-20		Install AVB - West Elevatio
W-1030	Prep Openings for Curtain Wall - West Elevation	15	20-Nov-20	14-Dec-20		Prep Openings for Curtai
W-1040	Install Curtain Wal - West Elevation	23	04-Dec-20	07-Jan-21		Install Curtain Wall - V
W-1050	Install Staging - West Elevation	20	18-Dec-20	19-Jan-21		Install Staging - We
W-1060	Install Stone - West Elevation	5	07-Jan-21	13-Jan-21		Install Stone - West
W-1070	Install Brick - West Elevation	36	19-Jan-21	10-Mar-21		Install Brick
W-1080	Washdown Masonry - West Elevation	10	03-Mar-21	16-Mar-21		🔲 Washdowr
W-1090	Remove Staging - West Elevation	10	10-Mar-21	23-Mar-21		Remove S
W-1100	Caulk Facade - West Elevation	19	24-Mar-21	20-Apr-21		Caul
	ion (CL 2.6 to 6.4)		·			
N-1000	Frame Exterior Walls - North Elevation	7	18-Nov-20	30-Nov-20		Frame Exterior Walls - Nort
						· · · · ·
	ng Level of Effort Remaining Work		Page 16 o	f 29	TASK filter: Uncompleted Activit	
Actual Le	evel of Effort Critical Remaining Work					© Oracle Corpo
Actual W	-				e 59 of 377	

Data Date: 10-Feb-20 / Run Date: 09-Jul-20 09:05 1 2022 Jul A S Oct N D Jan F Mar Apr M Jun Jul Aug S Oct N Dec -----anent Roof (Following Staging Removal) - L3 Walls Brick / Washdown / Remove Staging - - - - - - - - - ation /ation evation t Elevation levation levation -----Elev ation ation ion vation South Elevation uth Elevation th Elevation tion ation II - West Elevation Elevation vation tion st Elevation onry - West Elevation ng - West Elevation ade - West Elevation vation



ty ID	hool - Project A - 10Feb20 R1 Schedule Update - 1318014-CR - B26 Activity Name	Remaining	Start	Deta Finish	ed Schedule Data Date: 10-Feb-20 / Run Date: 09-Jul-20 09:05
IY ID	Activity Name	Duration	Start	FILISTI	2020 2021 2022
					F [Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul Aug S Oct N
N-1010	Sheath Exterior Walls - North Elevation	5	25-Nov-20	03-Dec-20	Sheath Exterior Walls - North Elevation
N-1020	Install AVB - North Elevation	5	08-Dec-20	14-Dec-20	Install AVB - North Elevation
N-1030	Prep Openings for Curtain Wall - North Elevation	3	15-Dec-20	17-Dec-20	Prep Openings for Curtain Wall - North Elevation
N-1040	Install Curtain Wal - North Elevation	10	28-Dec-20	11-Jan-21	Install Curtain Wal - North Elevation
N-1050	Install Staging - North Elevation	5	12-Jan-21	19-Jan-21	Install Staging - North Elevation
N-1070	Install Brick - North Elevation	10	04-Mar-21	17-Mar-21	Install Brick - North Elevation
N-1080	Washdown Masonry - North Elevation	3	18-Mar-21	22-Mar-21	Washdown Masonry - North Elevation
N-1090	Remove Staging - North Elevation	2	23-Mar-21	24-Mar-21	I Remove Staging - North Elevation
N-1100	Caulk Facade - North Elevation	3	21-Apr-21	23-Apr-21	Caulk Facade - North Elevation
		5	21-Apr-21	23-Apr-21	
	st Elevation (CL D to B)		40.4.00	04.4 00	
CE-1110	Install & Adjust Metal Relieving Angle at Perimeter Curb - Cafeteria East Elevation	5	18-Aug-20	24-Aug-20	Install & Adjust Metal Relieving Angle at Perimeter Curb - Cafeteria East Elevation
CE-1000	Frame Canopy - Cafeteria East Elevation	10	22-Sep-20	05-Oct-20	Frame Canopy - Cafeteria East Elevation
CE-1010	Sheath Canopy - Cafeteria East Elevation	10	06-Oct-20	20-Oct-20	Sheath Canopy - Cafeteria East Elevation
CE-1020	Install AVB - Cafeteria East Elevation	10	14-Oct-20	27-Oct-20	Install AVB - Cafeteria East Elevation
CE-1030	Prep Openings & Install Starter Sill for Curtain Wall - Cafeteria East Elevation	10	21-Oct-20	03-Nov-20	Prep Openings & Install Starter Sill for Curtain Wal - Cafeteria East Elevation
CE-1040	Install Curtain Wal - Cafeteria East Elevation	10	28-Oct-20	10-Nov-20	Install Curtain Wall - Cafeteria East Elevation
CE-1050	Install Staging - Cafeteria East Elevation	5	12-Nov-20	18-Nov-20	Install Staging - Cafeteria East Elevation
CE-1060	Install Stone - Cafeteria East Elevation	10	19-Nov-20	04-Dec-20	Install Stone - Cafeteria East Elevation
CE-1080	Washdown Masonry - Cafeteria East Elevation	4	07-Dec-20	10-Dec-20	Washdown Masonry - Cafeteria East Elevation
CE-1120	Install Metal Panel System at Canopy - Cafeteria East Elevation	10	11-Dec-20	24-Dec-20	Install Metal Panel System at Canopy - Cafeteria East Elevation
CE-1090	Remove Staging - Cafeteria East Elevation	5	28-Dec-20	04-Jan-21	Remove Staging - Cafeteria East Elevation
CE-1100	Caulk Facade - Cafeteria East Elevation	5	05-Jan-21	11-Jan-21	Caulk Facade - Cafeteria East Elevation
	orth Elevation (CL 1 to 17.2)				
		15	25 Aug 20	15 San 20	Install & Adjust Matel Delisving Angle at Derimeter Curb Cofeteria North Flovation
CN-1110	Install & Adjust Metal Relieving Angle at Perimeter Curb - Cafeteria North Elevation	15	25-Aug-20	15-Sep-20	Install & Adjust Metal Relieving Angle at Perimeter Curb - Cafeteria North Elevation
CN-1000	Frame Canopy - Cafeteria North Elevation	20	06-Oct-20	03-Nov-20	Frame Canopy - Cafeteria North Elevation
CN-1010	Sheath Canopy - Cafeteria North Elevation	20	21-Oct-20	18-Nov-20	Sheath Canopy - Cafeteria North Elevation
CN-1020	Install AVB - Cafeteria North Elevation	15	04-Nov-20	25-Nov-20	Install AVB - Cafeteria North Elevation
CN-1030	Prep Openings & Install Starter Sill for Curtain Wall - Cafeteria North Elevation	15	10-Nov-20	03-Dec-20	Prep Openings & Install Starter, Sill for Curtain Wal - Cafeter a North Elevation
CN-1040	Install Curtain Wal - Cafeteria North Elevation	45	18-Nov-20	26-Jan-21	Install Curtain Wal - Cafeteria North Elevation
CN-1050	Install Staging - Cafeteria North Elevation	10	20-Jan-21	02-Feb-21	Install Staging - Cafeteria North Elevation
CN-1060	Install Stone along CL B - Cafeteria North Elevation	11	27-Jan-21	10-Feb-21	Install Stone along CL B - Cafeteria North Elevation
CN-1065	Install Stone along Porch - Cafeteria North Elevation	10	11-Feb-21	25-Feb-21	Install Stone along Porch - Cafeteria North Elevation
CN-1080	Washdown Masonry - Cafeteria North Elevation	4	26-Feb-21	03-Mar-21	📕 Washdown Masonry - Cafeteria North Elevation
CN-1170	Remove Staging for Masonry - Cafeteria North Elevation	5	04-Mar-21	10-Mar-21	Remove Staging for Masonry - Cafeteria North Elevation
CN-1180	Install Staging for Upper Canopy - Cafeteria North Elevation	10	08-Mar-21	19-Mar-21	Install Staging for Upper Canopy - Cafeteria North Elevation
CN-1120	Install Metal Panel System at Upper Canopy - Cafeteria North Elevation	20	22-Mar-21	16-Apr-21	Install Metal Panel System at Upper Canopy - Cafeteria North Elevation
CN-1090	Remove Staging for Upper Canopy - Cafeteria North Elevation	5	20-Apr-21	26-Apr-21	Remove Staging for Upper Canopy - Cafeteria North Elevation
CN-1160	Frame & Sheath Lower Canopy - Cafeteria North Elevation	5	27-Apr-21	03-May-21	Frame & Sheath Lower Canopy - Cafeteria North Elevation
CN-1150	Install Metal Panel System at Lower Canopy - Cafeteria North Elevation	5	04-May-21	10-May-21	 Install Metal Panel System at Lower Canopy - Cafeteria North Elevation
CN-1100	Caulk Facade - Cafeteria North Elevation	5	11-May-21	17-May-21	Caulk Facade - Cafeteria North Elevation
CN-1190	Waterproof Porch - Cafetera North Elevation	10	18-May-21	01-Jun-21	Waterproof Porch - Cafetera North Elevation
	•		-		
CN-1130	Install Granite Treads - Cafetera North Elevation	15	02-Jun-21	22-Jun-21	Install Granite Treads - Cafetera North Elevation
CN-1200	Install Granite Pavers - Cafetera North Elevation	10	23-Jun-21	07-Jul-21	
CN-1140	Install Metal Railings - Cafetera North Elevation	15	08-Jul-21	28-Jul-21	Install Metal Railings - Cafetera North Elevation
	est Elevation (CLA.5 to D)				
CW-1000	Frame Canopy - Cafeteria West Elevation	5	04-Nov-20	10-Nov-20	Frame Canopy - Cafeteria West Elevation
CW-1010	Sheath Canopy - Cafeteria West Elevation	5	19-Nov-20	25-Nov-20	Sheath Canopy - Cafeteria West Elevation
CW-1020	Install AVB - Cafeteria West Elevation	5	30-Nov-20	04-Dec-20	Install AVB - Cafeteria West Elevation
CW-1030	Prep Openings & Install Starter Sill for Curtain Wall - Cafeteria West Elevation	5	07-Dec-20	11-Dec-20	Prep Openings & Install Starter Sill for Curtain Wal - Cafeteria West Elevation
CW-1046	Install Curtain Wallover Tracks - Cafeteria West Elevation (Weekend 1)	2	16-Jan-21	17-Jan-21	Install Curtain Wall over Tracks - Cafeteria West Elevation (Weekend 1)
CW-1210	Install Curtain Wallover Tracks - Cafeteria West Elevation (Weekend 2)	2	23-Jan-21	24-Jan-21	I Install Curtain Wall over Tracks - Cafeteria West Elevation (Weekend 2)
CW-1040	Install Curtain Wal - Cafeteria West Elevation including White Box (Weekday)	16	27-Jan-21	18-Feb-21	Install Curtain Wal - Cafeteria West Elevation including White Box (Weekday)
CW-1060	Install Stone - Cafeteria West Elevation	2	26-Feb-21	01-Mar-21	I Install Stone - Cafeteria West Elevation
CW-1080	Washdown Masonry - Cafete ria West Elevation	1	02-Mar-21	02-Mar-21	I Washdown Masonry - Cafeteria West Elevation
Remaini	ing Level of Effort Remaining Work		Page 17 c	of 20	TASK filter: Uncompleted Activities Two Months Prior.
			raye 17 C	n 23	
	evel of Effort Critical Remaining Work			_	© Oracle Corporation
Actual W	Vork	1		Page	60 of 377



y ID	ol - Project A - 10Feb20 R1 Schedule Update - 1318014-CR - B26	Remaining	Start	Finish	ed Schedule			
y iD		Duration	Otart	L F	2020			20
					F Mar Apr M Jun Jul A	3 Oct N D		
CW-1180	Install Staging for Upper Canopy - Cafeteria West Elevation	2	22-Mar-21	23-Mar-21			I	Install Staging
CW-1120	Install Metal Panel System at Upper Canopy - Cafeteria West Elevation	5	20-Apr-21	26-Apr-21				Install N
CW-1090	Remove Staging for Upper Canopy - Cafeteria West Elevation	2	27-Apr-21	28-Apr-21			 	Remov
levators								
ELEV-1000	Build Elevator Shafts - South	20	10-Sep-20	07-Oct-20		📥 Build Elevε	tor Shafts - Sou	uth
ELEV-1010	Install Elevators - South	60	08-Oct-20	07-Jan-21			1 1	itors - South
ELEV-1020	Build Elevator Shaft - North	10	11-Feb-21	25-Feb-21			1	d Elevator Sh
ELEV-1020	Install Elevators - North	60	26-Feb-21	21-May-21				
IEP System		00	2010021	21 May 21				
			40.0.00		_			
MEP-1500	Build Walls - Garden Level Mechanical & Electrical Rooms	15	10-Sep-20	30-Sep-20	•	1	Garden Level	
MEP-1510	FRP Equipment Pads - Garden Level Mechanical & Electrical Rooms	5	01-Oct-20	07-Oct-20		FRP Equip	ment Pads - Ga	arden Level N
Hot Wate r								
Garden Level					· · · · · · · · · · · · · · · · · · ·	 	 	
MEP-2050	Rig & Set Boilers (B-1/2/3) & Expansion Tank (ET-2) - Hot Water System	2	08-Oct-20	09-Oct-20		-	30ilers (B-1/2/3	
MEP-3350	Install Mechanical Piping to Boilers (B-1/2/3) & Expansion Tank (ET-2) - Hot Water System	20	13-Oct-20	09-Nov-20			Mechanical Pip	
MEP-3400	Install Electrical Conduits & Wiring to Boilers (B-1/2/3) & Expansion Tank (ET-2) - Hot Wate	15	10-Nov-20	03-Dec-20		📕 Ir	stall Electrical (Conduits & W
MEP-3360	Install Controls Wiring to Boilers (B-1/2/3) & Expansion Tank (ET-2) - Hot Water System	10	04-Dec-20	17-Dec-20			Install Controls	Wiring to Bo
MEP-3370	Fill, Flush & Treat Piping - Hot Water System	5	18-Dec-20	24-Dec-20			Fill, Flush & T	reat Piping - I
MEP-3380	Insulate Piping - Hot Water System	20	28-Dec-20	26-Jan-21			Insulate	Piping - Hot \
MEP-3390	Start-up & Test - Hot Water System	15	08-Jan-21	29-Jan-21			1	& Test - Hot
Chilled Water							· ·	
Roof								
MEP-2000	Pig & Sat Chillor (CH 1) at Paof. Chilled Water System	2	10 Aug 20	20 Aug 20	I P	g & Set Chiller ((U 1) at Boof	
MEP-2000	Rig & Set Chiller (CH-1) at Roof - Chilled Water System	2	19-Aug-20	20-Aug-20				
	Install Mechanical Piping to Chiller (CH-1) - Chilled Water System	20	21-Aug-20	18-Sep-20		Install Mechar		
MEP-2020	Install Electrical Conduits & Wiring to Chiller (CH-1) - Chilled Water System	15	21-Sep-20	09-Oct-20				-
MEP-2030	Install Controls Wiring to Chiller (CH-1) - Chilled Water System	10	13-Oct-20	26-Oct-20			ontrols Wiring	o Chiller (CH
Garden Level		•	10.0.1.00					(0.01)
MEP-2040	Rig & Set Chilled Water Pumps (GCHWP-1/2/3) & Expansion Tank (ET-1) - Chilled Water §	2	13-Oct-20	14-Oct-20			Chilled Water F	
MEP-3200	Rig & Set Gycol Feed System (GFT-1) - Chilled Water System	2	15-Oct-20	16-Oct-20			Gycol Feed Sy	
MEP-3170	Install Mechanical Piping to Chilled Water Pumps (GCHW P-1/2/3) & Expansion Tank (ET-1	20	27-Oct-20	24-Nov-20		1	tall Mechanical	
MEP-3180	Install Electrical Conduits & Wiring to Chilled Water Pumps (GCHWP-1/2/3) & Expansion Ta	15	18-Nov-20	10-Dec-20			nstall Electrical	
MEP-3210	Install Mechanical Piping to Glycol Feed System (GFT-1) - Chilled Water System	5	25-Nov-20	03-Dec-20			stall Mechanica	
MEP-3220	Install Electrical Conduits & Wiring to System (GFT-1) - Chilled Water System	5	11-Dec-20	17-Dec-20			Install Electrica	I Conduits &
MEP-3190	Install Controls Wiring to Chilled Water Pumps (GCHW P-1/2/3) & Expansion Tank (ET-1) -	10	11-Dec-20	24-Dec-20			Install Control	s Wiring to C
MEP-3230	Install Controls Wiring to Gycol Feed System (GFT-1) - Chilled Water System	5	28-Dec-20	04-Jan-21		1	Install Contr	ols Wiring to
MEP-3320	Fill, Flush & Treat Piping - Chilled Water System	5	05-Jan-21	11-Jan-21			Fill, Flush 8	k Treat Piping
MEP-3330	Insulate Piping - Chilled Water System	20	12-Jan-21	09-Feb-21			📕 Insulat	e Piping - Ch
MEP-3340	Start-up & Test - Chilled Water System	15	27-Jan-21	17-Feb-21			📕 Start	-up & Test - (
Air Handiling								
Garden Level								
	en) & AHU-4 (Cafe/Servery)							
MEP-2060	Rig & Set - AHU-3 (Kitchen) & AHU-4 (Cafe/Servery)	2	19-Oct-20	20-Oct-20		Ria & Se	t - AHU-3 (Kitch	en) & AHU-4
MEP-2070	Install Ductwork Connections - AHU-3 (Kitchen) & AHU-4 (Cafe/Servery)	15	02-Nov-20	23-Nov-20			all Ductwork C	,
MEP-3410	Install Mechanical Piping Connections - AHU-3 (Kitchen) & AHU-4 (Cafe/Servery)	15	17-Nov-20	09-Dec-20			hstall Mechanic	
MEP-3420	Install Electrical Conduits & Wiring - AHU-3 (Kitchen) & AHU-4 (Cafe/Servery)	15	03-Dec-20	23-Dec-20		1	Install Electric	
MEP-3430	Install Controls Wiring - AHU-3 (Kitchen) & AHU-4 (Cafe/Servery)	10	24-Dec-20	08-Jan-21		1	Install Cont	
MEP-3440		5				L		-
	Start-up & Test - AHU-3 (Kitchen) & AHU-4 (Cafe/Servery)	5	11-Mar-21	17-Mar-21				Start-up & Te
Roof								
-	Northeast) & AHU-6 (Class Northwest)		04 4	01 Avr 00				
MEP-3450	Rig & Set - AHU-5 (Class Northeast) & AHU-6 (Class Northwest)	1	21-Aug-20	21-Aug-20		g & Set - AHU-5	i l	
MEP-3460	Install Ductwork Connections - AHU-5 (Class Northeast) & AHU-6 (Class Northwest)	15	24-Aug-20	14-Sep-20		Install Ductwo	1	
MEP-3470	Install Mechanical Piping Connections - AHU-5 (Class Northeast) & AHU-6 (Class Northwe	15	08-Sep-20	28-Sep-20		Install Mech		
MEP-3480	Install Electrical Conduits & Wiring - AHU-5 (Class Northeast) & AHU-6 (Class Northwest)	15	22-Sep-20	13-Oct-20		Install Ele	trical Conduits	& Wiring - Al
					1			
Remaining	Level of Effort Remaining Work		Page 18 o	f 29	TASK filter: Uncompleted Activ	ities Two Month	s Prior.	
0								
Actual Lev	el of Effort Critical Remaining Work						© Ora	cle Corpora

Data Date: 10-Feb-20	/	Run Date: 09-Jul-20 09:05

1 Jul A S			lan	E Mar	Apri)22	¢		N	Dec
Jul A S or Upper Ca			Jan	F [Mar		MJun	Jul Aug	S	Oct	IN	Dec
					1	oct Ela	ation				
tal Panel Sys							auon				
Staging for U	pper Ca	anopy -	carete		sι⊨lev	alion					
	1	1			1		1		1		
	1				1		1		1		
		1			1		1		1		
t - North	-						1				
Elevators - 1	North	1			1		1		1		
							+				
		i					1		1		
ectrical Roo	ms	l			1		1		1		
chanical & Ele	ectrical	Rooms			1		1		1		
					1				1		
	1				1		1		1		
ank (ET-2) -	Hot Wa	ter Sys	tem								
, B-1/2/3) & Ex				- Hot W	ater S	ystem					
ng to Boilers (1				-	ater Svster	n			
rs (B-1/2/3) 8	1	· ·									
t Water Syste	1		(= 1	_,		5,510					
iter System											
-							- 				
ater System											
							- 				
					1				1		
ystem	 						 				
Chilled Water	System	n ¦									
ler (CH-1) - (Chilled V	VaterS	ys te m	l							
) - Chilled Wa	ater Sys	tem									
	 				 		- - 		 		
-1/2/3) & Ex	pansion	Tank (ET-1)	- Chillec	Wate	r Syster	ή				
Chilled Wate							1 1 1				
Water Pum			2/3)&	Expans	ion Ta	nk (ET-	1) - Chilled	Wat	ter Sv	stem	1
ing to Chilled	1				1		1				
ol Feed Syste	1				1.1			,	1		
iring to Syste							1		1		
led Water Pu						Tank (F	T-1) - Chill	ed W	/ater 9	Svste	 m
ycol Feed Sys							;-1)-01111 :			JySi	,,,,,
Chilled Water			Crime		Joyste		1 1 1				
d Water Sys		"					1				
	1	1									
led Water Sy	siem				 						
	1	1			1				1		
							- 				
	1 1	1					1 1				
Cafe/Servery					 		1 1		 		
IU-3 (Kitchen											
ctions - AHU	-3 (Kitc	hen) &	AHU-4	(Cafe	Serve	ry)					-
/iring - AHU-:	3 (Kitch	en) & A	HU-4	(Cafe/S	ervery)	- - 		 		
U-3 (Kitchen) & AHL	J-4 (Ca	afe/Se	rvery)			- - 		 		
- AHU-3 (Kitc	1						1				
`		İ		,			1				
							T		 '		
lass Northwe	est)	İ			1		1		1		
Northeast)		6 (Class	s Nort	hweet)			- - 		 		
U-5 (Class N					orthur	et)	1				
	i.	· ·			i		- - 		 		
I-5 (Class No	uleast		J-0 (U	1055 INO	uwes	or)					



ty ID	Activity Name	Domoinin	Chart	Einiah	
ty ID	Activity Name	Remaining Duration		Finish	2020 2021 2022
					F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul Aug S Oct N
MEP-3490	Install Controls Wiring - AHU-5 (Class Northeast) & AHU-6 (Class Northwest)	10	14-Oct-20	27-Oct-20	Install Controls Wiring - AHU-5 (Class Northeast) & AHU-6 (Class Northwest)
MEP-3500	Start-up & Test - AHU-5 (Class Northeast) & AHU-6 (Class Northwest)	5	18-Feb-21	24-Feb-21	Start-up & Test - AHU-5 (Class Northeast) & AHU-6 (Class Northwest)
AHU-7 (Class S	Southeast) & AHU-8 (Class South)				
MEP-3510	Rig & Set - AHU-7 (Class Southeast) & AHU-8 (Class South)	1	24-Aug-20	24-Aug-20	Rig & Set - AHU-7 (Class Southeast) & AHU-8 (Class South)
MEP-3520	Install Ductwork Connections - AHU-7 (Class Southeast) & AHU-8 (Class South)	15	08-Sep-20	28-Sep-20	Install Ductwork Connections - AHU-7 (Class Southeast) & AHU-8 (Class South)
	Install Mechanical Piping Connections - AHU-7 (Class Southeast) & AHU-8 (Class South)	15	22-Sep-20	13-Oct-20	Install Mechanical Piping Connections - AHU-7 (Class Southeast) & AHU-8 (Class South)
	Install Electrical Conduits & Wiring - AHU-7 (Class Southeast) & AHU-8 (Class South)	15	06-Oct-20	27-Oct-20	Install Electrical Conduits & Wiring - AHU-7 (Class Southeast) & AHU-8 (Class South)
	Install Controls Wiring - AHU-7 (Class Southeast) & AHU-8 (Class South)	10	28-Oct-20	10-Nov-20	Install Controls Wiring - AHU-7 (Class Southeast) & AHU-8 (Class South)
	Start-up & Test - AHU-7 (Class Southeast) & AHU-8 (Class South)	5	25-Feb-21	03-Mar-21	Start-up & Test - AHU-7 (Class Southeast) & AHU-8 (Class South)
	Box) & AHU-2 (Library)		2010021		
•	Rig & Set - AHU-1 (White Box) & AHU-2 (Library)	1	25-Aug-20	25-Aug-20	I Rig & Set - AHU-1 (White Box) & AHU-2 (Library)
	Install Ductwork Connections - AHU-1 (White Box) & AHU-2 (Library)	15	22-Sep-20	13-Oct-20	Install Ductwork Connections - AHU-1 (White Box) & AHU-2 (Library)
			•		
	Install Mechanical Piping Connections - AHU-1 (White Box) & AHU-2 (Library)	15	06-Oct-20	27-Oct-20	Install Mechanical Piping Connections - AHU-1 (White Box) & AHU-2 (Library)
	Install Electrical Conduits & Wiring - AHU-1 (White Box) & AHU-2 (Library)	15	21-Oct-20	10-Nov-20	Install Electrical Conduits & Wiring - AHU-1 (White Box) & AHU-2 (Library)
	Install Controls Wiring - AHU-7 (Class Southeast) & AHU-8 (Class South)	10	12-Nov-20	25-Nov-20	Install Controls Wiring - AHU-7 (Class Southeast) & AHU-8 (Class South)
	Start-up & Test - AHU-7 (Class Southeast) & AHU-8 (Class South)	5	04-Mar-21	10-Mar-21	Start-up & Test; AHU-7 (Class Southeast) & AHU-8 (Class South)
Domestic Wate	r				
MEP-3630	Rig & Set - Domestic Water Heaters (DMH-1/2)	2	19-Oct-20	20-Oct-20	Rig & Set - Domestic Water Heaters (DMH-1/2)
MEP-3640	Install Plumbing Connections - Domestic Water Heaters (DMH-1/2)	20	21-Oct-20	18-Nov-20	Install Plumbing Connections - Domestic Water Heaters (DMH-1/2)
MEP-3650	Test Piping - Domestic Water Heaters (DMH-1/2)	5	22-Jan-21	28-Jan-21	Test Piping - Domestic Water Heaters (DMH-1/2)
MEP-3660	Insulate Piping - Domestic Water Heaters (DMH-1/2)	15	29-Jan-21	19-Feb-21	Insulate Piping - Domestic Water Heaters (DMH-1/2)
Electrical				,	
Garden Level					
	Install Overhead Conduits & Electrical Panels - Permanent Power	15	08-Oct-20	29-Oct-20	Install Overhead Conduits & Electrical Panels - Permanent Power
		10	30-Oct-20	13-Nov-20	 Rig, Set & Assemble Switchgear - Permanent Power
	Rig, Set & Assemble Switchgear - Permanent Power				
	Install Doors & Secure Room - Permanent Power	10	16-Nov-20	01-Dec-20	Install Doors & Secure Room - Permanent Power
	Wire & Terminate Panels & Switchgear - Permanent Power	20	16-Nov-20	15-Dec-20	Wire & Terminate Panels & Switchgear - Permanent Power
	Pull Conductors & Terminate - Permanent Power	5	16-Dec-20	22-Dec-20	Pull Conductors & Terminate - Perman ent Power
	Test Switchgear - Permanent Power	5	23-Dec-20	30-Dec-20	Test Switchgear - Permanent Power
	Energize Switchgear - Permanent Power	5	31-Dec-20	07-Jan-21	Energize Switchgear - Permanent Power
MEP-3310	Permanent Power Available	0		07-Jan-21	Permanent Power Available
nteriors					
MEP-1000	MEP & Architectural Rough-in - L1	91	18-Aug-20	30-Dec-20	MEP & Architectural Rough-in - L1
	MEP & Architectural Rough-in - L2	62	01-Sep-20	02-Dec-20	MEP & Architectural Rough-in - L2
	MEP & Architectural Rough-in - Garden Level	101	10-Sep-20	08-Feb-21	MEP & Architectural Rough-in - Garden Level
	MEP & Architectural Rough-in - L3	67	16-Sep-20	23-Dec-20	MEP & Architectural Rough-in - L3
	MEP & Architectural Rough-in - L4	72	30-Sep-20	15-Jan-21	MEP & Architectural Rough-in - L4
	Interior Drywall & Finishes - L1	98	11-Feb-21	01-Jul-21	Interior Drywall & Finishes - L1
	Interior Drywali & Finishes - L1		26-Feb-21	13-Aug-21	Interior Drywall & Finishes - L2
		118		-	Interior Drywall & Finishes - L2
	Interior Drywall & Finishes - L3	123	12-Mar-21	03-Sep-21	
	Interior Drywall & Finishes - L4	128	26-Mar-21	27-Sep-21	Interior Drywall & Finishes + L4
	Interior Drywall & Finishes - Garden Level	120	09-Apr-21	29-Sep-21	Interior Drywall & Finishes - Garden Level
Level 1					
L1-1010	Install MEP Risers - L1	10	18-Aug-20	31-Aug-20	Install MEP Risers - L1
L1-1000	Install Tube Steel Wall Supports - L1	5	01-Sep-20	08-Sep-20	Install Tube Steel Wall Supports - L1
L1-1020	Rough-in Overhead Ductwork - L1	15	01-Sep-20	22-Sep-20	Rough-in Overhead Ductwork - L1
	Rough-in Overhead Plumbing - L1	15	01-Sep-20	22-Sep-20	Rough-in Overhead Plumbing - L1
	Rough-in Overhead Mechanical Piping - L1	15	09-Sep-20	29-Sep-20	Rough-in Overhead Mechanical Piping - L1
	Rough-in Overhead Electrical Conduit - L1	20	09-Sep-20	06-Oct-20	Rough-in Overhead Electrical Conduit - L1
	Frame Electrical Closets - L1	3	23-Sep-20	25-Sep-20	Frame Electrical Closets - L'1
	Rough Fire Protection - L1	10	23-Sep-20 23-Sep-20	06-Oct-20	Rough Fire Protection - L1
	Install Above Ceiling Mechanical Equipment - L1				Rough File Protection - Li Install Above Ceiling Mechanical Equipment - L1
		10 <i>F</i>	23-Sep-20	06-Oct-20	
	Board & Tape Electrical Closets - L1	5	28-Sep-20	02-Oct-20	Board & Tape Electrical Closets - L1
L1-1090	Frame Interior Wals - L1	10	30-Sep-20	14-Oct-20	Frame Interior Wals - L1
Remaining I	evel of Effort Remaining Work		Page 19 c	f 20	TASK filter: Uncompleted Activities Two Months Prior
			Faye 190	1 23	TASK filter: Uncompleted Activities Two Months Prior.
Actual Level	l of Effort Critical Remaining Work				© Oracle Corporation

-	nool - Project A - 10Feb20 R1 Schedule Update - 1318014-CR - B26		Chart	Detail	
vity ID	Activity Name		Start	Finish	2020 2021 2022
		Duration			F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul Aug S Oc
L1-1450	Insulate Overhead Mechanical Piping & HVAC Ductwork - L1	15	30-Sep-20	21-Oct-20	Insulate Øverhead Mechanical Piping & HVAC Ductwork - L1
L1-1120	Set Door Frames - L1	5	05-Oct-20	09-Oct-20	Set Door Frames - L1
L1-1110	Rough-in Plumbing In-Wall - L1	10	07-Oct-20	21-Oct-20	Rough-in Plumbing In-Wall - L1
L1-1100	Frame Soffits - L1	10	13-Oct-20	26-Oct-20	Frame Soffits - L1
L1-1140	Rough-in Electrical In-Wall & Pull Branch Circuits - L1	15	15-Oct-20	04-Nov-20	Rough-in Electrical In-Wall & Pull Branch Circuits - L1
L1-1150	Rough-in Low Voltage In-Wall & Pull Wire - L1	15	15-Oct-20	04-Nov-20	Rough∔in Low Voltage In-Wall & Pull Wire - L1
L1-1160	Perform Wall & Ceiling Punch List & Inspections - L1	10	04-Nov-20	18-Nov-20	Perform Wall & Ceiling Punch List & Inspections' - L1
L1-1170	Perform In-Wall Inspections with Town - L1	2	05-Nov-20	06-Nov-20	Perform In-Wall Inspections with Town - L1
L1-1180	Install Wood Blocking - L1	5	09-Nov-20	16-Nov-20	□ Install Wood Blocking - L1
L1-1330	Insulate In-Wall Piping - L1	5	09-Nov-20	16-Nov-20	Insulate In-Wall Piping - L1
L1-1190	Board Wals & Soffits - L1	10	11-Feb-21	25-Feb-21	Board Wals & Soffits - L1
L1-1210	Tape Walls & Soffits - L1	10	19-Feb-21	04-Mar-21	Tape Walls & Soffits - L1
L1-3050	Field Measure & Fab Interior Glass - L1	20	19-Feb-21	18-Mar-21	Field Measure'& Fab Interior'Glass - L1
				12-Mar-21	Prime & 1st Coat walls - L1
L1-1220	Prime & 1st Coat walls - L1	6	05-Mar-21		
L1-1230	Install Ceiling Grid & Cut/DeviceTies at Classrooms & Offices - L1	10	10-Mar-21	23-Mar-21	Install Ceiling Grid & Cut/DeviceTies at Classrooms & Offices - L1
L1-3060	Install Wall Tile at Corridors - L1	10	10-Mar-21	23-Mar-21	Install Wal Tile at Corridors - L1
L1-1240	Install MEP Drops at Classrooms & Offices - L1	10	17-Mar-21	30-Mar-21	Install MEP Drops at Classrooms & Offices - L1
L1-1250	Install Storefront Frames - L1	10	24-Mar-21	06-Apr-21	Install Storefront Frames - L1
L1-1260	Install Millwork at Classrooms & Offices - L1	10	31-Mar-21	13-Apr-21	Install Millwork at Classrooms & Offices - L1
L1-1440	Install Teledata Finishes & Terminations - L1	10	31-Mar-21	13-Apr-21	Install Teledata Finishes & Terminations - L1
L1-1390	Install Interior Glazing - L1	10	07-Apr-21	21-Apr-21	Install Interior Glazing - L1
L1-1445	Install Fintube Radiators - L1	10	07-Apr-21	21-Apr-21	Install Fintube Radiators - L1
L1-1275	Install Simulated Wood Aluminum Ceiling Panel System - L1	15	07-Apr-21	28-Apr-21	Install Simulated Wood Aluminum Ceiling Panel System - L1
L1-1270	Install Ceiling Grid & Cut/DeviceTles at Corridors - L1	5	14-Apr-21	21-Apr-21	Install Ceiling Grid & Cut/DeviceTiles at Corridors - L1
L1-1370	Install Doors & Hardware - L1	5	14-Apr-21	21-Apr-21	Install Doors & Hardware - L1
L1-1380	Install Flooring at Classrooms & Offices - L1	10	14-Apr-21	28-Apr-21	Install Flooring at Classrooms & Offices - L1
L1-1280	Install MEP Drops at Corridors - L1	8	22-Apr-21	03-May-21	Install MEP Drops at Corridors - L1
L1-1285	Install Fintube Covers - L1	10	22-Apr-21	05-May-21	Install Fintube Covers - L1
L1-1430	Install Fire Alarm Devices - L1	5	29-Apr-21	05-May-21	Install Fire Alarm Devices - L1
L1-1300	Install Terrazzo at Corridors - L1	20	29-Apr-21	26-May-21	Install Terrazzo at Corridors - L1
L1-1360	Install Terrazzo Base at Corridors - L1	10	20-May-21	03-Jun-21	Install Terrazzo Base at Corridors - L1
L1-1310	Install Lockers - L1	5	04-Jun-21	10-Jun-21	Install Lockers + L1
L1-1320	Install AV - L1	5	04-Jun-21	10-Jun-21	Install AV - L1
L1-1340	Install Whiteboards & Tack Boards - L1	5	04-Jun-21	10-Jun-21	Install Whiteboards & Tack Boards - L1
L1-1350	Install Window Shades - L1	5	04-Jun-21	10-Jun-21	Install Window Shades - L1
L1-1400	Construction Cleaning - L1	5	11-Jun-21	17-Jun-21	Construction Cleaning - L1
L1-1400	Balance HVAC - L1	5	18-Jun-21	24-Jun-21	Balance HVAC - L1
L1-1290	Skanska Punch List - L1	5		24-Jun-21 24-Jun-21	Skanska Punch List - L1
		5	18-Jun-21		
L1-1420	Architect Punch List - L1	5	25-Jun-21	01-Jul-21	Architect Punch List - L1
Bathrooms					
L1-1600	Board & Install Cement Board - L1 Bathrooms	5	19-Feb-21	25-Feb-21	Board & Install Cement Board - L1 Bathrooms
L1-1605	Tape & Finish - L1 Bathrooms	5	26-Feb-21	04-Mar-21	Tape & Finish - L1 Bathrooms
L1-1610	Prime Paint - L1 Bathrooms	3	05-Mar-21	09-Mar-21	Prime Paint - L1 Bathrooms
L1-1615	Install Counters - L1 Bathrooms	2	10-Mar-21	11-Mar-21	Install Counters - L1 Bathrooms
L1-1620	Install Wall & Floor Tile - L1 Bathrooms	10	12-Mar-21	25-Mar-21	Install Wall & Floor Tile - L1 Bathrooms
L1-1625	Install Plumbing Fixtures - L1 Bathrooms	5	26-Mar-21	01-Apr-21	Install Plumbing Fixtures - L1 Bathrooms
L1-1630	Field Measure & Fab Mirrors - L1 Bathrooms	10	26-Mar-21	08-Apr-21	Field Measure & Fab Mirrors - L1 Bathrooms
L1-1635	Install Toilet Partitions - L1 Bathrooms	4	02-Apr-21	07-Apr-21	Install Toilet Partitions - L1 Bathrooms
L1-1640	Install Bathroom Accessories - L1 Bathrooms	4	08-Apr-21	13-Apr-21	Install Bathroom Accessories - L1 Bathrooms
L1-1645	Install Mirrors - L1 Bathrooms	2	14-Apr-21	15-Apr-21	I Install Mirrors - L1 Bathrooms
L1-1650	Finish Paint - L1 Bathrooms	2	16-Apr-21	20-Apr-21	Finish Paint - L1 Bathropms
White Box		, _ ,			
L1WB-1000	Install HSS Tube Steel - L1 White Box	5	23-Sep-20	29-Sep-20	Install HSS Tube Steel - L1 White Box
L1WB-1000	Install Rolling Staging - L1 White Box	5	15-Oct-20	23-Gep-20 21-Oct-20	Install Rolling Staging - L1 White Box
L1WB-1001	Rough-in MEPs above Sound Barrier Ceiling - L1 White Box	10	22-Oct-20	04-Nov-20	Rough-in MEPs above Sound Barrier Ceiling - L1 White Box
			22-061-20	04-1007-20	
Remainir	ng Level of Effort Remaining Work		Page 20 o	of 29	TASK filter: Uncompleted Activities Two Months Prior.
Actual Le	evel of Effort Critical Remaining Work				© Oracle Corporation SKANSKA
	-				



	ol - Project A - 10Feb20 R1 Schedule Update - 1318014-CR - B26		Detailed S				
/ ID	Activity Name	Remaining Duration		Finish	2020	2021	2022
		Duration				N D Jan F Mar Apr M Jun Jul A S Oct N D Jan F Mar A	
L1WB-1090	Frame Interior Wals - L1 White Box	5	05-Nov-20	12-Nov-20		Frame Interior Wals - L1 White Box	
L1WB-1140	Rough-in Electrical In-Wall & Pull Branch Circuits - L1 White Box	5	13-Nov-20	19-Nov-20		Rough-in Electrical In-Wall & Pull Branch Circuits - L1 White Box	
L1WB-1150	Rough-in Low Voltage In-Wall & Pull Wire - L1 White Box	5	13-Nov-20	19-Nov-20		Rough-in Low Voltage In-Wall & Pull Wire - L1 White Box	
L1WB-1170	Perform In-Wall Inspections with Town - L1 White Box	2	20-Nov-20	23-Nov-20	Perform In-Wall Inspections with Town - L1 White Box		
L1WB-1180	Install Wood Blocking - L1 White Box	3	24-Nov-20	30-Nov-20		Install Wood Blocking - L1 White Box	
L1WB-1190	Board & Tape Walls - L1 White Box	5	26-Feb-21	04-Mar-21		Board & Tape Walls - L1 White Box	
L1WB-1210	Install Hangers & Frame Sound Barrier Ceiling - L1 White Box	10	05-Mar-21	18-Mar-21		Install Hangers & Frame Sound Barrier Ceiling - L1 White B	ο χ
L1WB-1405	Board & Tape Sound Barrier Ceiling - L1 White Box	5	19-Mar-21	25-Mar-21		Board & Tape Sound Barrier Ceiling - L1 White Box	
L1WB-1440	Paint Ceiling - L1 White Box	3	26-Mar-21	30-Mar-21		Paint Ceiling - L1 White Box	
L1WB-1440	Field Measure & Fab Interior Glazing - L1 White Box	25		30-Apr-21		Field Measure & Fab Interior Glazing - L1 White Box	
	-		26-Mar-21	· · · · · · · · · · · · · · · · · · ·			
L1WB-1450	Install Sound Absorbing 1" Perimeter Metal Ceiling Panels - L1 White Box	5	31-Mar-21	06-Apr-21		Install Sound Absorbing 1" Perimeter Metal Ceiling Panels	
L1WB-1425	Install Unistrut & Steel Pipe Grid System - L1 White Box	10	07-Apr-21	21-Apr-21		Install Unistrut & Steel Pipe Grid System - L1 White Bo	
L1WB-1415	Rough-in HVAC Below Sound Barrier Ceiling - L1 White Box	5	22-Apr-21	28-Apr-21		Rough-in HVAC Below Sound Barrier Ceiling - L1 White Rough - Rough - Rou	· · · · ·
L1WB-1460	Install Electical Rough-in Below Sound Barrier Ceiling - L1 White Box	5	29-Apr-21	05-May-21		Install Electical Rough-in Below Sound Barrier Ceiling	
L1WB-1470	Install Metal Strut Channel at Walls - L1 White Box	8	06-May-21	17-May-21		Install Metal Strut Channel at Walls - L1 White Box	
L1WB-1480	Install Perforated Plywood Wall Panels - L1 White Box	8	11-May-21	20-May-21		Install Perforated Plywood Wall Panels - L1 White	Box
L1WB-1490	Install Wood Sunshade Grille - L1 White Box	8	14-May-21	25-May-21		Install Wood Sunshade Grille - L1 White Box	
L1WB-1430	Install Floor Isolators & Plywood Subfloor - L1 White Box	10	26-May-21	09-Jun-21		Install Floor Isolators & Plywood Subfloor - L1 \	Nhite Box
L1WB-1250	Install Storefront Frames - L1 White Box	5	10-Jun-21	16-Jun-21		Install Storefront Frames - L1 White Box	
L1WB-1510	Build Seating Platforms - L1 White Box	15	10-Jun-21	30-Jun-21		Build Seating Platforms - L1 White Box	
L1WB-1390	Install Interior Glazing - L1 White Box	3	17-Jun-21	21-Jun-21		Install Interior Glazing - L1 White Box	
L1WB-1530	Install Barn Door - L1 White Box	3	01-Jul-21	06-Jul-21		Install Barn Door - L1 White Box	
L1WB-1520	Install Painted 1/4" Hardboard Flooring Panels - L1 White Box	5	07-Jul-21	13-Jul-21		Install Painted 1/4" Hardboard Flooring Painted	anels - I 1 White Box
L1WB-1515	Install Light Fixtures & Electrical Finishes - L1 White Box	5	14-Jul-21	20-Jul-21		 Install Light Fixtures & Electrical Finisher 	· · · ·
L1WB-1540	Install Black Sharkstooth Scrim - L1 White Box	2	21-Jul-21	20-Jul-21 22-Jul-21		■ Install Black Sharkstooth Scrim - L1 Wh	
L1WB-1560	Install Projection Screen - L1 White Box	2	23-Jul-21	26-Jul-21		Install Projection Screen - L1 White Bo	
L1WB-1590	Install AV Projectors & Speakers - L1 White Box	5	23-Jul-21	29-Jul-21		Install AV Projectors & Speakers - L1 V	
L1WB-1570	Install White Cyclorama - L1 White Box	3	30-Jul-21	03-Aug-21		Install White Cyclorama - L1 White Bo	x
L1WB-1550	Install Seating - L1 White Box	3	04-Aug-21	06-Aug-21		Install Seating - L1 White Box	
L1WB-1580	Install Curtain - L1 White Box	2	09-Aug-21	10-Aug-21		Install Curtain - L1 White Box	
L1WB-1400	Construction Cleaning - L1 White Box	2	11-Aug-21	12-Aug-21		I Construction Cleaning - L1 White Bo	x
L1WB-1410	Skanska Punch List - L1 White Box	2	13-Aug-21	16-Aug-21		Skanska Punch List - L1 White Box	
L1WB-1420	Architect Punch List - L1 White Box	2	17-Aug-21	18-Aug-21		Architect Punch List - L1 White Box	
Cafeteria							
L1CAFE-1012	Install Intumescent Paint at Columns - L1 Cafeteria	25	18-Aug-20	22-Sep-20	Insta	III Intumescent Paint at Columns - L1 Cafeteria	
L1CAFE-1002	Install Rolling Staging - L1 Cafeteria	5	29-Oct-20	04-Nov-20		Install Rolling Staging - L1 Cafeteria	
L1CAFE-1030	Rough-in Overhead Plumbing - L1 Cafeteria	5	05-Nov-20	12-Nov-20		Rough-in Overhead Plumbing - L1 Cafeteria	
L1CAFE-1020	Rough-in Overhead Ductwork - L1 Cafeteria	10	05-Nov-20	19-Nov-20		Rough-in Overhead Ductwork - L1 Cafeteria	
L1CAFE-1040	Rough-in Overhead Mechanical Piping - L1 Cafeteria	10	13-Nov-20	30-Nov-20		Rough-in Overhead Mechanical Piping - L1 Cafeteria	
L1CAFE-1040				07-Dec-20		Rough-in Overhead Mechanical Piping - L1 Caleteria	
	Rough-in Overhead Electrical Conduit - L1 Cafeteria	10	20-Nov-20				
L1CAFE-1070	5	5	01-Dec-20	07-Dec-20		Rough Fire Protection - L1 Cafeteria	
L1CAFE-1130	Install Above Ceiling Mechanical Equipment - L1 Cafeteria	5	01-Dec-20	07-Dec-20		Install Above Ceiling Mechanical Equipment - L1 Cafeteria	
L1CAFE-1090		5	08-Dec-20	14-Dec-20		Frame Interior Wals - L1 Cafeteria	
L1CAFE-1115		4	16-Dec-20	21-Dec-20		Rough-in Electrical In-Wall - L1 Cafeteria	
L1CAFE-1170	Perform In-Wall Inspections with Town - L1 Cafeteria	2	22-Dec-20	23-Dec-20		Perform In-Wall Inspections with Town - L1 Cafeteria	
L1CAFE-1160	Perform Wall & Ceiling Punch List & Inspections - L1 Cafeteria	5	23-Dec-20	30-Dec-20		Perform Wall & Ceiling Punch List & Inspections - L1 Cafeteria	
L1CAFE-1180	Install Wood Blocking - L1 Cafeteria	2	24-Dec-20	28-Dec-20		Install Wood Blocking - L1 Cafeteria	
L1CAFE-1190	Board Wals - L1 Cafeteria	3	03-Mar-21	05-Mar-21		Board Wals - L1 Cafeteria	
L1CAFE-1210	Tape Walls & Soffits - L1 Cafeteria	3	08-Mar-21	10-Mar-21		Tape Walls & Soffits - L1 Cafeteria	
L1CAFE-1220	Prime & First Coat Paint Walls - L1 Cafeteria	3	11-Mar-21	15-Mar-21		Prime & First Coat Paint Walls - L1 Cafeteria	
L1CAFE-1110	Install Wals under Library Box - L1 Cafeteria	10	16-Mar-21	29-Mar-21		Install Wals under Library Box - L1 Cafeteria	
	Install Vestibule Storefront - L1 Cafeteria	10	16-Mar-21	29-Mar-21		Install Vestibule Storefront - L1 Cafeteria	
		15	16-Mar-21	05-Apr-21		Install Ceiling Grid & Cut/DeviceTies - L1 Cafeteria	
	Install MEP Drops - L1 Cafeteria	15	23-Mar-21			Install MEP Drops - L1 Cafeteria	
				12-Apr-21			
LIGAFE-1485	Install Vestibule Ceiling - L1 Cafeteria	10	30-Mar-21	12-Apr-21		Install Vestibule Ceiling - L1 Cafeteria	
Remaining	Level of Effort Remaining Work		Page 21 o	f 29	TASK filter: Uncompleted Activities Tw	o Months Prior.	
· · J		1	-		· · · · · · · · · · · · · · · · · · ·		
Actual Leve	el of Effort Critical Remaining Work					© Oracle Corporation	



vity ID	ol - Project A - 10Feb20 R1 Schedule Update - 1318014-CR - B26 Activity Name	Remaining	Start	Det Finish	
Vity ID		Duration	Start	1 111511	2020 2021 2022
					F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul Aug S Oct N
	Install Fire Alarm Devices - L1 Cafeteria	5	06-Apr-21	12-Apr-21	Install Fire Alarm Devices - L1 Cafeteria
	Perform Above Ceiling Inspections & Punch List - L1 Cafeteria	5	13-Apr-21	20-Apr-21	Perform Above Ceiling Inspections & Punch List - L1 Cafeteria
L1CAFE-1465	Install Ceiling Tile - L1 Cafeteria	8	21-Apr-21	30-Apr-21	Install Ceiling Tile - L1 Cafeteria
L1CAFE-1495	Remove Rolling Staging - L1 Cafeteria	5	03-May-21	07-May-21	Remove Rolling Staging - L1 Cafeteria
L1CAFE-1300	Install Terrazzo - L1 Cafeteria	20	20-May-21	17-Jun-21	Install Terrazzo - L1 Cafeteria
L1CAFE-1200	Install Resin Impregnated Wood Look Panels - L1 Cafeteria	10	18-Jun-21	01-Jul-21	Install Resin Impregnated Wood Look Panels - L1 Cafeteria
L1CAFE-1445	Install Fintube Radiators - L1 Cafeteria	10	18-Jun-21	01-Jul-21	Install Fintube Radiators - L1 Cafeteria
L1CAFE-1505	Install Back Painted Glass - L1 Cafeteria	10	05-Jul-21	16-Jul-21	Install Back Painted Glass - L1 Cafeteria
	Install Millwork - L1 Cafeteria	15	05-Jul-21	23-Jul-21	Install Millwork - L1 Cafeteria
	Install AV - L1 Cafeteria	5	19-Jul-21	23-Jul-21	Install AV - L1 Cafeteria
	Install Window Shades - L1 Cafeteria	5	26-Jul-21	30-Jul-21	Install Window Shades - L1 Cafeteria
		5			Construction Cleaning - L1 Cafeteria
	Construction Cleaning - L1 Cafeteria		02-Aug-21	06-Aug-21	
	Balance HVAC - L1 Cafeteria	5	09-Aug-21	13-Aug-21	Balance HVAC - L1 Cafeteria
	Skanska Punch List - L1 Cafeteria	5	09-Aug-21	13-Aug-21	Skanska Punch List - L1 Cafeteria
L1CAFE-1420	Architect Punch List - L1 Cafeteria	2	16-Aug-21	17-Aug-21	Architect Punch List - L1 Cafeteria
Servery					
L1SERV-1000	Frame Wals - L1 Servery	5	15-Oct-20	21-Oct-20	Frame Wals - L1 Servery
L1SERV-1010	Rough-in Plumbing In-Wall - L1 Servery	10	22-Oct-20	04-Nov-20	Roughtin Plumbing In-Wall - L1 Servery
L1SERV-1020	Rough-in Electrical In-Wall - L1 Servery	5	05-Nov-20	12-Nov-20	Rough-in Electrical In-Wall - L1 Servery
L1SERV-1030	Perform In-Wall Inspections with Town & Punch List- L1 Servery	5	23-Dec-20	30-Dec-20	Perform In-Wall Inspection's with Town & Punch List- L1 Servery
L1SERV-1040	Install Wood Blocking - L1 Servery	3	31-Dec-20	05-Jan-21	Install Wood Blocking - L1 Servery
L1SERV-1050	Board Wals - L1 Servery	3	26-Feb-21	02-Mar-21	Board Walls - L1 Servery
L1SERV-1060	-	3	03-Mar-21	05-Mar-21	I Tape & Finish Walls - L1 Servery
	Prime Paint & 1st Coat Walls - L1 Servery	3	08-Mar-21	10-Mar-21	I Prime Paint & 1st Coat Walls - L1 Servery
L1SERV-1080	·	3	11-Mar-21	15-Mar-21	Install Ceiling Grid & Cut/Device Tiles - L1 Servery
L1SERV-1085		6	11-Mar-21	18-Mar-21	 Install Simulated Wood Aluminum Ceiling Panels - L1 Servery
L1SERV-1090	Install MEP Drops at Ceiling Grid - L1 Servery	5	16-Mar-21	22-Mar-21	Install MEP Drops at Ceiling Grid - L1 Servery
L1SERV-1100	Above Ceiling Punch List - L1 Servery	5	23-Mar-21	29-Mar-21	Above Ceiling Punch List - L1 Servery
L1SERV-1110	Install Wal Tile - L1 Servery	10	23-Mar-21	05-Apr-21	🔲 Install Wal Tile - L1 Servery
L1SERV-1120	Install Epoxy Flooring - L1 Servery	3	06-Apr-21	08-Apr-21	I Install Epoxy Flooring - L1 Servery
L1SERV-1130	Install Terrazzo Flooring - L1 Servery	5	09-Apr-21	15-Apr-21	Install Terrazzo Flooring - L1 Servery
L1SERV-1135	Install Overhead Garage Doros - L1 Servery	2	16-Apr-21	20-Apr-21	Install Overhead Garage Doros - L1 Servery
L1SERV-1140	Install Kitchen Equipment - L1 Servery	10	07-Jul-21	20-Jul-21	Install Kitchen Equipment - L1 Servery
L1SERV-1775	Install Plumbing Connections to Kitchen Equipment - L1 Servery	5	21-Jul-21	27-Jul-21	Install Plumbing Connections to Kitchen Equipment - L1 Servery
L1SERV-1785	Install Electrical Connections to Kitchen Equipment - L1 Servery	5	26-Jul-21	30-Jul-21	Install Electrical Connections to Kitchen Equipment - L1 Servery
L1SERV-1795	Install Ceiling Tile - L1 Servery	3	02-Aug-21	04-Aug-21	Install Ceiling Tile - L1 Servery
L1SERV-1825	Test & Balance HVAC - L1 Servery	3	05-Aug-21	09-Aug-21	Test & Balance HVAC - L1 Servery
L1SERV-1815	-	10	05-Aug-21	18-Aug-21	Startup & Test Kitchen/Servery Equipment - L1 Servery
L1SERV-1835		1	21-Sep-21	21-Sep-21	I Board of Health Inspections - L1 Servery
Level 2		· _ · _ · _ /			
		10	01 Can 20	15 Can 20	Install MEP Risers - L2
L2-1010	Install MEP Risers - L2	10	01-Sep-20	15-Sep-20	
L2-1000	Install Tube Steel Wall Supports - L2	5	16-Sep-20	22-Sep-20	Install Tube Steel Wall Supports - L2
L2-1020	Rough-in Overhead Ductwork - L2	15	23-Sep-20	14-Oct-20	Rough-in Øverhead Ductwork - L2
L2-1030	Rough-in Overhead Plumbing - L2	15	23-Sep-20	14-Oct-20	Rough-in Overhead Plumbing - L2
L2-1040	Rough-in Overhead Mechanical Piping - L2	15	30-Sep-20	21-Oct-20	Rough-in Overhead Mechanical Piping - L2
L2-1050	Rough-in Overhead Electrical Conduit - L2	20	30-Sep-20	28-Oct-20	Rough-in Overhead Electrical Condulit - L2
L2-1060	Frame Electrical Closets - L2	3	15-Oct-20	19-Oct-20	I Frame Electrical Closets - L2
L2-1070	Rough Fire Protection - L2	10	15-Oct-20	28-Oct-20	Rough Fire Protection - L2
L2-1130	Install Above Ceiling Mechanical Equipment - L2	10	15-Oct-20	28-Oct-20	Install Above Ceiling Mechanical Equipment - L2
L2-1080	Board & Tape Electrical Closets - L2	5	20-Oct-20	26-Oct-20	■ Board & Tape Electrical Closets - L2
L2-1090	Frame Interior Wals - L2	10	22-Oct-20	04-Nov-20	Frame Interior Wals + L2
L2-1090	Insulate Overhead Mechanical Piping & HVAC Ductwork - L2	15	22-Oct-20 22-Oct-20	12-Nov-20	Insulate Overhead Mechanical Piping & HVAC Ductwork - L2
	Set Door Frames - L2	5	22-0ct-20 27-0ct-20	02-Nov-20	Set Door Frames - L2
L2-1120					
L2-1110	Rough-in Plumbing In-Wall - L2	10	29-Oct-20	12-Nov-20	🗖 Rough-in Plumbing In-Wall - L2

Remaining Level of Effort		Remaining Work	Page 22 of 29	TASK filter: Uncompleted Activities Two Months Prior.	
Actual Level of Effort		Critical Remaining Work			© Oracle Corporation
Actual Work	•	♦ Milestone	Page 6	5 of 377	



ivity ID	Activity Name	Remaining	Start	Finish	etailed Schedule Data Date: 10-Feb-20 / Run Date: 09-Jul-20 09		
		Duration	oturt		2020 2021 2022		
1.2.4400	Frame Soffits - L2	10	02 Nov 00	17-Nov-20	F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul Aug S Oct N I		
L2-1100 L2-1140	Frame Somits - L2 Rough-in Electrical In-Wall & Pull Branch Circuits - L2	10	03-Nov-20 05-Nov-20	17-Nov-20 30-Nov-20	Rough-in Electrical In-Wall & Pull Branch Circuits - L2		
L2-1140 L2-1150	Rough-in Electrical In-Wall & Pull Branch Circuits - L2 Rough-in Low Voltage In-Wall & Pull Wire - L2	15	05-Nov-20 05-Nov-20	30-Nov-20 30-Nov-20	Rough-in Liectrical in-Wall & Pull Branch Orcuits - L2		
L2-1150 L2-1160	Perform Wall & Ceiling Punch List & Inspections - L2	10	30-Nov-20	11-Dec-20	Rougn-In Low Voltage In-Wall & Pull Wire - L2		
L2-1170	Perform In-Wall Inspections with Town - L2	2	01-Dec-20	02-Dec-20	Perform In-Wall inspections with Town - L2		
L2-1180	Install Wood Blocking - L2	5	01-Dec-20 03-Dec-20	02-Dec-20 09-Dec-20	Install Wood Blocking - L2		
L2-1130	Insulate In-Wall Piping - L2	5	03-Dec-20 03-Dec-20	09-Dec-20	Insulate In-Wall Piping - L2		
L2-1190	Board Wals & Soffits - L2	10	26-Feb-21	11-Mar-21	Board Walls & Soffits - L2		
L2-1130	Tape Walls & Soffits - L2	10	05-Mar-21	18-Mar-21	Tape Walls & Soffits - L2		
L2-3050	Field Measure & Fab Interior Glass - L2	20	05-Mar-21	01-Apr-21	Field Measure & Fab Interior Glass - L2		
L2-3030	Prime & 1st Coat walls - L2	6	19-Mar-21	26-Mar-21	Prime & 1st Coat walls - L2		
L2-1230	Install Ceiling Grid & Cut/DeviceTies at Classrooms & Offices - L2	10	24-Mar-21	06-Apr-21	Install Ceiling Grid & Cut/DeviceTiles at Classrooms & Offices - L2		
L2-3060	Install Wall Tile at Corridors - L2	10	24-Mar-21	06-Apr-21	Install Wall Tile at Corridors - L2		
L2-3000	Install MEP Drops at Classrooms & Offices - L2	10	31-Mar-21	13-Apr-21	Install MEP Drops at Classrooms & Offices - L2		
L2-1240	Install MEP Drops at classrooms & Onices - L2	10	07-Apr-21	21-Apr-21	Install NLP Drops at Classificities & Offices - L2		
L2-1260	Install Otoren on Transes - L2	10	14-Apr-21	28-Apr-21	Install Millwork at Classrooms & Offices - L2		
L2-1260	Install Teledata Finishes & Terminations - L2	10	14-Apr-21	28-Apr-21	Install Teledata Finishes & Terminations - L2		
L2-1440 L2-1390	Install Interior Glazing - L2	10	22-Apr-21	05-May-21	Install Interior Glazing - L2		
L2-1390	Install Fintube Radiators - L2	10	22-Apr-21 22-Apr-21	05-May-21	Install Fintube Radiators - L2		
L2-1270	Install Ceiling Grid & Cut/DeviceTies at Corridors - L2	5	29-Apr-21	05-May-21	Install Ceiling Grid & Cut/DeviceTiles at Corridors - L2		
L2-1370	Install Doors & Hardware - L2	5	29-Apr-21	05-May-21	Install Doors & Hardware - L2		
L2-1380	Install Booring at Classrooms & Offices - L2	10	29-Apr-21	12-May-21	 Install Flooring at Classrooms & Offices - L2 		
L2-1430	Install Fire Alarm Devices - L2	5	06-May-21	12-May-21	Install Fire Alarm Devices - L2		
L2-1280	Install MEP Drops at Corridors - L2	8	06-May-21	17-May-21	Install MEP Drops at Corridors - L2		
L2-1285	Install Fintube Covers - L2	10	06-May-21	19-May-21	Install Fintube Covers - L2		
L2-1300	Install Terrazzo at Corridors - L2	20	11-Jun-21	09-Jul-21	Install Terrazzo at Corridors - L2		
L2-1360	Install Terrazzo Base at Corridors - L2	10	05-Jul-21	16-Jul-21	Install Terrazzo Base at Corridors - L2		
L2-1305	Install Railings at Opening - L2	5	12-Jul-21	16-Jul-21	Install Railings at Opening - L2		
L2-1310	Install Lockers - L2	5	12-Jul-21	23-Jul-21	Install Lockers - L2		
L2-1320	Install AV - L2	5	19-Jul-21	23-Jul-21	Install AV - L2		
L2-1340	Install Whiteboards & Tack Boards - L2	5	19-Jul-21	23-Jul-21	Install Whiteboards & Tack Boards - L2		
L2-1350	Install Window Shades - L2	5	19-Jul-21	23-Jul-21	Install Window Shades L2		
L2-1400	Construction Cleaning - L2	5	26-Jul-21	30-Jul-21	Construction Cleaning - L2		
L2-1290	Balance HVAC - L2	5	02-Aug-21	06-Aug-21	Balance HVAC - L2		
L2-1410	Skanska Punch List - L2	5	02-Aug-21	06-Aug-21	Skanska Punch List ½ L2		
L2-1420	Architect Punch List - L2	5	09-Aug-21	13-Aug-21	Architect Punch List - L2		
Bathrooms		0	00 / lug 21	107/0g 21			
L2-1600	Board & Install Cement Board - L2 Bathrooms	5	26-Feb-21	04-Mar-21	Board & Install Cement Board - L2 Bathrooms		
L2-1605	Tape & Finish - L2 Bathrooms	5	05-Mar-21	11-Mar-21	Tape & Finish - L2 Bathrooms		
L2-1610	Prime Paint - L2 Bathrooms	3	12-Mar-21	16-Mar-21	Prime Paint - L2 Bathrooms		
L2-1615	Install Counters - L2 Bathrooms	2	17-Mar-21	18-Mar-21	Install Counters - L2 Bathrooms		
L2-1620	Install Wall & Floor Tile - L2 Bathrooms	10	26-Mar-21	08-Apr-21	Install Wal & Floor Tile - L2 Bathrooms		
L2-1625	Install Plumbing Fixtures - L2 Bathrooms	5	09-Apr-21	15-Apr-21	■ Install Plumbing Fixtures - L2 Bathrooms		
L2-1630	Field Measure & Fab Mirrors - L2 Bathrooms	10	09-Apr-21	23-Apr-21	Field Measure & Fab Mirrors - L2 Bathrooms		
L2-1635	Install Toilet Partitions - L2 Bathrooms	4	16-Apr-21	22-Apr-21	 Install Toilet Partitions - L2 Bathrooms 		
L2-1640	Install Bathroom Accessories - L2 Bathrooms	4	23-Apr-21	22-Apr-21 28-Apr-21	 Install Bathroom Accessories - L2 Bathrooms 		
L2-1645	Install Mirrors - L2 Bathrooms	2	29-Apr-21	30-Apr-21	Install Mirrors - L2 Bathrooms		
L2-1650	Finish Paint - L2 Bathrooms	2	03-May-21	04-May-21	Finish Paint - L2 Bathrooms		
Library		_	00 May-21				
L2LIB-1000	Frame Soffits - L2 Library	10	18-Nov-20	03-Dec-20	Frame Soffits - L2 Library		
L2LIB-1000	Install MEP Drops at Soffits - L2 Library	10	04-Dec-20	17-Dec-20	 Install MEP Drpps at Soffits - L2 Library 		
L2LIB-1010	Board Wals & Soffits - L2 Library	5	12-Mar-21	18-Mar-21	Board Wals & Soffits - L2 Library		
L2LIB-1020	Drywall & Tape Walls & Soffits - L2 Library	5	12-Mar-21	25-Mar-21	Drywall & Tape Walls & Soffits - L2 Library		
L2LIB-1050	Prime & 1st Coat Walls & Soffits - L2 Library	5	26-Mar-21	01-Apr-21	Prime & 1st Coat Walls & Soffits - L2 Library		
L2LIB-1050	Field & Measure & Fab Interior Glazing - L2 Library	25	26-Mar-21	30-Apr-21	Field & Measure & Fab Interior Glazing - L2 Library		
		25					
Remainin	g Level of Effort Remaining Work		Page 23 d	of 29	TASK filter: Uncompleted Activities Two Months Prior.		
Actual Le	evel of Effort Critical Remaining Work				© Oracle Corporation		
Actual W	ork Milestone	1		_	e 66 of 377		



tivity ID	ool - Project A - 10Feb20 R1 Schedule Update - 1318014-CR - B26	Domoining	Start		ed Schedule Data Date: 10-Feb-20 / Run Date: 09-Jul-20 09:
	Activity Name	Remaining	Start	Finish	2020 2021 2022
				ļ	F [Mar Apr M Jun Jul A S Oct N D Jan F [Mar Apr M Jun Jul A S Oct N D Jan F [Mar Apr M Jun Jul Aug S Oc
L2LIB-1060	Install Ceiling Grid & Cut/DeviceTiles - L2 Library	5	02-Apr-21	08-Apr-21	Install Ceiling Grid & Cut/DeviceTiles - L2 Library
L2LIB-1070	Install MEP Drops at Ceiling Grid - L2 Library	6	09-Apr-21	16-Apr-21	Install MEP Drops at Celling Grid - L2 Library
L2LIB-1080	Above Ceiling Punch List - L2 Library	5	20-Apr-21	26-Apr-21	Above Ceiling Punch List - L2 Library
L2LIB-1090	Install Storefronts - L2 Library	10	03-May-21	14-May-21	Install Storefronts - L2 Library
L2LIB-1100	Install Interior Glazing - L2 Library	5	17-May-21	21-May-21	Install Interior Glazing - L2 Library
L2LIB-1105	Install Ceiling Tiles - L2 Library	5	17-May-21	21-May-21	Install Ceiling Tiles - L2 Library
L2LIB-1210	Install Fintube Radiators - L2 Library	5	24-May-21	28-May-21	Install Fintube Radiators - L2 Library
L2LIB-1220	Install Electrical Finishes & Hanging Light Fixtures - L2 Library	5	24-May-21	28-May-21	Install Electrical Finishes & Hanging Light Fixtures - L2 Library
L2LIB-1120	Intall Guardrail in Front of Glass - L2 Library	10	24-May-21	07-Jun-21	🔲 Intall Guardrail in Front of Glass - L2 Library
L2LIB-1110	Install Millwork & Shelving - L2 Library	5	08-Jun-21	14-Jun-21	Install Millwork & Shelving - L2 Library
L2LIB-1130	Install Plumbing Fixtures at Library Office - L2 Library	1	15-Jun-21	15-Jun-21	I Install Plumbing Fixtures at Library Office - L2 Library
L2LIB-1230	Install Custom Millwork Barndoor with Glass Panel - L2 Library	3	15-Jun-21	17-Jun-21	Install Custom Millwork Barndoor with Glass Panel - L2 Library
L2LIB-1140	Install Flooring & Base - L2 Library	5	18-Jun-21	24-Jun-21	Install Flooring & Base - L2 Library
L2LIB-1150	Install Fintube Radiator Covers - L2 Library	5	25-Jun-21	01-Jul-21	Install Fintube Radiator Covers - L2 Library
L2LIB-1400	Construction Cleaning - L2 Library	2	05-Jul-21	06-Jul-21	Construction Cleaning - L2 Library
L2LIB-1410	Skanska Punch List - L2 Library	2	07-Jul-21	08-Jul-21	I Skanska Punch List - L2 Library
L2LIB-1420	Architect Punch List - L2 Library	2	09-Jul-21	12-Jul-21	I Architect Punch List - L2 Library
Level 3					
L3-1005	Install Intumescent Paint at Physics Classrooms - L3	25	25-Aug-20	29-Sep-20	Install Intumescent Paint at Physics Classrooms - L3
L3-1010	Install MEP Risers - L3	10	16-Sep-20	29-Sep-20	Install MEP Risers - L3
L3-1000	Install Tube Steel Wall Supports - L3	5	30-Sep-20	06-Oct-20	Install Tube Steel Wall Supports - L3
L3-1020	Rough-in Overhead Ductwork - L3	15	15-Oct-20	04-Nov-20	Rough-in Overhead Ductwork - L3
L3-1030	Rough-in Overhead Plumbing - L3	15	15-Oct-20	04-Nov-20	Rough _t in Overhead Plumbing - L3
L3-1040	Rough-in Overhead Mechanical Piping - L3	15	22-Oct-20	12-Nov-20	Rough-in Overhead Mechanical Piping - L3
L3-1050	Rough-in Overhead Electrical Conduit - L3	20	22-Oct-20	19-Nov-20	Rough-in Overhead Electrical Conduit - L3
L3-1060	Frame Electrical Closets - L3	3	05-Nov-20	09-Nov-20	I Frame Electrical Closets - L3
L3-1070	Rough Fire Protection - L3	10	05-Nov-20	19-Nov-20	Rough Fire Protection - L3
L3-1130	Install Above Ceiling Mechanical Equipment - L3	10	05-Nov-20	19-Nov-20	🔲 Install Above Ceiling Mechanical Equipment - L3
L3-1080	Board & Tape Electrical Closets - L3	5	10-Nov-20	17-Nov-20	Board & Tape Electrical Closets - L3
L3-1090	Frame Interior Walls - L3	10	13-Nov-20	30-Nov-20	Frame Interior Walls - L3
L3-1450	Insulate Overhead Mechanical Piping & HVAC Ductwork - L3	15	13-Nov-20	07-Dec-20	Insulate Overhead Mechanical Piping & HVAC Ductwork - Ц3
L3-1120	Set Door Frames - L3	5	18-Nov-20	24-Nov-20	Set Door Frames - L3
L3-1110	Rough-in Plumbing In-Wall - L3	10	20-Nov-20	07-Dec-20	Rough-in Plumbing In-Wall - L3
L3-1100	Frame Soffits - L3	10	25-Nov-20	10-Dec-20	Frame Soffits - L3
L3-1140	Rough-in Electrical In-Wall & Pull Branch Circuits - L3	15	01-Dec-20	21-Dec-20	Rough-in Electrical In-Wall & Pull Branch Circuits - L3
L3-1150	Rough-in Low Voltage In-Wall & Pull Wire - L3	15	01-Dec-20	21-Dec-20	Rough-in Low Voltage In-Wall & Pull Wire - L3
L3-1160	Perform Wall & Ceiling Punch List & Inspections - L3	10	21-Dec-20	05-Jan-21	Perform Wall & Ceiling Punch List & Inspections - L3
L3-1170	Perform In-Wall Inspections with Town - L3	2	22-Dec-20	23-Dec-20	Perform In-Wall Inspections with Town - L3
L3-1180	Install Wood Blocking - L3	5	24-Dec-20	31-Dec-20	Install Wood Blocking - L3
L3-1330	Insulate In-Wall Piping - L3	5	24-Dec-20	31-Dec-20	Insulate In-Wall Piping - L3
L3-1335	Install Steel Tube Grid at Physics Classrooms - L3	20	11-Feb-21	11-Mar-21	Install Steel Tube Grid at Physics Classrooms - L3
L3-1190	Board Wals & Soffits - L3	10	12-Mar-21	25-Mar-21	Board Walls & Soffits - L3
L3-1210	Tape Walls & Soffits - L3	10	19-Mar-21	01-Apr-21	Tape Walls & Soffits - L3
L3-3050	Field Measure & Fab Interior Glass - L3	20	19-Mar-21	15-Apr-21	Field Measure & Fab Interior Glass - L3
L3-1220	Prime & 1st Coat walls - L3	6	02-Apr-21	09-Apr-21	Prime & 1st Coat walls - L3
L3-1230	Install Ceiling Grid & Cut/DeviceTies at Classrooms & Offices - L3	10	07-Apr-21	21-Apr-21	Install Ceiling Grid & Cut/DeviceTies at Classrooms'& Offices - L3
L3-3060	Install Wall Tile at Corridors - L3	10	07-Apr-21	21-Apr-21	Install Wal Tile at Corridors - L3
L3-1240	Install MEP Drops at Classrooms & Offices - L3	10	14-Apr-21	28-Apr-21	■ Install MEP Drops at Classrooms & Offices - L3
L3-1250	Install Storefront Frames - L3	10	22-Apr-21	05-May-21	Install Storefront Frames - L3
L3-1260	Install Millwork at Classrooms & Offices - L3	10	22-Apr-21 29-Apr-21	12-May-21	Install Millwork at Classrooms & Offices - L3
L3-1200	Install Teledata Finishes & Terminations - L3	10	29-Apr-21 29-Apr-21	12-May-21	Install Teledata Finishes & Terminations - L3
L3-1440 L3-3070	Install Laboratory Casework at Classrooms - L3	10	29-Apr-21 29-Apr-21	12-May-21	Install Laboratory Casework at Classrooms - L3
			•		Install Laboratory Casework at Classrooms - L3 Install Interior Glazing - L3
L3-1390 L3-1445	Install Interior Glazing - L3 Install Fintube Radiators - L3	10	06-May-21	19-May-21	Install Interior Glazing - L3
1.3-1445		10	06-May-21	19-May-21	Install Finlude Radiators - L3

Remaining Level of Effort		Remaining Work	Page 24 of 29	TASK filter: Uncompleted Activities Two Months Prior.	
Actual Level of Effort		Critical Remaining Work			© Oracle Corporation
Actual Work	•	♦ Milestone	Page	67 of 377	

Data Date: 10-Feb-20	1	Run Date: 09-Jul-20 09:05
Dulu Dulo. 101 00 20 /		



ivity ID	Activity Name	Demaining	Start	Finish		Data Date: 10-Feb-20 / Run Date: 09-Jul-20 09:05				
ivity ID	Activity Name	Remaining	Start	1 111511	2020	2021	2022			
					F Mar Apr M Jun Jul A S Oct N	D Jan F Mar Apr M Jun Jul A S Oct N D				
L3-1270	Install Ceiling Grid & Cut/DeviceTiles at Corridors - L3	5	13-May-21	19-May-21		Install Ceiling Grid & Cut/Device	les at Corridors - L3			
L3-1370	Install Doors & Hardware - L3	5	13-May-21	19-May-21		Install Doors & Hardware - L3				
L3-1380	Install Flooring at Classrooms & Offices - L3	10	13-May-21	26-May-21		Install Flooring at Classrooms 8				
L3-1375	Install Garage Doors at Physics Classrooms - L3	3	20-May-21	24-May-21		Install Garage Doors at Physics	Classrooms - L3			
L3-1430	Install Fire Alarm Devices - L3	5	20-May-21	26-May-21		Install Fire Alarm Devices - L3				
L3-1280	Install MEP Drops at Corridors - L3	8	20-May-21	01-Jun-21		Install MEP Drops at Corridors	- L3			
L3-1285	Install Fintube Covers - L3	10	20-May-21	03-Jun-21		Install Fintube Covers - L3				
L3-1300	Install Terrazzo at Corridors - L3	20	05-Jul-21	30-Jul-21		Install Terrazzo at Co	ntidors - L3			
L3-1360	Install Terrazzo Base at Corridors - L3	10	26-Jul-21	06-Aug-21		Install Terrazzo Base	at Corridors - L3			
L3-1310	Install Lockers - L3	5	09-Aug-21	13-Aug-21		Instal Lockers - L3	, <u> </u>			
L3-1320	Install AV - L3	5	09-Aug-21	13-Aug-21		Instal AV - L3				
L3-1340	Install Whiteboards & Tack Boards - L3	5	09-Aug-21	13-Aug-21		Install Whiteboards	& Tack Boards - L3			
L3-1350	Install Window Shades - L3	5	09-Aug-21	13-Aug-21		Install Window Sha	des - L3			
L3-1400	Construction Cleaning - L3	5	16-Aug-21	20-Aug-21		Construction Clea	ning - L3			
L3-1290	Balance HVAC - L3	5	23-Aug-21	27-Aug-21		Balance HVAC -	L3			
L3-1410	Skanska Punch List - L3	5	23-Aug-21	27-Aug-21		Skanska Punch	⊔ist - L3			
L3-1420	Architect Punch List - L3	5	30-Aug-21	03-Sep-21		Architect Punch	List - L3			
Bathrooms				· · · · · · · · · · · · · · · · · · ·						
L3-1600	Board & Install Cement Board - L3 Bathrooms	5	12-Mar-21	18-Mar-21		Board & Install Cement Board - L3 Bathroom	ıms			
L3-1605	Tape & Finish - L3 Bathrooms	5	19-Mar-21	25-Mar-21	1	Tape & Finish - L3 Bathrooms				
L3-1610	Prime Paint - L3 Bathrooms	3	26-Mar-21	30-Mar-21		Prime Paint + L3 Bathrooms				
L3-1615	Install Counters - L3 Bathrooms	2	31-Mar-21	01-Apr-21		Install Counters - L3 Bathrooms				
L3-1620	Install Wall & Floor Tile - L3 Bathrooms	10	09-Apr-21	23-Apr-21		Install Wal & Floor Tile - L3 Bathroon	ns			
L3-1625	Install Plumbing Fixtures - L3 Bathrooms	5	26-Apr-21	30-Apr-21		Install Plumbing Fixtures - L3 Bathro	uoms			
L3-1630	Field Measure & Fab Mirrors - L3 Bathrooms	10	26-Apr-21	07-May-21		Field Measure & Fab Mirrors - L3 F				
L3-1635	Install Toilet Partitions - L3 Bathrooms	4	03-May-21	06-May-21		Install Toilet Partitions - L3 Bathroo				
L3-1640	Install Bathroom Accessories - L3 Bathrooms	4	07-May-21	12-May-21		Install Bathroom Accessories - L3				
L3-1645	Install Mirrors - L3 Bathrooms	2	13-May-21	14-May-21		Instal Mirrors - L3 Bathrooms				
L3-1650	Finish Paint - L3 Bathrooms	2	17-May-21	18-May-21	+	Finish Paint - L3 Bathrooms				
Level 4			11 1100 21	To may 21						
L4-1005	Install Intumescent Paint at Physics Classrooms - L4	25	23-Sep-20	28-Oct-20		all Intumescent Paint at Physics Classrooms - L4				
L4-1003	Install MEP Risers - L4	10	30-Sep-20	14-Oct-20		MEP Risers - L4				
L4-1010	Install Tube Steel Wall Supports - L4	5	15-Oct-20	21-Oct-20		I Tube Steel Wall Supports - L4				
L4-1020	Rough-in Overhead Ductwork - L4	15	05-Nov-20	30-Nov-20		Rough-in Overhead Ductwork - L4				
L4-1020	Rough-in Overhead Ductwork - L4 Rough-in Overhead Plumbing - L4	15	05-Nov-20	30-Nov-20		Rough-in Overhead Plumbing - L4				
			13-Nov-20	07-Dec-20		Rough-in Overhead Mechanical Piping - L4				
L4-1040	Rough-in Overhead Mechanical Piping - L4	15								
L4-1050	Rough-in Overhead Electrical Conduit - L4	20	13-Nov-20	14-Dec-20		Rough-in Overhead Electrical Conduit - L4 Frame Electrical Closets - L4				
L4-1060	Frame Electrical Closets - L4	3	01-Dec-20	03-Dec-20						
L4-1070	Rough Fire Protection - L4	10	01-Dec-20	14-Dec-20		Rough Fire Protection - L4				
L4-1130	Install Above Ceiling Mechanical Equipment - L4	10	01-Dec-20	14-Dec-20		Install Above Ceiling Mechanical Equipment - L4				
L4-1080	Board & Tape Electrical Closets - L4	5	04-Dec-20	10-Dec-20		Board & Tape Electrical Closets - L4				
L4-1090	Frame Interior Walls - L4	10	08-Dec-20	21-Dec-20		Frame Interior Wals - L4				
L4-1450	Insulate Overhead Mechanical Piping & HVAC Ductwork - L4	15	08-Dec-20	29-Dec-20	+	Insulate Overhead Mechanical Piping & HVAC Ductwor	<u>K - L4</u>			
L4-1120	Set Door Frames - L4	5	11-Dec-20	17-Dec-20		Set Door Frames - L4				
L4-1110	Rough-in Plumbing In-Wall - L4	10	15-Dec-20	29-Dec-20		Rough-in Plumbing In-Wall- L4				
L4-1100	Frame Soffits - L4	10	18-Dec-20	04-Jan-21		Frame Soffits - L4				
L4-1140	Rough-in Electrical In-Wall & Pull Branch Circuits - L4	15	22-Dec-20	13-Jan-21		Rough-in Electrical In-Wall & Pull Branch Circuits - Le	4			
L4-1150	Rough-in Low Voltage In-Wall & Pull Wire - L4	15	22-Dec-20	13-Jan-21	<u> </u>	Rough-in Low Voltage In-Wall & Pull Wire - L4				
L4-1160	Perform Wall & Ceiling Punch List & Inspections - L4	10	13-Jan-21	27-Jan-21		Perform Wall & Ceiling Punch List & Inspections - I	_ 4			
L4-1170	Perform In-Wall Inspections with Town - L4	2	14-Jan-21	15-Jan-21		Perform In-Wall Inspections with Town - L4				
L4-1180	Install Wood Blocking - L4	5	19-Jan-21	25-Jan-21		Install Wood Blocking - L4				
L4-1330	Insulate In-Wall Piping - L4	5	19-Jan-21	25-Jan-21		Insulate In-Wall Piping - L4				
L4-1335	Install Steel Tube Grid at Physics Classrooms - L4	20	05-Mar-21	01-Apr-21	<u> </u>	Install Steel Tube Grid at Physics Classr	ooms - L4			
L4-1190	Board Wals & Soffits - L4	10	26-Mar-21	08-Apr-21		Board Wals & Soffits - L4				

Actual Work

Milestone

•



Vame Vame Valls & Soffits - L4 asure & Fab Interior Glass - L4 1st Coat Wals & Exposed Ceilings - L4 eiling Grid & Cut/DeviceTies at Classrooms & Offices - L4 al Tile at Corridors - L4 EP Drops at Classrooms & Offices - L4 orefront Frames - L4 Illwork at Classrooms & Offices - L4 eledata F n ishes & Terminations - L4 eledata F n ishes & Terminations - L4 eledata F n ishes & Terminations - L4 eledata Gazing - L4 eiling Grid & Cut/DeviceTies at Corridors - L4 cors & Hardware - L4 arage Doors at Physics Classrooms - L3 re Alarm Devices - L4	Remaining Duration 10 20 6 10	Start 02-Apr-21 02-Apr-21 16-Apr-21 22-Apr-21 29-Apr-21 06-May-21 13-May-21 13-May-21 13-May-21	Finish 15-Apr-21 30-Apr-21 26-Apr-21 05-May-21 05-May-21 12-May-21 19-May-21 26-May-21	2020 2021 2022 Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jun <th>lul Aug S Oct N</th>	lul Aug S Oct N
asure & Fab Interior Glass - L4 1st Coat Wals & Exposed Ceilings - L4 eiling Grid & Cut/DeviceTiles at Classrooms & Offices - L4 al Tile at Corridors - L4 EP Drops at Classrooms & Offices - L4 orefront Frames - L4 illwork at Classrooms & Offices - L4 eledata Finishes & Terminations - L4 eledata Finishes & Terminations - L4 eledata Grid & Cut/DeviceTiles at Corridors - L4 eiling Grid & Cut/DeviceTiles at Corridors - L4 eiling Grid & Cut/DeviceTiles at Corridors - L4 eiling Grid & Cut/DeviceTiles at Corridors - L4 arage Doors at Physics Classrooms - L3	10 20 6 10 10 10 10 10 10 10 10 10 10 10	02-Apr-21 16-Apr-21 22-Apr-21 29-Apr-21 06-May-21 13-May-21 13-May-21	15-Apr-21 30-Apr-21 26-Apr-21 05-May-21 05-May-21 12-May-21 19-May-21	Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun J Tape Walls & Soffits - L4; Image: Control of the state of t	lul Aug S Oct N
asure & Fab Interior Glass - L4 1st Coat Wals & Exposed Ceilings - L4 eiling Grid & Cut/DeviceTiles at Classrooms & Offices - L4 al Tile at Corridors - L4 EP Drops at Classrooms & Offices - L4 orefront Frames - L4 illwork at Classrooms & Offices - L4 eledata Finishes & Terminations - L4 eledata Finishes & Terminations - L4 eledata Grid & Cut/DeviceTiles at Corridors - L4 eiling Grid & Cut/DeviceTiles at Corridors - L4 eiling Grid & Cut/DeviceTiles at Corridors - L4 eiling Grid & Cut/DeviceTiles at Corridors - L4 arage Doors at Physics Classrooms - L3	20 6 10 10 10 10 10 10 10 10 10 10	02-Apr-21 16-Apr-21 22-Apr-21 29-Apr-21 06-May-21 13-May-21 13-May-21	15-Apr-21 30-Apr-21 26-Apr-21 05-May-21 05-May-21 12-May-21 19-May-21	 Tape Walls & Soffits - L4 Field Measure & Fab Interior Glass - L4 Prime & 1st Coat Walls & Exposed Ceilings - L4 Install Ceiling Grid & Cut/DeviceTies at Classrooms & Offices - L4 Install Wal Tile at Corridors - L4 	
1st Coat Walls & Exposed Ceilings - L4 eiling Grid & Cut/DeviceTiles at Classrooms & Offices - L4 al Tile at Corridors - L4 EP Drops at Classrooms & Offices - L4 orefront Frames - L4 illwork at Classrooms & Offices - L4 eledata Finishes & Terminations - L4 eledata Finishes & Terminations - L4 eledata Gring - L4 eiling Grid & Cut/DeviceTiles at Corridors - L4 eiling Grid & Cut/DeviceTiles at Corridors - L4 arage Doors at Physics Classrooms - L3	6 10 10 10 10 10 10 10 10 10	02-Apr-21 16-Apr-21 22-Apr-21 29-Apr-21 06-May-21 13-May-21 13-May-21	30-Apr-21 26-Apr-21 05-May-21 05-May-21 12-May-21 19-May-21	Field Measure & Fab Interior Glass - L4 Prime & 1st Coat Wals & Exposed Ceilings - L4 Install Ceiling Grid & Cut/DeviceTies at Classrooms & Offices - L4 Install Wal Tile at Corridors - L4	
eiling Grid & Cut/DeviceTies at Classrooms & Offices - L4 al Tile at Corridors - L4 EP Drops at Classrooms & Offices - L4 orefront Frames - L4 Illwork at Classrooms & Offices - L4 eledata F n ishes & Terminations - L4 eledata F n ishes & Terminations - L4 eledata Gazing - L4 eiling Grid & Cut/DeviceTies at Corridors - L4 poors & Hardware - L4 arage Doors at Physics Classrooms - L3	6 10 10 10 10 10 10 10 10 10	16-Apr-21 22-Apr-21 22-Apr-21 29-Apr-21 06-May-21 13-May-21 13-May-21	26-Apr-21 05-May-21 05-May-21 12-May-21 19-May-21	 Prime & 1st Coat Wals & Exposed Ceilings - L4 Install Ceiling Grid & Cut/DeviceTies at Classrooms & Offices - L4 Install Wal Tile at Corridors - L4 	
eiling Grid & Cut/DeviceTies at Classrooms & Offices - L4 al Tile at Corridors - L4 EP Drops at Classrooms & Offices - L4 orefront Frames - L4 Illwork at Classrooms & Offices - L4 eledata F n ishes & Terminations - L4 eledata F n ishes & Terminations - L4 eledata Gazing - L4 eiling Grid & Cut/DeviceTies at Corridors - L4 poors & Hardware - L4 arage Doors at Physics Classrooms - L3	10 10 10 10 10 10 10 10	22-Apr-21 22-Apr-21 29-Apr-21 06-May-21 13-May-21 13-May-21	05-May-21 05-May-21 12-May-21 19-May-21	Install Ceiling Grid & Cut/DeviceTiles at Classrooms & Offices - L4 Install Wal Tile at Corridors - L4	
al Tile at Corridors - L4 EP Drops at Classrooms & Offices - L4 orefront Frames - L4 Illwork at Classrooms & Offices - L4 eledata F n ishes & Terminations - L4 eledata F	10 10 10 10 10 10 10 10	22-Apr-21 29-Apr-21 06-May-21 13-May-21 13-May-21	05-May-21 12-May-21 19-May-21	Install Wal Tile at Corridors - L4	
EP Drops at Classrooms & Offices - L4 orefront Frames - L4 illwork at Classrooms & Offices - L4 eledata F n ishes & Terminations - L4 aboratory Casework at Classrooms - L4 terior Glazing - L4 eiling Grid & Cut/DeviceTiles at Corridors - L4 pors & Hardware - L4 arage Doors at Physics Classrooms - L3	10 10 10 10 10 10 10	29-Apr-21 06-May-21 13-May-21 13-May-21	12-May-21 19-May-21		
orefront Frames - L4 Illwork at Classrooms & Offices - L4 Illedata Finishes & Terminations - L4 Iboratory Casework at Classrooms - L4 terior Glazing - L4 Illing Grid & Cut/DeviceTiles at Corridors - L4 Dors & Hardware - L4 arage Doors at Physics Classrooms - L3	10 10 10 10 10 10	06-May-21 13-May-21 13-May-21	19-May-21		
Illwork at Classrooms & Offices - L4 Eledata F nishes & Terminations - L4 Eledata F n	10 10 10 10 10	13-May-21 13-May-21		Install Storefront Frames - L4	
eledata Finishes & Terminations - L4 aboratory Casework at Classrooms - L4 terior Glazing - L4 eiling Grid & Cut/DeviceTiles at Corridors - L4 bors & Hardware - L4 arage Doors at Physics Classrooms - L3	10 10 10	13-May-21	20-11/12/21	 Install Storen ont Frames - L4 Install Millwork at Classrooms & Offices - L4 	
aboratory Casework at Classrooms - L4 terior Glazing - L4 eiling Grid & Cut/DeviceTiles at Corridors - L4 bors & Hardware - L4 arage Doors at Physics Classrooms - L3	10 10				
terior Glazing - L4 eiling Grid & Cut/DeviceTites at Corridors - L4 oors & Hardware - L4 arage Doors at Physics Classrooms - L3	10		26-May-21	Install Teledata Finishes & Termihations - L4	
eiling Grid & Cut/DeviceTiles at Corridors - L4 bors & Hardware - L4 arage Doors at Physics Classrooms - L3		-	26-May-21	Install Laboratory Casework at Classrooms - L4	
oors & Hardware - L4 arage Doors at Physics Classrooms - L3		20-May-21	03-Jun-21	Install Interior Glazing - L4	
arage Doors at Physics Classrooms - L3	5	27-May-21	03-Jun-21	Install Ceiling Grid & Cut/DeviceTiles at Corridors - L4	
	5	27-May-21	03-Jun-21	Install Doors & Hardware - L4	
re Alarm Devices - L4	3	04-Jun-21	08-Jun-21	Install Garage Doors at Physics Classrooms - L3	
	5	04-Jun-21	10-Jun-21	Install Fire Alarm Devices - L4	1
EP Drops at Corridors - L4	8	04-Jun-21	15-Jun-21	Install MEP Drops at Corridors - L4	
ntube Radiators - L4	10	04-Jun-21	17-Jun-21	Install Fintube Radiators - L4	
ooring at Classrooms & Offices - L4	10	11-Jun-21	24-Jun-21	Install Flooring at Classrooms & Offices - L4	
ntube Covers - L4	10	18-Jun-21	01-Jul-21	Install Fintube Covers - L4	
errazzo at Corridors - L4	20	26-Jul-21	20-Aug-21	Install Terrazzo at Corridors - L4	
errazzo Base at Corridors - L4	10	16-Aug-21	27-Aug-21	Install Terrazzo Base at Corridors - L4	
ailings at Openings - L2	10	23-Aug-21	03-Sep-21	Install Railings at Openings - L2	
ninge at openinge 22	5	30-Aug-21	03-Sep-21	Install Lockers - L4	
/-L4	5	30-Aug-21	03-Sep-21	Install AV - L4	
hiteboards & Tack Boards - L4	5	-	03-Sep-21	Install Whiteboards & Tack Boards - L4	
	5	30-Aug-21		Install Winteboards & Tack Boards - L4	
indow Shades - L4	5	30-Aug-21	03-Sep-21		
ction Cleaning - L4	5	07-Sep-21	13-Sep-21	Construction Cleaning - L4	
HVAC - L4	5	14-Sep-21	20-Sep-21	Balance HVAC - L4	
I Punch List - L4	5	14-Sep-21	20-Sep-21	Skanska Punch List - L4	
t Punch List - L4	5	21-Sep-21	27-Sep-21	Architect Punch List - L4	
Install Cement Board - L4 Bathrooms	5	26-Mar-21	01-Apr-21	Board & Install Cement Board - L4 Bathrooms	
inish - L4 Bathrooms	5	02-Apr-21	08-Apr-21	Tape & Finish - L4 Bathrooms	
aint - L4 Bathrooms	3	09-Apr-21	13-Apr-21	Prime Paint - L4 Bathrooms	, , ,
ounters - L4 Bathrooms	2	14-Apr-21	15-Apr-21	I Install Counters - L4 Bathrooms	
all & Floor Tile - L4 Bathrooms	10	26-Apr-21	07-May-21	Install Wal & Floor Tile - L4 Bathrooms	
umbing Fixtures - L4 Bathrooms	5	10-May-21	14-May-21	Install Plumbing Fixtures - L4 Bathrooms	
asure & Fab Mirrors - L4 Bathrooms	10	10-May-21	21-May-21	Field Measure & Fab Mirrors - L4 Bathrooms	
ilet Partitions - L4 Bathrooms	4	17-May-21	20-May-21	Install Toilet Partitions - L4 Bath rooms	
athroom Accessories - L4 Bathrooms	4	21-May-21	26-May-21	Install Bathroom Accessories - L4 Bathrooms	
irrors - L4 Bathrooms	2	27-May-21	28-May-21	Install Mirrors - L4 Bathrooms	
aint - L4 Bathrooms	2	01-Jun-21	02-Jun-21	Finish Paint - L4 Bathrooms	
		01001121	02 0411 21		
ED Dissues - O and as lawal	10	40.0 00	00.0 00		
EP Risers - Garden Level	10	10-Sep-20	23-Sep-20	Install MEP Risers - Garden Level	
MU Wals - Garden Level	30	24-Sep-20	05-Nov-20	Install CMU Wals - Garden Level	
ibe Steel Wall Supports - Garden Level	5	06-Nov-20	13-Nov-20	Install Tube Steel Wall Supports - Garden Level	
n Overhead Ductwork - Garden Level	15	01-Dec-20	21-Dec-20	Rough-in Overhead Ductwork - Garden Level	
n Overhead Plumbing - Garden Level	15				
n Overhead Mechanical Piping - Garden Level	15	08-Dec-20	29-Dec-20	Rough-in Overhead Mechanical Piping - Garden Level	
n Overhead Electrical Conduit - Garden Level	20	08-Dec-20	06-Jan-21	Rough-in Overhead Electrical Conduit - Garden Level	
lectrical Closets - Garden Level	3	22-Dec-20	24-Dec-20	Frame Electrical Closets - Garden Level	
ire Protection - Garden Level	10	22-Dec-20	06-Jan-21	🗖 Rough Fire Protection - Garden Level	
	10	22-Dec-20	06-Jan-21	install Above Ceiling Mechanical Equipment - Garden Level	
ove Ceiling Mechanical Equipment - Garden Level	5	28-Dec-20	04-Jan-21	Board & Tape Electrical Closets - Garden Level	
ove Ceiling Mechanical Equipment - Garden Level Tape Electrical Closets - Garden Level		Page 26 c	of 29	TASK filter: Uncompleted Activities Two Months Prior	
	1				
n O n O n O ilec ire	verhead Plumbing - Garden Level verhead Mechanical Piping - Garden Level verhead Electrical Conduit - Garden Level trical Closets - Garden Level Protection - Garden Level e Ceiling Mechanical Equipment - Garden Level be Electrical Closets - Garden Level	verhead Plumbing - Garden Level 15 verhead Mechanical Piping - Garden Level 15 verhead Electrical Conduit - Garden Level 20 trical Closets - Garden Level 3 Protection - Garden Level 10 e Ceiling Mechanical Equipment - Garden Level 10 be Electrical Closets - Garden Level 5 t Remaining Work	verhead Plumbing - Garden Level1501-Dec-20verhead Mechanical Piping - Garden Level1508-Dec-20verhead Electrical Conduit - Garden Level2008-Dec-20trical Closets - Garden Level322-Dec-20Protection - Garden Level1022-Dec-20e Ceiling Mechanical Equipment - Garden Level1022-Dec-20be Electrical Closets - Garden Level528-Dec-20	verhead Plumbing - Garden Level1501-Dec-2021-Dec-20verhead Mechanical Piping - Garden Level1508-Dec-2029-Dec-20verhead Electrical Conduit - Garden Level2008-Dec-2006-Jan-21trical Closets - Garden Level322-Dec-2024-Dec-20Protection - Garden Level1022-Dec-2006-Jan-21e Ceiling Mechanical Equipment - Garden Level1022-Dec-2006-Jan-21be Electrical Closets - Garden Level528-Dec-2004-Jan-21	verhead Plumbing - Garden Level 15 01-Dec-20 21-Dec-20 verhead Mechanical Piping - Garden Level 15 08-Dec-20 29-Dec-20 verhead Electrical Conduit - Garden Level 20 08-Dec-20 06-Jan-21 trical Closets - Garden Level 3 22-Dec-20 24-Dec-20 Protection - Garden Level 10 22-Dec-20 06-Jan-21 e Ceiling Mechanical Equipment - Garden Level 10 22-Dec-20 06-Jan-21 be Electrical Closets - Garden Level 5 28-Dec-20 06-Jan-21 be Electrical Closets - Garden Level 10 22-Dec-20 06-Jan-21 be Electrical Closets - Garden Level 10 22-Dec-20 06-Jan-21 be Electrical Closets - Garden Level 10 22-Dec-20 06-Jan-21 be Electrical Closets - Garden Level 5 28-Dec-20 04-Jan-21



ID	hool - Project A - 10Feb20 R1 Schedule Update - 1318014-CR - B26 Activity Name	Remaining	Start	Detai Finish		Data Date: 10-Feb-20 / Run Date: 09-Jul-20 09:05		
		Duration	Otart		2020	2021 2022		
					F Mar Apr M Jun Jul A S Oct N	D Jan F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul Aug S Oct		
G-1090	Frame Interior Walls - Garden Level	10	30-Dec-20	13-Jan-21		Frame Interior Wals - Garden Level		
G-1450	Insulate Overhead Mechanical Piping & HVAC Ductwork - Garden Level	15	30-Dec-20	21-Jan-21		Insulate Overhead Mechanical Piping & HVAC Ductwork - Garden Level		
G-1120	Set Door Frames - Garden Level	5	05-Jan-21	11-Jan-21		Set Door Frames - Garden Level		
G-1110	Rough-in Plumbing In-Wall - Garden Level	10	07-Jan-21	21-Jan-21		🔲 Rough-in Plumbing In-Wall - Garden Level		
G-1100	Frame Soffits - Garden Level	10	12-Jan-21	26-Jan-21		Frame Soffits - Garden Level		
G-1140	Rough-in Electrical In-Wall & Pull Branch Circuits - Garden Level	15	14-Jan-21	04-Feb-21		Rough-in Electrical In-Wall & Pull Branch Circuits - Garden Level		
G-1150	Rough-in Low Voltage In-Wall & Pull Wire - Garden Level	15	14-Jan-21	04-Feb-21		Rough-in Low Voltage In-Wall & Pull Wire - Garden Level		
G-1160	Perform Wall & Ceiling Punch List & Inspections - Garden Level	10	04-Feb-21	18-Feb-21		Perform Wall & Celling Punch List & Inspections - Garden Level		
G-1170	Perform In-Wall Inspections with Town - Garden Level	2	05-Feb-21	08-Feb-21		Perform In-Wall Inspections with Town - Garden Level		
G-1180	Install Wood Blocking - Garden Level	5	09-Feb-21	16-Feb-21		Install Wood Blocking - Garden Level		
G-1330	Insulate In-Wall Piping - Garden Level	5	09-Feb-21	16-Feb-21		Insulate In-Wall Piping - Garden Level		
G-1190	Board Wals & Soffits - Garden Level	5		15-Apr-21		Board Walls & Soffits - Garden Level		
			09-Apr-21					
-1210	Tape Walls & Soffits - Garden Level	5	16-Apr-21	23-Apr-21		Tape Walls & Soffits - Garden Level		
-3050	Field Measure & Fab Interior Glass - Garden Level	20	16-Apr-21	14-May-21		Field Measure & Fab Interior Glass - Garden Level		
6-1220	Prime & 1st Coat walls - Garden Level	3	26-Apr-21	28-Apr-21		Prime & 1st Coat walls - Garden Level		
6-1230	Install Ceiling Grid & Cut/DeviceTiles at Classrooms & Offices - Garden Level	5	06-May-21	12-May-21		Install Ceiling Grid & Cut/DeviceTies at Classrooms & Offices - Garden Level		
-1240	Install MEP Drops at Classrooms & Offices - Garden Level	5	13-May-21	19-May-21		Install MEP Drops at Classrooms & Offices - Garden Level		
-1250	Install Storefront Frames - Garden Level	5	20-May-21	26-May-21		Install Storefront Frames - Garden Level		
-1440	Install Teledata Finishes & Terminations - Garden Level	5	20-May-21	26-May-21		Install Teledata Finishes & Terminations - Garden Level		
-1260	Install Millwork at Classrooms & Offices - Garden Level	5	27-May-21	03-Jun-21		Install Millwork at Classrooms & Offices - Garden Level		
-1370	Install Doors & Hardware - Garden Level	2	04-Jun-21	07-Jun-21		Install Doors & Hardware - Garden Level		
i-1270	Install Ceiling Grid & Cut/DeviceTiles at Corridors - Garden Level	3	04-Jun-21	08-Jun-21		Install Ceiling Grid & Cut/DevideTies at Corridors - Garden Level		
-1390	Install Interior Glazing - Garden Level	5	04-Jun-21	10-Jun-21		Install Interior Glazing - Garden Level		
-1445	Install Fintube Radiators - Garden Level	5	04-Jun-21	10-Jun-21		Install Fintube Radiators - Garden Level		
-1430	Install Fire Alarm Devices - Garden Level	3	11-Jun-21	15-Jun-21		Install Fire Alarm Devices - Garden Level		
-1280	Install MEP Drops at Corridors - Garden Level	4	16-Jun-21	21-Jun-21		Install MEP Drops at Corridors - Garden Level		
-1380	Install Flooring at Classrooms & Offices - Garden Level	4	25-Jun-21	30-Jun-21		 Install Flooring at Classrooms & Offices - Garden Level 		
G-1285	Install Flooring at Classiforns & Onices - Garden Level	5	01-Jul-21	08-Jul-21		 Install Flooring at Classifications & Offices - Garden Level Install Fintube Covers - Garden Level 		
-1300	Install Flooring at Corridors - Garden Level	5	09-Jul-21	15-Jul-21		Install Flooring at Corridors - Garden Level		
5-1360	Install Base at Corridors - Garden Level	3	16-Jul-21	20-Jul-21		Install Base at Corridors - Garden Level		
-1310	Install Lockers - Garden Level	3	07-Sep-21	09-Sep-21		Install Lockers + Garden Level		
i-1320	Install AV - Garden Level	3	07-Sep-21	09-Sep-21		Install AV - Garden Level		
-1340	Install Whiteboards & Tack Boards - Garden Level	3	07-Sep-21	09-Sep-21		Install Whiteboards & Tack Boards - Garden Level		
-1350	Install Window Shades - Garden Level	3	07-Sep-21	09-Sep-21		Install Window Shades - Garden Level		
-1400	Construction Cleaning - Garden Level	3	10-Sep-21	14-Sep-21		Construction Cleaning - Garden Level		
-1290	Balance HVAC - Garden Level	3	15-Sep-21	17-Sep-21		Balance HVAC - Garden Level		
-1410	Skanska Punch List - Garden Level	3	15-Sep-21	17-Sep-21		Skanska Punch List - Garden Level		
-1420	Architect Punch List - Garden Level	2	28-Sep-21	29-Sep-21		Architect Punch List - Garden Level		
itchen								
G-1675	Prime & First Coat Paint - Garden Level Kitchen	5	26-Apr-21	30-Apr-21		Prime & First Coat Paint - Garden Level Kitchen		
G-1685	Install Epoxy Flooring - Garden Level Kitchen	10	03-May-21	14-May-21		Install Epoxy Flooring - Garden Level Kitchen		
G-1705	Install FRP at Walls - Garden Level Kitchen	5	17-May-21	21-May-21		Install FRP at Walls - Garden Level Kitchen		
G-1695	Install Wak-in Cooler/Freezer - Garden Level Kitchen	5	24-May-21	28-May-21		Install Wak-in Cooler/Freezer - Garden Level Kitchen		
G-1715	Install Kitchen Hoods - Garden Level Kitchen	5	24-May-21*	28-May-21		Install Kitchen Hoods - Garden Level Kitchen		
			-					
G-1725	Install Ansul System - Garden Level Kitchen	5	01-Jun-21	07-Jun-21		Install Ansul System - Garden Level Kitchen		
G-1735	Install Ceiling Grid & Boarder/Device Tiles - Garden Level Kitchen	5	08-Jun-21	14-Jun-21		Install Ceiling Grid & Boarder/Device Tiles - Garden Level Kitchen		
G-1745	Install MEP Drops at Celing Grid - Garden Level Kitchen	5	15-Jun-21	21-Jun-21		Install MEP Drops at Celing Grid - Garden Level Kitchen		
G-1755	Above Ceiling Punch List - Garden Level Kitchen	5	22-Jun-21	28-Jun-21		Above Ceiling Punch List - Garden Level Kitchen		
G-1765	Install Kitchen Equipment - Garden Level Kitchen	15	22-Jun-21	13-Jul-21		Install Kitchen Equipment - Garden Level Kitchen		
G-1775	Install Plumbing Connections to Kitchen Equipment - Garden Level Kitchen	5	14-Jul-21	20-Jul-21		Install Plumbing Connections to Kitchen Equipment - Garden Level Kitch		
G-1785	Install Electrical Connections to Kitchen Equipment - Garden Level Kitchen	5	19-Jul-21	23-Jul-21		Install Electrical Connections to Kitchen Equipment - Garden Level Kitch		
G-1787	Start-up & Test Kitchen Hoods - Garden Level Kitchen	5	26-Jul-21	30-Jul-21		Start-up & Test Kitchen Hoods - Garden Level Kitchen		
G-1795	Install Ceiling Tile - Garden Level Kitchen	3	02-Aug-21	04-Aug-21		Install Ceiling Tile - Garden Level Kitchen		
G-1815	Startup & Test Kitchen Equipment - Garden Level Kitchen	15	05-Aug-21	25-Aug-21		Startup & Test Kitchen Equipment - Garden Level Kitchen		
G-1825	Balance HVAC - Garden Level Kitchen	3	15-Sep-21	17-Sep-21		Balance HVAC - Garden Level Kitchen		
	ing Level of Effort Remaining Work		Page 27 o	of 29	TASK filter: Uncompleted Activities Two Mor			
 Actual L 	evel of Effort Critical Remaining Work					© Oracle Corporation		
Actual W	Vork Milestone			Page				

vity ID	Activity Name	Remaining	g Start	Finish	ed Schedule Data Date: 10-Feb-20 / Run Date: 09-Jul-20 09:05				
		Duration	Start		2020 2021 2022				
					F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul Aug S Oct N				
G-1835	Board of Health Inspections - Garden Level Kitchen	1	20-Sep-21	20-Sep-21	I Board of Health Inspections - Garden Level Kitchen				
Bathrooms									
G-1600	Board & Install Cement Board - Garden Level Bathrooms	3	16-Apr-21	21-Apr-21	Board & Install Cement Board - Garden Level Bathrooms				
G-1605	Tape & Finish - Garden Level Bathrooms	3	22-Apr-21	26-Apr-21	I Tape & Finish - Garden Level Bathrooms				
G-1610	Prime Paint - Garden Level Bathrooms	1	27-Apr-21	27-Apr-21	I Prime Paint - Garden Level Bathrooms				
G-1615	Install Counters - Garden Level Bathrooms	1	28-Apr-21	28-Apr-21	I Install Counters - Garden Level Bathrooms				
G-1620	Install Wall & Floor Tile - Garden Level Bathrooms	5	10-May-21	14-May-21	Install Wall & Floor Tile - Garden Level Bathrooms				
G-1625	Install Plumbing Fixtures - Garden Level Bathrooms	3	17-May-21	19-May-21	Install Plumbing Fixtures - Garden Level Bathrooms				
G-1630	Field Measure & Fab Mirrors - Garden Level Bathrooms	10	17-May-21	28-May-21	Field Measure & Fab Mirrors - Garden Level Bathrooms				
G-1635	Install Toilet Partitions - Garden Level Bathrooms	2	21-May-21	24-May-21	Install Toilet Partitions - Garden Level Bathrooms				
G-1640	Install Bathroom Accessories - Garden Level Bathrooms	2	25-May-21	26-May-21	Install Bathroom Accessories - Garden Level Bathrooms				
G-1645	Install Mirrors - Garden Level Bathrooms	1	01-Jun-21	01-Jun-21	I Install Mirrors - Garden Level Bathrooms				
G-1650	Finish Paint - Garden Level Bathrooms	1	02-Jun-21	02-Jun-21	Finish Paint - Garden Level Bathrooms				
Stair Finishe									
	÷>								
Stair 1									
ST1-1000	Frame Wals - Stair 1	5	05-Nov-20	12-Nov-20	Frame Wals - Stair 1				
ST1-1010	Rough-in In-Wall Electric - Stair 1	3	13-Nov-20	17-Nov-20	Rough-in In-Wall Electric - Stair 1				
ST1-1020	Board Walls - Stair 1	3	12-Mar-21	16-Mar-21	Board Walls - Stair 1				
ST1-1030	Tape & Finish Walls - Stair 1	4	17-Mar-21	22-Mar-21	Tape & Finish Walls - Stair 1				
ST1-1040	Prime Paint Walls & Stairs - Stair 1	3	23-Mar-21	25-Mar-21	Prime Paint Walls & Stairs - Stair 1				
ST1-1050	Install Tile Walls - Stair 1	5	30-Mar-21	05-Apr-21	Install Tile Walls - Stair 1				
ST1-1100	Install Wood Wall Panels - Stair 1	10	06-Apr-21	20-Apr-21	Install Wood Wall Panels - Stair 1				
ST1-1060	Install Wall Railings - Stair 1	3	21-Apr-21	23-Apr-21	Install Wal Raings - Stair 1				
ST1-1070	Finish Paint Stairs - Stair 1	2	26-Apr-21	27-Apr-21	Finish Paint Stairs - Stair 1				
ST1-1090	Install Terrazzo Treads - Stair 1	5	28-Apr-21	04-May-21	Install Terrazzo Treads - Stair 1				
		5	20-Apr-21	04-1vidy-21					
Stair 2									
ST2-1000	Frame Wals - Stair 2	15	13-Nov-20	07-Dec-20	Frame Wals - Stair 2				
ST2-1010	Rough-in In-Wall Electric - Stair 2	5	08-Dec-20	14-Dec-20	Rough-in In-Wall Electric - Stair 2				
ST2-1020	Board Walls - Stair 2	10	26-Mar-21	08-Apr-21	Board Wals - Stair 2				
ST2-1030	Tape & Finish Walls - Stair 2	10	09-Apr-21	23-Apr-21	Tape & Finish Walls - Stair 2				
ST2-1040	Prime Paint Walls & Stairs - Stair 2	5	26-Apr-21	30-Apr-21	Prime Paint Walls & Stairs - Stair 2				
ST2-1050	Install Tile Walls - Stair 2	20	03-May-21	28-May-21	Install Tile Walls - Stair 2				
ST2-1060	Install Wall Railings - Stair 2	10	01-Jun-21	14-Jun-21	Install Wal Raings - Stair 2				
ST2-1070	Paint Railings & Finish Paint Stairs - Stair 2	5	15-Jun-21	21-Jun-21	Paint Railings & Finish Paint Stairs - Stair 2				
ST2-1080	Install Light Fixtures - Stair 2	2	22-Jun-21	23-Jun-21	I Install Light Fixtures - Stair 2				
ST2-1090	Install Rubber Flooring - Stair 2	10	24-Jun-21	08-Jul-21	Install Rubber Flooring - Stair 2				
Stair 3									
ST3-1000	Frame Wals - Stair 3	15	08-Dec-20	29-Dec-20	Frame Wals - Stair 3				
ST3-1000	Rough-in In-Wall Electric - Stair 3		30-Dec-20	06-Jan-21	Rough-in In-Wall Electric - Stair 3				
		5							
ST3-1020	Board Wals - Stair 3	10	09-Apr-21	23-Apr-21	Board Walls - Stair 3				
ST3-1030	Tape & Finish Walls - Stair 3	10	26-Apr-21	07-May-21	Tape & Finish Walls - Stair 3				
ST3-1040	Prime Paint Walls & Stairs - Stair 3	5	10-May-21	14-May-21	Prime Paint Walls & Stairs - Stair 3				
ST3-1050	Install Tile Walls - Stair 3	20	01-Jun-21	28-Jun-21	Install Tile Walls - Stair 3				
ST3-1060	Install Wal Railings - Stair 3	10	29-Jun-21	13-Jul-21	Install Wal Railings - Stair 3				
ST3-1070	Paint Railings & Finish Paint Stairs - Stair 3	5	14-Jul-21	20-Jul-21	Paint Raitings & Finish Paint Stairs - Stair 3				
ST3-1080	Install Light Fixtures - Stair 3	2	21-Jul-21	22-Jul-21	I Install Light Fixtures - Stair 3				
ST3-1090	Install Rubber Flooring - Stair 3	10	23-Jul-21	05-Aug-21	Install Rubber Flooring - Stair 3				
Stair 6/7									
ST6/7-1000	Frame Wals - Stair 6/7	15	30-Dec-20	21-Jan-21	Frame Walls - Stair 6/7				
ST6/7-1010	Rough-in In-Wall Electric - Stair 6/7	5	22-Jan-21	28-Jan-21	Rough-in In-Wall Electric - Stair 6/7				
ST6/7-1020	Board Wals - Stair 6/7	8	26-Apr-21	05-May-21	Board Wals - Stair 6/7				
ST6/7-1030	Tape & Finish Walls - Stair 6/7	8	06-May-21	17-May-21	Tape & Finish Walls - Stair 6/7				
ST6/7-1030	Prime Paint Walls & Stairs - Stair 6/7	4	18-May-21	21-May-21	Prime Paint Walls & Stair 6/7				
			•						
ST6/7-1050	Install Tile Walls - Stair 6/7	15	29-Jun-21	20-Jul-21					
Remaining	Level of Effort Remaining Work		Page 28 c	of 29	TASK filter: Uncompleted Activities Two Months Prior.				
-	vel of Effort Critical Remaining Work			-					
ACTUALLEY									
Actual Lev	5			Dogo	© Oracle Corporation				



ST6/7-1060 ST6/7-1070 ST6/7-1080 ST6/7-1090 SEN-1090 SEN-1000	Activity Name Install Wall Railings - Stair 6/7 Paint Railings & Finish Paint Stairs - Stair 6/7	Remaining Duration	Start	Finish	2021 A S Oct N D Jan F Mar Apr M Jun Jul A S Oct N D Jan F Mar Apr M Jun Jul Aug S Oc
ST6/7-1070 ST6/7-1080 ST6/7-1090 General GEN-1000					
ST6/7-1070 ST6/7-1080 ST6/7-1090 General GEN-1000					
ST6/7-1080 ST6/7-1090 General GEN-1000	Paint Railings & Finish Paint Stairs - Stair 6/7	8	21-Jul-21	30-Jul-21	Install Wal Railings - \$tair 6/7
ST6/7-1090 ieneral GEN-1000		4	02-Aug-21	05-Aug-21	Paint Railings & Finish Paint Stairs - Stair 6/7
eneral GEN-1000	Install Light Fixtures - Stair 6/7	2	06-Aug-21	09-Aug-21	Install Light Fixtures - Stair 6/7
EN-1000	Install Linoleum Flooring - Stair 6/7	8	10-Aug-21	19-Aug-21	Install Linoleum Flooring - Stair 6/7
EN-1000					
		45	00 4 04	40.0 04	
ammiaalani	Install Building Signage	15	23-Aug-21	13-Sep-21	Install Building Signage
ommissioniı	ing				
OMM-1000	Commission MEPs	60	26-Aug-21	22-Nov-21	Commission MEPs
ardscapes 8	& Landscaping				
			10.4 0.4*	00.4.04	
	Remove Temp Poles from Park	9	12-Apr-21*	23-Apr-21	Remove Temp Poles from Park
	Install Hardscapes & Landscaping	80	29-Apr-21*	20-Aug-21	Install Hardscapes & Landscaping
nal Testing,	, Inspections & Occupancy				
umbing Syster	m				
	Perform Potable Water Chlorination	5	28-Jul-21	03-Aug-21	Perform Potable Water Chlorination
		5	20-JUI-2 I	03-Aug-21 03-Aug-21	■ Perform Potable Water Chlorination
	Issue Potable Water Chlorination Report	U		03-Aug-21	
ater & Sewer		1			
	Acquire GSA Permit	1	04-Aug-21	04-Aug-21	Acquire GSA Permit
DA Testing					
SI-1330	Test Bi-Directional Amplifier	1	10-Aug-21	10-Aug-21	I Test Bi-Directional Amplifier
nergency Pov	ver System & Power Outage Testing				
	Ceilings, Lights & Exit Signs Complete	0		09-Aug-21	♦ Ceilings, Lights & Exit Signs Complete
	Pre-test for Lights Out Testing	1	10-Aug-21	10-Aug-21	I Pre-test for Lights Out Testing
	Correct Issues for Brookline Lights Out Testing	2	11-Aug-21	12-Aug-21	Correct Issues for Brookline Lights Out Testing
	Perform Lights Out Testing with Brookline		13-Aug-21	13-Aug-21	 Perform Lights Out Testing with Brookline
			13-Aug-21	13-Aug-21	
ire Alarm Syste		-			
	Test Fire Alarm - Garden Level Devices, Speakers & Duct Smokes	2	06-Aug-21	09-Aug-21	Test Fire Alarm - Garden Level Devices, Speakers & Duct Smokes
	NFPA 72 Fire Alarm Testing	9	06-Aug-21	18-Aug-21	NFPA 72 Fire Alarm Testing
	Test Fire Alarm - L1 Devices, Speakers & Duct Smokes	2	10-Aug-21	11-Aug-21	I Test Fire Alarm - L1 Devices, Speakers & Duct Smokes
SI-1090	Test Fire Alarm - L2 Devices, Speakers & Duct Smokes	2	12-Aug-21	13-Aug-21	Test Fire Alarm - L2 Devices, Speakers & Duct \$mokes
SI-1110	Test Fire Alarm - L3 Devices, Speakers & Duct Smokes	2	16-Aug-21	17-Aug-21	Test Fire Alarm - L3 Devices, Speakers & Duct Smokes
SI-1260	Test Fire Alarm - L4 Speakers & Duct Smokes	1	18-Aug-21	18-Aug-21	I Test Fire Alarm - L4 Speakers & Duct Smokes
SI-1370	Submit Record of Completion (ROC) to Brookline	5	20-Aug-21	26-Aug-21	Submit Record of Completion (ROC) to Brookline
	Brookline ROC NFPA 72 Test	3	27-Aug-21	31-Aug-21	Brookline ROC NFPA 72 Test
evators		ļ	- 3		
	Draliminary Test Elevator with Fire Alarm Becall	2	16 Aug 21	19 Aug 21	Preliminary Test Elevator with Fire Alarm Recall
	Preliminary Test Elevator with Fire Alarm Recall Complete Elevator Cleaning & Adjustment for Inspection	10	16-Aug-21	18-Aug-21	Complete Elevator Cleaning & Adjustment for Inspection
			19-Aug-21	01-Sep-21	·
	Complete Phone Service to Elevators	0		01-Sep-21	◆ Complete Phone Service to Elevators
	State (Mass 524) Inspection & Signoff	3	02-Sep-21	07-Sep-21	State (Mass 524) Inspection & Signoff
re Protection S	-				
SI-1000	Flow Test Fire Protection System	5	10-Aug-21	16-Aug-21	Flow Test Fire Protection System
SI-1020	Checkout Tampers & Flows	1	17-Aug-21	17-Aug-21	I Checkout Tampers & Flows
SI-1350	Test Stand Pipe & Floor Control Valves with PRVs - Stair 2	2	18-Aug-21	19-Aug-21	I Test Stand Pipe & Floor Control Valves with PRVs - Stair 2
SI-1520	Test Stand Pipe & Floor Control Valves with PRVs - Stair 3	2	20-Aug-21	23-Aug-21	Test Stand Pipe & Floor Control Valves with PRVs - Stair 3
	Brookline Fire Protection Test	1	01-Sep-21	01-Sep-21	I Brookline Fire Protection Test
nal Inspection					
-	Final Plumbing Signoff	1	04-Aug-21	04-Aug-21	Final Plumbing Signoff
			-		·
	Final Electrical Signoff	1	16-Aug-21	16-Aug-21	Final Electrical Signoff
	Owner Install FF&E	10	23-Aug-21	03-Sep-21	Owner Install FF&E
	Final Life Safety Wak-thru	2	21-Sep-21	22-Sep-21	I Final Life Safety Wak-thru
	Receive Final Architectural, Mechanical & Structural Affadavits	2	30-Sep-21	01-Oct-21	Receive Final Architectural, Mechanical & Structural Affada
NSP-1010	Final Building Sigh Off Acquire C of O	5	04-Oct-21	08-Oct-21	Final Building Sigh Off Acquire C of O
NSP-1020	Substantial Completion - Project A: 111 Cypress Street	0		08-Oct-21*	Substantial Completion - Project A: 111 Cypress Street
		1			
 Remaining I 	Level of Effort Remaining Work		Page 29 o	f 29	Activities Two Months Prior.
 Actual Level 	el of Effort Critical Remaining Work		0		
Actual Work				Der	© Oracle Corporation
	k			Page	



Activity ID	chool - Project C - 10Feb20 R1 Schedule Update - 1318015-CR - B22	Pomoinine			Detailed Schedule	Data Date: 10-Feb-20 / Run Date: 09-Jul-20 08:54			
vity ID	Activity Name	Remaining Duration	Start	Finish	2020	2021	1	20	022
		Duration				Jan F Mar Apr M Jun Jul A S Oct N De	Jan F Mar		
Brookline	High School - Project C - 10Feb20 R1 Schedule Update								
		00	04 Mar 40 A	40 Max 00					
		23	04-Mar-19 A	12-Mar-20	Bid Period				NA/:
EXEC-1060	Construction Project C - Demo Roberts Wing & Build New STEM Wing	303	21-Aug-19 A	27-Apr-21	 Used Devider Observed Electrical Delection 	Construction Project C - Demo Rob	erts wing & Bui	d New STEM	vving
EXEC-1110	Last Day for Overhead Electrical Relocation in Order to Start Steel	0	40 Mar 04	13-Mar-20	♦ Last Day for Overhead Electrical Relocation				
EXEC-1320	Construction Project C - Owner Install FF&E New STEM Wing	10	18-Mar-21	31-Mar-21		Construction Project C - Owner Install F		1 wing	
EXEC-1310		0		27-Apr-21		 Summary - STEM Interim Completio 	Date		
Work Ord	er Milestones								
EXEC-1390		0		11-Feb-20	◆ Last Day for STEM Fire, Water & Sewer Service	Installation			
EXEC-1330	Last Day for Overhead Wire Relocation	0		13-Mar-20	Last Day for Overhead Wire Relocation		i 		· · · · · · · · · · · · · · · · · · ·
BHS Acad	lemic Calendar								
BHS-1030	February Break - 2020	5	18-Feb-20*	22-Feb-20*	February Break - 2020				
BHS-1040	April Break - 2020	5	20-Apr-20*	24-Apr-20*	April Break - 2020				
BHS-1050	Last Day of School - 2019/2020	0		22-Jun-20*	◆ Last Day of School - 2019/2	020	1		
BHS-1060	First Day of School - 2020/2021	0		03-Sep-20*	♦ First Day of Sch				
BHS-1070	December Break - 2020	8	25-Dec-20*	01-Jan-21*		December Break - 2020			
BHS-1080	February Break - 2021	5	15-Feb-21*	19-Feb-21*		February Break - 2021			
BHS-1090	April Break - 2021	5	19-Apr-21*	23-Apr-21*		April Break - 2021			
BHS-1100	Last Day of School - 2020/2021	0		22-Jun-21*		♦ Last Day of School - 2020/2	021		
BHS-1110	First Day of School - 2021//2022	0		02-Sep-21*		 First Day of Sch 		2	
Design / P	Preconstruction Phase			•					-
GMP (Proje									
PRE-1170	Prepare & Submit - GMP	14	02-Aug-19 A	28-Feb-20	Prepare & Submit - GMP				
PRE-1180	Review & Execute - GMP	15	02-Mar-20	20-Mar-20	Review & Execute - GMP				
PRE-1190	Agreement Executed - GMP	0		20-Mar-20	♦ Agreement Executed - GMP				
Schedule	Impacts								
Bulletin 022	2 - Remaining Building Demo								
IMP-1260	Patch, Repair & Clean Rooms - Bulletin 022	3	30-Jan-20 A	12-Feb-20	Patch, Repair & Clean Rooms - Bulletin 022				
RFI 190 - R	emaining Building Demo						j l		
IMP-1370	Engineer Shoring - RFI 190	2	31-Jan-20 A	11-Feb-20	Engineer Shoring - RFI 190		1		
IMP-1440	Perform Added L3 Corridor Work - RFI 190	5	10-Feb-20	14-Feb-20	Perform Added L3 Corridor Work + RFI 190				
IMP-1410	Review & Approve -Shoring - RFI 190	2	12-Feb-20	13-Feb-20	Review & Approve -Shoring - RFI 190		1		
IMP-1460	Patch Temp Exterior Walls - RFI 190	2	15-Feb-20	16-Feb-20	Patch Temp Exterior Walls - RFI 190				
IMP-1450	Install Shoring - RFI 190	4	15-Feb-20	19-Feb-20	Install Shoring - RFI 190		1		
IMP-1270	Complete Building Demo - Bulletin 022 / RFI 190	10	20-Feb-20	29-Feb-20	Complete Building Demo - Bulletin 022 / RFI 19	90			
IMP-1280	Tie In Roofing / Complete Waterproofing - Bulletin 022 / RFI 190	7	02-Mar-20	10-Mar-20	Tie In Roofing / Complete Waterproofing - Budgete W				
Procurem									
Design Ass									
	II Design Assist	70	00 1 00 4	04 Mar 00					
	Fab & Available for Delivery - Curtain Wall	72	29-Jan-20 A	21-May-20	Fab & Available for Delivery - Cur	rtain Wall			i
Early Bid P	ackages								
Elevators									
	Fab & Available for Delivery - Elevators	46	06-Nov-19A	14-Apr-20	Fab & Available for Delivery - Elevators				
Structural S							1		
	Fab & Available for Delivery - Structural Steel	1	12-Dec-19 A	10-Feb-20	Fab & Available for Delivery - Structural Steel				
	Procurement Post CDs (Trade Contractors)								
	Trade Contractor)						i i		
	Fab/Deliver Equipment - Plumbing Fixtures	65	31-Dec-19A	12-May-20	Fab/Deliver Equipment - Plumbing	Fixtures			
	tion (Trade Contractor)						j		
	A/E Review & Approve Submittals - Fire Protection Piping	25	19-Dec-19 A	16-Mar-20	A/E Review & Approve Submittals - Fire Pro	otection Piping			1 I 1 I -
HVAC (Trac	le Contractor)								
- Domo:	ning Level of Effort Remaining Work			4 -640					
			Page	1 of 16	TASK filter: % Complete <100.				
	Level of Effort Critical Remaining Work					© Oracle Corporation	SK	ANS	КД
	Work Milestone				Page 7β of 377				

	hool - Project C - 10Feb20 R1 Schedule Update - 1318015-CR - B22		Chart			Data Date: 10-Feb-20 / Run Date: 09-Jul-20 08:54		
D	Activity Name	Remaining	Start	Finish	2020 2021	2022		
					F Mar Apr M Jun Jul Aug S Oct N D Jan F Mar Apr M Jun Jul A S Oct			
PRO-4780	A/E Review & Approve Submittals - HVAC Ductwork	15	27-Jan-20 A	02-Mar-20	A/E Review & Approve Submittals - HVAC Ductwork			
PRO-2190	Fab/Deliver Equipment - HVAC VRF Units	54	31-Jan-20 A	27-Apr-20	Fab/Deliver Equipment - HVAC VRF Units			
PRO-2200	Fab/Deliver Equipment - HVAC RTUs	56	04-Feb-20 A	29-Apr-20	Fab/Deliver Equipment - HVAC RTUs			
PRO-2220	Fab/Deliver Equipment - Air Cooled Chiller	56	04-Feb-20 A	29-Apr-20	Fab/Deliver Equipment - Air Cooled Chiller			
PRO-4830	A/E Review & Approve Submittals - HVAC Exhaust Fans	5	05-Feb-20 A	14-Feb-20	A/E Review & Approve Submittals - HVAC Exhaust Fans			
PRO-4870	Fab/Deliver Equipment - HVAC Pumps	60	10-Feb-20	05-May-20	Fab/Deliver Equipment - HVAC Pumps			
PRO-4820	Fab/Deliver Equipment - HVAC Exhaust Fans	50	18-Feb-20	28-Apr-20	Fab/Deliver Equipment - HVAC Exhaust Fans			
ectrical & C	Communications (Trade Contractor)							
PRO-2280	Subcontractor Issue Submittals - Electrical Interior Lighting	15	12-Nov-19 A	02-Mar-20	Subcontractor Issue Submittals - Electrical Interior Lighting			
PRO-2300	A/E Review & Approve Submittals - Electrical Interior Lighting	15	03-Mar-20	23-Mar-20	A/E Review & Approve Submittals - Electrical Interior Lighting			
PRO-2320	Fab/Deliver Equipment - Interior Lighting	65	24-Mar-20	24-Jun-20	Fab/Deliver Equipment - Interior Lighting			
iscellaneou	us Metals & Ornamental Iron (Trade Contractor)							
PRO-2370	Subcontractor Issue Submittals - Misc. Metals Lintels	15	25-Nov-19 A	02-Mar-20	Subcontractor Issue Submittals - Misc. Metals Lintels			
PRO-2380	Subcontractor Issue Submittals - Misc. Metals Stair 1	25	25-Nov-19A	16-Mar-20	Subcontractor Issue Submittals - Misc. Metals Stair 1			
PRO-2400	Subcontractor Issue Submittals - Misc. Metals Stair 3	15	08-Jan-20 A	02-Mar-20	Subcontractor Issue Submittals - Misc. Metals Stair 3			
PRO-2410	Subcontractor Issue Submittals - Misc. Metals Stair 2	15	09-Jan-20 A	02-Mar-20	Subcontractor Issue Submittals - Misc. Metals Stair 2			
PRO-2420	A/E Review & Approve Submittals - Misc. Metals Lintels	15	03-Mar-20	23-Mar-20	A/E Review & Approve Submittals - Misc. Metals Lintels			
PRO-2450	A/E Review & Approve Submittals - Misc. Metals Stair 3	15	03-Mar-20	23-Mar-20	A/E Review & Approve Submittals - Misc. Metals Stair 3			
PRO-2460	A/E Review & Approve Submittals - Misc. Metals Stair 2	15	03-Mar-20	23-Mar-20	A/E Review & Approve Submittals - Misc. Metals Stair 2			
PRO-2430	A/E Review & Approve Submittals - Misc. Metals Stair 1	15	17-Mar-20	06-Apr-20	A/E Review & Approve Submittals - Misc Metals Stair 1			
PRO-2500	Fab & Available for Delivery - Misc. Metals Stair 2	25	24-Mar-20	28-Apr-20	Fab & Available for Delivery - Misc. Metals Stair 2			
PRO-2510	Fab & Available for Delivery - Misc. Metals Stair 3	25	24-Mar-20	28-Apr-20	Fab & Available for Delivery - Misc. Metals Stair 3			
PRO-2470	Fab & Available for Delivery - Misc. Metals Lintels	20	31-Mar-20	28-Apr-20	Fab & Available for Delivery - Misc. Metals Lintels			
PRO-2480	Fab & Available for Delivery - Misc. Metals Stair 1	25	07-Apr-20	12-May-20	Fab & Available for Delivery - Misc. Metals Stair 1			
asonry (Tra	ade Contractor)							
PRO-2010	Fab & Available for Delivery - Masonry (Brick)	75	06-Jan-20 A	27-May-20	Fab & Available for Delivery - Masonry (Brick)			
PRO-2000	A/E Review & Approve Initial Shop Drawings - Masonry	36	23-Jan-20 A	31-Mar-20	A/E Review & Approve Initial Shop Drawings - Masonry			
uilding AVE	3 & Caulking (Trade Contractor)							
PRO-2540	Subcontractor Issue Submittals - Building AVB & Caulking	4	18-Nov-19 A	13-Feb-20	Subcontractor Issue Submittals - Building AVB & Caulking			
PRO-2550	A/E Review & Approve Submittals - Building AVB & Caulking	15	14-Feb-20	06-Mar-20	A/E Review & Approve Submittals - Building AVB & Caulking			
'RO-2560	Fab & Available for Delivery - Building AVB & Caulking	20	09-Mar-20	03-Apr-20	Fab & Available for Delivery - Building AVB & Caulking			
oofing & Fl	lashing (Trade Contractor)							
PRO-2600	Subcontractor Issue Submittals - Membrane Roofing	25	29-Nov-19 A	16-Mar-20	Subcontractor Issue Submittals - Membrane Roofing			
PRO-2590	Subcontractor Issue Submittals - Roofing Metal Flashing & Trim	30	29-Nov-19 A	23-Mar-20	Subcontractor Issue Submittals - Roofing Metal Flashing & Trim			
'RO-2620	A/E Review & Approve Submittals - Membrane Roofing	15	17-Mar-20	06-Apr-20	A/E Review & Approve Submittals - Membrane Roofing			
PRO-2610	A/E Review & Approve Submittals - Roofing Metal Flashing & Trim	0	24-Mar-20	24-Mar-20	I A/E Review & Approve Submittals - Roofing Metal Flashing & Trim			
PRO-2640	Fab & Available for Delivery - Roofing Metal Flashing & Trim	25	24-Mar-20	28-Apr-20	Fab & Available for Delivery - Roofing Metal Flashing & Trim			
PRO-2630	Fab & Available for Delivery - Membrane Roofing	20	07-Apr-20	05-May-20	Fab & Available for Delivery - Membrane Roofing			
ainting (Tra	ide Contractor)							
PRO-7230	Subcontractor Issue Submittals - Painting	31	28-Oct-19A	24-Mar-20	Subcontractor Issue Submittals - Painting			
PRO-7220	A/E Review & Approve Submittals - Painting	15	25-Mar-20	14-Apr-20	A/E Review & Approve Submittals - Painting			
PRO-7210	Fab & Available for Delivery - Painting	10	15-Apr-20	29-Apr-20	Fab & Available for Delivery - Painting			
terior Glas	s & Glazing (Trade Contractor)							
PRO-2670	Subcontractor Issue Submittals - Interior Glass	40	06-Nov-19 A	06-Apr-20	Subcontractor Issue Submittals - Interior Glass			
PRO-2700	A/E Review & Approve Submittals - Interior Glass Mirrors	15	27-Dec-19 A	02-Mar-20	A/E Review & Approve Submittals - Interior Glass Mirrors			
PRO-2710	Fab & Available for Delivery - Interior Glass Mirrors	25	03-Mar-20	06-Apr-20	Fab & Available for Delivery - Interior Glass Mirrors			
PRO-2690	A/E Review & Approve Submittals - Interior Glass	15	07-Apr-20	28-Apr-20	A/E Review & Approve Submittals - Interior Glass			
PRO-2720	Fab & Available for Delivery - Interior Glass	40	29-Apr-20	24-Jun-20	Fab & Available for Delivery - Interior Glass			
ile (Trade C	ontractor)							
PRO-2750	Subcontractor Issue Submittals - Ceramic Tile	35	13-Nov-19 A	30-Mar-20	Subcontractor Issue Submittals - Ceramic Tile			
PRO-2760	A/E Review & Approve Submittals - Ceramic Tile	15	31-Mar-20	21-Apr-20	A/E Review & Approve Submittals - Ceramic Tile			
PRO-2770	Fab & Available for Delivery - Ceramic Tile	50	22-Apr-20	01-Jul-20	Fab & Available for Delivery - Ceramic Tile			
errazzo (Tra	ade Contractor)							
PRO-5290	Subcontractor Issue Submittals - Terrazzo	35	14-Nov-19 A	30-Mar-20	Subcontractor Issue Submittals - Terrazzo			
PRO-5300	A/E Review & Approve Submittals - Terrazzo	15	31-Mar-20	21-Apr-20	A/E Review & Approve Submittals - Terrazzo			
	ng Level of Effort Remaining Work	,,	<u> </u>	0 -5 40				
			Page	2 of 16	TASK filter: % Complete <100.			
	evel of Effort Critical Remaining Work				© Oracle Corporation	SKANSKA		
Actual W	Vork				Page 74 of 377			

	Project C - 10Feb20 R1 Schedule Update - 1318015-CR - B22	Domaining	Start		Detailed Schedule	Data Date: 10-Feb-20 / Run Date: 09-Jul-20 08:54				
ity ID Activ	<i>v</i> ity Name	Remaining Duration	Start	Finish	2020	2021 202				
				Ļ		N D Jan F Mar Apr M Jun Jul A S Oct N Dec Jan F Mar Apr M Jun	Jul A S Oct N I			
	& Available for Delivery - Terrazzo	30	22-Apr-20	03-Jun-20	Fab & Available for De	elivery - Terrazzo				
	g Tile (Trade Contractor)									
	contractor Issue Submittals - Acoustical Metal Panels	40	07-Nov-19 A	06-Apr-20	Subcontractor Issue Submittals					
	contractor Issue Submittals - ACT	40	08-Nov-19 A	06-Apr-20	Subcontractor Issue Submittals	· · · · · · · · · · · · · · · · · · ·				
	Review & Approve Submittals - ACT	15	07-Apr-20	28-Apr-20	A/E Review & Approve Subr					
	Review & Approve Submittals - Acoustical Metal Panels	15	07-Apr-20	28-Apr-20	A/E Review & Approve Subr					
	& Available for Delivery - ACT	15	29-Apr-20	19-May-20						
PRO-2850 Fab	& Available for Delivery - Acoustica I Metal Panels	40	29-Apr-20	24-Jun-20	Fab & Available for	r Delivery - Acous tica I Metal Panels				
Resilient Flooring	(Trade Contractor)						, , ,			
PRO-2880 Subo	contractor Issue Submittals - Resilient Flooring	58	13-Nov-19 A	01-May-20	Subcontractor Issue Submi	ittals - Resilient Flooring				
PRO-2890 A/E	Review & Approve Submittals - Resilient Flooring	15	04-May-20	22-May-20	A/E Review & Approve S	Submittals - Resilient Flooring				
PRO-2900 Fab	& Available for Delivery - Resilient Flooring	30	26-May-20	07-Jul-20	Fab & Available f	for Delivery - Resilient Flooring				
Remaining Procu	rement Post CDs (Subcontractors)									
Carpentry & Dryw	all									
	cute Contract - Carpentry & Drywall	5	23-Dec-19 A	14-Feb-20	Execute Contract - Carpentry & Drywall		·			
	contractor Issue Submittals - Carpentry & Drywall Exterior Cold Formed Metal Framing	15	31-Dec-19A	09-Mar-20		arpentry & Drywall Exterior Cold Formed Metal Framing				
	contractor Issue Submittals - Carpentry & Drywall Non-Structural Metal Framing	15	31-Dec-19 A	09-Mar-20		arpentry & Drywall Non-Structural Metal Framing	1			
	Review & Approve Submittals - Carpentry & Drywall Exterior Cold Formed Metal Framin	10	10-Mar-20	23-Mar-20		s - Carpentry & Drywall Exterior Cold Formed Metal Framing	1			
	Review & Approve Submittals - Carpentry & Drywall Non-Structural Metal Framing	15	10-Mar-20	30-Mar-20		Is - Carpentry & Drywall Non-Structural Metal Framing				
	& Available for Delivery - Carpentry & Drywall Exterior Cold Formed Metal Framing	15	24-Mar-20	13-Apr-20		Carpentry & Drywall Exterior Cold Formed Metal Framing	· · · · · · · · · · · · · · · · · · ·			
	& Available for Delivery - Carpentry & Drywall Non-Structural Metal Framing	10	31-Mar-20	13-Apr-20		Carpentry & Drywall Non-Structural Metal Framing				
Spray Fireproofin		10	51-10101-20	10-Apr-20						
	9 Review & Approve Submittals - Spray Fireproofing	0	07-Feb-20 A	21-Feb-20	A/E Review & Approve Submittals - Sp					
	& Available for Delivery - Spray Fireproofing	3	24-Feb-20A	26-Feb-20						
Doors, Frames An		3	24-Feb-20	20-Feb-20	I Fab & Available for Delivery - Spray F		· · · · · · · · · · · · · · · · · · ·			
	contractor Issue Submittals - Door Hardware	4	22 Jan 20 A	13-Feb-20	Subcontractor Issue Submittals - Door	Herduard	 			
		4	22-Jan-20 A							
	cute Contract - Doors, Frames & Hardware	5	22-Jan-20 A	14-Feb-20	Execute Contract - Doors, Frames & H		1 1 1			
	contractor Issue Submittals - Interior Wood Doors	4	10-Feb-20	13-Feb-20	Subcontractor Issue Submittals - Interio		1			
	contractor Issue Submittals - HM Door Frames	4	10-Feb-20	13-Feb-20	Subcontractor Issue Submittals - HM D	·				
	contractor Issue Submittals - HM Doors	4	10-Feb-20	13-Feb-20	Subcontractor Issue Submittals - HM D					
	Review & Approve Submittals - Interior Wood Doors	15	14-Feb-20	06-Mar-20	A/E Review & Approve Submittals -					
	Review & Approve Submittals - Door Hardware	15	14-Feb-20	06-Mar-20	A/E Review & Approve Submittals -					
	Review & Approve Submittals - HM Door Frames	15	14-Feb-20	06-Mar-20	A/E Review & Approve Submittals - I					
	Review & Approve Submittals - HM Doors	15	14-Feb-20	06-Mar-20	A/E Review & Approve Submittals - I	·	, , , ,			
PRO-3300 Fab	& Available for Delivery - HM Door Frames	25	09-Mar-20	10-Apr-20	Fab & Available for Delivery - I		 			
	& Available for Delivery - HM Doors	50	09-Mar-20	18-May-20	Fab & Available for Delive	ery - HM Doors				
PRO-3310 Fab	& Available for Delivery - Interior Wood Doors	65	09-Mar-20	09-Jun-20	Fab & Available for D	elivery - Interior Wood Doors				
PRO-3320 Fab	& Available for Delivery - Door Hardware	65	09-Mar-20	09-Jun-20	Fab & Available for D	elivery - Door Hardware				
Millwork & Finish	Carpentry									
PRO-3350 Own	ner Review/Approve RTA - Millwork & Finish Carpentry	3	07-Feb-20 A	12-Feb-20	Owner Review/Approve RTA - Millwork	& Finish Carpentry				
PRO-6720 Build	ling Commission Approves Contract - Millwork & Finish Carpentry	1	10-Mar-20	10-Mar-20	I Building Commission Approves Con	ntract - Millwork & Finish Carpentry				
PRO-3360 Awa	rd Contract - Millwork & Finish Carpentry	2	11-Mar-20	12-Mar-20	I Award Contract - Millwork & Finish	Carpentry	1			
PRO-3370 Exec	cute Contract - Millwork & Finish Carpentry	5	13-Mar-20	19-Mar-20	Execute Contract - Millwork & Fini	ish Carpentry	1 1 1			
PRO-3380 Subo	contractor Issue Submittals - Millwork Display Cases	25	20-Mar-20	24-Apr-20	Subcontractor Issue Submit	tals - Millwork Display Cases	1 1 1			
PRO-3390 Subo	contractor Issue Submittals - Millwork Wood Benches	25	20-Mar-20	24-Apr-20	Subcontractor Issue Submitt	tals - Millwork Wood Benches	 I I			
PRO-3400 Subo	contractor Issue Submittals - Millwork Countertops	25	20-Mar-20	24-Apr-20	Subcontractor Issue Submit	tals - Millwork Countertops				
PRO-3410 Subo	contractor Issue Submittals - Millwork Wood Veneer Casework	25	20-Mar-20	24-Apr-20	Subcontractor Issue Submit	tals - Millwork Wood Veneer Casework				
PRO-3420 Subo	contractor Issue Submittals - Millwork Plastic Laminate Casework	25	20-Mar-20	24-Apr-20	Subcontractor Issue Submit	tals - Millwork Plastic Laminate Casework				
PRO-3430 A/E	Review & Approve Submittals - Millwork Display Cases	15	27-Apr-20	15-May-20	A/E Review & Approve S	ubmittals - Millwork Display Cases				
	Review & Approve Submittals - Millwork Wood Benches	15	27-Apr-20	15-May-20	* *	ubmittals - Millwork Wood Benches				
	Review & Approve Submittals - Millwork Countertops	15	27-Apr-20	15-May-20		ubmittals - Millwork Couhtertops	1			
	Review & Approve Submittals - Millwork Wood Veneer Casework	15	27-Apr-20	15-May-20		ubmittals - Millwork Wood Veneer Casework	1			
	Review & Approve Submittals - Millwork Plastic Laminate Casework	15	27-Apr-20	15-May-20		ubmittals - Millwork Plastic Laminate Casework	1 1 1			
	& Available for Delivery - Millwork Display Cases	35	18-May-20	07-Jul-20		for Delivery - Millwork Display Cases	1 1 1			
	articulation for Delivery million Display Cases	00	10 May-20	07-00F20						
Remaining Le	vel of Effort Remaining Work		Dogo	3 of 16	TASK filtor: % Complete <100					
Actual Level of	-		Page	3 of 16	TASK filter: % Complete <100.		/ A			
	5					© Oracle Corporation	KA			
Actual Work	♦ Milestone				Page 75 of 377					

ty ID	Activity Name	Remaining	Start	Finish			
		Duration			2020 F Mar Apr M Jun Jul Aug S Oct	2021 N D Jan F Mar Apr M Jun Jul A S Oct	2022 N Dec Jan F Mar Apr M Jun Jul A S Oct N
PRO-3490	Fab & Available for Delivery - Millwork Wood Benches	35	18-May-20	07-Jul-20		or Delivery - Millwork Wood Benches	
PRO-3500	Fab & Available for Delivery - Millwork Wood Veneer Casework	35	18-May-20	07-Jul-20	Fab & Available f	or Delivery - Millwork Wood Veneer Casework	
PRO-3510	Fab & Available for Delivery - Millwork Plastic Laminate Casework	35	18-May-20	07-Jul-20	Fab & Available f	or Delivery - Millwork Plastic Laminate Casework	
PRO-3520	Fab & Available for Delivery - Millwork Countertops	40	18-May-20	14-Jul-20	Fab & Available	for Delivery - Millwork Countertops	
Laboratory	Casework						
PRO-5340	Owner Review/Approve RTA - Laboratory Casework	1	31-Jan-20 A	10-Feb-20	Owner Review/Approve RTA - Laborator		
PRO-6730	Building Commission Approves Contract - Laboratory Casework	1	11-Feb-20	11-Feb-20	Building Commission Approves Contract	t - Laboratory Casework	
PRO-5330	Award Contract - Laboratory Casework	2	12-Feb-20	13-Feb-20	Award Contract - Laboratory Casework		
PRO-5320	,	5	14-Feb-20	21-Feb-20	Execute Contract - Laboratory Casewo		
PRO-5370	,	20	24-Feb-20	20-Mar-20	Subcontractor Issue Submittals - I		
PRO-5360		15	23-Mar-20	10-Apr-20	A/E Review & Approve Submitt		
PRO-5350	Fab & Available for Delivery - Laboratory Casework	65	13-Apr-20	15-Jul-20	Fab & Available	for Delivery - Laboratory Casework	
	e Equipment						
PRO-3540	Owner Review/Approve RTA - Food Service Equipment	1	03-Feb-20 A	10-Feb-20	Owner Review/Approve RTA - Food Ser		
PRO-6740		1	11-Feb-20	11-Feb-20	Building Commission Approves Contract		
PRO-3550		2	12-Feb-20	13-Feb-20	Award Contract - Food Service Equipm		
PRO-3560	Execute Contract - Food Service Equipment	5	14-Feb-20	21-Feb-20	Execute Contract - Food Service Equi		
PRO-3570		20	02-Mar-20	27-Mar-20	Subcontractor Issue Submittals -		
PRO-3590		20	02-Mar-20	27-Mar-20	Subcontractor Issue Submittals -		
PRO-3600	The second s	15	30-Mar-20	17-Apr-20	🔲 A/E Review & Approve Submi		
PRO-3620		15	30-Mar-20	17-Apr-20		ttals - Hopd System (Make Up Air Exhaust)	
PRO-3630	, , , , , , , , , , , , , , , , , , ,	65	21-Apr-20	22-Jul-20		e for Deliγery - Hood System (Make Up Air Exhaust)	
PRO-3640	Fab & Available for Delivery - Food Service Equipment	65	21-Apr-20	22-Jul-20	Fab & Availabl	e for Deliγery - Food Service Equipment	
Overhead D	oors & Fire Shutters						
PRO-5400	Award Contract - Overhead Doors & Fire Shutters	5	19-Dec-19 A	14-Feb-20	Award Contract - Overhead Doors & Fi	re Shutters	
PRO-5390	Execute Contract - Overhead Doors & Fire Shutters	5	18-Feb-20	24-Feb-20	Execute Contract - Overhead Doors &	& Fire Shutters	
PRO-5440	Subcontractor Issue Submittals - Overhead Doors & Fire Shutters	20	25-Feb-20	23-Mar-20	Subcontractor Issue Submittals -		
PRO-5430	A/E Review & Approve Submittals - Overhead Doors & Fire Shutters	15	24-Mar-20	13-Apr-20		tals - Overhead Doors & Fire Shutters	
PRO-5420	Fab & Available for Delivery - Overhead Doors & Fire Shutters	65	14-Apr-20	16-Jul-20	Fab & Available	for Delivery - Overhead Doors & Fire Shutters	
Epoxy Floo							
PRO-3840	1, , , , , , , , , , , , , , , , , , ,	20	05-Feb-20 A	09-Mar-20	Subcontractor Issue Submittals - Ep		
PRO-3850		15	10-Mar-20	30-Mar-20	A/E Review & Approve Submittal		
PRO-3860	Fab & Available for Delivery - Epoxy Flooring	25	31-Mar-20	05-May-20	Fab & Available for Deliver	y - Epoxy Flooring	
Carpet							
	Subcontractor Issue Submittals - Carpet	10	14-Jan-20 A	24-Feb-20	Subcontractor Issue Submittals - Carr		
PRO-3920	A/E Review & Approve Submittals - Carpet	15	25-Feb-20	16-Mar-20	A/E Review & Approve Submittals		
PRO-3930	Fab & Available for Delivery - Carpet	40	17-Mar-20	12-May-20	Fab & Available for Delive	ry - Carpet	
Site Concre							
PRO-5550		5	10-Feb-20	14-Feb-20	Owner Review/Approve RTA - Site Con	crete	
PRO-6850	Building Commission Approves Contract - Site Concrete	1	10-Mar-20	10-Mar-20	I Building Commission Approves Con	tract - Site Concrete	
PRO-5540	Award Contract - Site Concrete	2	11-Mar-20	12-Mar-20	Award Contract - Site Concrete		
PRO-5530	Execute Contract - Site Concrete	5	13-Mar-20	19-Mar-20	Execute Contract - Site Concrete		
PRO-5580	Subcontractor Issue Submittals - Site Concrete	15	20-Mar-20	09-Apr-20	Subcontractor Issue Submittal		
PRO-5570		15	10-Apr-20	01-May-20	A/E Review & Approve Sub		
PRO-5560	Fab & Available for Delivery - Site Concrete	20	04-May-20	01-Jun-20	Fab & Available for De	livery - Site Concrete	
Specialties							
PRO-6860	Building Commission Approves Contract - Specialties	1	11-Feb-20	11-Feb-20	Building Commission Approves Contract	t - Specialties	
PRO-4100		2	12-Feb-20	13-Feb-20	Award Contract - Specialties		
PRO-4110		5	14-Feb-20	21-Feb-20	Execute Contract - Specialties		
PRO-4120		20	24-Feb-20	20-Mar-20	Subcontractor Issue Submittals -		
	A/E Review & Approve Submittals - Specialties	15	23-Mar-20	10-Apr-20	A/E Review & Approve Submitt		
	Fab & Available for Delivery - Specialties	30	13-Apr-20	26-May-20	Fab & Available for Deli	very - Specialties	
Window Tre							
	Owner Review/Approve RTA - Window Treatments	1	06-Feb-20 A	10-Feb-20	Owner Review/Approve RTA - Window		
PRO-6870	Building Commission Approves Contract - Window Treatments	1	11-Feb-20	11-Feb-20	Building Commission Approves Contract	t - Window Treatments	
Remain	ning Level of Effort Remaining Work		Pana	4 of 16	TASK filter: % Complete <100.		
	Level of Effort Critical Remaining Work		i age			© Oracle Corporation	CIZANICIZA
- Actual I							SKANSKA

-	School - Project C - 10Feb20 R1 Schedule Update - 1318015-CR - B22				Detailed Schedule Data Date: 10-Feb-20 / Run Date: 09-Jul-20 08:54
Activity ID		aining	Start	Finish	2020 2021 2022 J23
		ation			F Mar Apr M Jun Jul Aug S Oct N D Jan F Mar Apr M Jun Jul A S Oct N Dec Jan A S Oct N Dec Jan Apr Apr M Dec Jan Apr Apr M Dec Jan Apr Apr Apr M Dec Jan Apr A
PRO-4380	O Award Contract - Window Treatments	2	12-Feb-20	13-Feb-20	Award Contract - Window Treatments
PRO-4390	D Execute Contract - Window Treatments	5	14-Feb-20	21-Feb-20	Execute Contract - Window Treatments
PRO-4400	O Subcontractor Issue Submittals - Window Treatments	20	24-Feb-20	20-Mar-20	Subcontractor Issue Submittals - Window Treatments
PRO-4410	A/E Review & Approve Submittals - Window Treatments	15	23-Mar-20	10-Apr-20	A/E Review & Approve Submittals - Window Treatments
		20	13-Apr-20	11-May-20	Fab & Available for Delivery - Window Treatments
Signage		-			
	0 Building Commission Approves Contract - Signage	1	11-Feb-20	11-Feb-20	Building Commission Approves Contract - Signage
		2	12-Feb-20	13-Feb-20	Award Contract - Signage
PRO-4460		5	14-Feb-20	21-Feb-20	Execute Contract - Signage
		20	24-Feb-20	20-Mar-20	Subcontractor Issue Submittals - Signage
		15	23-Mar-20	10-Apr-20	A/E Review & Approve Submittals - Signage
		40	13-Apr-20	09-Jun-20	Fab & Available for Delivery - Signage
Landscapi			10740-20		
		3	06-Feb-20 A	12-Feb-20	Owner Review/Approve RTA - Landscaping
PRO-6890		1	10-Mar-20	10-Mar-20	Building Commission Approves Contract - Landscaping
	Award Contract - Landscaping	2	11-Mar-20	12-Mar-20	Award Contract - Landscaping
PRO-4030		5	13-Mar-20	12-Mar-20	Execute Contract - Landscaping
		15	20-Mar-20	09-Apr-20	Subcontractor Issue Submittals - Landscaping
		15	10-Apr-20	09-Apr-20 01-May-20	A/E Review & Approve Submittals - Landscaping
		50	•	-	
Final Clear	, , , , , , , , , , , , , , , , , , , ,	0	04-May-20	14-Jul-20	Fab & Available for Delivery - Landscaping
		1	21 Jan 20 A	10 Eab 20	Ourset Daviau/Approva DTA Findl Cleaning
	O Owner Review/Approve RTA - Final Cleaning	1	31-Jan-20 A	10-Feb-20	Owner Review/Approve RTA - Final Cleaning
	D Building Commission Approves Contract - Final Cleaning	1	11-Feb-20	11-Feb-20	Building Commission Approves Contract - Final Cleaning
	0 Award Contract - Final Cleaning	2	12-Feb-20	13-Feb-20	Award Contract - Final Cleaning
	D Execute Contract - Final Cleaning	5	14-Feb-20	21-Feb-20	Execute Contract - Final Cleaning
	5	20	24-Feb-20	20-Mar-20	Subcontractor Issue Submittals - Final Cleaning
		15	23-Mar-20	10-Apr-20	A/E Review & Approve Submittals - Final Cleaning
		10	13-Apr-20	27-Apr-20	Fab & Available for Delivery - Final Cleaning
Mockups					
Exterior Fa	acade				
MOCK-100	0 Prepare & Submit - Framing - Exterior Mockup	10	10-Feb-20	24-Feb-20	Prepare & Submit - Framing - Exterior Mockup
		10	10-Feb-20	24-Feb-20	Prepare & Submit - HSS Steel - Exterior Mockup
MOCK-106	0 Prepare & Submit - Sheathing - Exterior Mockup	10	10-Feb-20	24-Feb-20	Prepare & Submit - Sheathing - Exterior Mockup
		10	10-Feb-20	24-Feb-20	Prepare & Submit - AVB/Insulation - Exterior Mockup
		10	10-Feb-20	24-Feb-20	Prepare & Submit - Curtain Wall - Exterior Mockup
MOCK-115	0 Prepare & Submit - Granite/Limestone - Exterior Mockup	10	10-Feb-20	24-Feb-20	Prepare & Submit - Granite/Limestone - Exterior Mockup
		10	10-Feb-20	24-Feb-20	Prepare & Submit - Brick - Exterior Mockup
		10	10-Feb-20	24-Feb-20	Prepare & Submit - Masonry Exterior Sealants - Exterior Mockup
		10	10-Feb-20	24-Feb-20	Prepare & Submit - JK Glass Exterior Sealants - Exterior Mockup
		10	10-Feb-20	24-Feb-20	Prepare & Submit - Roof Cap - Exterior Mockup
		10	10-Feb-20	24-Feb-20	Prepare & Submit - Waterproofing Exterior Sealants - Exterior Mock up
		10	25-Feb-20	09-Mar-20	Review & Approve - Framing - Exterior Mockup
		10	25-Feb-20	09-Mar-20	Review & Approve - HSS Steel - Exterior Mockup
		10	25-Feb-20	09-Mar-20	Review & Approve - Sheathing - Exterior Mockup
		10	25-Feb-20	09-Mar-20	Review & Approve - AVB/Insulation - Exterior Mockup
		10	25-Feb-20	09-Mar-20	Review & Approve - Curtain Wall - Exterior Mockup
		10	25-Feb-20	09-Mar-20	Review & Approve - Curtain Wair - Exterior Mockup
		10	25-Feb-20	09-Mar-20	Review & Approve - Brick - Exterior Mockup
4		10	25-Feb-20 25-Feb-20	09-Mar-20	Review & Approve - Masonry Exterior Sealants - Exterior Mockup
		10	25-Feb-20 25-Feb-20	09-Mar-20	 Review & Approve - JK Glass Exterior Sealants - Exterior Mockup Review & Approve - JK Glass Exterior Sealants - Exterior Mockup
		10	25-Feb-20 25-Feb-20	09-Mar-20	Review & Approve - SK Glass Exterior Sealarits - Exterior Mockup
		10		09-Mar-20 09-Mar-20	Review & Approve - Rool Cap - Exterior Mockup
		-	25-Feb-20		
	, , , , , , , , , , , , , , , , , , , ,	5 5	10-Mar-20 10-Mar-20	16-Mar-20 16-Mar-20	 Fab & Available for Delivery - Framing - Exterior Mockup Fab & Available for Delivery - Sheathing - Exterior Mockup
MOCK-108	Fab & Available for Delivery - Sheathing - Exterior Mockup	5	10-Mar-20	16-1417-20	
Domo	ining Level of Effort Remaining Work		D	E of 10	TASK filter: % Complete <100
			Page	5 of 16	TASK filter: % Complete <100.
	I Level of Effort Critical Remaining Work				© Oracle Corporation
Actua	I Work Milestone				Page 77 of 377
L					

rookline High School - Project C - 10Feb20 R1 Schedule Update - 1318015-CR - B22	Remaining	Start	Finish	Detailed Schedule	Data Date: 10-Feb-20 / Run Date: 09-Jul-20 08:54
	Duration	Start	1 111511	2020 F Mar Apr M Jun Jul Aug S Oct N D Jan F Mar Apr M Jun Jul A S Oct	2022 N Dec Jan F Mar Apr M Jun Jul A S Oct N De
MOCK-1110 Fab & Available for Delivery - AVB/Insulation - Exterior Mockup	5	10-Mar-20	16-Mar-20	 Fab & Available for Delivery - AVB/Insulation - Exterior Mockup 	
MOCK-1280 Fab & Available for Delivery - Roof Cap - Exterior Mockup	5	10-Mar-20	16-Mar-20	Fab & Available for Delivery - Roof Cap - Exterior Mockup	
MOCK-1170 Fab & Available for Delivery - Granite/Limestone - Exterior Mockup	10	10-Mar-20	23-Mar-20	Fab & Available for Delivery - Granite/Limestone - Exterior Mockup	
MOCK-1200 Fab & Available for Delivery - Brick - Exterior Mockup	10	10-Mar-20	23-Mar-20	Fab & Available for Delivery - Brick - Exterior Mockup	
MOCK-1225 Fab & Available for Delivery - Masonry Exterior Sealants - Exterior Mockup	10	10-Mar-20	23-Mar-20	Fab & Available for Delivery - Masonry Exterior Sealants - Exterior Mockup	
MOCK-1250 Fab & Available for Delivery - JK Glass Exterior Sealants - Exterior Mockup	10	10-Mar-20	23-Mar-20	Fab & Available for Delivery - JK Glass Exterior Sealants - Exterior Mockup	
MOCK-1310 Fab & Available for Delivery - Waterproofing Exterior Sealants - Exterior Mockup	10	10-Mar-20	23-Mar-20	■ Fab & Available for Delivery - Waterproofing Exterior Seatants - Exterior Mockup	
MOCK-1050 Fab & Available for Delivery - HSS Steel - Exterior Mockup	20	10-Mar-20	06-Apr-20	Fab & Available for Delivery - HSS Steel - Exterior Mockup	
MOCK-1140 Fab & Available for Delivery - Curtain Wall - Exterior Mockup	30	10-Mar-20	21-Apr-20	Fab & Available for Delivery - Curtain Wall - Exterior Mockup	
MOCK-1320 Pre-Installation Meeting - Exterior Mockup	1	06-Apr-20*	06-Apr-20	I Pre-Installation Meeting - Exterior Mockup	
MOCK-1330 Install Perimeter Fence - Exterior Mockup	1	22-Apr-20	22-Apr-20	Install Perimeter Fence - Exterior Mockup	
MOCK-1340 FRP & Strip Concrete Anchor Pad - Exterior Mockup	5	23-Apr-20	29-Apr-20	FRP & Strip Concrete Anchor Pad - Exterior Mockup	
	2	•	· ·	Install LGMF & Bracing - Exterior Mockup	
MOCK-1350 Install LGMF & Bracing - Exterior Mockup	2	30-Apr-20	01-May-20		
MOCK-1360 Install Tube Steel & Relieving Angle - Exterior Mockup	1	04-May-20	04-May-20	Install Tube Steel & Relieving Angle Exterior Mockup	
MOCK-1370 Install Sheathing - Exterior Mockup	1	05-May-20	05-May-20	Install Sheathing - Exterior Mockup	
MOCK-1380 Install AVB - Exterior Mockup	2	06-May-20	07-May-20	Install AVB - Exterior Mockup	
MOCK-1390 Install Thermal Insulation - Exterior Mockup	1	08-May-20	08-May-20	Install Thermal Insulation - Exterior Mockup	
MOCK-1400 Install Curtain Wall Frames - Exterior Mock up	2	11-May-20	12-May-20	I Install Curtain Wal Frames - Exterior Mock up	
MOCK-1410 Install Exterior Glazing Frames - Exterior Mockup	1	13-May-20	13-May-20	Install Exterior Glazing Frames - Exterior Mockup	
MOCK-1420 Install Punch Windows Frames - Exterior Mockup	1	14-May-20	14-May-20	I Instal Punch Windows Frames - Exterior Mockup	
MOCK-1430 Install Exterior Glazing - Exterior Mockup	1	15-May-20	15-May-20	I Install Exterior Glazing - Exterior Mockup	i
MOCK-1440 Install Granite Base - Exterior Mockup	1	18-May-20	18-May-20	I Install Granite Base - Exterior Mockup	
MOCK-1450 Install Brick & Limestone Cornice - Exterior Mockup	5	19-May-20	26-May-20	Install Brick & Limestone Cornice - Exterior Mockup	
MOCK-1460 Washdown Brick - Exterior Mock up	1	27-May-20	27-May-20	I Washdown Brick - Exterior Mock up	
MOCK-1470 Install Exterior Sealents & Control Joints - Exterior Mockup	1	28-May-20	28-May-20	I Install Exterior Sealents & Control Joints - Exterior Mockup	
MOCK-1480 Install Roof & Cap - Exterior Mockup	2	29-May-20	01-Jun-20	Install Roof & Cap - Exterior Mockup	
MOCK-1490 Architect Review & Approve - Exterior Mockup	15	02-Jun-20	22-Jun-20	Architect Review & Approve - Exterior Mockup	
MEP Coordination					
Basement					
		04 Dec 40 A	14 Est 00	Review & Approve MEPs - Basement	
MEP-3030 Review & Approve MEPs - Basement		31-Dec-19 A			
MEP-3040 Fab & Deliver - Duct & Pipe - Basement	15	17-Mar-20	06-Apr-20	Fab & Deliver - Duct & Pipe - Basement	
Level 1					
MEP-3050 Coordinate MEPs - L1				Coordinate MEPs - L1	
MEP-3060 Review & Approve MEPs - L1	5	14-Feb-20	21-Feb-20	Review & Approve MEPs - L1	
MEP-3070 Fab & Deliver - Duct & Pipe - L1	15	31-Mar-20	21-Apr-20	Fab & Deliver - Duct & Pipe - L1	
Level 2					
MEP-3080 Coordinate MEPs - L2	9	04-Dec-19 A	21-Feb-20	Coordinate MEPs + L2	
MEP-3090 Review & Approve MEPs - L2	5	24-Feb-20	28-Feb-20	Review & Approve MEPs - L2	
MEP-3100 Fab & Deliver - Duct & Pipe - L2	15	14-Apr-20	05-May-20	Fab & Deliver - Duct & Pipe - L2	
Level 3					
MEP-3110 Coordinate MEPs - L3	30	13-Feb-20*	26-Mar-20	Coordinate MEPs - L3	
MEP-3120 Review & Approve MEPs - L3	5	27-Mar-20	02-Apr-20	Review & Approve MEPs - L3	
MEP-3130 Fab & Deliver - Duct & Pipe - L3	15	29-Apr-20	19-May-20	Fab & Deliver - Duct & Pipe - L3	
			10 May-20		
Construction Summary					
Project C - STEM Wing					
SUM-1090 Summary - Sitework & Foundations	37	08-Nov-19 A	01-Apr-20	Summary - Sitework & Foundations	
SUM-1100 Summary - Erect Structural Steel	44	16-Mar-20	15-May-20	Summary - Erect Structural Steel	
SUM-1120 Summary - Detail & Deck Structural Steel	55	23-Mar-20	09-Jun-20	Summary - Detail & Deck Structural Steel	
SUM-1130 Summary - Prep & Place Slabs on Deck	40	21-Apr-20	16-Jun-20	Summary - Prep & Place Slabs on Deck	
SUM-1140 Summary - Level 1 Slab on Grade	30	20-May-20	01-Jul-20	Summary - Level 1 Slab on Grade	
SUM-1150 Summary - Spray Fireproofing	23	15-Jun-20	16-Jul-20	Summary - Spray Fireproofing	
SUM-1160 Summary - Exterior Facade	170	29-Jun-20	05-Mar-21	Summary - Exterior Facade	
SUM-1170 Summary - MEP & Architectural Rough-in	84	07-Jul-20	03-Nov-20	Summary - MEP & Architectural Rough-in	
Remaining Level of Effort Remaining Work		Page	6 of 16	TASK filter: % Complete <100.	
Actual Level of Effort Critical Remaining Work		Faye		© Oracle Corporation	CIZANICIZA
Ū Ū					SKANSKA
Actual Work				Page 78 of 377	

-	ol - Project C - 10Feb20 R1 Schedule Update - 1318015-CR - B22		Otest		Detailed Schedule					Data Date: 10-Feb-20 / Run Date: 09-Jul-20 08:54		
vity ID Ac	ctivity Name	Remaining Duration	Start	Finish	2020		2021 2022					
		2 41 44 611			F Mar Apr M Jun Jul Aug S Oct			M Jun		Oct N Dec Jan F Mar Apr M Jun Jul A S Oc	T N T	
	ummary - Building Temp Tight	0		30-Oct-20		Summary -	- Building Temp T	ight				
	ummary - Interior Drywall & Finishes	114	02-Nov-20	20-Apr-21				Summary	- Interior Dryv	vall & Finishes		
SUM-1240 Su	ummary - Final Inspections & C of O	34	10-Mar-21	27-Apr-21				Summar	/ - Final Inspe	ctions & C of O		
SUM-1260 Su	ummary - Complete Punch List	20	13-Apr-21	11-May-21		 !		 Summa 	ary - Complete	e Punch List		
SUM-1250 Su	ummary - STEM Interim Completion Date	0		27-Apr-21			•	Summary	/- STEM Inte	rim Completion Date		
SUM-1270 Su	ummary - Move-in	10	28-Apr-21	11-May-21				Summa	ary - Move-in			
Construction			·					1	-			
								1				
Project C - STEI	-					l						
Enabling & Abat												
Misc. Enabling				1								
	elocate Overhead High Voltage Wires (by Owner)	5	28-Jan-20 A	14-Feb-20	Relocate Overhead High Voltage Wires	(by Owner)						
Sitework & Four	ndations											
Basement				1								
FOUND-1 Wa	aterproof Foundation Walls - Basement	5	27-Jan-20 A									
FOUND-1 Ba	ackfill Foundation Wals - Basement	14	07-Feb-20 A	28-Feb-20	Backfill Foundation Wals - Basemen							
Upper Foundat												
FOUND-1 Ex	xcavate, Fill & Prep for Upper Footings	5	27-Feb-20	04-Mar-20	Excavate, Fill & Prep for Upper Foo	tings						
FOUND-1 Re	e-Route Plumbing Lines	5	27-Feb-20	04-Mar-20	Re-Route Plumbing Lines							
FOUND-1 De	emo Existing MH & Plumbing Lines	2	05-Mar-20	06-Mar-20	I Demo Existing MH & Plumbing Lines	; ·····						
FOUND-1 FF	RP Upper Footings & Mat Slab	10	05-Mar-20	18-Mar-20	FRP Upper Footings & Mat Slab							
FOUND-1 FF	RP Upper Foundation Walls	15	12-Mar-20	01-Apr-20	FRP Upper Foundation Walls	1						
FOUND-1 Wa	aterproof Upper Foundations	10	26-Mar-20	08-Apr-20	📕 Waterproof Upper Foundations	;						
	ackfill Upper Foundations	10	31-Mar-20	13-Apr-20	Backfill Upper Foundations							
Basement Slab	••			•								
	xcavate & Install Underslab Utiltites & Drainage System - Basement	15	12-Feb-20*	04-Mar-20	Excavate & Install Underslab Utiltites	& Drainadoe	System - Basen	nent				
	rep & Place Slab on Grade - Basement	5	05-Mar-20	11-Mar-20	Prep & Place Slab on Grade - Base	-						
Structure			00 11101 20									
STRUCT-1 Mc	ohilize Crane	2	12-Mar-20	13-Mar-20	Mobilize Crane			1				
	rect Structural Steel	44	16-Mar-20	15-May-20	Erect Structural Steel							
	etail & Deck Steel	55	23-Mar-20	09-Jun-20	Detail & Deck Steel							
Level 1 & Level			23-10101-20	09-3011-20								
	rect Structural Steel & Planks - L1 & L2 Partial (Seq 1 & 3)	5	16-Mar-20	20-Mar-20	Erect Structural Steel & Planks - I	1 8 2 Dorti	al(Soc 1.82)					
		20			Detail & Deck Steel & Planks	1						
	etail & Deck Steel & Planks - L1 & L2 Partial (Seg 1 & 3)		23-Mar-20	17-Apr-20			(/					
	rep & Place Slab on Deck - L1 & L2 Partial (Seq 1 & 3)	5	21-Apr-20	27-Apr-20	Prep & Place Slab on Deck		intial (Seq 1 & S)					
	stall Relieving Angles - L1	5	29-Apr-20	05-May-20	Install Relieving Angles - L	I						
Level 2			44.4 00	04.4 00								
	rect Structural Steel & Precast Planks - L2	5	14-Apr-20	21-Apr-20	Erect Structural Steel & Prec	1						
	etail & Deck Steel / Grout Precast Planks - L2	20	22-Apr-20	19-May-20	Detail & Deck Steel / Gr		rianks - L2					
	rep & Place Slab on Deck - L2	5	20-May-20	27-May-20	Prep & Place Slab on D							
	stall Relieving Angles - L2	5	20-May-20	27-May-20	Install Relieving Angles	- L2		1				
Level 3		i i										
	rect Structural Steel - L3	7	22-Apr-20	30-Apr-20	Erect Structural Steel - L3	 						
	etail & Deck Steel - L3	20	01-May-20	29-May-20	Detail & Deck Steel - L							
	rep & Place Slab on Deck - L3	5	01-Jun-20	05-Jun-20	Prep & Place Slab on							
STRUCT- Ins	stall Relieving Angles - L3	5	01-Jun-20	05-Jun-20	Install Relieving Angle	s - L3						
Roof						 						
STRUCT- Er	rect Structural Steel - Roof	7	01-May-20	11-May-20	Erect Structural Steel - R	oof						
STRUCT- Er	rect Structural Steel for Roof Screen - Roof	4	12-May-20	15-May-20	Erect Structural Steel for	Roof Screer	n - Roof	1				
STRUCT- De	etail & Deck Steel - Roof	20	12-May-20	09-Jun-20	Detail & Deck Steel -	Roof						
STRUCT- Pro	rep & Place Slab on Deck - Roof	5	10-Jun-20	16-Jun-20	Prep & Place Slab of the state of the sta	n Deck - Ro	of	1				
	stall Roof Dunnage - Roof	5	17-Jun-20	23-Jun-20	Install Roof Dunna			1				
Level 1 Slab on	-	1				- '		1				
	xcavate & Install Underslab Utiltites & Drainage System - L1	20	20-May-20	17-Jun-20	Excavate & Install L	Inderslah	iltites & Drainage	System -	L1			
	rep & Place Slab on Grade - L1	10	18-Jun-20	01-Jul-20	Prep & Place Slal			-,5.6/11				
							<u> </u>					
Remaining I	Level of Effort Remaining Work		Paga	7 of 16	TASK filter: % Complete <100.							
Actual Leve			Faye	, 01 10				cle Corpora	ation	CI/ALICI/A		
	5				Dage 70 of 277		S Old			SKANSKA		
Actual Work	k 🔶 🔶 Milestone				Page 79 of 377							

Kline High School - Project C - 10Feb20 R1 Schedule Update - 1318015-CR - B22 ID Activity Name	Remaining	Start	Finish			
	Duration	Start	1 111511	2020	2021	2022
				F Mar Apr M Jun Jul Aug S Oct N	D Jan F Mar Apr M Jun Jul A S	Oct N Dec Jan F Mar Apr M Jun Jul A S Oct N
Layout & Install Top Track L1-3000 Layout & Install Top Track - L2	5	08-Jun-20	12-Jun-20	Layout & Install Top Track		
L1-3010 Layout & Install Top Track - L2 L1-3010 Layout & Install Top Track - Basement	2	15-Jun-20	12-Jun-20	Layout & Install Top Track		
L1-3020 Layout & Install Top Track - Basement L1-3020 Layout & Install Top Track - L3	5	15-Jun-20 17-Jun-20	23-Jun-20	Layout & Install Top Track		
L1-3030 Layout & Install Top Track - L1	5	02-Jul-20	09-Jul-20	Layout & Install Top Trac		······
Spray Fireproofing	5	02-Jui-20	09-Jul-20			
SPF-1010 Spray Fireproof - L2	5	15-Jun-20	19-Jun-20	Spray Fireproof - L2		
SPF-1030 Spray Fireproof - Basement	2	22-Jun-20	23-Jun-20	Spray Fireproof - Baseme	anti	
SPF-1020 Spray Fireproof - L3	5	22-Jun-20 24-Jun-20	30-Jun-20	Spray Fireproof - L3		
SPF-1020 Spray Fireproof - L1	5	10-Jul-20	16-Jul-20	Spray Fireproof - L1		·
	5	10-Jui-20	TO-JUE20	Spray Fileprool - LT		
Stairs ST-1000 Install - Stair 1	E	12 May 20	10 May 20	Install - Stair 1		
	5	13-May-20	19-May-20	Install - Stall 1		
ST-1010 Install - Stair 2	15	20-May-20	10-Jun-20			
ST-1020 Install - Stair 3	15	04-Jun-20	24-Jun-20	Install - Stair 3		÷
Roofing	45	47 1	00 1.1 00			
RF-1010 Frame & Sheath Roof Parapet	15	17-Jun-20	08-Jul-20	Frame & Sheath Roof I		
RF-1040 Frame & Sheath Clerestory Light Monitor	10	01-Jul-20	15-Jul-20	Frame & Sheath Clere		
RF-1000 Temp-in Roofs / Install Roof AVB	15	09-Jul-20	29-Jul-20	Temp-in Roofs / Ins		
RF-1050 Install Roofing at Clerestory Light Monitor	5	16-Jul-20	22-Jul-20	Install Roofing at Cle		······································
RF-1060 Install Sill Flashing & Curtain Wall at Light Monitor	10	23-Jul-20	05-Aug-20		& Curtain Wall at Light Monitor	
RF-1020 Install Roof Screens	20	18-Aug-20	15-Sep-20	Install Roof		
RF-1030 Install Permanent Roof - Roof Level	15	16-Sep-20	06-Oct-20		ermanent Roof - Roof Level	
RF-1070 Install Stair at Roof	5	07-Oct-20	14-Oct-20		Stair at Roof	
RF-1080 Install Roof Pavers	5	15-Oct-20	21-Oct-20	I Install	Rdof Pavers	<u>.</u>
Exterior Facade						
EXT-1000 Frame Exterior Walls	45	29-Jun-20	31-Aug-20	Frame Exterio		
EXT-105 Sheath Exterior Walls	40	15-Jul-20	09-Sep-20	Sheath Exter		
EXT-1010 AVB Exterior Walls	34	29-Jul-20	15-Sep-20	AVB Exterior		
EXT-1040 Install Curtain Wall	58	10-Aug-20	30-Oct-20		ıll Curtain Wal	
EXT-1020 Stage Exterior Walls	48	31-Aug-20	06-Nov-20	Sta	ge Exterior Walls	
EXT-1030 Install Stone & Brick / Washdown / Remove Staging	74	21-Sep-20	08-Jan-21		Install Stone & Brick / Washdown / Rem	no ve Staging
EXT-1050 Building Temp Tight	0		30-Oct-20	♦ Build	ling Temp Tight	
North Elevation						
N-1000 Frame Exterior Walls - North Elevation	18	29-Jun-20	23-Jul-20	Frame Exterior Walk	s - North Elevation	
N-1010 Sheath Exterior Walls - North Elevation	12	15-Jul-20	30-Jul-20	Sheath Exterior Wa		
N-1020 Install AVB - North Elevation	7	29-Jul-20	06-Aug-20	Install AVB - North	Elevation	
N-1030 Prep Openings for Curtain Wall - North Elevation	10	03-Aug-20	14-Aug-20	Prep Openings for	or Çurtain Wall - North Elevation	
N-1040 Install Curtain Wall - North Elevation	23	10-Aug-20	10-Sep-20	Install Curtai	n Wall - North ⊟evation	
N-1050 Install Staging - North Elevation	15	31-Aug-20	21-Sep-20	Install Stag	ing - North Elevation	
N-1060 Install Stone - North Elevation	4	15-Sep-20	18-Sep-20	Install Ston	e - North Elevation	
N-1070 Install Brick - North Elevation	23	22-Sep-20	23-Oct-20	Install	Brick - North Elevation	
N-1080 Washdown Masonry - North Elevation	10	16-Oct-20	29-Oct-20	🗖 Was	hdown Masonry - North Elevation	
N-1090 Remove Staging - North Elevation	10	23-Oct-20	05-Nov-20	🗖 Rer	nove Staging - North Elevation	
N-1100 Caulk Facade - North Elevation	6	06-Nov-20	16-Nov-20		aulk Facade - North Elevation	
South & West Elevations	/					
S-1000 Frame Exterior Walls - South & West Elevations	26	14-Jul-20	18-Aug-20	Frame Exterior \	Walls - South & West Elevations	
S-1010 Sheath Exterior Walls - South & West Elevations	17	03-Aug-20	25-Aug-20	Sheath Exterior	Walls - South & West Elevations	
S-1020 Install AVB - South & West Elevations	12	17-Aug-20	01-Sep-20		outh & West Elevations	
S-1030 Prep Openings for Curtain Wall - South & West Elevations	10	26-Aug-20	09-Sep-20		gs for Curtain Wall - South & West Elevations	
S-1040 Install Curtain Wall - South & West Elevations	25	03-Sep-20	08-Oct-20		urtain Wall - South & West Elevations	
S-1050 Install Staging - South & West Elevations	15	25-Sep-20	16-Oct-20		Staging - South & West Elevations	
S-1070 Install Brick - South & West Elevations	38	20-Oct-20	15-Dec-20		Install Brick - South & West Elevations	
S-1080 Washdown Masonry - South & West Elevations	10	08-Dec-20	21-Dec-20		Washdown Masonry - South & West Elev	ations
S-1090 Remove Staging - South & West Elevations	10	15-Dec-20	29-Dec-20		Remove Staging - South & West Elevation	
S-1100 Caulk Facade - South & West Elevations	10	30-Dec-20	13-Jan-21		Caulk Facade - South & West Elevation	
Remaining Level of Effort Remaining Work		Page	8 of 16	TASK filter: % Complete <100.		
Actual Level of Effort Critical Remaining Work					© Oracle Corporation	SKANSKA
Actual Work	1				1	

<u> </u>	hool - Project C - 10Feb20 R1 Schedule Update - 1318015-CR - B22	Remaining	Start	Finish	Detailed Schedule Data Date: 10-Feb-20 / Run Date: 09-Jul-20 08:54			
U	Activity Name	Duration	Start	FILIST	2020	2021	2022	
					F Mar Apr M Jun Jul Aug S Oct N D	Jan F Mar Apr M Jun Jul A S	Oct N Dec Jan F Mar Apr M Jun Jul A S Oct	
East Elevation			44.4.00					
	Frame Exterior Walls & Canopy- East Elevation	15	11-Aug-20	31-Aug-20		Valls & Canopy - East Elevation		
	Sheath Exterior Walls & Canopy - East Elevation	10	26-Aug-20	09-Sep-20		Walls & Canopy - East Elevation		
	Install AVB - East Elevation	1	04-Sep-20	15-Sep-20	Install AVB - E		······	
	Prep Openings for Curtain Wall - East Elevation	10	16-Sep-20	29-Sep-20		ngs for Curtain Wall - East ⊟evation		
E-1040	Install Curtain Wal - East Elevation	23	29-Sep-20	30-Oct-20		Curtain Wal - East Elevation		
	Install Staging - East Elevation	5	02-Nov-20	06-Nov-20		Staging - East Elevation		
	Install Stone - East Elevation	3	16-Dec-20	18-Dec-20		Install Stone - East Elevation		
	Install Brick - East Elevation	8	21-Dec-20	31-Dec-20		Install Brick - East Elevation	÷	
	Washdown Masonry - East Elevation	3	04-Jan-21	06-Jan-21 08-Jan-21		Washdown Masonry - East Elevation		
	Remove Staging - East Elevation	2	07-Jan-21	08-Jan-21 08-Feb-21		Remove Staging - East Elevation Install Metal Panels at Canopy - Ea		
	Install Metal Panels at Canopy - East Elevations	20	11-Jan-21					
-	Install Metal Column Enclosures - East Elevation	10	09-Feb-21	23-Feb-21		Install Metal Column Enclosures	· · · · · · · · ·	
	Caulk Facade - East Elevation	8	24-Feb-21	05-Mar-21		Caulk Facade - East Elevation	·····	
Elevators	Build Elevator Shaft	20	17 101 20	12 Aug 20	Duild Elevator Shaff			
	Install Elevator	20 60	17-Jul-20 14-Aug-20	13-Aug-20 09-Nov-20	Build Elevator Shaft			
IEP Systems		00	14-Aug-20	09-1100-20				
-	Build Wals - Basement Level Mechanical & Electrical Rooms	15	24-Jun-20	15-Jul-20	Ruid Wals Basement	│ Level Mechanical & ⊟ectrical Rooms		
	FRP Equipment Pads - Basement Level Mechanical & Electrical Rooms	5	09-Jul-20	15-Jul-20		Basement Level Mechanical & Electrical Rooms		
Hot Water	TRE Equipment Faus - Dasement Level Mechanical & Liectrical Rooms	J	09-30-20	13-30-20			51115	
Basement								
	Rig & Set Heat Exchanger (HEX-1.1), Expansion Tanks (ET-1/2) & Pumps (HHWP-1.1/1.2)	2	16-Jul-20	17-Jul-20	Dig & Sat Haat Evolution	ubr (HEX 1.1) Expansion Tanka (ET 1/2) 8	Pumps (HHWP-1.1/1.2) - Hot Water System	
	Install Mechanical Piping to Exchanger (HEX-1.1), Expansion Tanks (E1-1/2) & Pumps (HHVP-1.1/1.2)	2	20-Jul-20	14-Aug-20			anks (ET-1/2) & Pumps (HHWP-1.1/1.2) - Hot Water System	
	Install Mechanical Piping to Exchanger (HEX-1.1), Expansion Tanks (ET-1/2) & Pumps (HFWF) Install Electrical to Heat Exchanger (HEX-1.1), Expansion Tanks (ET-1/2) & Pumps (HHWF	15	03-Aug-20	21-Aug-20	+		ks (ET-1/2) & Pumps (HHWP-1.1/1.2) - Hot Water System	
	Install Electrical to Heat Exchanger (HEX-1.1), Expansion Tanks (E1-1/2) & Pumps (HHWP Install Controls Wiring to Heat Exchanger (HEX-1.1), Expansion Tanks (ET-1/2) & Pumps (10	24-Aug-20	04-Sep-20			sion Tanks (ET-1/2) & Pumps (HHWP-1.1/1.2) - Hot Water System	
	Fill, Flush & Treat Piping - Hot Water System	5	08-Sep-20	14-Sep-20		eat Piping - Hot Water System		
	Insulate Piping - Hot Water System	20	15-Sep-20	13-Oct-20		ping - Hot Water System		
	Start-up & Test - Hot Water System	15	25-Sep-20	16-Oct-20		& Test - Hot Water System		
Chilled Wate		15	23-3ep-20	10-001-20			<u>+</u>	
Roof				_				
	Rig & Set Chiller (ACC-1.1) at Roof - Chilled Water System	2	24-Jun-20	25-Jun-20	■ ■ Rig & Set Chiller (ACC-1.1)	at Roof - Chilled Water System		
	Install Mechanical Piping to Chiller (ACC-1.1) - Chilled Water System	20	26-Jun-20	23-Jul-20		ng to Chiller (ACC-1.1) - Chilled Water System	m	
	Install Electrical Conduits & Wiring to Chiller (ACC-1.1) - Chilled Water System	15	27-Jul-20	14-Aug-20		nduits & Wiring to Chiller (ACC-1.1) - Chilled	1 I I I I	
	Install Controls Wiring to Chiller (ACC-1.1) - Chilled Water System	10	17-Aug-20	28-Aug-20	* •	/iring to Chiller (ACC-1.1) - Chilled Water Sy	······································	
Basement		10	17-Aug-20	20-Aug-20				
_	Rig & Set Chilled Water Pumps (CHWP-1/2/3) & Expansion Tank (ET-1) - Chilled Water Sy	2	20-Jul-20	21-Jul-20	I Rig & Set Chilled Water	Pumps (CHWP-1/2/3) & Expansion Tank (E	T_1) - Chilled Water System	
	Rig & Set Gycol Feed System (GFT-1) - Chilled Water System	2	22-Jul-20	23-Jul-20		System (GFT-1) - Chilled Water System		
	Install Mechanical Piping to Chilled Water Pumps (CHWP-1/2/3) & Expansion Tank (ET-1) -	20	03-Aug-20	28-Aug-20			/3) & Expansion Tank (ET-1) - Chilled Water System	
	Install Electrical Conduits & Wiring to Chilled Water Pumps (CHWP-1/2/3) & Expansion Tan	15	17-Aug-20	04-Sep-20			CHWP-1/2/3) & Expansion Tank (ET-1) - Chilled Water System	
	Install Distall Distall Distall Provided Participation (GFT-1) - Chilled Water System	5	31-Aug-20	04-Sep-20		al Piping to Glycol Feed System (GFT-1) - C		
	Install Electrical Conduits & Wiring to System (GFT-1) - Chilled Water System	5	08-Sep-20	14-Sep-20		al Conduits & Wiring to System (GFT-1) - Ch		
	Install Controls Wiring to Chilled Water Pumps (CHW P-1/2/3) & Expansion Tank (ET-1) - C	10	08-Sep-20	21-Sep-20			2/3) & Expansion Tank (ET-1) - Chiled Water System	
	Install Controls Wiring to Gycol Feed System (GFT-1) - Chilled Water System	5	22-Sep-20	28-Sep-20		ols Wiring to Gycol Feed System (GFT-1) -		
	Fill, Flush & Treat Piping - Chilled Water System	5	29-Sep-20	05-Oct-20	* •	A Treat Piping - Chilled Water System		
	D Insulate Piping - Chilled Water System	20	06-Oct-20	03-Nov-20		te Piping - Chilled Water System		
) Start-up & Test - Chiled Water System	15	16-Oct-20	05-Nov-20		up & Test - Chilled Water System		
Air Handilin		10	10 001 20	001107 20				
Roof	'9			_				
	(STEM) & AHU-1.2 (STEM)					·}	÷÷÷÷÷÷	
	Rig & Set - AHU-1.1 (STEM) & AHU-1.2 (STEM)	1	26-Jun-20	26-Jun-20	I Rig & Set - AHU-1.1 (STEM	1 & AHU-1 2 (STEM)		
	Install Ductwork Connections - AHU-1.1 (STEM) & AHU-1.2 (STEM)	15	28-Jun-20 29-Jun-20	20-Jul-20		tions - AHU-1.1 (STEM) & AHU-1.2 (STEM)		
	Install Mechanical Piping Connections - AHU-1.1 (STEM) & AHU-1.2 (STEM)	15	29-Juli-20 14-Jul-20	03-Aug-20		ping Connections - AHU-1.1 (STEM) & AHU-1.2 (STEM)		
	Install Mechanical Piping Connections - AHU-1.1 (STEM) & AHU-1.2 (STEM) Install Electrical Conduits & Wiring - AHU-1.1 (STEM) & AHU-1.2 (STEM)	15	28-Jul-20	17-Aug-20		ng Connections - AHU-1.1 (STEM) & AHU- nduits & Wiring - AHU-1.1 (STEM) & AHU-1		
	Install Electrical Conduits & Wining - AHU-1.1 (STEM) & AHU-1.2 (STEM) Install Controls Wiring - AHU-1.1 (STEM) & AHU-1.2 (STEM)	15	28-Jui-20 18-Aug-20	31-Aug-20	+ +	Viring - AHU-1.1 (STEM) & AHU-1.2 (STEM)	·'`	
			10-Aug-20	51-Aug-20			1	
Remainir	ing Level of Effort Remaining Work		Page	9 of 16	TASK filter: % Complete <100.			
Actual Le	evel of Effort Critical Remaining Work					© Oracle Corporation	SKANSKA	
	Vork Milestone				Page 81 of 377		ANCINA	

y ID	chool - Project C - 10Feb20 R1 Schedule Update - 1318015-CR - B22	Remaining	Start	Finish	Detailed Schedule	Data Date: 10-Feb-20 / Run Date: 09-Jul-20 08:54
уЮ		Remaining Duration	Start	FILIST	2020	2021 2022
				40.11.00	F Mar Apr M Jun Jul Aug S Oc	ct N D Jan F Mar Apr M Jun Jul A S Oct N Dec Jan F Mar Apr M Jun Jul A S Oct N
	Start-up & Test - AHU-1.1 (STEM) & AHU-1.2 (STEM)	5	06-Nov-20	13-Nov-20		Start-up & Test - AHU-1.1 (STEM) & AHU-1.2 (STEM)
AHU-2.1			00 1 00			
	Rig & Set - AHU-2.1 (Kitchen)	1	29-Jun-20	29-Jun-20	Rig & Set - AHU	
	Install Ductwork Connections - AHU-2.1 (Kitchen)	15	14-Jul-20	03-Aug-20		twork Connections - AHU-2.1 (Kitchen)
	Install Mechanical Piping Connections - AHU-2.1 (Kitchen)	15	28-Jul-20	17-Aug-20		lechanical Piping Connections - AHU-2.1 (Kitchen)
	Install Electrical Conduits & Wiring - AHU-2.1 (Kitchen)	15	11-Aug-20	31-Aug-20		Electrical Conduits & Wiring - AHU-2.1 (Kitchen)
	Install Controls Wiring - AHU-2.1 (Kitchen) Start-up & Test - AHU-2.1 (Kitchen)	10	01-Sep-20	15-Sep-20		tall Controls Wiring - AHU-2.1 (Kitchen)
1	Start-up & Test - AHU-2.1 (Kitchen)	5	16-Nov-20	20-Nov-20		Start-up & Test - AHU-2.1 (Kitchen)
Electrical						
Basement		10	10 101 00	29-Jul-20		rhead Conduits & Electrical Panels - Permanent Power
	0 Install Overhead Conduits & Electrical Panels - Permanent Power	10	16-Jul-20			
	0 Rig & Set Electrical Gear & Panels - Permanent Power 0 Install Doors & Secure Room - Permanent Power	5	30-Jul-20	05-Aug-20		Electrical Gear & Panels - Permanent Power pors & Secure Room - Permanent Power
		5	06-Aug-20	12-Aug-20		& Secure Room - Permanent Power & Terminate Panels & Gear- Permanent Power
	0 Wire & Terminate Panels & Gear- Permanent Power	20	06-Aug-20	02-Sep-20		
	0 Pull Conductors & Terminate - Permanent Power	5	03-Sep-20	10-Sep-20		Conductors & Terminate - Permanent Power
	0 Test Switchgear - Permanent Power	5	11-Sep-20	17-Sep-20		st Switchgear - Permanent Power nergize Switchgear - Permanent Power
	0 Energize Switchgear - Permanent Power	5	18-Sep-20	24-Sep-20		
	0 Permanent Power Available	U		24-Sep-20	↓ Pe	ermanent Ppwer Available
Interiors	MED & Arabitastural Daugh in 1.2	57	00 lun 00	10 Can 20		P & Architectural Rough-in - L2
MEP-1010	MEP & Architectural Rough-in - L2	57	22-Jun-20	10-Sep-20		5
MEP-1020	MEP & Architectural Rough-in - L3	62	07-Jul-20	01-Oct-20		/EP & Architectural Rough-in - L3
MEP-1000	MEP & Architectural Rough-in - L1	75	21-Jul-20	04-Nov-20		MEP & Architectural Rough-in - L1
INT-1010	Interior Drywall & Finishes - L2	84	02-Nov-20	08-Mar-21		Interior Drywall & Finishes - L2
INT-1020	Interior Drywall & Finishes - L3	89	17-Nov-20	29-Mar-21	·	Interior Drywall & Finishes - L3
INT-1000	Interior Drywall & Finishes - L1	94	03-Dec-20	20-Apr-21		Interior Drywall & Finishes - L1
Level 2						
L2-1010	Install MEP Risers - L2	10	22-Jun-20	06-Jul-20	Install MEP Ris	
L2-1000	Install Tube Steel Wall Supports - L2	5	07-Jul-20	13-Jul-20		teel Wall Supports - L2
L2-1020	Rough-in Overhead Ductwork - L2	15	07-Jul-20	27-Jul-20		verhead Ductwork - L2
L2-1030	Rough-in Overhead Plumbing - L2	15	07-Jul-20	27-Jul-20		verhead Plumbing - L2
L2-1040	Rough-in Overhead Mechanical Piping - L2	15	14-Jul-20	03-Aug-20		Overhead Mechanical Piping - L2
L2-1050	Rough-in Overhead Electrical Conduit - L2	20	14-Jul-20	10-Aug-20		Overhead Electrical Conduit - L2
L2-1060	Frame Electrical Closets - L2	3	28-Jul-20	30-Jul-20		ctrical Closets - L2
L2-1070	Rough Fire Protection - L2	10	28-Jul-20	10-Aug-20	+ +	re Protection - L2
L2-1130	Install Above Ceiling Mechanical Equipment - L2	10	28-Jul-20	10-Aug-20		ove Ceiling Mechanical Equipment - L2
L2-1080	Board & Tape Electrical Closets - L2	5	31-Jul-20	06-Aug-20		ape Electrical Closets - L2
L2-1090	Frame Interior Wals - L2	10	04-Aug-20	17-Aug-20		nterior Wals - L2
L2-1450	Insulate Overhead Mechanical Piping & HVAC Ductwork - L2	15	04-Aug-20	24-Aug-20		e Overhead Mechanical Piping & HVAC Ductwork - L2
L2-1120	Set Door Frames - L2	5	07-Aug-20	13-Aug-20	↓	Frames - L2
L2-1110	Rough-in Plumbing In-Wall - L2	10	11-Aug-20	24-Aug-20		in Plumbing In-Wall - L2
L2-1100	Frame Soffits - L2	10	14-Aug-20	27-Aug-20	📕 Frame	
L2-1140	Rough-in Electrical In-Wall & Pull Branch Circuits - L2	15	18-Aug-20	08-Sep-20		gh-in Electrical In-Wall & Pull Branch Circuits - L2
L2-1150	Rough-in Low Voltage In-Wall & Pull Wire - L2	15	18-Aug-20	08-Sep-20	4 I I I I I I I I I I I I I I I I I I I	gh-in Low Voltage In-Wall & Pull Wire - L2
L2-1160	Perform Wall & Ceiling Punch List & Inspections - L2	10	08-Sep-20	21-Sep-20	* *	rform Wall & Ceiling Punch List & Inspections - L2
L2-1170	Perform In-Wall Inspections with Town - L2	2	09-Sep-20	10-Sep-20		orm In-Wal Inspections with Town - L2
L2-1180	Install Wood Blocking - L2	5	11-Sep-20	17-Sep-20		tall Wood Blocking - L2
L2-1330	Insulate In-Wall Piping - L2	5	11-Sep-20	17-Sep-20	Insi	ulate In-Wall Piping - L2
L2-1190	Board Walls & Soffits - L2	10	02-Nov-20	16-Nov-20		Board Wals & Soffits - L2
L2-1210	Tape Walls & Soffits - L2	10	06-Nov-20	20-Nov-20		Tapę Walls & Soffits - L2
L2-3050	Field Measure & Fab Interior Glass - L2	20	09-Nov-20	09-Dec-20		Field Measure & Fab Interior Glass - L2
L2-1220	Prime & 1st Coat walls - L2	6	23-Nov-20	02-Dec-20		Prime & 1st Coat walls - L2
L2-1230	Paint Exposed Ceilings at Classrooms & Offices - L2	10	23-Nov-20	08-Dec-20		Paint Exposed Ceilings at Classrooms & Offices - L2
L2-1225	Install Ceiling Grid & Cut/DeviceTiles at Classrooms & Offices - L2	5	30-Nov-20	04-Dec-20		Install Ceiling Grid & Cut/DeviceTies at Classrooms & Offices - L2
L2-3060	Install Wal Tile at Corridors - L2	10	30-Nov-20	11-Dec-20		Install Wal Tile at Corridors - L2
L2-1240	Install MEP Drops at Classrooms & Offices - L2	10	02-Dec-20	15-Dec-20		Install MEP Drops at Classrooms & Offices - L2
Remain	ning Level of Effort Remaining Work		Page (10 of 16	TASK filter: % Complete <100.	
	Level of Effort Critical Remaining Work		raye			© Oracle Corporation
	5				Page 82 of 377	© Oracle Corporation
	Work Milestone					

	chool - Project C - 10Feb20 R1 Schedule Update - 1318015-CR - B22	Domaining	Start	Finish	Detailed Schedule	Data Date: 10-Feb-20 / Run Date: 09-Jul-20 08:54
ID	Activity Name	Remaining Duration	Start	Finish	2020 2021	2022
					F Mar Apr M Jun Jul Aug S Oct N D Jan F Mar Apr M Jun Jul A S Oct	N Dec Jan F Mar Apr M Jun Jul A S Oct N
L2-1235	Install Fume Hoods - L2	5	07-Dec-20	11-Dec-20	Install Fume Hoods - L2	
L2-1250	Install Storefront Frames - L2	10	10-Dec-20	23-Dec-20	Install Storefront Frames - L2	
L2-1260	Install Millwork at Classrooms & Offices - L2	10	16-Dec-20	30-Dec-20	Install Millwork at Classrooms & Offices - L2	
L2-1440	Install Teledata Finishes & Terminations - L2	10	16-Dec-20	30-Dec-20	Install Teledata Finishes & Terminations - L2	
L2-1390	Install Interior Glazing - L2	10	17-Dec-20	31-Dec-20	Install Interior Glazing - L2	
L2-1445	Install Fintube Radiators - L2	10	22-Dec-20	06-Jan-21	Install Fintube Radiators - L2	
L2-1270	Install Ceiling Grid & Cut/Device Tiles at Corridors - L2	5	29-Dec-20	05-Jan-21	Install Ceiling Grid & Cut/Device Tiles at Corrid	ors - L2
L2-1380	Install Flooring at Classrooms & Offices - L2	10	30-Dec-20	13-Jan-21	Install Flooring at Classrooms & Offices - L2	
L2-1370	Install Doors & Hardware - L2	5	31-Dec-20	07-Jan-21	Install Doors & Hardware - L2	
L2-1305	Install Railings at Opening - L2	5	06-Jan-21	12-Jan-21	Install Railings at Opening - L2	
L2-1430	Install Fire Alarm Devices - L2	5	06-Jan-21	12-Jan-21	Install Fire Alarm Devices - L2	
L2-1280	Install MEP Drops at Corridors - L2	8	06-Jan-21	15-Jan-21	Install MEP Drops at Corridors - L2	
L2-3070	Install Laboratory Casework at Classrooms - L2	10	06-Jan-21	20-Jan-21	Install Laboratory Casework at Classrooms	- L2
L2-1285	Install Fintube Covers - L2	10	07-Jan-21	21-Jan-21	Install Fintube Covers - L2	
L2-3080	Install Plumbing Fixtures at Classrooms & Offices - L2	10	12-Jan-21	26-Jan-21	Install Plumbing Fixtures at Classrooms & C	Diffices - L2
L2-1300	Install Terrazzo at Corridors - L2	18	14-Jan-21	09-Feb-21	Install Terrazzo at Corridors - L2	
L2-1360	Install Terrazzo Base at Corridors - L2	10	01-Feb-21	12-Feb-21	Install Terrazzo Base at Corridors - L2	
L2-1320	Install AV - L2	5	08-Feb-21	12-Feb-21	I Install AV - L2	
L2-1340	Install Whiteboards & Tack Boards - L2	5	08-Feb-21	12-Feb-21	Install Whiteboards & Tack Boards - L2	
L2-1350	Install Window Shades - L2	5	08-Feb-21	12-Feb-21	Install Window Shades - L2	
L2-1400	Construction Cleaning - L2	5	16-Feb-21	22-Feb-21	Construction Cleaning - L2	
L2-1400	Balance HVAC - L2	5	23-Feb-21	01-Mar-21	Balance HVAC - L2	
	Skanska Punch List - L2	5	23-Feb-21 23-Feb-21	01-Mar-21	Skanska Punch List - L2	
L2-1410						
L2-1420	Architect Punch List - L2	5	02-Mar-21	08-Mar-21	Architect Punch List - L2	
Bathroom						
L2-1600		5	02-Nov-20	06-Nov-20	Board & Install Cement Board - L2 Bathrooms	
L2-1605		5	09-Nov-20	16-Nov-20	Tape & Finish - L2 Bathrooms	
L2-1610		3	17-Nov-20	19-Nov-20	Prime Paint - L2 Bathrooms	
L2-1615		2	20-Nov-20	23-Nov-20	Install Counters - L2 Bathrooms	
L2-1620	Install Wal & Floor Tile - L2 Bathrooms	10	24-Nov-20	09-Dec-20	Install Wal & Floor Tile - L2 Bathrooms	
L2-1625	Install Plumbing Fixtures - L2 Bathrooms	5	10-Dec-20	16-Dec-20	Install Plumbing Fixtures - L2 Bathrooms	
L2-1630	Field Measure & Fab Mirrors - L2 Bathrooms	10	10-Dec-20	23-Dec-20	Field Measure & Fab Mirrors - L2 Bathrooms	
L2-1635	Install Toilet Partitions - L2 Bathrooms	4	17-Dec-20	22-Dec-20	Install Toilet Partitions - L2 Bath rooms	
L2-1640	Install Bathroom Accessories - L2 Bathrooms	4	23-Dec-20	29-Dec-20	Install Bathroom Accessories - L2 Bathrooms	
L2-1645	Install Mirrors - L2 Bathrooms	2	30-Dec-20	31-Dec-20	Install Mirrors - L2 Bathrooms	
L2-1650	Finish Paint - L2 Bathrooms	2	04-Jan-21	05-Jan-21	I Finish Paint - L2 Bathrooms	
IT Room 2	204C					
L2-1660	Install MEP Above Ceiling Rough-in - L2 IT Room 204C	3	28-Jul-20	30-Jul-20	Install MEP Above Ceiling Rough-in - L2 IT Room 204C	
		2	31-Jul-20	03-Aug-20	Frame Wals & Instal Door Frame - L2 IT Room 204C	
L2-1680		2	04-Aug-20	05-Aug-20	I Install In-Wal Rough₁n - L2 IT Room 204C	
L2-1690		1	06-Aug-20	06-Aug-20	I Install In-Wal Blocking - L2 IT Room 204C	
L2-1090		1	09-Oct-20	09-Oct-20	Board Wals - L2 IT Room 204C	
L2-1700		3	13-Oct-20	15-Oct-20	Tape Walls - L2 IT Room 204C	
L2-1710		2	16-Oct-20	19-Oct-20	Prime & 1st Coat Paint Walls - L2 IT Room 204C	
		1	20-Oct-20		++·······························	
L2-1730 L2-1740	5			20-Oct-20 22-Oct-20	I Install Ceiling Grid - L2 (T Room 204C	
		2	21-Oct-20		Install MEP Drops at Grid - L2 IT Room 204C	
L2-1750	5	1	23-Oct-20	23-Oct-20	I Install Moisture Mitigation - L2 IT Room 204C	
L2-1760		2	26-Oct-20	27-Oct-20	I Install Flooring - L2 IT Room 204C	
		2	28-Oct-20	29-Oct-20	Final Paint - L2 IT Room 204C	
L2-1780		5	02-Nov-20	06-Nov-20	Install T Racks & Equipment - L2 IT Room 204C	
L2-1790		1	09-Nov-20	09-Nov-20	I Install Ceiling Tile - L2 IT Room 204C	
L2-1810		5	10-Nov-20	17-Nov-20	Construction Clean - L2 IT Room 204C	
L2-1820		1	18-Nov-20	18-Nov-20	I Balance HVAC - L2 IT Room 204C	
L2-1830	Skanska Punch List- L2 IT Room 204C	1	19-Nov-20	19-Nov-20	I Skanska Punch Lişt- L2 IT Room 204C	
L2-1840	Architect Punch List - L2 IT Room 204C	1	20-Nov-20	20-Nov-20	Architect Punch List - L2 IT Room 204C	
Remain	ning Level of Effort Remaining Work		Daga	11 of 16	TASK filter: % Complete <100	
			Page	11 of 16	TASK filter: % Complete <100.	CI /ANICI/A
	Level of Effort Critical Remaining Work				© Oracle Corporation	SKANSKA
Actual	Work Milestone				Page 88 of 377	

ity ID Activity Name		Remaining	Start	Finish		
		Duration	otart	1 11011	2020	2021 2022
10 (07)			04.51	40 5 1 5	F Mar Apr M Jun Jul Aug S Oct	N D Jan F Mar Apr M Jun Jul A S Oct N Dec Jan F Mar Apr M Jun Jul A S Oct N
L2-1850	Complete 90 Calendar Days Prior to STEM Interim Completion Date - L2 IT Room 204C	90	21-Nov-20	18-Feb-21		Complete 90 Calendar Days Prior to STEM Interim Completion Date - L2 IT Room 204C
Level 3		10				
L3-1010	Install MEP Risers - L3	10	07-Jul-20	20-Jul-20		
L3-1000	Install Tube Steel Wall Supports - L3	5	21-Jul-20	27-Jul-20	_	steel Wall Supports - L3
L3-1020	Rough-in Overhead Ductwork - L3	15	28-Jul-20	17-Aug-20		Overhead Ductwork - 43
L3-1030	Rough-in Overhead Plumbing - L3	15	28-Jul-20	17-Aug-20		Overhead Plumbing - L3 Overhead Mechanical Piping - L3
L3-1040	Rough-in Overhead Mechanical Piping - L3	15	04-Aug-20	24-Aug-20		
L3-1050	Rough-in Overhead Electrical Conduit - L3	20	04-Aug-20	31-Aug-20		in Overhead Electrical Conduit - L3
L3-1060	Frame Electrical Closets - L3	3	18-Aug-20	20-Aug-20		ectrical Closets - L3
L3-1070	Rough Fire Protection - L3	10	18-Aug-20	31-Aug-20		Fire Protection - L3
L3-1130	Install Above Ceiling Mechanical Equipment - L3	10	18-Aug-20	31-Aug-20		bove Ceiling Mechanical Equipment - L3
L3-1080	Board & Tape Electrical Closets - L3	5	21-Aug-20	27-Aug-20		Tape Electrical Closets - L3
L3-1090	Frame Interior Wals - L3	10	25-Aug-20	08-Sep-20		e Interior Wals - L3
L3-1450	Insulate Overhead Mechanical Piping & HVAC Ductwork - L3	15	25-Aug-20	15-Sep-20		ate Overhead Mechanical Piping & HVAC Ductwork - L3
L3-1120	Set Door Frames - L3	5	28-Aug-20	03-Sep-20		or Frames - L3
L3-1110	Rough-in Plumbing In-Wall - L3	10	01-Sep-20	15-Sep-20		h-in Plumbing In-Wall - L3
L3-1100	Frame Soffits - L3	10	04-Sep-20	18-Sep-20		ne Soffits + L3
L3-1140	Rough-in Electrical In-Wall & Pull Branch Circuits - L3	15	09-Sep-20	29-Sep-20		ugh-in Electrical In-Wall & Pull Branch Circuits - L3
L3-1150	Rough-in Low Voltage In-Wall & Pull Wire - L3	15	09-Sep-20	29-Sep-20	+	ugh-in Low Voltage In-Wall & Pull Wire - L3
L3-1160	Perform Wall & Ceiling Punch List & Inspections - L3	10	29-Sep-20	13-Oct-20		Perform Wall & Ceiling Punch List & Inspections - L3
L3-1170	Perform In-Wall Inspections with Town - L3	2	30-Sep-20	01-Oct-20		rform In-Wall Inspections with Town - L3
L3-1180	Install Wood Blocking - L3	5	02-Oct-20	08-Oct-20		nstall Wood Blocking - L3
L3-1330	Insulate In-Wall Piping - L3	5	02-Oct-20	08-Oct-20		nsulate In-Wall Piping - L3
L3-1190	Board Wals & Soffits - L3	10	17-Nov-20	02-Dec-20	+ +	Bdard Walls & Soffits - L3
L3-1210	Tape Walls & Soffits - L3	10	23-Nov-20	08-Dec-20		Tape Walls & Soffits - L3
L3-3050	Field Measure & Fab Interior Glass - L3	20	24-Nov-20	23-Dec-20		Field Measure & Fab Interior Glass - L3
L3-1220	Prime & 1st Coat walls - L3	6	09-Dec-20	16-Dec-20		Prime & 1st Coat walls - L3
L3-1230	Paint Exposed Ceilings & MEPs at Classrooms & Offices - L3	10	09-Dec-20	22-Dec-20		Paint Exposed Ceilings & MEPs at Classrooms & Offices - L3
L3-1225	Install Ceiling Grid & Cut/DeviceTiles at Classrooms & Offices - L2	5	14-Dec-20	18-Dec-20		Install Ceiling Grid & Cut/DeviceTies at Classrooms & Offices - L2
L3-3060	Install Wal Tile at Corridors - L3	10	14-Dec-20	28-Dec-20		Install Wal Tile at Corridors - L3
L3-1240	Install MEP Drops at Classrooms & Offices - L3	10	16-Dec-20	30-Dec-20		Install MEP Drops at Classrooms & Offices - L3
L3-1235	Install Fume Hoods - L3	5	21-Dec-20	28-Dec-20		Install Fume Hoods - L3
L3-1250	Install Storefront Frames - L3	10	24-Dec-20	08-Jan-21		Install Storefront Frames - L3
L3-1260	Install Millwork at Classrooms & Offices - L3	10	31-Dec-20	14-Jan-21		Install Millwork at Classrooms & Offices - L3
L3-1440	Install Teledata Finishes & Terminations - L3	10	31-Dec-20	14-Jan-21		Install Teledata Finishes & Terminations - L3
L3-1390	Install Interior Glazing - L3	10	04-Jan-21	15-Jan-21		Install Interior Glazing - L3
L3-1445	Install Fintube Radiators - L3	10	07-Jan-21	21-Jan-21		Install Fintube Radiators - L3
L3-1270	Install Ceiling Grid & Cut/DeviceTiles at Corridors - L3	5	13-Jan-21	20-Jan-21		Install Ceiling Grid & Cut/DeviceTies at Corridors - L3
L3-1380	Install Flooring at Classrooms & Offices - L3	10	14-Jan-21	28-Jan-21		Install Flooring at Classrooms & Offices - L3
L3-1370	Install Doors & Hardware - L3	5	15-Jan-21	22-Jan-21		Install Doors & Hardware - L3
L3-1305	Install Railings at Opening - L3	5	21-Jan-21	27-Jan-21		Install Railings at Opening - L3
L3-1430	Install Fire Alarm Devices - L3	5	21-Jan-21	27-Jan-21		Install Fire Alarm Devices - L3
L3-1280	Install MEP Drops at Corridors - L3	8	21-Jan-21	01-Feb-21		Install MEP Drops at Corridors - L3
L3-3070	Install Laboratory Casework at Classrooms - L3	10	21-Jan-21	03-Feb-21		Install Laboratory Casework at Classrooms - L3
L3-1285	Install Fintube Covers - L3	10	22-Jan-21	04-Feb-21		Install Fintube Covers - L3
L3-3080	Install Plumbing Fixtures at Classrooms & Offices - L3	10	27-Jan-21	09-Feb-21		Install Plumbing Fixtures at Classrooms & Offices - L3
L3-1300	Install Terrazzo at Corridors - L3	18	05-Feb-21	03-Mar-21		Install Terrazzo at Corridors - L3
L3-1360	Install Terrazzo Base at Corridors - L3	10	23-Feb-21	08-Mar-21		Install Terrazzo Base at Corridors - L3
L3-1320	Install AV - L3	5	02-Mar-21	08-Mar-21		Install AV - L3
L3-1340	Install Whiteboards & Tack Boards - L3	5	02-Mar-21	08-Mar-21		Install Whiteboards & Tack Boards - L3
L3-1350	Install Window Shades - L3	5	02-Mar-21	08-Mar-21		Install Window Shades - L3
L3-1400	Construction Cleaning - L3	5	09-Mar-21	15-Mar-21		Construction Cleaning - L3
L3-1290	Balance HVAC - L3	5	16-Mar-21	22-Mar-21		Balance HVAC - L3
L3-1410	Skanska Punch List - L3	5	16-Mar-21	22-Mar-21		Skanska Punch List - L3
L3-1420	Architect Punch List - L3	5	23-Mar-21	29-Mar-21		Architect Punch List - L3
	hing Level of Effort Remaining Work Level of Effort Critical Remaining Work Work \blacklozenge Milestone		Page	12 of 16	TASK filter: % Complete <100.	© Oracle Corporation

ty ID	Activity Name	Remaining	Start	Finish		
		Duration			2020 2021 F [Mar Apr] M [Jun Jul Aug] S [Oct] N] D [Jan] F [Mar Apr] M [Jun Jul] A] S [Oct] N	2022 Dec Jan F Mar Apr M Jun Jul A S Oct N
Bathrooms	Ś					
L3-1600	Board & Install Cement Board - L3 Bathrooms	5	17-Nov-20	23-Nov-20	Board & Install Cement Board - L3 Bathrooms	
L3-1605	Tape & Finish - L3 Bathrooms	5	24-Nov-20	02-Dec-20	Tape & Finish - L3 Bathrooms	
L3-1610	Prime Paint - L3 Bathrooms	3	03-Dec-20	07-Dec-20	Prime Paint - L3 Bathrooms	
L3-1615	Install Counters - L3 Bathrooms	2	08-Dec-20	09-Dec-20	I Install Counters - L3 Bathrooms	
L3-1620	Install Wal & Floor Tile - L3 Bathrooms	10	10-Dec-20	23-Dec-20	Install Wal & Floor Tile - L3 Bathrooms	
L3-1625	Install Plumbing Fixtures - L3 Bathrooms	5	24-Dec-20	31-Dec-20	Install Plumbing Fixtures - L3 Bathrooms	
L3-1630	Field Measure & Fab Mirrors - L3 Bathrooms	10	24-Dec-20	08-Jan-21	Field Measure & Fab Mirrors - L3 Bathrooms	
L3-1635	Install Toilet Partitions - L3 Bathrooms	4	04-Jan-21	07-Jan-21	I Install Toilet Partitions - L3 Bathrooms	
L3-1640	Install Bathroom Accessories - L3 Bathrooms	4	08-Jan-21	13-Jan-21	Install Bathroom Accessories - L3 Bathrooms	
L3-1645	Install Mirrors - L3 Bathrooms	2	14-Jan-21	15-Jan-21	Install Mirrors - L3 Bathrooms	
L3-1650	Finish Paint - L3 Bathrooms	2	19-Jan-21	20-Jan-21	I Finish Paint - L3 Bathrooms	
Level 1						
L1-1010	Install MEP Risers - L1	10	21-Jul-20	03-Aug-20	Install MEP Risers - L1	
L1-1000	Install Tube Steel Wall Supports - L1	5	04-Aug-20	10-Aug-20	Install Tube Steel Wall Supports - L1	
L1-1020	Rough-in Overhead Ductwork - L1	15	18-Aug-20	08-Sep-20	Rough-in Overhead Ductwork - L1	
L1-1030	Rough-in Overhead Plumbing - L1	15	18-Aug-20	08-Sep-20	Rough-in Overhead Plumbing - L1	
L1-1040	Rough-in Overhead Mechanical Piping - L1	15	25-Aug-20	15-Sep-20	Rough-in Overhead Mechanical Piping - L1	
L1-1050	Rough-in Overhead Electrical Conduit - L1	20	25-Aug-20	22-Sep-20	Rough-in Overhead Electrical Conduit - L1	
L1-1060	Frame Electrical Closets - L1	3	09-Sep-20	11-Sep-20	Frame Electrical Closets - L1	
L1-1070	Rough Fire Protection - L1	10	09-Sep-20	22-Sep-20	Rough Fire Protection - L1	
L1-1130	Install Above Ceiling Mechanical Equipment - L1	10	09-Sep-20	22-Sep-20	Install Above Ceiling Mechanical Equipment - L1	
L1-1080	Board & Tape Electrical Closets - L1	5	14-Sep-20	18-Sep-20	Board & Tape Electrical Closets - L1	
L1-1090	Frame Interior Walls - L1	10	16-Sep-20	29-Sep-20	📕 Frame Interior Wals - L1	
L1-1450	Insulate Overhead Mechanical Piping & HVAC Ductwork - L1	15	16-Sep-20	06-Oct-20	Insulate Overhead Mechanical Piping & HVAC Ductwork - L1	
L1-1120	Set Door Frames - L1	5	21-Sep-20	25-Sep-20	Set Door Frames - L1	
L1-1110	Rough-in Plumbing In-Wall - L1	10	23-Sep-20	06-Oct-20	Rough-in Plumbing In-Wall - L1	
L1-1100	Frame Soffits - L1	10	28-Sep-20	09-Oct-20	Frame Soffits - L1	
L1-1140	Rough-in Electrical In-Wall & Pull Branch Circuits - L1	15	30-Sep-20	21-Oct-20	Rough-in Electrical In-Wall & Pull Branch Circuits - L1	
L1-1150	Rough-in Low Voltage In-Wall & Pull Wire - L1	15	30-Sep-20	21-Oct-20	Rough-in Low Voltage In-Wall & Pull Wire - L1	
L1-1160	Perform Wall & Ceiling Punch List & Inspections - L1	10	21-Oct-20	03-Nov-20	Perform Wall & Ceiling Punch List & Inspections - L1	
L1-1170	Perform In-Wall Inspections with Town - L1	2	22-Oct-20	23-Oct-20	Perform In-Wall Inspection s with Town - L1	
L1-1180	Install Wood Blocking - L1	5	26-Oct-20	30-Oct-20	Install Wood Blocking - L1	
L1-1330	Insulate In-Wall Piping - L1	5	26-Oct-20	30-Oct-20	Insulate In-Wall Piping - L1	
L1-1190	Board Walls & Soffits - L1	10	03-Dec-20	16-Dec-20	Board Wals & Soffits - L1	
L1-1210	Tape Walls & Soffits - L1	10	09-Dec-20	22-Dec-20	Tape Walls & Soffits - L1	
L1-3050	Field Measure & Fab Interior Glass - L1	20	10-Dec-20	08-Jan-21	Field Measure & Fab Interior Glass - L1	
L1-1230	Paint Exposed Ceiling at Makerspace - L1	3	23-Dec-20	28-Dec-20	Paint Exposed Ceiling at Makerspace - L1	
L1-1220	Prime & 1st Coat Walls - L1	6	23-Dec-20	31-Dec-20	Prime & 1st Coat Walls - L1	
L1-1225	Install Ceiling Grid & Cut/DeviceTiles at Classrooms & Offices - L1	5	29-Dec-20	05-Jan-21	Install Ceiling Grid & Cut/DeviceTles at Classrool	ns & Offices - L1
L1-1333	Install Unistrut Grid at Makerspace - L1	5	29-Dec-20	05-Jan-21	Install Unistrut Grid at Makerspace - L1	
L1-3060	Install Wal Tile at Corridors - L1	10	29-Dec-20	12-Jan-21	Install Wal Tile at Corridors - L1	
L1-1240	Install MEP Drops at Classrooms & Offices - L1	10	31-Dec-20	14-Jan-21	Install MEP Drops at Classrooms & Offices - L1	
L1-3070	Install Overhead Garage Doors - L1	5	06-Jan-21	12-Jan-21	Install Overhead Garage Doors - L1	
L1-1250	Install Storefront Frames - L1	10	11-Jan-21	25-Jan-21	📕 Install Storefront Frames - L1	
L1-1440	Install Teledata Finishes & Terminations - L1	10	15-Jan-21	29-Jan-21	Install Teledata Finishes & Terminations - L1	
L1-1260	Install Millwork at Classrooms & Offices - L1	10	19-Jan-21	01-Feb-21	Install Millwork at Classrooms & Offices - L1	
L1-1390	Install Interior Glazing - L1	10	19-Jan-21	01-Feb-21	Install Interior Glazing - L1	
L1-1445	Install Fintube Radiators - L1	10	25-Jan-21	05-Feb-21	Install Fintube Radiators - L1	
L1-1275	Install Simulated Wood Aluminum Ceiling Panel System - L1	20	26-Jan-21	23-Feb-21	Install Simulated Wood Aluminum Ceiling F	Panel System - L1
L1-1270	Install Ceiling Grid & Cut/DeviceTiles at Corridors - L1	5	29-Jan-21	04-Feb-21	Install Ceiling Grid & Cut/DeviceTies at Corr	dars L1
L1-1380	Install Flooring at Classrooms & Offices - L1	10	01-Feb-21	12-Feb-21	Install Flooring at Classrooms & Offices - L	1
L1-1370	Install Doors & Hardware - L1	5	02-Feb-21	08-Feb-21	Install Doors & Hardware - L1	
L1-1280	Install MEP Drops at Corridors - L1	15	05-Feb-21	26-Feb-21	Install MEP Drops at Corridors - L1	
L1-1285	Install Fintube Covers - L1	10	08-Feb-21	22-Feb-21	Install Fintube Covers - L1	
Remaini	ing Level of Effort Remaining Work		Pane	13 of 16	TASK filter: % Complete <100.	
	evel of Effort Critical Remaining Work		i aye		© Oracle Corporation	SKANSKA
/ 101001 L						

okline High School - Project C - 10Feb20 R1 Schedule Update - 1318015-CR - B22 y ID Activity Name Remainin		Start	Finish	etailed Schedule	Data Date: 10-Feb-20 / Run Date: 09-Jul-20 08:5	
., 10		Duration	Start	1 111311	2020	2021 2022
14.4400			04 5-6 04	00 Max 04	F Mar Apr M Jun Jul Aug S Oc	t N D Jan F Mar Apr M Jun Jul A S Oct N Dec Jan F Mar Apr M Jun Jul A S Oct N
	Install Fire Alarm Devices - L1	5	24-Feb-21	02-Mar-21		Install Fire Alarm Devices - L1
L1-1300	Install Terrazzo at Corridors - L1	18	01-Mar-21	24-Mar-21		Install Terrazzo at Corridors - L1
L1-1360	Install Terrazzo Base at Corridors - L1	10	16-Mar-21	29-Mar-21 29-Mar-21		 Install Terrazzo Base at Corridors - L1 Install AV - L1
L1-1320	Install AV - L1	5	23-Mar-21			
L1-1340	Install Whiteboards & Tack Boards - L1	5	23-Mar-21	29-Mar-21 29-Mar-21		 Install Whiteboards & Tack Boards - L1 Install Window Shades - L1
L1-1350 L1-1400	Install Window Shades - L1 Construction Cleaning - L1	5	23-Mar-21 30-Mar-21	29-Mar-21 05-Apr-21		Construction Cleaning - L1
L1-1400	Balance HVAC - L1	5	06-Apr-21	12-Apr-21		Balance HVAC - L1
L1-1290	Skanska Punch List - L1	5	06-Apr-21	12-Apr-21		Skanska Punch List - L1
L1-1410	Architect Punch List - L1	5	13-Apr-21	20-Apr-21		Architect Punch List - L1
Bathroom		5	10-Api-21	20-Apr-21		
L1-1600	Board & Install Cement Board - L1 Bathrooms	5	03-Dec-20	09-Dec-20		Board & Install Cement Board - L1 Bathrooms
L1-1605	Tape & Finish - L1 Bathrooms	5	10-Dec-20	16-Dec-20		Tape & Finish - L1 Bathrooms
L1-1610		3	17-Dec-20	21-Dec-20		Prime Paint - L1 Bathrooms
L1-1615		2	22-Dec-20	23-Dec-20		I Install Counters - L1 Bathrooms
L1-1620	Install Wal & Floor Tile - L1 Bathrooms	10	22-Dec-20 24-Dec-20	08-Jan-21		Install Wal & Floor Tile - L1 Bathrooms
L1-1625	Install Plumbing Fixtures - L1 Bathrooms	5	11-Jan-21	15-Jan-21		Install Plumbing Fixtures - L1 Bathrooms
L1-1620	Field Measure & Fab Mirrors - L1 Bathrooms	10	11-Jan-21	25-Jan-21		 Field Measure & Fab Mirrors - L1 Bathrooms
L1-1635	Install Toilet Partitions - L1 Bathrooms	4	19-Jan-21	22-Jan-21		Install Toilet Partitions - L1 Bathrooms
L1-1640	Install Bathroom Accessories - L1 Bathrooms	4	25-Jan-21	28-Jan-21		Install Bathroom Accessories - L1 Bathrooms
L1-1645	Install Mirrors - L1 Bathrooms	2	29-Jan-21	01-Feb-21		Install Mirrors - L1 Bathrooms
L1-1650	Finish Paint - L1 Bathrooms	2	02-Feb-21	03-Feb-21		Finish Paint - L1 Bathrooms
Servery			0210021	0010021		
	Frame Wals - L1 Kitchen	5	30-Sep-20	06-Oct-20		Frame Walls - L1 Kitchen
-	Rough-in Plumbing In-Wall - L1 Kitchen	10	07-Oct-20	21-Oct-20	τ	Rough-in Plumbing In-Wall - L1 Kitchen
	Rough-in Electrical In-Wall - L1 Kitchen	5	22-Oct-20	28-Oct-20		Rough-ih Electrical In-Wall - L1 Kitchen
	Perform In-Wall Inspections with Town & Punch List - L1 Kitchen	5	22-Oct-20 29-Oct-20	04-Nov-20		Perform In-Wall Inspections with Town & Punch List - L1 Kitchen
	Install Wood Blocking - L1 Kitchen	3	05-Nov-20	09-Nov-20		Install Wood Blocking - L1 Kitchen
	Board Wals - L1 Kitchen	3	14-Dec-20	16-Dec-20		Board Wals - L1 Kitchen
	Tape & Finish Walls - L1 Kitchen	3	17-Dec-20	21-Dec-20		Tape & Finish Walls - L1 Kitchen
	Prime Paint & 1st Coat Walls - L1 Kitchen	3	22-Dec-20	24-Dec-20		Prime Paint & 1st Coat Walls - L1 Kitchen
	Install Fiberglass Reinforced Panels - L1 Kitchen	5	28-Dec-20	04-Jan-21		Install Fiberglass Reinforced Panels - L1 Kitchen
	Install Ceiling Grid & Cut/Device Tiles - L1 Kitchen	3	05-Jan-21	07-Jan-21		I Install Ceiling Grid & Cut/Device Tiles - L1 Kitchen
	Install Wak-in Cooler/Freezer - L1 Kitchen	5	05-Jan-21	11-Jan-21		Install Wak-in Cooler/Freezer - L1 Kitchen
	Install Simulated Wood Aluminum Ceiling Panels - L1 Kitchen	6	08-Jan-21	15-Jan-21		Install Simulated Wood Aluminum Ceiling Panels - L1 Kitchen
	Install MEP Drops at Ceiling Grid - L1 Kitchen	5	13-Jan-21	20-Jan-21		Install MEP Drops at Ceiling Grid - L1 Kitchen
	Above Ceiling Punch List - L1 Kitchen	5	21-Jan-21	27-Jan-21		Above Ceiling Punch List - L1 Kitchen
	Install Wal Tile - L1 Kitchen	10	21-Jan-21	03-Feb-21		 Install Wal Tile - L1 Kitchen
	Install Epoxy Flooring - L1 Kitchen	3	04-Feb-21	08-Feb-21		Install Epoxy Flooring - L1 Kitchen
	Install Terrazzo Flooring - L1 Kitchen	5	09-Feb-21	16-Feb-21		Install Terrazzo Flooring - L1 Kitchen
	Install Overhead Garage Doros - L1 Kitchen	2	17-Feb-21	18-Feb-21		Install Overhead Garage Doros - L1 Kitchen
	Install Kitchen Equipment - L1 Kitchen	10	19-Feb-21	04-Mar-21		Install Stehen Equipment - L1 Kitchen
	Install Plumbing Connections to Kitchen Equipment - L1 Kitchen	5	05-Mar-21	11-Mar-21		 Install Remember 2 Gradener - La Ritchen Equipment - L1 Kitchen
	Install Electrical Connections to Kitchen Equipment - L1 Kitchen	5	10-Mar-21	16-Mar-21		 Install Electrical Connections to Kitchen Equipment - L1 Kitchen
	Install Ceiling Tile - L1 Kitchen	3	17-Mar-21	19-Mar-21	+	 Install Ceiling Tile - L1 Kitchen
L1KIT-18		10	17-Mar-21	30-Mar-21		Startup & Test Kitchen/Kitchen Equipment - L1 Kitchen
	Test & Balance HVAC - L1 Kitchen	3	22-Mar-21	24-Mar-21		Test & Balance HVAC - L1 Kitchen
	Board of Health Inspections - L1 Kitchen	1	31-Mar-21	31-Mar-21		Board of Health Inspections - L1 Kitchen
Stair Finishe	· ·					
Stair 1	••				+	······································
	Frame Wals - Stair 1	5	18-Aug-20	24-Aug-20	Frame \	Wals - Stair 1
	Rough-in In-Wall Electric - Stair 1	3	25-Aug-20	27-Aug-20	i i i	-in In-Wall Electric - Stair 1
	Board Walls - Stair 1	3	17-Nov-20	19-Nov-20	u Rough	Board Wals - Stair 1
	Tape & Finish Walls - Stair 1	4	20-Nov-20	25-Nov-20		Tape & Finish Walls - Stair 1
	Prime Paint Walls & Stairs - Stair 1	3	30-Nov-20	02-Dec-20	<u> </u>	Prime Paint Walls & Stair 1
	ning Level of Effort Remaining Work		Page	14 of 16	TASK filter: % Complete <100.	
Actual L	Level of Effort Critical Remaining Work					© Oracle Corporation
	Work Milestone				age 86 of 377	

	hool - Project C - 10Feb20 R1 Schedule Update - 1318015-CR - B22	i Darrestration i			tailed Schedule	Data Date: 10-Feb-20 / Run Date: 09-Jul-20 08:54
ID	Activity Name	Remaining	Start	Finish	2020 2021	2022
		Duration			F Mar Apr M Jun Jul Aug S Oct N D Jan F Mar Apr M Jun Ju	
ST1-1050	Install Tile Walls - Stair 1	5	03-Dec-20	09-Dec-20		
	Install Wood Wall Panels - Stair 1	10	10-Dec-20	23-Dec-20	□ Install Wood Wall Panels - Stair	r1
	Install Wal Raings - Stair 1	3	24-Dec-20	29-Dec-20	Install Wall Raings - Stair 1	
	Finish Paint Stairs - Stair 1	2	30-Dec-20	31-Dec-20	Finish Paint Stairs - Stair 1	
	Install Terrazzo Treads - Stair 1	5	04-Jan-21	08-Jan-21	Install Terrazzo Treads - Stair	
Stair 2		5	04-341-21	00-3411-21		
		40	05 4	00.0 00		
	Frame Wals - Stair 2	10	25-Aug-20	08-Sep-20	Frame Wals - Stair 2	
	Rough-in In-Wall Electric - Stair 2	5	09-Sep-20	15-Sep-20	Rough-in In-Wall Electric - Stair 2	
	Board Wals - Stair 2	10	24-Nov-20	09-Dec-20	Board Walls - Stair 2	·····
	Tape & Finish Walls - Stair 2	10	10-Dec-20	23-Dec-20	Tape & Finish Walls - Stair 2	
	Prime Paint Walls & Stairs - Stair 2	5	24-Dec-20	31-Dec-20	Prime Paint Walls & Stairs - St	ar 2
ST2-1050	Install Tile Walls - Stair 2	15	04-Jan-21	25-Jan-21	Install Tile Walls - Stair 2	
ST2-1060	Install Wal Railings - Stair 2	5	26-Jan-21	01-Feb-21	Install Wall Ratings - Stai	r2
ST2-1070	Paint Railings & Finish Paint Stairs - Stair 2	5	02-Feb-21	08-Feb-21	Paint Railings & Finish P	aint Stairs - Stair 2
ST2-1080	Install Light Fixtures - Stair 2	2	09-Feb-21	10-Feb-21	I Install Light Fixtures - St	(air 2
ST2-1090	Install Terrazo Treads - Stair 2	10	11-Feb-21	25-Feb-21	Install Terrazo Treads	s - Stair 2
Stair 3		· · · ·		,		
ST3-1000	Frame Wals - Stair 3	10	09-Sep-20	22-Sep-20	🔲 Frame Wals - Stair 3	
	Rough-in In-Wall Electric - Stair 3	5	23-Sep-20	29-Sep-20	🔲 Rough-in In-Wall Electric - Stair 3	
	Board Wals - Stair 3	10	10-Dec-20	23-Dec-20	Board Wals - Stair 3	······································
	Tape & Finish Walls - Stair 3	10	24-Dec-20	08-Jan-21	Tape & Finish Walls - Stair 3	
	Prime Paint Walls & Stair 3				Prime Paint Walls & Stairs -	
		5	11-Jan-21	15-Jan-21		
	Install Wal Raings - Stair 3	10	19-Jan-21	01-Feb-21	Install Wall Railings - Stai	
	Paint Railings & Finish Paint Stairs - Stair 3	5	02-Feb-21	08-Feb-21	Paint Railings & Finish P	
	Install Light Fixtures - Stair 3	2	09-Feb-21	10-Feb-21	I Install Light Fixtures - St	
	Seal Concrete Floor - Stair 3	5	26-Feb-21	04-Mar-21	Seal Concrete Floor	- Stair 3
Hardscapes	& Landscaping					
5500	Install Hardscapes & Landscaping	45	05-Feb-21	09-Apr-21	Install Hardsca	apes & Landscaping
General						
GEN-1000	Install Building Signage	15	11-Mar-21	31-Mar-21	Install Building S	Jignage
Commission	ling					
	Commission MEPs	60	31-Mar-21	24-Jun-21		ommission MEPs
	, Inspections & Occupancy					
Plumbing S						
	Perform Potable Water Chlorination	5	12-Mar-21	18-Mar-21	Perform Potable V	Nater Chloringtion
	Issue Potable Water Chlorination Report	0	12-10101-21	18-Mar-21		ter Chloring tion Report
	· ·	0		10-1111-21		
Water & Sev	-		40 Max 04	40 Max 04		
	Acquire GSA Permit	1	19-Mar-21	19-Mar-21	Acquire GSA Pern	at i i i i i i i i i i i i i i i i i i i
- · ·	Power System & Power Outage Testing			1		
	Ceilings, Lights & Exit Signs Complete	0		19-Mar-21	◆ Ceilings, Lights &	
	Pre-test for Lights Out Testing	1	22-Mar-21	22-Mar-21	I Pre-test for Lights	
LSI-1300	Correct Issues for Brookline Lights Out Testing	2	23-Mar-21	24-Mar-21	Correct Issues for	or Brookline Lights Out Testing
LSI-1320	Perform Lights Out Testing with Brookline	1	25-Mar-21	25-Mar-21	I Perform Lights O	Out Testing with Brookline
Fire Alarm S	System					
LSI-1030	Test Fire Alarm - Basement Level Devices, Speakers & Duct Smokes	2	03-Mar-21	04-Mar-21	I Test Fire Alarm - Bas	sement Level Devices, Speakers & Duct Smokes
	NFPA 72 Fire Alarm Testing	21	03-Mar-21	31-Mar-21	NFPA 72 Fire Al	
	Test Fire Alarm - L1 Devices, Speakers & Duct Smokes	2	05-Mar-21	08-Mar-21		Devices, Speakers & Duct Smokes
LSI-1090	Test Fire Alarm - L2 Devices, Speakers & Duct Smokes	2	09-Mar-21	10-Mar-21		2 Devices, Speakers & Duct Smokes
LSI-1030	Test Fire Alarm - L3 Devices, Speakers & Duct Smokes	2	11-Mar-21	12-Mar-21		3 Devices, Speakers & Duct Smokes
	· ·					
LSI-1370	Submit Record of Completion (ROC) to Brookline	5	01-Apr-21	07-Apr-21		I of Complețion (ROC) to Brookline
LSI-1420	Brookline ROC NFPA 72 Test	3	08-Apr-21	12-Apr-21	Brookline ROC	JINFPA / 2 IESL
Elevators		1				
LSI-1310	Preliminary Test Elevator with Fire Alarm Recall	3	10-Mar-21	12-Mar-21		evator with Fire Alarm Redall
LSI-1390	Complete Elevator Cleaning & Adjustment for Inspection	10	15-Mar-21	26-Mar-21		or Cleaning & Adjustment for Inspection
LSI-1470	Complete Phone Service to Elevators	0		26-Mar-21	Complete Phone	Service to Elevators
Remaini	ng Level of Effort Remaining Work		Page	15 of 16	TASK filter: % Complete <100.	
	evel of Effort Critical Remaining Work		Faye			
					© Oracle Corporation	
Actual L	0				ige 87 of 377	

Brookline High Sc	hool - Project C - 10Feb20 R1 Schedule Update - 1318015-CR - B22			I	etailed Schedule Data Date: 10-Feb-20 / Run Date: 09-Jul-20 08:54
Activity ID	Activity Name	Remaining	Start	Finish	
		Duration			2020 2021 2022
					F Mar Apr M Jun Jul Aug S Oct N D Jan F Mar Apr M Jun Jul A S Oct N Dec Jan F Mar Apr M Jun Jul A S Oct N
LSI-1480	State (Mass 524) Inspection & Signoff	3	29-Mar-21	31-Mar-21	State (Mass 524) Inspection & Signoff
Fire Protect	tion System				
LSI-1000	Flow Test Fire Protection System	5	22-Mar-21	26-Mar-21	Flow Test Fire Protection System
LSI-1020	Checkout Tampers & Flows	1	29-Mar-21	29-Mar-21	Checkout Tampers & Flows
LSI-1350	Test Stand Pipe & Floor Control Valves with PRVs - Stair 2	2	30-Mar-21	31-Mar-21	Test Stand Pipe & Floor Control Valves with PRVs - Stair 2
LSI-1520	Test Stand Pipe & Floor Control Valves with PRVs - Stair 3	2	01-Apr-21	02-Apr-21	Test Stand Pipe & Floor Control Valves with PRVs - Stair 3
LSI-1450	Brookline Fire Protection Test	1	13-Apr-21	13-Apr-21	Brookline Fire Protection Test
Final Inspe	ctions & C of O				
INSP-1050	Owner Install FF&E	10	18-Mar-21	31-Mar-21	Owner Install FF&E
LSI-1230	Final Plumbing Signoff	1	19-Mar-21	19-Mar-21	I Final Plumbing Signoff
LSI-1340	Final Electrical Signoff	1	26-Mar-21	26-Mar-21	I Final Electrical Signoff
INSP-1030	Complete Punch List	20	13-Apr-21	11-May-21	Complete Punch List
LSI-1490	Final Life Safety Wak-thru	2	14-Apr-21	15-Apr-21	Final Life Safety Wak-thru
LSI-1460	Receive Final Architectural, Mechanical & Structural Affadavits	2	16-Apr-21	20-Apr-21	Receive Final Architectural, Mechanical & Structural Affadavits
	Final Building Sigh Off Acquire C of O	5	21-Apr-21	27-Apr-21	Final Building Sigh Off Acquire C of O
	STEM Interim Completion Date	0	· ·	27-Apr-21*	STEM Interim Completion Date
	Move-in to New STEM Wing	10	28-Apr-21	11-May-21	Move+in to New STEM Wing

Remaining Level of Effort Remaining Work	Page 16 of 16	TASK filter: % Complete <100.	
Actual Level of Effort Critical Remaining Work		© Oracle Co	poration
Actual Work Milestone	Page 8	8 of 377	

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT E: SCHEDULE OF VALUES

See attached worksheets

Guaranteed Maximum Price Submission Revision Number: 001 Date: July 10, 2020

EXHIBIT E – SCHEDULE OF VALUES

10.15.0.015.0015.011 Grand Inquerements S 1.88.1.13 S 2.402.025 S 2.400.000 PROUCE At 31.1 Operation S S 0.800.000 S 2.400.000 SUBCET At 31.1 Operation S S 1.88.1.16 S S SUBCET At 31.1 Operation Find Cleaning S S 1.88.1.16 S SUBCET AT 31.0 Operation Find Cleaning S S 1.80.0.00 S SUBCET AT 31.0 Operation S S S S S S SUBCET AT 31.0 Operation S S S S S S S SUBCET AT 31.0 Operation S S S S S S S S SUBCET AT 31.0 Operation S S S S S S S S S S SUBCET AT 31.0 Operation S S S S S S S S S S SUBCET AT 31.0 Operation S S S S S S S S S S S SUBCET AT 31.0 Operation S S S S S S S S S<		DESCRIPTION OF WORK	Summary of Pre GMP Amendments 1 to 18	GMP AMENDMENT VALUE	TOTAL GMP VALUE
Direct Carts to its Assigned to its Parkages \$ 0 0	PROJECTS A AND B				
Second B S Image: Second B SUBCRT M. 11 Corrests 5 - - SUBCRT M. 12 Corrests 5 - 5 - SUBCRT M. 12 Corrests 5 - 5 - 77.444 700 700.0720000 5000 Berneliton and Abstrement 5 331.685 - 5 331.685 700 700.0720000 5000 Machinery allowance 5 1.02.000 5 1.02.000 700 700.0720000 5000 Maconny Bernet Monoson 5 1.02.000 5 3.28.949 700 700.072000 5000 Maconny Moduly 5 5.04.97.07 - 5 6.2.02.00 700 700.072000 5000 Maconny Moduly 5 5.04.97.07 - 5 3.2.00 700 700.072000 5000 Maconny Moduly 5 5.04.97.00 - 5 3.2.00 700 700.072000 5000 Maconny Moduly 5 5.04.97.00 - 5 3.2.00 700 700.07200 5000 Domina Maconny Moduly 5 5.04.97.00 - 7.0.98.87.00 700 700.07200 50000 Domina M	100.150.01500000.5031	General Requirements	\$ 1,838,113	\$ 2,962,525	\$ 4,800,638
PROLET A: LI Liggens Interview S Image: Signal and Signal Activity of Si		Direct Costs to Be Assigned to Bid Packages	\$ -	\$ 2,003,000	\$ 2,003,000
SUBCONTRACTS (D0) Final Clearing S - Image Final Clearing S 31.088 S 7.72,408 S 7.72,408 200 2000 202000 0020 Montoring Risewire S 31.020 S 7.72,408 200 2000 20200 0020 Montoring Risewire S 2.020,002 S 7.72,408 200 2000 20200 0020 Montoring Risewire S 1.020,002 S 1.020,002 200 2000 20200 00200 Preast Contert S 0.427,27 C S 6.323,99 200 200 0000 00200 Preast Contert S 0.042,77 C S 5.027,550 C S 5.020,550 C S 5.020,550 C S 5.020,550			\$ -		
Find Clamming S 1 21,24.68 \$ 173,448 202 20202005 0500 Monitoring Allowarce \$ 231,028 \$ 331,028 202 202021 52000 Support of Council and Abatement \$ 1,102,020 \$ 5 1,202,000 202 2020,2150000,0200 Support of Council and Abatement \$ 4,503,020 \$ 5 2,203,000 \$ 5 2,203,000 \$ 5 2,203,000 \$ 5 2,203,000 \$ 5 5,203,000 \$ 5 5,607,500 \$ 5,607,500 \$ 5,607,500 \$ 5,607,500 \$ 5,607,500 \$ 7,503,000 \$ 2,202,203,000 2,000,203 \$ 2,202,203,000 \$ 2,202,203,000 \$ 2,202,203,000 \$ 2,202,203,000 \$ 2,202,203,000 \$ 2,202,203,000 \$ 2,202,203,000 \$ 2,202,203,000 \$ 2,202,203,000 \$ 2,202,203,000 \$ 2,202,203,000 \$ 2,202,203,000 \$ 2,202,203,000			ć		
100.200.202000.520 Montoniand Abservert \$ 313.68 \$ 313.68 200.200.220000.520 Support of Excretion \$ 1,102.000 \$ 1,102.000 200.200.23000.0500 Stateoff Ad foundations \$ 4,540.52 \$ 5 4,540.52 \$ 5 4,540.52 \$ 5 4,540.52 \$ 3,397.99 200.200.25000.0500 Miscory Miscore \$ 3,297.97 \$ 223.04 \$ 3,397.99 200.200.45000.0500 Miscory Miscore \$ 3,247.97 \$ 23.344 \$ 3,397.99 200.200.45000.0500 Miscory Miscore \$ 3,247.97 \$ 23.346 \$ 3,397.99 200.200.45000.0500 Miscore \$ 3,347.97 \$ 23.346 \$ 3,347.99 200.200.45000.0500 Simes framework \$ 3,347.99 \$ 3,347.99 200.200.51200.05200 Done, frame framework \$ 3,347.99 \$ 3,349.99 \$ 3,349.99	SUBCONTRACTS (SDI)	Final Cleaning		¢ 172.469	¢ 172.469
202.200.025200 Support of Seavation \$ 1.200.00 \$ 1.302.00 202.200.02450005.920 Strework and Foundations \$ 4.506.52 \$ 3.497.98 202.200.02450005.920 Strework and Foundations \$ 4.262.20 \$ 3.397.99 \$ 3.23.94 \$ 3.23.94 \$ 3.23.94 \$ 3.23.94 \$ 3.23.94 \$ 3.23.94 \$ 5.23.94 \$ 5.23.94 \$ 5.23.94 \$ 5.23.94 \$ 5.23.94 \$ 5.23.94 \$ 5.23.94 \$ 5.23.94 \$ 5.23.94 \$ 5.23.94 \$ 5.23.94 \$ 5.23.94 \$ 5.23.94 \$ 5.23.94 \$ 5.39.92 \$ 5.23.92 \$ 5.39.92 \$ 5.23.93 \$ 5.38.93 \$ \$ 5.38.93 \$ \$ 5.38.93 \$ \$ 5.38.93 \$ \$ 5.38.93 \$ \$ 5.38.93 \$ \$ \$ \$	200 200 02220000 5020			\$ 173,408	
200.200.23000.5500 Support of Excavation \$ 1.102.600 \$ 5 3.4940,542 200.200.245000.5500 Cencrete \$ 3.997,993 \$ 5.23,948 \$ 3.937,993 200.200.0450000.500 Precist Concrete \$ 0.242,072 \$ 5.23,948 \$ 3.33,948 200.200.04510000.500 Maximy (Mok Upi) \$ 1.64,85 \$ 2.20,200.21,200,200 \$ 2.20,200.21,200,200 \$ 2.22,200,200 \$ 2.22,200,200 \$ 2.22,200,200 \$ 2.22,200,200 \$ 2.22,200,200 \$ 2.22,200,200 \$ 2.22,200,200,200,200,200 Curante Hardware \$ 3.83,000 \$ \$ 7.23,33 2000,200,200,200,200,200,200,200,200 Droyn, Franes Hardware \$ 3.83,000 \$ \$ 7.23,33 \$ \$ 7.23,33 \$ \$ 7.23,33 \$ \$ 7.23,33 \$ \$ 7.23,33 \$ \$ 7.23,33 \$ \$ 7.23,33,300 \$ \$ 7.23,3			, ,		
200.200.04/0001.5202 Cancrete \$ 3.927,993 \$ 5.323.94 200.200.05/0000.5202 Precast Concrete \$ 6.24,727 \$ 6.6437 200.200.05/00000.5202 Macory (Mock Up) \$ 6.4647 \$ 5.607,850 \$ 2.00,200,021 \$ 6.647 200.200.0512000.05020 Steel \$ 5.007,850 \$ 2.00,200,021 \$ 6.647,900 Doors, Frame Markwine \$ 0.1500 \$ 2.000,021 \$ 6.73,931 \$ 7.73,931 \$ 7.73,931 200.200.095/2000 Doryall \$ 6.47,500 \$ 6.43,600 \$ 4.600 200.200.095/2000 Drywall \$ 6.47,500 \$ 4.30,600 \$ 1.00,485 \$ 1.000,485 \$ 1.000,485 1.000,485 \$ 1.000,485 \$ 1.000,485 \$ 1.000,485 \$ 1.000,485 \$ 1.000,485 \$ 1.000,485 \$ 1.000,485 \$ 1.000,485 \$ </td <td></td> <td></td> <td>\$ 1,102,600</td> <td></td> <td></td>			\$ 1,102,600		
Str Concrets \$ 5 5 523,242 \$ 523,242 200.200.0400000.5020 Masony (Mok Up) \$ 16,459 \$ 6,44,727 200.200.052000 Stel \$ 5,05,050 \$ 5,627,650 200.200.052000 Stel \$ 15,075,050 \$ 2,222,233 200.200.052000 Dors, Frames Hardware \$ 119,075 \$ 2,222,233 200.200.052000 Dors, Frames Hardware \$ 100,085 \$ 7,538 \$ 7,538 \$ 7,538 \$ 7,538 \$ 7,538 \$ 7,538 \$ 7,538 \$ 7,538 \$ 7,538 \$ 7,538 \$ 7,538 \$ 7,538 \$ 7,538 \$ 7,538 \$ 7,538 \$ 7,538 \$ 7,548 \$ 7,548 \$ 7,548 \$ 7,548 \$ 7,548 \$ 7,548 \$ 7,548 \$ 7,549 \$ 7,548	200.200.02450000.5020	Sitework and Foundations			\$ 4,540,542
200.200.0940000 5020 Misory (Mock Up) \$ 64.4727 \$ 64.4727 200.200.0512000 5020 Steel \$ 5.607.650 \$ 5.607.650 Millwork \$ 15.175 \$ 2.070.258 \$ 2.222.33 Outhoad Doors \$ \$ 5.7538 \$ 6.153.00 Outhoad Doors \$ \$ 7.153.451 \$ 7.153.451 200.200.08210000.5020 Curtarwall \$ 7.153.451 \$ 7.153.451 200.200.0220005.5020 Drawall \$ 6.477.000 \$ \$ 6.477.000 Carpet And Doors \$ 3.89.000 \$ \$ 9.138.000 \$ 4.67.000 \$ \$ 4.67.000 \$ \$ 9.29.000 \$ \$ 9.29.000 \$ \$ 9.20.001.43.000 \$ 9.29.000 \$ \$ 9.29.000 \$ \$ 9.29.000 \$ \$ 9.29.000 \$ \$ 9.29.000 \$ \$ 9.29.000	200.200.03400010.5020		, ,		. , , ,
200.200.0450000.5020 Masory (Mock Up) \$ 16,459 \$ 5,67,560 \$ \$ 5,67,560 Milkork \$ 115,975 \$ 2,070,258 \$ 2,222,235 Deors, Frames Hardware \$ 615,900 \$ - \$ 615,900 Deors, Frames Hardware \$ 7,158,815 \$ 7,538 \$ 7,389,900 200.200.0930005.5020 Curvail \$ 6,475,000 \$ \$ 6,475,000 100.00230005.5020 Curvail \$ 6,475,000 \$ \$ 4,4800 \$				\$ 523,984	
200.200.05120000 S020 Steel \$ 5,507,650 \$ 2,702.88 \$ 2,222.28 Firepoofing \$ 615,500 \$ 0.5380 \$ 2,723.88 \$ 2,222.28 Operhead Dors \$ 0.5380 \$ 7,538 \$ 7,538 \$ 7,538 Doors, Frame, Hardware \$ 380,000 \$ 7,538 \$ 7,538 \$ 7,538 200.200.05910000 S020 Curtainwall \$ 7,548,51 \$ 7,558,51 \$ 7,558,51 200.200.0592000 S020 Curtainwall \$ 0.6475,000 \$ 46,000,63 \$ 46,000,63 Mesinous Hooring \$ 0.5 \$ 0.100,455 \$ 0.100,485 \$ 0.9566 Mesinous Hooring \$ 0.15,000 \$ 7,34,500 \$ 0.352,005 \$ 39,200 </td <td></td> <td></td> <td></td> <td></td> <td></td>					
Milwork S 115,1975 S 2,070,285 S 2,222,235 Overhead Doors S <td></td> <td></td> <td>. ,</td> <td></td> <td></td>			. ,		
Interprofing \$ 619,500 \$ > \$ 7,938 \$ 7,7398 <th< td=""><td>200.200.03120000.3020</td><td></td><td> , ,</td><td>\$ 2,070,258</td><td></td></th<>	200.200.03120000.3020		, ,	\$ 2,070,258	
Overhead Doors 5 7.9.98 \$ 7.9.98 Doors, Frames Hardware 5 8.99,000 \$ \$ 8.99,000 200.200.0820000.5020 Drywall \$ 6.75,500 \$ 6.475,000 Carpet \$ 1.00,485 \$ 100,485 Reinous Flooring \$ 4.500 \$ 4.38,00 Mite: Specialtes \$ 4.500 \$ 4.36,00 Signage \$ 1.50,00 \$ 7.5,98 Jood Service \$ 17,500 \$ 7.35,00 \$ 7.5,200 Window Shades (Allowance) \$ 1.50,200 \$ 158,200 \$ 158,200 Operable Wall \$ \$ 5.00,132 \$ 30,210 Laboratory Casework \$ 111,000 \$ 30,210 \$ 30,220 Denable Wall \$ \$ 5,425 \$ 5,4425 200.200.14200000 5020 Elevators \$ 812,693 \$ 71,948 \$ 72,200 200.200.14200000 5020 Macionsul \$ 6,550 \$ 71,948 \$ 2,423,000 200.200.0400020 5020 Macionsul \$ 2,430,000 \$ 2,430,000 \$ 2,					
202.02.0910000.5200 Curtainvall \$ 7,159,81 \$ \$ 7,159,81 200.200.09250005.5200 Carpet \$ 6,475,000 \$ 100,485 \$ 100,485 Carpet \$ 6,475,000 \$ 43,800 \$ 43,800 Misc. Specialities \$ 15 466,000 \$ 446,000 Signage \$ 17,500 \$ 734,500 \$ 734,500 Window Shades (Allowance) \$ 110,000 \$ 361,324 \$ 372,232 Carbotardor Casework \$ 110,000 \$ 361,324 \$ 372,232 Carbotardor Casework \$ 110,000 \$ 361,324 \$ 372,232 Carbotardor Casework \$ 83,838 \$ 166,711 \$ 166,711 200.200.1420000.5020 Elevators \$ 832,838 \$ 156,713 \$ 1319,916 200.200.040002.5020 Maiony \$ 2,830,000 \$ <					
201200.09250005 5020 Drywall \$ 6.475.000 \$ \$ 10.04.85 \$ 10.02.85 \$ 10.02.85 \$ 10.02.85 \$ 10.02.85 \$ 10.02.85 \$ 10.02.85 \$ 10.02.85 \$ 10.02.85 \$ 10.02.85 \$ 10.02.85 \$ 10.02.85 \$ 10.02.85 \$ 10.02.85 \$ 10.02.85 \$ <td></td> <td>Doors, Frames Hardware</td> <td>\$ 389,000</td> <td></td> <td>\$ 389,000</td>		Doors, Frames Hardware	\$ 389,000		\$ 389,000
Carpet S S 100.485 S 100.485 Reinous-Flooring S S A3.800 \$ 34.800 Misc. Specialties S S 36.600.6 \$ 466.000.6 Sigrage S 1.5 39.866.6 \$ 99.866 \$ Window Shades (Allowance) S 1.5 30.210.5 \$ 78.200 Operable Wall S 1.5 30.210.5 \$ 78.200 Ubordstrop:Casework S 1.000 \$ 61.324.5 \$ \$ 200.200.14200000.5020 Elevators S 822.893 \$ \$ 822.893 Audiovisal S 6.900 \$ 71.914 \$ 72.242.915 TRADE CONTRACTS (DONOSI) Macony S 2.830.000 \$ 2.830.000 \$ 2.830.000 \$ 2.830.000 \$ 2.830.000 \$ 2.830.000 \$ 2.830.000 \$ 2.830.000 \$ 2.830.000 \$ <t< td=""><td>200.200.08910000.5020</td><td>Curtainwall</td><td></td><td></td><td></td></t<>	200.200.08910000.5020	Curtainwall			
Resinous, Flooring \$	200.200.09250005.5020				
Misc. psecialities \$ - \$ 466,000 \$ 446,000 Signage \$ - \$ 93,866 \$ 93,866 \$ 93,866 \$ 93,866 \$ 93,866 \$ 93,820 \$ 158,200 \$ 158,200 \$ 100,100,100,100 \$ 100,100,100,100 \$ 100,100,100,100,100,100 \$ 100,100,100,100,100,100,100,100,100,100					
Signage \$ 5 93,866 \$ 93,866 Food Service \$ 174,000 \$ 723,000 Operable Wall \$ - \$ 188,200 \$ 178,200 Operable Wall \$ - \$ 30,210 \$ 302,210 Theatre Oragery \$ 5 5 \$ 54,423 \$ <td< td=""><td></td><td></td><td></td><td>,</td><td></td></td<>				,	
Food Service § 1734,500 § 734,500 § 734,500 § 732,500 § 158,200 § 158,200 § 158,200 § 158,200 § 158,200 § 138,200 § 138,201 § 138,201 § 138,201 § 138,201 § 138,201 § 138,201 § 138,201 § 138,201 § 14,425 § 14,425 § 14,425 § 14,425 § 14,425 § 14,425 § 14,425 § 14,425 § 14,425 \$ 14,425 \$ 14,425 \$ 14,425 \$ 14,425 \$ 14,425 \$ 14,329,415 \$ 14,329,415 14,329,415 14,329,415 14,329,415 14,329,415 14,329,415 14,329,415 14,329,415 14,329,415 14,329,415 14,329,415 14,329,415 14,329,415 14,329,415 14,329,415 14,329,415 14,329,415 14,323,415 14,339,415					
Window Shades (Allowance) \$ 158,200 \$ 158,200 Operable Wall \$ \$ 30,210 \$ 30,210 \$ 30,210 \$ 30,210 \$ 30,210 \$ 30,210 \$ 30,210 \$ 30,210 \$ 30,210 \$ 30,210 \$ 30,210 \$ 30,210 \$ 30,210 \$ 30,210 \$ <td></td> <td></td> <td></td> <td>,</td> <td></td>				,	
Operable Wall S 3.0210 \$ 30,210 Laboratory Casework 5 11,00 \$ 361,324 \$ 372,224 Thestre Drapery \$ \$ \$ 54,425 \$ 372,224 200.200.14200000.5020 Elevators \$ 822,893 \$ \$ 882,283 200.200.14200000.5020 Elevators \$ 822,893 \$ \$ 882,283 200.200.14200000.5020 Elevators \$ 820,000 \$ \$ 1,319,916 7RADE CONTRACTS (BONDS) 2 \$ 1,319,916 \$ 1,319,916 \$ 1,319,916 7RADE CONTRACTS (BONDS) 2 \$ \$ 2,342,185 \$ 2,342,					
Laboratory Casework \$ 11,000 \$ 361,324 \$ 372,224 Interito Propery \$ \$ \$ \$4,425 \$ \$4,425 \$ \$4,425 \$ \$4,425 \$ \$4,245 \$ \$6,213 \$ \$6,213 \$ \$6,213 \$ \$6,2283 \$ \$ \$6,2283 \$ \$ \$6,2283 \$ \$ \$6,2283 \$ \$ \$6,2283 \$ \$ \$6,22830 \$ \$ \$6,2830,000 \$ \$2,830,000 \$ \$2,830,000 \$ \$2,830,000 \$ \$2,830,000 \$ \$2,830,000 \$ \$2,830,000 \$ \$2,830,000 \$ \$2,830,000 \$ \$2,830,000 \$ \$2,830,000 \$ \$ \$2,830,000 \$ \$ \$2,830,000 \$ \$2,830,000 \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$<				. ,	
Theatr Drapery \$ 5 5 54,425 \$ 54,425 200.200.14200000.5020 Elevators \$ 832,893 \$ 166,711 \$ 832,893 Audiovisual \$ 6,950 \$ 719,348 \$ 726,298 TRADE CONTRACTS (BONDS)) Landscape / Hardscape \$ 8,280,000 \$ 2,339,016 \$ 1,319,916					
200.200.14200000.5020 Elevators \$ 832,893 \$ 832,893 Audiovisal \$ 6,950 \$ 719,348 \$ 726,293 TRADE CONTRACTS (BONDS)) Iandiscape / Hardscape \$ 1,319,916 \$ 1,319,916 TRADE CONTRACTS (BONDS)) Masonry \$ 2,330,000 \$ 2,330,000 200.200.0400020.5020 Masonry \$ 2,342,185 \$ 2,342,185 200.200.0710000.5020 Waterproofing (Above Grade) \$ 815,066 \$ 813,060 200.200.0750000.5020 Roofing \$ 1,014,000 \$ 1,034,000 200.200.0750000.5020 Roofing \$ 1,015,000 \$ 1,034,000 200.200.09510000.5020 Resiltent Floor \$ 41,2335 \$ 41,2335 200.200.09510000.5020 Ferrazo \$ 95,1,311 \$ 95,1,331 200.200.0950000.5020 Ferrazo \$ 7,441,360 \$ 1,893,000 200.200.1500000.5020 Flerr Protection					
Audiovisual \$ 6,950 \$ 719,348 \$ 726,298 TRADE CONTRACTS (BONDS)) Iandscape / Hardscape \$ 1,319,916 \$ 1,319,916 \$ 1,319,916 \$ 1,319,916 \$ 1,319,916 \$ 1,319,916 \$ 1,319,916 \$ 1,319,916 \$ 1,319,916 \$ 1,319,916 \$ 1,319,916 \$ 1,319,916 \$ 1,319,916 \$ 1,319,916 \$ 1,319,916 \$ 1,319,916 \$ 1,319,916 \$ 1,319,916 \$ 1,319,916 \$ 1,339,900 \$ 2,342,185 \$ 2,342,185 \$ 2,342,185 \$ 2,342,185 \$ 2,342,185 \$ 2,342,185 \$ 2,342,185 \$ 2,342,185 \$ 2,342,185 \$ 2,342,185 \$ 2,342,185 \$ 2,342,185 \$ 2,342,185 \$ 2,342,185 \$ 2,342,185 \$ 2,342,185 \$ 1,213,500 \$ 1,213,500 \$ <		Stage/Theater Equipment	\$-	\$ 166,711	\$ 166,711
Landscape / Hardscape \$ 1,319,916 \$	200.200.14200000.5020	Elevators	\$ 832,893		\$ 832,893
TRADE CONTRACTS (BONDS)) Autors S 2,830,000 \$ 2,830,000 200.200.400020.5020 Miss. Metal \$ 2,830,000 \$ 2,830,000 200.200.5500000.5020 Miss. Metal \$ 2,830,000 \$ 2,830,000 200.200.710000.5020 Waterproofing (Below Grade) \$ 153,713 \$ 153,713 200.200.7500000.5020 Roofing \$ 1,213,500 \$ 1,213,500 200.200.0200.05020 Interior Glass \$ 1,015,800 \$ 1,015,800 200.200.09510000.5020 Acoustic Cellings \$ 1,059,000 \$ 1,059,000 200.200.0950000.5020 Resiltent Floor \$ 412,333 \$ 9 200.200.0950000.5020 Paint \$ 34,000 \$ 334,000 200.200.15300000.5020 Plumbing \$ 1,893,000 \$ 1,893,000 200.200.15400000.5020 Plumbing \$ 1,893,000 \$ 1,893,000 200.200.154000000.5020 Electric \$		Audiovisual	\$ 6,950	· · · ·	· •
200.200.400020.5020 Misc. Metal \$ 2,330,000 \$ 2,342,185 \$ 2,342,185 200.200.0710000.5020 Waterproofing (Below Grade) \$ 8,51,713 \$ 153,713 200.200.0710000.5020 Waterproofing (Above Grade) \$ 851,060 \$ 851,060 200.200.0710000.5020 Roofing \$ 1,213,500 \$ 1,213,500 200.200.0930000.5020 Interior Glass \$ 1,004,000 \$ 1,004,000 200.200.0951000.5020 Tile \$ 1,015,000 \$ 1,015,000 200.200.0950000.5020 Resilient Floor \$ 412,335 \$ 412,335 200.200.0950000.5020 Terrazzo \$ 951,131 \$ 951,131 200.200.15300000.5020 Fire Protection \$ 789,125 \$ 789,125 200.200.15300000.5020 Fire Protection \$ 7,441,500 \$ 7,441,500 200.200.1600000.5020 HVAC \$ 7,441,500 \$ 7,441,500 200.200.160		Landscape / Hardscape		\$ 1,319,916	\$ 1,319,916
200.200.05500000.5020 Misc. Metal \$ 2,342,185 \$ 2,342,185 200.200.0710000.5020 Waterproofing (Below Grade) \$ 153,713 \$ 153,713 200.200.0710000.5020 Roofing \$ 1,213,500 \$ 1,213,500 200.200.07500000.5020 Roofing \$ 1,204,000 \$ 1,213,500 200.200.0810000.5020 Interior Glass \$ 1,004,000 \$ 1,005,000 200.200.09510000.5020 Tile \$ 1,015,800 \$ 1,015,800 200.200.09510000.5020 Resilient Floor \$ 412,335 \$ 412,335 200.200.09500000.5020 Terrazo \$ 951,131 \$ 951,133 200.200.09400000.5020 Fire Protection \$ 789,125 \$ 789,125 200.200.15400000.5020 Fire Protection \$ 789,125 \$ 789,125 200.200.15400000.5020 Humbing \$ 1,893,000 \$ 1,893,000 200.200.15400000.502	· · · · · · · · · · · · · · · · · · ·		4		
200.200.0710000.5020 Waterproofing (Below Grade) \$ 153,713 \$ 153,713 200.200.07100010.5020 Waterproofing (Above Grade) \$ 851,060 \$ 851,060 200.200.0750000.5020 Roofing \$ 1,213,500 \$ 1,213,500 200.200.08810000.5020 Interior Glass \$ 1,015,800 \$ 1,004,000 \$ 1,004,000 200.200.0950000.5020 Acoustic Cellings \$ 1,015,800 \$ 1,015,800 200.200.0950000.5020 Resilient Floor \$ 412,335 \$ 412,335 200.200.09400000.5020 Terrazo \$ 334,000 \$ 1,839,000 200.200.15400000.5020 Fire Protection \$ 7,89,125 \$ 7,89,125 200.200.15400000.5020 Fire Protection \$ 7,441,500 \$ 7,441,500 200.200.15400000.5020 Hird \$ 7,441,500 \$ 7,441,500 \$ 7,441,500 \$ 7,441,500 \$ 7,441,500 \$ 7,441,500 \$ 7,441,500 \$ 7,441,500 \$ 7,441,500 \$					
200.200.07100010.5020 Waterproofing (Above Grade) \$					
200.200.0750000.5020 Roofing \$ 1,213,500 \$ 1,213,500 200.200.08810000.5020 Interior Glass \$ 1,004,000 \$ 1,004,000 200.200.09930000.5020 Tile \$ 1,015,800 \$ 1,015,800 200.200.09510000.5020 Acoustic Cellings \$ 1,059,000 \$ 1,059,000 200.200.09650000.5020 Resilient Floor \$ 412,335 \$ 412,335 200.200.09650000.5020 Terrazzo \$ 951,131 \$ 951,131 200.200.0960000.5020 Fire Protection \$ 789,125 \$ 789,125 200.200.15400000.5020 Plumbing \$ 1,893,000 \$ 1,893,000 200.200.1570000.5020 HVAC \$ 7,441,500 \$ 1,493,000 200.201.15400000.5020 HUMDing \$ 4,096,000 \$ 0,996,000 200.201.1570000.5020 HVAC \$ 7,441,500 \$ 1,493,000 200.201.1570000.5020 HVAC \$ 7,441,500 \$ 1,493,000 200.201.1570000.5020 HVAC \$ 7,441,500 \$ 1,493,000 200.201.1570000.5020 Electric \$ 4,096,000 \$ 0,902,000 200.201.1570000.5020 Electric<					
200.200.08810000.5020 Interior Glass \$ 1,004,000 \$ 1,004,000 200.200.0930000.5020 Tile \$ 1,015,800 \$ 1,015,800 200.200.0950000.5020 Acoustic Cellings \$ 1,059,000 \$ 1,059,000 200.200.0950000.5020 Resilient Floor \$ 412,335 \$ 412,335 200.200.0940000.5020 Terrazzo \$ 951,131 \$ 951,133 200.200.01540000.5020 Paint \$ 334,000 \$ 334,000 200.200.15300000.5020 Plumbing \$ 1,893,000 \$ 1,893,000 200.200.15400000.5020 Plumbing \$ 1,893,000 \$ 1,893,000 200.200.15400000.5020 HVAC \$ 7,441,500 \$ 7,441,500 200.200.16000000.5020 Electric \$ 4,096,000 \$ 4,096,000 200.200.1600000.5020 Electric \$ 4,096,000 \$ 4,096,000 PROJECT B: Tappan Gym \$ 1,001,000 SUBCONTRACTS (BONDS)) \$ 1,002,000 \$ 2,14,050 \$ 2,14,050 SUBCONTRACTS (SDI) \$ 1,512,041 \$ 1,512,041 \$ 2,580,500 \$ 2,580,500 <td></td> <td></td> <td></td> <td></td> <td></td>					
200.200.0930000.5020 Tile \$ 1,015,800 \$ 1,015,800 200.200.0951000.5020 Acoustic Cellings \$ 1,059,000 \$ 1,059,000 200.200.095000.5020 Resilient Floor \$ 412,335 \$ 412,335 200.200.095000.5020 Terrazzo \$ 951,131 \$ 951,131 200.200.09000.5020 Paint \$ 334,000 \$ 334,000 200.200.15300000.5020 Plumbing \$ 1,893,000 \$ 1,893,000 200.200.1540000.5020 Plumbing \$ 1,893,000 \$ 1,893,000 200.200.1570000.5020 HVAC \$ 7,441,500 \$ 7,441,500 200.200.1600000.5020 Electric \$ 4,096,000 \$ 4,096,000 PROJECT B: Tappan Gym SUBCONTRACTS (BONDS)) Final Cleaning \$ \$ 102,000 \$ 214,055 300.300.00206000.5020 Scaffold and Overhead Protection \$ 102,000 \$ 214,055 300.300.00206000.5020 Scaffold and Overhead Protection \$ 102,000 \$ 214,055 300.300.00206000.5020 Scaffold and			, ,		
200.200.09510000.5020 Acoustic Ceilings \$ 1,059,000 \$ 1,059,000 200.200.09650000.5020 Resilient Floor \$ 412,335 \$ 412,335 200.200.0900000.5020 Terrazzo \$ 951,131 \$ \$ 951,131 200.200.0900000.5020 Paint \$ 334,000 \$ \$ 334,000 200.200.15300000.5020 Plumbing \$ 1,889,000 \$ \$ 1,899,000 200.200.15400000.5020 Plumbing \$ 1,893,000 \$ \$ 1,899,000 200.200.1540000.5020 HVAC \$ 7,441,500 \$ 7,441,500 200.200.1500000.5020 Electric \$ 4,096,000 \$ 4,096,000 PROJECT B: Tappan Sym Image: Solid Symmetric Solid Symmetric Solid Symmetric Solid Symmetric Solid Symmetric Solid Symmetric Solid Symmetric Symmetric Solid Symmetric Symmetric Symmetric Solid Symmetric Symmet					
200.200.09400000.5020 Terrazzo \$ 951,131 \$ 951,131 200.200.090000.5020 Paint \$ 334,000 \$ 334,000 200.200.15300000.5020 Fire Protection \$ 789,125 \$ 789,125 200.200.15400000.5020 Plumbing \$ 1,893,000 \$ 1,893,000 200.200.15400000.5020 HVAC \$ 7,441,500 \$ 7,441,500 200.200.1600000.5020 Electric \$ 4,096,000 \$ 4,096,000 PROJECT B: Tappan Gym SUBCONTRACTS (BONDS)) TRADE CONTRACTS (BONDS))		Acoustic Ceilings			
200.200.090000.5020 Paint \$ 334,000 \$ 334,000 200.200.15300000.5020 Fire Protection \$ 789,125 \$ 789,125 200.200.15300000.5020 Plumbing \$ 1,893,000 \$ 1,893,000 200.200.15700000.5020 HVAC \$ 7,441,500 \$ 7,441,500 200.200.15700000.5020 Electric \$ 4,096,000 \$ 4,096,000 PROJECT B: Tappan Gym SUBCONTRACTS (SDI) \$ 4,096,000 PROJECT B: Tappan Gym SUBCONTRACTS (SDI) TRADE CONTRACTS (BONDS)) \$ 0.0000 \$ 0.00000 \$ 0.00000 SUBCONTRACTS (SDI) \$ 0.00000000000000000000000000000000000	200.200.09650000.5020	Resilient Floor	\$ 412,335		\$ 412,335
200.200.15300000.5020 Fire Protection \$ 789,125 \$ 789,125 200.200.15400000.5020 Plumbing \$ 1,893,000 \$ 1,893,000 200.200.15700000.5020 HVAC \$ 7,441,500 \$ 7,441,500 200.200.15000000.5020 Electric \$ 4,096,000 \$ 4,096,000 PROJECT B: Tappan Gym Image: Constraint of the symbolic o					
200.200.15400000.5020 Plumbing \$ 1,893,000 \$ 1,893,000 200.200.15700000.5020 HVAC \$ 7,441,500 \$ 7,441,500 200.200.15000000.5020 Electric \$ 4,096,000 \$ 4,096,000 PROJECT B: Tappan Gym SUBCONTRACTS (SDI) <					
200.200.15700000.5020 HVAC \$ 7,441,500 \$ 7,441,500 200.200.16000000.5020 Electric \$ 4,096,000 \$ 4,096,000 PROJECT B: Tappan Gym SUBCONTRACTS (SDI) TRADE CONTRACTS (BONDS)) \$ \$					
200.200.1600000.5020 Electric \$ 4,096,000 \$ 4,096,000 PROJECT B: Tappan Gym Image: Constraint of the symbol of th			*		
PROJECT B: Tappan Gym Image: Subcontracts (SDI) Image:					
SUBCONTRACTS (SDI) Image: Subscript of the system of the sys			ə 4,096,000		ə 4,096,000
TRADE CONTRACTS (BONDS)) \$ \$ \$ PROJECT C: STEM \$					
PROJECT C: STEM Final Cleaning \$	TRADE CONTRACTS (BONDS))		\$ -		\$-
SUBCONTRACTS (SDI) Final Cleaning \$ - \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 124,050 \$ \$ 124,050 \$ 2,580,500 \$ \$ 2,580,500 \$ 2,580,500 \$ \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$			\$ -		\$ -
Final Cleaning \$ - \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 102,000 \$ 124,050 \$ 124,050 \$ 124,050 \$ 124,050 \$ 124,050 \$ 124,050 \$ 124,050 \$ 124,050 \$ 124,050 \$ 124,050 \$ 124,050 \$ 124,050 \$ 124,050 \$ 124,050 \$ 124,050 \$ 124,050 \$ 124,050 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041 \$ 1,912,041					
300.300.01583500.5020 Scaffold and Overhead Protection \$ 214,050 \$ 214,050 300.300.00200020.5020 Sitework (STEM) \$ 2,580,500 \$ \$ 2,580,500 300.300.02065000.5020 Concrete (STEM) \$ 1,912,041 \$ 1,912,041 300.300.0220000.5020 Demolition and Abatement (STEM) \$ 1,515,859 \$ 369,000 300.300.02220000.5020 Demolition and Abatement (STEM) \$ 1,515,859 \$ 209,442 300.300.03400000.5020 Precast Concrete (STEM) \$ 3,00,000 \$ 3,00,000 300.300.05120000.5020 Structural Steel (STEM) \$ 3,00,000 \$ \$,00,442 300.300.07520000.5020 Structural Steel (STEM) \$ 3,00,000 \$ \$,00,442 300.300.0752000.5020 Fireprofing \$ 3,00,000 \$ \$,00,310,00,314 \$ 3,00,000 300.300.0725000.5020 Fireprofing \$ 6,8,900 \$ 5,88,900		Final Cleaning	\$ -	\$ 102,000	\$ 102,000
300.300.02000020.5020 Sitework (STEM) \$ 2,580,500 \$ 2,580,500 300.300.02065000.5020 Concrete (STEM) \$ 1,912,041 \$ 1,912,041 Site Concrete \$ 0.300,02065000.5020 \$ 1,912,041 \$ 1,912,041 Site Concrete \$ 0.300,02065000.5020 \$ 1,912,041 \$ 1,912,041 Site Concrete \$ 0.300,012,0000,000 \$ 369,000 \$ 369,000 300.300.02220000.5020 Demolition and Abatement (STEM) \$ 1,515,859 \$ 1,515,859 300.300.03400000.5020 Precast Concrete (STEM) \$ 209,442 \$ 209,442 300.300.05120000.5020 Structural Steel (STEM) \$ 3,100,000 \$ 3,100,000 Millwork \$ 10,631 177,486 \$ 1,81,117 300.300.07250000.5020 Fireproofing \$ 68,900 \$ 68,900	300.300.01583500.5020			,000	
300.300.02065000.5020 Concrete (STEM) \$ 1,912,041 \$ 1,912,041 Site Concrete \$ - \$ 369,000 \$ 369,000 \$ 369,000 \$ 369,000 \$ 369,000 \$ 369,000 \$ 369,000 \$ 369,000 \$ 369,000 \$ 369,000 \$ 369,000 \$ 369,000 \$ 369,000 \$ 369,000 \$ 369,000 \$ 369,000 \$ 369,000 \$ \$ 369,000 \$ \$ 369,000 \$ \$ 369,000 \$ \$ 369,000 \$ \$ 369,000 \$ \$ 369,000 \$ \$ 369,000 \$ \$ 369,000 \$ \$ 309,420 \$ \$ 209,442 \$ \$ 3,100,000 \$ \$ 3,100,000 \$ \$ 3,100,000 \$ \$ 3,100,000 \$ \$ 3,100,000 \$ \$ 3,100,000 \$ </td <td></td> <td></td> <td></td> <td></td> <td></td>					
300.300.0222000.5020 Demolition and Abatement (STEM) \$ 1,515,859 \$ 1,515,859 300.300.03400000.5020 Precast Concrete (STEM) \$ 209,442 \$ 209,442 300.300.05120000.5020 Structural Steel (STEM) \$ 3,000,000 \$ 3,000,000 Millwork \$ 1,0631 \$ 177,486 \$ 188,117 300.300.07250000.5020 Fireprofing \$ 68,900 \$ 68,900	300.300.02065000.5020		\$ 1,912,041		\$ 1,912,041
300.300.03400000.5020 Precast Concrete (STEM) \$ 209,442 \$ 209,442 300.300.05120000.5020 Structural Steel (STEM) \$ 3,100,000 \$ 3,100,000 Millwork \$ 10,631 \$ 177,486 \$ 188,117 300.300.07250000.5020 Fireproofing \$ 68,900 \$ 68,900				\$ 369,000	
300.300.05120000.5020 Structural Steel (STEM) \$ 3,100,000 \$ 3,100,000 Millwork \$ 10,631 \$ 177,486 \$ 188,117 300.300.07250000.5020 Fireproofing \$ 68,900 \$ 68,900					
Millwork \$ 10,631 \$ 177,486 \$ 188,117 300.300.07250000.5020 Fireproofing \$ 68,900 \$ 68,900					
300.300.07250000.5020 Fireproofing \$ 68,900 \$ 68,900	300.300.05120000.5020			A	
	200 200			\$ 177,486	
	300.300.07250000.5020 300.300.08300020.5020	Fireproofing Overhead Doors	\$ 68,900 \$ 34,446		\$ 68,900 \$ 34,446

EXHIBIT E – SCHEDULE OF VALUES

	DESCRIPTION OF WORK	Summary of Pre GMP Amendments 1 to 18	GMP AMENDMENT VALUE	TOTAL GMP VALUE
300.300.08100000.5020	Doors, Frames Hardware	\$ 157,800		\$ 157,800
300.300.08910000.5020	Curtainwall (STEM)	\$ 3,039,510		\$ 3,039,510
300.300.09250005.5020	Drywall (STEM)	\$ 3,497,950		\$ 3,497,950
300.300.09680020.5020	Carpet	\$ 13,845		\$ 13,845
	Resinous Flooring	\$ 22,845		\$ 22,845
	Misc. Specialties	\$ 135,901		\$ 135,901
	Signage	\$ 49,977		\$ 49,977
	Food Service	\$ 7,500	\$ 505,150	\$ 512,650
	Window Shades		\$ 46,625	\$ 46,625
	Laboratory Casework	\$ 30,000	\$ 959,914	\$ 989,914
300.300.1420000.5020	Elevators (STEM)	\$ 197,445		\$ 197,445
	Audio Visual	\$ 8,170	\$ 227,091	\$ 235,261
TRADE CONTRACTS (BONDS))	Landscape / Hardscape		\$ 244,644	\$ 244,644
300.300.04000010.5020	Masonry (STEM)	\$ 1,532,000		\$ 1,532,000
300.300.05000010.5020	Misc. Metal (STEM)	\$ 1,010,000		\$ 1,010,000
300.300.07100010.5020	Waterproofing (STEM Below Grade)	\$ 91,972		\$ 1,010,000
300.300.07100020.5020	Waterproofing (STEM Below Grade)	\$ 349,600		\$ 349,600
300.300.07330010.5020	Roofing (STEM)	\$ 527,675		\$ 527,675
300.300.08800000.5020	Interior Glass (STEM)	\$ 496,650		\$ 496,650
300.300.09300000.5020	Tile (STEM)	\$ 455,262		\$ 455,262
300.300.09510000.5020	Acoustic Ceilings (STEM)	\$ 593,900		\$ 593,900
300.300.09650000.5020	Resilient Floor (STEM)	\$ 339,539		\$ 339,539
300.300.09400000.5020	Terrazzo (STEM)	\$ 868,498		\$ 868,498
300.300.09900000.5020	Paint (STEM)	\$ 237,780		\$ 237,780
300.300.15300010.5020	Fire Protection (STEM)	\$ 436,922		\$ 436,922
300.300.15400010.5020	Plumbing (STEM)	\$ 1,503,800		\$ 1,503,800
300.300.15700010.5020	HVAC (STEM)	\$ 4,342,400		\$ 4,342,400
300.300.16000010.5020	Electric (STEM)	\$ 3,027,000		\$ 3,027,000
PROJECT C: Enabling				
SUBCONTRACTS (SDI)				
300.310.01406500.5020	Final Cleaning (Enabling)	\$ -		\$
300.310.0200000.5020	Sitework (Enabling)	\$ 853,300		\$ 853,300
300.310.02065000.5020	Concrete (Enabling)	\$ 263,500		\$ 263,500
300.310.07400000.5020	Roofing (Enabling)	\$ 78,000		\$ 78,000
300.310.08000000.5020	Doors, Frames, HDW (Enabling)	\$ 17,366		\$ 17,366
300.310.09250000.5020	Drywall (Enabling)	\$ 340,050		\$ 340,050
300.310.09600000.5020	Flooring (Enabling)	\$ 10,000		\$ 10,000
TRADE CONTRACTS (BONDS))	Hooring (Endoning)	\$ 10,000		<i>\$</i> 10,000
300.310.04000000.5020	Masonry (Enabling)	\$ 163,700		\$ 163,700
300.310.05000000.5020	Misc. Metals (Enabling)	\$ 86,540		\$ 86,540
300.310.07100000.5020	Waterproofing (Enabling)	\$ 61,139		\$ 61,139
300.310.09910000.5020	Painting (Enabling)	\$ 35,900		\$ 35,900
	Fire Protection (Enabling)			· ,
300.310.15300000.5020	(6)			\$ 96,263
300.310.15400000.5020	Plumbing (Enabling)	\$ 278,000		\$ 278,000
300.310.15700000.5020	HVAC (Enabling)	\$ 847,000		\$ 847,000
300.310.16000000.5020	Electric (Enabling)	\$ 383,000		\$ 383,000
PROJECT D: 3rd Floor				
SUBCONTRACTS (SDI)				
TRADE CONTRACTS (BONDS))		\$ -		\$
		\$ -		\$
PROJECT E: Streetscapes				
SUBCONTRACTS (SDI)				
TRADE CONTRACTS (BONDS))		\$ -		\$
PROJECT F: Deferred Maintenance		\$ -		\$
SUBCONTRACTS (SDI) 300.320.14400000.5020	l	ć 000.017		ć 000.041
		\$ 898,317		\$ 898,317
TRADE CONTRACTS (BONDS))		ć		ć
CURTOTAL		\$ -	¢ 44.055.074	\$
SUBTOTAL		\$ 97,391,645	\$ 14,655,874	\$ 112,047,519
100.110.01912000.5040	Subcontractor Default Insurance	\$ 693,936	\$ 130,820	\$ 824,756
PROJECT H: MBTA WORK				
400.400.02800010.5020	Enabling and OCS / Platform	\$ 11,259,791		\$ 11,259,791
TOTAL DIRECT COST		\$ 109,345,372	\$ 14,786,694	\$ 124,132,066
	Design Contingency	\$ -		\$
TOTAL DIRECT COST 100.800.23900200.5040			\$ 14,786,694 \$ (125,260)	\$
	Design Contingency	\$ -		\$

EXHIBIT E – SCHEDULE OF VALUES

	DESCRIPTION OF WORK	ummary of Pre GMP mendments 1 to 18	GMP AMENDMENT VALUE			OTAL GMP VALUE
C19.850.0000020.5020	COVID Emergency Allowance	\$ 50,000			\$	50,000
TOTAL CONTINGENCIES		\$ 3,127,067	\$	(125,260)	\$	3,001,807
100.110.01901000.5040	Builder's Risk Insurance	\$ 314,923	\$	41,052	\$	355,975
100.110.01922500.5040	C.C.I.P.	\$ 3,095,264	\$	528,393	\$	3,623,657
100.110.01903500.5040	Railroad Insurance	\$ 95,950	\$	1,971	\$	97,921
100.110.01911000.5040	Skanska Bond	\$ 897,876	\$	153,293	\$	1,051,169
TOAL INSURACNE AND BONDS		\$ 4,404,013	\$	724,709	\$	5,128,722
100.100.0100000.5010	General Conditions	\$ 3,919,105	\$	5,234,895	\$	9,154,000
SUBTOTAL CM SERVICES		\$ 3,919,105	\$	5,234,895	\$	9,154,000
100.900.26500000.4400	Fee	\$ 2,201,258	\$	378,030	\$	2,579,289
100.100.01100000.5010	Change Order OH&P	\$ -	\$	-	\$	-
CONSTRUCTION TOTAL		\$ 122,996,815	\$	20,999,068	\$	143,995,883
100.PRE.00100000.5010	Preconstruction Services	\$ 476,928			\$	476,928
100.PRE.00100000.5010	MBTA Preconstruction	\$ 70,512			\$	70,512
	PCCO 1 (Pre GMP Amendment 12b)	\$ 88,281			\$	88,281
	PCCO 2 (Pre GMP Amendment 13b)	\$ 37,453			\$	37,453
	PCCO 3 (Pre GMP Amendment 14b)	\$ 64,993			\$	64,993
	PCCO 4 (Pre GMP Amendment 15b)	\$ 45,978			\$	45,978
	PCCO 5 (Pre GMP Amendment 17b)	\$ 218,483			\$	218,483
	PCCO 6 (Pre GMP Amendment 18b)	\$ 71,821			\$	71,821
	Owner Pandemic Allowance		\$	150,000	\$	150,000
GRAND TOTAL		\$ 124,071,264	\$	21,149,068	\$	145,220,332

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT F: SCHEDULE OF ALTERNATES

None

Town of Brookline Brookline High School Expansion Project | Project A and B

EXHIBIT G: SCHEDULE OF UNIT PRICES

The following unit prices were previously included in Pre-GMP Amendments and approved by the Brookline Building Commission.

Unit prices include subcontractor's labor and equipment in the unit costs, they do not include construction manager's costs or mark ups.

DESCRIPTION	UNIT COST ADD	UNIT COST DEDUCT		
Disposal of material classified	\$30.60/cy	\$30.60/cy		
as Less Than RCS-1	\$17/ton	\$17/ton		
Disposal of material classified	\$73.80/cy	\$73.80/cy		
as Regulated A Material	\$41/ton	\$41/ton		
Disposal of material classified	\$92.70/cy	\$92.70/cy		
as Regulated B Material	\$51.50/ton	\$51.50/ton		
Disposal of material classified	\$109.80/cy	\$109.80/cy		
as Regulated C Material	\$61/ton	\$61/ton		
Disposal of material classified	\$154.80/cy	\$154.80/cy		
as Regulated D Material	\$86/ton	\$86/ton		
Open General Excavation	\$12/cy	\$12/cy		
Trench General Excavation	\$25/cy	\$25/cy		
Gravel burrow, Compacted In-Place, from Off-Site Source	\$55/cy	\$55/cy		
Crushed Stone, Compacted In-Place, from Off-Site Source	\$60/cy	\$60/cy		
Structural Fill, Compacted In- Place, from On-Site Source	\$45/cy	\$45/cy		
Structural Fill, Compacted In- Place, from Off-Site Source	\$55/cy	\$55/cy		
Ordinary Fill, Compacted In- Place, from Off-Site Source	\$40/cy	\$40/cy		

Town of Brookline Brookline High School Expansion Project | Project A and B

EXHIBIT G: SCHEDULE OF UNIT PRICES

Ordinary Fill, Compacted In- Place, from On-Site Source	\$50/cy	\$50/cy
Removal & Disposal of unreinforced concrete	\$90/cy	\$90/cy
Removal & Disposal of reinforced concrete	\$100/cy	\$100/cy
Removal & Disposal of solid waste	\$150/cy	\$150/cy
Resilient Flooring unit cost per s.f. for 1000 square feet	\$6.83	
Disposal of material classified as less than RCS-1	\$52.95/CY	
Disposal of material classified as less than RCS-1	\$36.50/TN	
Disposal of material classified as less than RCS-2	\$56.35/CY	
Disposal of material classified as less than RCS-2	\$38.85/TN	
Disposal of Regulated A Material – in state unlined	\$91.50/CY	
Disposal of Regulated A Material – in state unlined	\$63.10/TN	
Disposal of Regulated B Material – in state lined	\$79.95/CY	
Disposal of Regulated B Material – in state lined	\$55/TN	
Disposal of Regulated C Material – in state asphalt batch	\$78.75/CY	
Disposal of Regulated C Material – in state asphalt batch	\$54.30/TN	

Town of Brookline Brookline High School Expansion Project | Project A and B

EXHIBIT G: SCHEDULE OF UNIT PRICES

Disposal of Regulated D Material – out of state	\$201.50/CY
Disposal of Regulated D Material – out of state	\$139/TN
Open General Excavation	\$30/CY
Trench – General Excavation	\$65/CY
Gravel Burrow, compacted in-place from off-site source	\$120/CY
Crushed stone, compacted in-place from off-site source	\$55/CY
Structural Fill, compacted in- place from on-site source	\$55/CY
Structural Fill, compacted in- place from off-site source	\$75/CY
Ordinary Fill, compacted in- place from off-site source	\$65/CY
Ordinary Fill, compacted in- place from on-site source	\$50/CY
Removal and disposal of unreinforced concrete	\$179/CY
Removal and disposal of reinforced concrete	\$350/CY
Removal and disposal of solid waste	\$ - /CY
Removal of obstructions within a trench box	\$750/HR
Removal of obstructions with temp. earth support	\$50/SF
Drilled mini=pile with 200 ton compression/15 kips lateral capacity	\$17,560/Pile

Town of Brookline Brookline High School Expansion Project | Project A and B

EXHIBIT G: SCHEDULE OF UNIT PRICES

Drilled mini-pile with 200 ton compression	\$17,560/Pile
Drilled mini-pile with 200 ton compression and 10 tons tension	\$18,810/Pile
Drilled mini-pile with 50 tons compression	\$14,185/Pile
Drilled mini-piles – coring or using a "down-hole hammering" to penetrate granite blocks	\$1,920/HR
Drilled mini-piles – pile load test for 200 ton compression	\$107,300/Test
Drilled mini=piles – Removal of obstructions below depth of 10 feet	\$1,920/HR
Aggregate piers – additional mobilization	\$46,400/EA
Aggregate piers – additional installed piers (w/o remobilization)	\$350/EA
Aggregate piers – additional installed piers (with mobilizations)	\$47,450/EA
Aggregate Piers – additional successful modulus Tests	\$16,870/EA
Aggregate Piers – pre- auguring or spudding	\$192/HR
6" Diameter shop fabricated Beam Penetration	\$50/Each
6" Diameter field welded Beam Penetration	\$440/Each
12" x 18" shop fabricated Beam Penetration	\$400/Each

Town of Brookline Brookline High School Expansion Project | Project A and B

EXHIBIT G: SCHEDULE OF UNIT PRICES

12" x 18" field welded Beam Penetration	\$2,800/Each	
3" 18 GA Galvanized Metal Decking - installed	\$600/Each	
3-1/2" 18 GA Acoustic Decking - installed	\$1,400/Each	
20" x 10" shop fabricated Beam Penetrations	\$400/Each	
20" x 10" field welded Beam Penetrations	\$2,800/Each	
12" x 8" shop fabricated Beam Penetration	\$350/Each	
12" x 8" field welded Beam Penetration	\$2,000/Each	

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT H: TIME LIMIT FOR ACCEPTANCE

Submitted Date	Required Acceptance Date
Original Submission:	Original Submission:
March 13, 2020	June 11, 2020
Revision 001: July 10, 2020	Revision 001: July 14, 2020

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT I: OWNER CHANGE LOG SUMMARY – OUT OF SCOPE ONLY

This GMP excludes all change orders, proposed change orders and cost events in the SKA change management system (except prior approved PCCO's)

- \$ 2,600,887 Approximate Projection
- \$ 2,017,504 Proposed Projection
- \$ 4,618,391 Total Change Management Projection

See attached worksheets dated July 8, 2020 for detailed log of projections.



Owner Change Log

Summary - Out of Scope Only

Skanska USA Building Inc.

1318014 -Brookline High School

115 Greenough Street, Brookline, MA 02445

Projec	t # 13	18014		Brookline High Scho	ol						
Chang	e Sumn	nary									- Shading identifies CE budget allocation
AR	CE		Out of Scope	Description	Approximate	Proposed	AR Status	AR Sent	Approved	PCCO No	Executed Date
200.069	200.1002	8/7/2019	, <u>N</u>	CYPRESS - Impacts to Elevator Decommissioning Due to Work by Others	\$5,512	\$4,574	Submitted	06/15/2020	\$0		
	200.1004	8/12/201	9 v	CYPRESS - RFI 032 - Add Embeds for Future OCS	\$0	\$0			\$0		
	200.1006	9/20/201	9 M	CYPRESS - Elevator Decommissioning	\$0	\$0			\$0		
200.081	200.1007	9/20/201	9 🗹	CYPRESS - Refrigerant Recovery	\$4,409	\$4,194	Submitted	07/06/2020	\$0		
	200.1008	9/20/201	9 M	CYPRESS - MBTA License of Entry Delay	\$0	\$0			\$0		
200.068	200.1018	9/20/201	9 🗹	CYPRESS - Field Bulletin 009 - GMP Set	\$418,890	\$424,280	Submitted	06/09/2020	\$0		
	200.1019	9/20/201	۹ ^و	CYPRESS - Field Bulletin 009.1 - GMP Set Addenda 01	\$0	\$0			\$0		
200.048	200.1020	9/20/201	⁹ 🗹	CYPRESS - Dow Company/Iron Tree Weekend Cancellation	\$38,582	\$22,281	Submitted	05/21/2020	\$0		
	200.1022	9/20/201	9 v	CYPRESS - Fire Protection Service at Cypress	\$0	\$0			\$0		
200.017	200.1023	9/20/201	⁹ 🗹	CYPRESS - Credit for Furniture Removed by Others	\$(842)	\$(772)	Submitted	04/15/2020	\$0		
	200.1025	10/10/20	¹⁹ 🗹	CYPRESS - Replenish Line Protection Provided by MBTA	\$11,023	\$0			\$0		
	200.1029	10/25/20	¹⁹ 🕅	CYPRESS - Field Bulletin 009.2 - GMP Set Addenda 02	\$0				\$0		
	200.1030	10/25/20	¹⁹ 🗹	CYPRESS - Field Bulletin 009.3 - GMP Set Addenda 03	\$0	\$0			\$0		
	200.1031	10/25/20	N 9	CYPRESS - Field Bulletin 009.4 - GMP Set Addenda 04	\$0	\$0			\$0		
	200.1032	10/25/20	¹⁹ 🗹	CYPRESS - Field Bulletin 009.5 - GMP Set Addenda 05	\$0				\$0		
	Pr	inted on:	7/8/202	0							Page 1 of 14



Projec	t # 13	18014		Brookline High Schoo	ol						
Change	e Sumi	nary									- Shading identifies CE budget allocation
AR	CE	Initiated	Out of Scope	Description	Approximate	Proposed	AR Status	AR Sent	Approved	PCCO No	Executed Date
200.050	200.1033	10/25/20	¹⁹ 🗹	CYPRESS - Field Bulletin 011 - Ductbank, Slab and Window Updates	\$4,724	\$2,967	Submitted	05/21/2020	5	50	
	200.1034	10/25/20	19 🗹	CYPRESS - Field Bulletin 009.6 - GMP Set Addenda 06	\$0				5	50	
	200.1036	10/25/20	¹⁹ 🗹	CYPRESS - RFI 019 - Mini Pile Loading	\$0	\$0			5	50	
200.054	200.1040	0 11/4/201	⁹ 🗹	CYPRESS - Field Bulletin 017 - Physics Collaboration HSS	\$2,756	\$1,774	Submitted	05/26/2020	5	50	
200.015	200.1041	11/4/201	9 🕅	CYPRESS - Field Bulletin 018 - Head Details at Acoustic Deck	\$1,654	\$0	Submitted	04/15/2020	S	60	
200.071	200.1042	2 11/4/201	⁹ 🗹	CYPRESS - Field Bulletin 012 - Elevator Hoistway Updates	\$0	\$16,353	Submitted	06/15/2020	5	50	
	200.1044	11/4/201	9 🕅	CYPRESS - Field Bulletin 019 - Anchor Bolt Clarifications	\$0	\$0			5	50	
200.016	200.1045	11/19/20	¹⁹ 🗹	CYPRESS - Field Bulletin 020 - Steel Detail Revisions	\$36,536	\$0	Open	04/14/2020	5	50	
	200.1050) 1/7/202) 🕅	CYPRESS - Field Bulletin 024 - Signage Update per Commission on Disability Meeting	\$0				5	50	
200.061	200.1052	2 1/7/202) 🗹	CYPRESS - Field Bulletin 027 - Window Shades & White Box Barn Door	\$1,419	\$24,549	Submitted	05/29/2020	5	50	
	200.1054	1/7/202) 🗹	CYPRESS - Field Bulletin 031 - RFI-072 Lintel Clarification	\$2,104	\$0			S	60	
	200.1056	5 1/7/202) 🗹	CYPRESS - Field Bulletin 032 - Footing Coordination at Existing Site Retaining Wall	\$0	\$0			5	50	
	200.1057	1/7/202) 🗹	CYPRESS - Field Bulletin 036 - RFI-078 Condensing Unit Clarification	\$256	\$0			5	50	
	200.1058	3 1/7/202) M	CYPRESS - Field Bulletin 037 - Metal Wall Panel Specification Update	\$0	\$0			5	50	
	200.1059	1/14/202	0 🗹	CYPRESS - Field Bulletin 038 - Streetscape Revisions	\$0	\$0			S	60	
	200.1060	1/30/202	0 🔽	CYPRESS - CLOSED	\$0				5	50	
	200.1063	2/3/202) 🗹	CYPRESS - Field Bulletin 040 - Shaft Dimensional Adjustment	\$0	\$0				50	
	D	rinted on:	7/8/202	0							Page 2 of 14



AR CE Initiated None Out of None Description Approximate Proposed AR Status Approved PCCO Executed Date 200.095 202.007 C VPEXS: Field Buildie 451 - (PL093 APIL-3 A diti-12 Plat Landons. 30 9 90 90 200.092 200.088 3/4200 C C VPEXS: Field Buildie 451 - (PL093 APIL-3 A diti-12 Plat Landons. 90 381 Solemited (S10-202) 90 200.092 24/200 C VPEXS: Field Buildie 451 - (PL093 APIL-3 A diti-12 Plat Landons. 90 381 Solemited (S10-202) 90 200.097 24/200 C VPEXS: Field Buildie 451 - (PL093 APIL-3 A ditabase 512 90 90 90 200.077 24/200 C VPEXS: Field Buildie 451 - (PL093 APIL-3 A ditabase Apine 55312 90 90 90 200.073 25/200 C VPEXS: Field Buildie 401 - Tappes Stoat Sages 500/144 50 50 50 200.075 25/200 C VPEXS: Field Buildie 401 - (PL011) 50 90 50 200.075 25/200 C VPEXS: Field Buildie	Projec	:t # 13	18014		Brookline High Schoo	J						
Image: Note of the second s	Chang	e Sumi	mary									- Shading identifies CE budget allocation
International Control Production (C): Proprint Production (C): Properties (C): Properite (C): Properties (C): Properties (C): Properties (C): Properties (C): Properties (C): Properties (C): Properties (C): Properties (C): Properties (C): Properties (C): Properties (C): Properties (C): Properties (C): Properties (C): Properties (C): Properties (C): Properties (C): Properties (C): Properties (C): Properis (C): Properis (C): Properite (C): Properite (C): Properis (C): P	AR	CE	Initiated		Description	Approximate	Proposed	AR Status		Approved		
Initial Control Control <t< td=""><td></td><td>200.1066</td><td>5 2/3/20</td><td>20</td><td></td><td>\$0</td><td>\$0</td><td></td><td></td><td>\$</td><td>)</td><td></td></t<>		200.1066	5 2/3/20	20		\$0	\$0			\$)	
1 201070 24/2020 C CYPRESS - Field Bulletin 043 - Refronza 55512 50 2 201070 25/2020 C CYPRESS - Field Bulletin 041 - Tappan Street Seage 5701.682 50 2 201070 25/2020 C CYPRESS - Field Bulletin 041 - Tappan Street Seage 5701.682 50 50 2 201070 25/2020 C CYPRESS - Field Bulletin 042 - RF1 15 5472.2020 50 50 2 201070 25/2020 C CYPRESS - Field Bulletin 042 - RF1 03, 103, 103 50 50 2 201070 25/2020 C CYPRESS - Field Bulletin 042 - RF1 03, 103, 103 50 50 2 201070 25/2020 C CYPRESS - Field Bulletin 042 - RF1 03, 103, 103 50 50 2 201070 25/2020 C CYPRESS - Field Bulletin 042 - RF1 03, 103, 103 50 50 50 2 201070 25/2020 C CYPRESS - Field Bulletin 042 - RF1 03, 103, 103 50 50 50 2 201070 2 C CYPRESS - Field Bulletin 042 - RF1 03, 103, 103 50 50 <td>200.042</td> <td>200.1068</td> <td>8 2/4/20</td> <td>20</td> <td>-</td> <td>\$0</td> <td>\$0</td> <td>Submitted</td> <td>05/19/2020</td> <td>\$</td> <td>)</td> <td></td>	200.042	200.1068	8 2/4/20	20	-	\$0	\$0	Submitted	05/19/2020	\$)	
1 200107 25200 C CYPRESS-Field Bulken 00 - RF1 103 5070142 50 50 2001073 252000 C CYPRESS-Field Bulken 00 - RF1 103 547220 50 50 2001074 252020 C CYPRESS-Field Bulken 00 - RF1 003 AHL/3 50 50 2001076 252020 C CYPRESS-Field Bulken 00 - RF1 003 AHL/3 50 50 2001076 252020 C CYPRESS-Field Bulken 00 - RF1 003 AHL/3 50 50 2001076 252020 C CYPRESS-Field Bulken 00 - RF1 003 AHL/3 50 50 2001076 252020 C CYPRESS-Field Bulken 00 - RF1 003 AHL/3 50 50 2001076 252020 C CYPRESS-Field Bulken 00 - RF1 003 AHL/3 50 50 2001076 252020 C CYPRESS-Field Bulken 00 - RF1 003 AHL/3 50 50 2001076 252020 C CYPRESS-Field Bulken 00 - RF1 003 AHL/3 50 50 200107 260107 CYPRESS-Field Bulken 00 - RF1 003 AHL/3 50 50 50 200107 201070 C CYPRESS-Field		200.1069	9 2/4/20	20		\$94,590	\$0			\$)	
Latit Latit Contracts Field Bulletin 041 - Trippen Steed Latit 200.107 245/202 C CYPRESS - Field Bulletin 050 - RFI 115 S47/220 S0 S0 200.107 245/202 C CYPRESS - Field Bulletin 054 - RFI 053 ARU/3 S0 S0 S0 200.107 25/2020 C CYPRESS - Field Bulletin 054 - RFI 053 ARU/3 S0 S0 S0 200.107 25/2020 C CYPRESS - Field Bulletin 041 - Streetsape S0 S0 S0 200.107 25/2020 C CYPRESS - Field Bulletin 042 - RFI 053, 103, 103, 103 S0 S0 S0 200.107 25/2020 C CYPRESS - Field Bulletin 042 - RFI 053, 103, 103, 103, 103 S0 S0 S0 200.107 25/2020 C CYPRESS - Field Bulletin 042 - RFI 053, 103, 103, 103, 103 S0 S0 S0 200.107 25/2020 C CYPRESS - Field Bulletin 042 - RFI 053, 103, 103, 103, 103, 103 S0 S0 S0 S0 S0 200.108 20.1082 C CYPRESS - Field		200.1070) 2/4/20	20		\$5,512	\$0			\$)	
200.07 200.1074 25 2020 C C C S0 200.1074 25 2020 C C C S0 S0 200.1075 25 2020 C C C S0 S0 200.1075 25 2020 C C C S0 S0 200.1075 25 2020 C C C S0 S0 200.1076 25 2020 C C C S0 S0 105 Currents S10 S0 S0 S0 200.1076 25 2020 C C C S0 S0 105 Currents S10 S0 S0 S0 200.1070 25 2020 C C C S164 Balletin 64.5 2 Food Service S0 S0 200.053 200.1079 26 2020 C C C S164 Balletin 64.5 2 Food Service S0 S0 S0 S0 200.053 201.090 26 2020 C C C C S16 377 S86 728 Submitted <td< td=""><td></td><td>200.1072</td><td>2 2/5/20</td><td>20</td><td></td><td>\$701,842</td><td>\$0</td><td></td><td></td><td>\$</td><td>)</td><td></td></td<>		200.1072	2 2/5/20	20		\$701,842	\$0			\$)	
200.075 25/2020 Image: Crimeria Field Bulletin 041.1 - Streetscape Sincetural Solis 50 200.1075 25/2020 Image: Crimeria Solis S0 200.1075 25/2020 Image: Crimeria Solis S0 200.1076 25/2020 Image: Crimeria Solis S0 200.1076 25/2020 Image: Crimeria Solis S0 200.1077 2/5/2020 Image: Crimeria Solis S0 200.0177 2/5/2020 Image: Crimeria Solis S0 200.0177 2/5/2020 Image: Crimeria Solis S0 S0 200.0177 2/5/2020 Image: Crimeria Solis S0 S0 S0 200.0178 2/01/020 Image: Crimeria Solis S1 S1 S1 S0 200.0185 2/11/2020 Image: Crimeria Solis S1 S1 S1 S0		200.1073	3 2/5/20	20		\$47,220	\$0			\$)	
Interview Exercise CVPRESS - Field Bulletin 042 - RFI-053, 103, 105 S0 S0 200.107 2/5/2020 CVPRESS - Field Bulletin 042 - RFI-053, 103, 105 S0 S0 200.107 2/5/2020 CVPRESS - Field Bulletin 042 - RFI-05 8, 103, 105 S0 S0 200.107 2/5/2020 CVPRESS - Field Bulletin 047 - Smoke Detectors S16,377 S86,738 Submitted 05/26/202(S0 200.055 200.1080 2/6/2020 CVPRESS - Field Bulletin 017 - Smoke Detectors S16,377 S86,738 Submitted 05/26/202(S0 200.055 2/01.080 2/6/2020 CVPRESS - Field Bulletin 017 - Smoke Detectors S16,377 S86,738 Submitted 05/26/202(S0 200.055 2/01.080 2/11/2020 CVPRESS - Field Bulletin 018 - NFI - 05 N. Perch S0 S0 Open 06/16/202(S0 200.067 2/11/2020 CVPRESS - Field Bulletin 043 - RFI-052 S0 S0 S0 S0 S0 200.068 2/11/2020 CVPRESS - Field Bulletin 043 - RFI-052 S0 S0 S0		200.1074	4 2/5/20	20		\$0				\$)	
200.0107 2/5/2020 Image: CryRESS - Field Bulletin 045.2 Food Service Condenser Locations S0 200.053 200.1077 2/5/2020 Image: CryRESS - Field Bulletin 045.2 Food Service Condenser Locations S0 200.053 200.1079 2/6/2020 Image: CryRESS - Field Bulletin 047 - Smoke Detectors (ref. Fire Smoke Dampers) S36.377 S86.738 Submitted 05/26/2020 S0 200.053 200.1080 2/6/2020 Image: CryRESS - Field Bulletin 016 - Curthinwall (s0 in Curthinwall s0 in S0 in S0 in S0 in S15.378) Open 05/26/2020 S0 200.054 200.1082 2/11/2020 Image: CryRESS - Field Bulletin 028 - VM - Tile and Bases S(10.450) S15.378 Open 06/16/2020 S0 200.057 2/11/2020 Image: CryRESS - Field Bulletin 028 - VM - Tile and Bases S(10.450) S15.378 Open 06/16/2020 S0 200.057 2/11/2020 Image: CryRESS - Field Bulletin 03 - RFI-075 N. Porch TOC S0 S0 S0 S0 200.068 2/11/2020 Image: CryRESS - Field Bulletin 043 - RFI-082 S0 S0 S0 S0 200.068 2/11/2020 Image: CryRESS - Field Bulletin 044 - RFI-082 S0 S0		200.1075	5 2/5/20	20	-	\$0	\$0			\$)	
200.073 200.1079 2/6/2020 ✓ CYPRESS - Field Bulletin 047 - Smoke Detectors (ref; Fire Smoke Dampers) \$36,377 \$86,738 Submitted 05/26/2020 \$0 200.053 200.1080 2/6/2020 ✓ CYPRESS - Field Bulletin 016 - Curtainwall Updates \$0 \$0 \$0 \$0 200.054 200.1082 2/11/2020 ✓ CYPRESS - Field Bulletin 028 - VM - Tile and Bases \$(10,450) \$15,378 Open 06/16/2020 \$0 200.057 2/01.082 2/11/2020 ✓ CYPRESS - Field Bulletin 035 - RFI-075 N. Porch TOC \$0 \$0 \$0 \$0 200.01087 2/11/2020 ✓ CYPRESS - Field Bulletin 043 - RFI-075 N. Porch TOC \$0 \$0 \$0 \$0 200.01087 2/11/2020 ✓ CYPRESS - Field Bulletin 043 - RFI-082 \$0 \$0 \$0 \$0 200.01087 2/11/2020 ✓ CYPRESS - Field Bulletin 043 - RFI-082 \$0 \$0 \$0 \$0 200.0108 2/11/2020 ✓ CYPRESS - Field Bulletin 044 - Eye Wash Station \$5,512 \$5,870 \$ubmitted \$0/29/2020 \$0 200.0108		200.1076	5 2/5/20	20		\$0				\$)	
200.018 2/6/2020 ☑ CYPRESS - Field Bulletin 016 - Curtainwall S0 S0 Open 05/26/202(S0 200.018 2/01/082 2/11/2020 ☑ CYPRESS - Field Bulletin 028 - VM - Tile and Bases S(10,450) S15,378 Open 06/16/202(S0 200.018 2/11/2020 ☑ CYPRESS - Field Bulletin 028 - VM - Tile and Bases S(10,450) S15,378 Open 06/16/202(S0 200.0185 2/11/2020 ☑ CYPRESS - Field Bulletin 035 - RFI-075 N. Porch TOC S0 S0 S0 S0 200.1087 2/11/2020 ☑ CYPRESS - Field Bulletin 043 - RFI-082 S0 S0 S0 S0 200.0060 200.1088 2/11/2020 ☑ CYPRESS - Field Bulletin 044 - Eye Wash Station S5,512 S5,870 Submitted 05/29/202(S0 200.0060 200.1088 2/11/2020 ☑ CYPRESS - Field Bulletin 044 - Eye Wash Station S5,512 S5,870 Submitted 05/29/202(S0 200.008 2/12/2020 ☑ CYPRESS - UG Electric Conduit S75,000 S0 S0 S0 <td></td> <td>200.1077</td> <td>7 2/5/20</td> <td>20</td> <td></td> <td>\$0</td> <td></td> <td></td> <td></td> <td>\$</td> <td>)</td> <td></td>		200.1077	7 2/5/20	20		\$0				\$)	
Lotities Lotities <thlotities< th=""> Lotities <th< td=""><td>200.053</td><td>200.1079</td><td>9 2/6/20</td><td>20</td><td></td><td>\$36,377</td><td>\$86,738</td><td>Submitted</td><td>05/26/2020</td><td>\$</td><td>)</td><td></td></th<></thlotities<>	200.053	200.1079	9 2/6/20	20		\$36,377	\$86,738	Submitted	05/26/2020	\$)	
Image: Second Secon	200.055	200.1080) 2/6/20	20		\$0	\$0	Open	05/26/2020	\$)	
2001005 2/11/2020 Image: Construction of the function of the fun	200.074	200.1082	2 2/11/20	20		\$(10,450)	\$15,378	Open	06/16/2020	\$)	
200.060 200.1088 2/1/2020 ✓ CYPRESS - Field Bulletin 044 - Eye Wash Station \$5,512 \$5,870 Submitted 05/29/202(\$0 200.1089 2/12/2020 ✓ CYPRESS - UG Electric Conduit \$75,000 \$0 \$0		200.1085	5 2/11/20	20		\$0	\$0			\$)	
200.1089 2/12/2020 CYPRESS - UG Electric Conduit \$75,000 \$0 \$0		200.1087	7 2/11/20	20	CYPRESS - Field Bulletin 043 - RFI-082	\$0	\$0			\$)	
	200.060	200.1088	8 2/11/20	20	CYPRESS - Field Bulletin 044 - Eye Wash Station	\$5,512	\$5,870	Submitted	05/29/2020	\$)	
Printed on: 7/8/2020 Page 3 of 14		200.1089	9 2/12/20	20	CYPRESS - UG Electric Conduit	\$75,000	\$0			\$)	
		P	rinted on [.]	7/8/202	0							Page 3 of 14



Project # 1318014 Brookline High School												
Change	e Sumn	nary									- Shading identifies CE budget allocation	
AR	CE	Initiated	Out of Scope	Description	Approximate	Proposed	AR Status	AR Sent	Approved	PC N		
200.045	200.1091	2/14/202	20 1	CYPRESS - Field Bulletin 054 - Electric Duct Bank Revisions	\$0	\$0	Submitted	05/21/2020		\$0		
200.040	200.1094	3/2/202	0 🗹	CYPRESS - Field Bulletin 058 White Box Tile Replacement & Room Name Changes	\$0	\$12,878	Submitted	05/19/2020		\$0		
200.037	200.1098	3/5/202	N 0	CYPRESS - Precast - Cypress Bridge Abutment Conflict	\$16,535	\$13,960	Submitted	05/15/2020		\$0		
200.029	200.1099	3/5/202		CYPRESS - Sequence 1 - Structural Bracing at North Side (CL A to B)	\$22,047	\$15,898	Submitted	05/08/2020		\$0		
	200.1100	3/11/202	20 🔽	CYPRESS - Field Bulletin - 060 - Electrical Specification Revisions	\$0					\$0		
200.070	200.1102	3/13/202	20	CYPRESS - Field Bulletin 057 -Sliding Gates	\$0	\$(28,105)	Submitted	06/15/2020		\$0		
200.020	200.1105	3/17/202	20 🔽	CYPRESS - Field Bulletin 070 - Brook Chanel Culvert Manhole Abandonment	\$33,070	\$58,480	Submitted	04/23/2020		\$0		
	200.1107	3/19/202	20	CYPRESS - CLOSED	\$0					\$0		
	200.1109	3/19/202	20 🔽	CYPRESS - Regulated Soil Disposal / Reuse on Site / Material Qty Overruns	\$125,000	\$0				\$0		
200.019	200.1110	3/23/202	20 🗹	CYPRESS - Excavate for Domestic Water cut, cap, and relocation	\$0	\$10,495	Open	04/23/2020		\$0		
200.076	200.1111	3/23/202	20	CYPRESS - Field Bulletin 068 - Water Heater Vent, Easement Louvers, Boiler Power	\$7,716	\$2,679	Submitted	06/19/2020		\$0		
200.056	200.1112	3/25/202	20	CYPRESS - Field Bulletin 016.1 Curtain Wall Revisions	\$0	\$11,241	Open	05/27/2020		\$0		
	200.1125	3/30/202	20	CYPRESS - Field Bulletin 071 - Cafeteria AV Lift Shades + Delete Bungalow Fa Speaker/Strobes	\$5,095	\$0				\$0		
	200.1126	3/31/202	20 🔽	CYPRESS - RFI-145 - Eversource Electrical Feeder	\$9,354	\$0				\$0		
200.077	200.1128	4/6/202	0 🗹	CYPRESS - Field Bulletin 063 - Switchgear Pad Scope Revisions	\$(2,205)	\$(1,450)	Submitted	06/23/2020		\$0		
200.078	200.1131	4/13/202	20 🔽	CYPRESS - Field Bulletin 079 - RFI - 174 Water Service Connection Revision	\$0	\$0	Submitted	06/23/2020		\$0		
	200.1132	4/13/202	20 🗹	CYPRESS - Field Bulletin 080 - RFI-147 - Gas, Oil, and Sand Separator	\$102,233	\$0				\$0		
		inted on:									Page 4 of 14	



Projec	Project # 1318014 Brookline High School											
Chang	e Sumr		- Shading identifies CE budget allocation									
AR	CE	Initiated	Out of Scope	Description	Approximate	Proposed	AR Status	s AR Sent	Approved	PCCO No	Executed Date	
	200.1134	4/16/20	20	CYPRESS - Field Bulletin 033 - Non Trade Pre Bid RFI Responses	\$0				\$	0		
	200.1136	4/16/20	20	CYPRESS - Field Bulletin 072 - Intumescent Paint Scope	\$611	\$0			\$	0		
	200.1137	4/16/20	20	CYPRESS - Field Bulletin 082 - RFI-181 Level 3 Brick Support Revisions	\$6,615	\$0			\$	0		
	200.1139	4/16/20	20	CYPRESS - Field Bulletin 084 - Gridline PP Post Relocation	\$2,206	\$0			\$	0		
	200.1140	4/24/20	²⁰ 🗹	CYPRESS - Remove Portal Base 173 Ref. RFI #182	\$5,271	\$0			\$	0		
	200.1143	5/4/202	20	CYPRESS - Field Bulletin 087 - Angle location Length Revisions at Iso Bearing Pads	\$0	\$0			\$	0		
200.080	200.1144	5/5/202	20 N	CYPRESS - Cypress Street Utilities Conflict	\$4,961	\$3,150	Open	06/29/2020	S	0		
200.079	200.1145	5/11/20	20	CYPRESS - Field Bulletin 073 - MBTA Bungalow Grading & EMR Rating Revisions	\$0	\$14,112	Open	06/23/2020	\$	0		
	200.1146	5/11/20	²⁰ 🕅	CYPRESS - Field Bulletin 086 - Irrigation Connections	\$0				\$	0		
	200.1147	5/11/20	20	CYPRESS - Replenishment of OA for Rammed Aggregate Pier Obstruction Removal	\$29,855	\$0			\$	0		
	200.1148	5/18/20	20	CYPRESS - Field Bulletin 080.1 - RFI-147 - Gas, Oil, & Sand Separator	\$0	\$0			\$	0		
	200.1149	5/21/20	20	CYPRESS - Dow - Lost Productivity Due to N. Side Laydown Unavailable	\$11,972	\$0			\$	0		
	200.1150	5/22/20	20	CYPRESS - Field Bulletin 041.4 - Irrigation Connections - Tappan Streetscape	\$19,844	\$0			\$	0		
	200.1151	5/26/20	20	CYPRESS - Field Bulletin 088 - East Stair Stone Updates	\$9,370	\$0			\$	0		
	200.1152	6/1/202	20 🗹	CYPRESS - MBTA Surge Shut Down	\$105,294	\$0			\$	0		
	200.1153	6/5/202	20	CYPRESS - Field Bulletin 091 - Conference Room Projector	\$0	\$0			\$	0		
	200.1154	6/8/202	20	CYPRESS - Field Bulletin 092 - Stair 3 Exterior Wall Revisions for Code	\$8,267	\$0			\$	0		
		inted on:	7/8/202	0							Page 5 of 14	
	PI	inteu off.	1/0/202	v							1 490 0 01 14	



Project # 1318014 Brookline High School													
Change	e Sumr		- Shading identifies CE budget allocatio										
AR	CE	Initiated	Out of Scope	Description	Approximate	Proposed	AR Status	AR Sent	Approved	PCCO No	Executed Date		
	200.1155	6/10/202	0 🕅	CYPRESS - Field Bulletin 055 - De-Escalation Rm Wall Padding Floor	\$0				\$0)			
	200.1156	6/10/202		CYPRESS - Field Bulletin 093 - Attic Stock Reductions	\$0				\$0)			
	200.1158	6/18/202		CYPRESS - Field Bulletin 080.2 - RFI-205-R1 & RFI-217 - Gas, Oil, & Sand Separator	\$0	\$0			\$()			
	200.1159	6/18/202	0 🗹	CYPRESS - Field Bulletin 077 - B-Line Stone Support Reductions	\$0	\$0			\$()			
	200.1160	6/18/202	0 🕅	CYPRESS - Field Bulletin 041.5 - Irrigation Connections - RFI-216	\$5,513	\$0			\$()			
	200.1162	6/18/202	0 🗹	CYPRESS - Precast Modifications	\$0				\$0)			
	200.1163	6/22/202	0 🕅	CYPRESS - Precast - Cypress Bridge Abutment Conflict - South Side	\$4,823	\$0			\$0)			
300.067	300.1002	8/19/201	9 ☑	STEM - FB 005, 005.1, 005.2 and 005.3: GMP Bid Set	\$96,418	\$92,338	Submitted	06/29/2020	\$0)			
300.066	300.1013	10/7/201	۶ Г	STEM - FB 004 - Structural Coordination	\$16,536	\$18,581	Submitted	06/29/2020	\$0)			
	300.1014	8/19/201	⁹ 🗹	STEM - FB 022 & 022.1 - West Demo and Expansion Joint	\$128,385	\$0			\$0)			
	300.1016	10/28/201	9 v	STEM - Reduced SOE Scope	\$(33,070)	\$0			\$0)			
300.033	300.1019	11/14/201	9 🗹	STEM - FB 024 & 24.1 - Haunch for Granite Base at Archway	\$9,921	\$13,168	Open	05/29/2020	\$0)			
300.048	300.1023	12/16/201	9 🗹	STEM - FB 044: Sewer Tie In at Greenough	\$16,583	\$70,169	Open	06/09/2020	\$0)			
300.068	300.1037	1/6/2020) N	STEM - FB 048 - Additional Auto Operators at Entry Doors 100A1 and 101A1	\$6,614	\$13,497	Submitted	07/06/2020	\$0)			
	300.1044	1/31/202	0 🗹	STEM - RFI 186 & FB 022.2: Chase Wall Adjacent L3 Demo Line	\$7,982	\$0			\$0)			
	300.1045	1/31/202		STEM - RFI 190 & FB 022.2: Remaining Corner at NW Demo Line	\$116,151	\$0			\$0)			
	300.1047	2/7/2020) 🗹	STEM - Remove Plywood from Overhead Protection	\$4,657	\$0			\$0)			

Printed on: 7/8/2020

Page 6 of 14



AR CE Infliked Source Out of None Description Approximate Proposed AR Status AR Approx/ed Proc Val No Procession 30.0191 2102000 STEM: AEI 14821: Interior Guang Franing Came \$53.934 50 50 30.0192 2192000 STEM: TRUE of Para Stace, Korf and , W \$19,091 \$32.3397 56emiled 070 072027 50 300.0192 2252000 STEM: TRUE of State, Status, Modage Classications \$1 59 56emiled 070 072027 50 300.0106 3520000 STEM: TRUE of Status Modage Classications \$1 59 50 50 50 300.0106 3520000 STEM: TRUE of Status Modage Classications \$1 59 50 50 50 300.0107 30130200 STEM: TRUE of Status Modage Classications \$112727 Solemiled 6105202 \$0 50 300.0173 31320200 STEM: TRUE of Status Modage Classications \$100,50 \$11248 Solemiled 61062021 \$0 50	Project # 1318014 Brookline High School												
NUMBER NUMBER NUMBER Number<	Chang	e Sumi	nary									- Shading identifies CE budget allocation	
Interface Interface Interface Interface Interface 00.000 201000 219000 Interface STRM-TP 100P Prom Stoce, Ref Infl, NV Strm 100P Prom Stoce, Ref Infl, NV Strm 100P Prom Stoce, Ref Infl, NV Strm 100P Prom Stoce, Ref Infl, NV Strm 100P Prom Stoce, Ref Infl, NV Strm 100P Prom Stoce, Ref Infl, NV Strm 100P Prom Stoce, Ref Infl, NV Strm 100P Prom Stoce, Ref Infl, NV Strm 100P Prom Stoce, Ref Infl, NV Strm 100P Prom Stoce, Ref Infl, NV	AR	CE	Initiated		Description	Approximate	Proposed	AR Status		Approved			
International Problem International Problem International Problem International Problem 30000 30105 27200 7 STMA-FE000-Smir Stanger and Dama \$32085 60 0pm 0127021 \$70 30000 301000 270 GTMA-FE000-Smir Stanger and Dama \$32085 50 0pm 0127021 \$70 30000 301000 301000 GT STMA-FE000-Smir Stanger and Dama \$30000 \$30000 \$100000 \$100000 \$100000 \$100000 \$100000 \$100000 \$100000 \$100000 \$100000 \$100000 \$100000 \$100000 \$100000 \$100000 \$1000000 \$1000000 \$1000000 \$1000000 \$1000000 \$1000000 \$1000000 \$1000000 \$10000000 \$10000000 \$100000000 \$1000000000000 \$100000000000000000000000000000 \$100000000000000000000		300.1048	3 2/10/20	20		\$43,934	\$0			\$0)		
Number Number Number Number Number Number Number Number 100160 30160 3 S STAM-FB 0655 Exterior Modeley Clainfactions 50 S	300.069	300.1054	4 2/19/20	20		\$19,091	\$23,197	Submitted	07/07/2020	\$0)		
Markan Markan Table Parkan Table Parkan Table Parkan 30007 30108 36202 7 SEM + RB 042: Existing RWL Tie In S00206 S12273 Submited 06152020 SD 300107 301070 0 SEM + RB 042: Existing RWL Tie In S314388 S0 - SD 300107 301300 0 STEM + RB 032: Existing Foundation at ISEN + RD 70, 80 (902): Existin RD 70, 80 (902): Existin RD 70, 80 (902): Existin RD 70	300.056	300.1055	5 2/25/20	²⁰ 🗹	STEM - FB 060: Stair 1 Stringer and Dims	\$20,857	\$0	Open	06/12/2020	\$0)		
Number Number Number Number Number Number Number Number 300.007 301.007 311.200 \$\veel\$ STEM - FB 013A K033R1: Repair Conactor \$\$34.988 \$\$0 \$\$000000 \$\$000000 \$\$000000 \$\$000000		300.1060) 3/5/202	.0 🗹	STEM - FB 065: Exterior Mockup Clarifications	\$0				\$0)		
Mathematical State Automatical State Mathematical State Mathematical State 300.00 301.073 313200 G State-FR0 300 A G03R1: Repair Crack in Existing Insserted Ciding Slab. \$5.51 \$1.540 Submitted 0708/202X \$20 300.00 301.007 313200 G State-FR0 300 A G03R1: Existing Foundation at Instance \$5.005 \$7.591 Submitted 0706/202X \$0 300.00 301.007 313200 G STEM-FB 070 A G070R2: Existing Foundation at Instance \$50.005 \$7.591 Submitted 0706/202X \$0 300.00 301.007 302000 G STEM-FB 070: CW-12 Adjustment \$10200 \$0 S \$20 301.007 302000 G STEM-FB 071: CW-12 Adjustment \$11200 \$0 \$2 \$20 301.007 302000 G STEM-FB 071: CW-12 Adjustment \$11200 \$0 \$0 \$10200 \$2 \$17200 \$1000 \$10000 \$10000 \$10000 \$10000 \$10000 \$10000 \$100000 \$10000 \$10000	300.057	300.057 300.1064 3/6/2020 🔽 STEM - FB 062: Existing RWL Tie In \$30,206 \$12,757 Submitted 06/15/2020 \$0											
Internet internet													
Instruction Instruction Instruction Instruction Instruction Instruction 102 300.1075 3/17.2020 77 STEM - FB 021.1: RFI #122 \$5,000 \$0 \$0 300.1075 3/20.2020 70 STEM - FB 021.1: RFI #122 \$5,000 \$0 \$0 \$0 300.1075 3/20.2020 70 STEM - FB 021.1: RFI #122 \$5,000 \$00 \$0 \$0 300.1075 3/20.2020 70 STEM - FB 021.1: RFI #122 \$1,200 \$00 \$0 \$0 300.1075 3/20.2020 70 STEM - FB 026.4: Interior Finishes \$1,200 \$00 \$0 \$0 \$1,000 \$0 \$0 \$0 \$1,000 \$0 \$1,000 \$0 \$1,000 \$0 \$1,000 \$0 \$1,000 \$0 \$1,000 \$0 \$1,000 \$1,000 \$0 \$1,000<	300.062	300.1073	3 3/13/20	20		\$5,512	\$11,546	Submitted	07/08/2020	\$0)		
Joine of the set of the	300.063	300.1074	4 3/13/20	20	-	\$100,500	\$77,591	Submitted	07/06/2020	\$0)		
Joined Joined		300.1075	5 3/17/20	²⁰ 🗹	STEM - FB 021.1: RFI #122	\$5,000	\$0			\$0)		
100001 100000 100000 100000 100000 100000 100000 100000 100000 100000 100000 1000000 1000000 1000000 1000000 1000000 1000000 1000000 1000000 1000000 1000000 1000000000 10000000 10000000 10000000 100000000 1000000000000 1000000000000000000000000000000000000		300.1076	5 3/20/20	20	STEM - FB 071: CW-12 Adjustment	\$1,290	\$0			\$0)		
Instruction Note Note Note Note Note Note Note 300.060 300.1081 4/16/2020 Image: State Stat		300.1077	7 3/20/20	20	STEM - FB 063 & 063R1: Interior Finishes	\$(1,808)	\$0			\$0)		
No. 108 4/22/202 Image: No. 108 STEM - FB 074: Reduce Mock Up Scope Step 257 So So 300.058 300.058 4/26/202 Image: Step 25 and Ste		300.1080) 5/5/202	0 🗹	-	\$(34,990)	\$0			\$0)		
Joined Justice M Justice	300.060	300.1081	4/16/20	20	STEM - FB 073: Split Unit Piping	\$3,858	\$0	Open	07/01/2020	\$0)		
300.1086 4/28/2020 Image: Strict of B 0/3 C 0/3 C 1. Exterior Figures Construction Figures Construction Figures Construction \$1,003 \$0,000 \$0 300.1086 4/28/2020 Image: Strict of B 082: Delete Modify Thru Wall Flashing, Additional Control Joints \$1,103 \$0 \$0 300.055 300.1087 4/29/2020 Image: Strict of B 083: Acoustic Revisions \$23,149 \$20,798 Open 06/12/202(\$0 300.055 300.1090 5/7/2020 Image: Strict of B 083: Acoustic Revisions \$23,149 \$20,798 Open 06/12/202(\$0 300.053 300.1090 5/7/2020 Image: Strict of B 081: Electrical, IT, and AV Coordination \$6,556 \$0 Open 06/12/202(\$0 300.1092 5/14/2020 Image: Strict of B 079: Toilet Accessories, EWCs \$1,222 \$0 \$0		300.1084	4/22/20	20	STEM - FB 074: Reduce Mock Up Scope	\$(257)	\$0			\$0)		
300.052 300.1087 4/29/2020 Image: State of the observation of the obse	300.054	300.1085	5 4/26/20	20	-	\$1,322	\$5,109	Open	06/29/2020	\$0)		
300.053 300.1090 5/7/2020 Image: STEM - FB 081: Electrical, IT, and AV Coordination \$6,556 \$0 Open 06/12/2020 \$0 300.1092 5/14/2020 Image: STEM - FB 079: Toilet Accessories, EWCs \$1,222 \$0 \$0		300.1086	5 4/28/20	20	-	\$1,103	\$0			\$0)		
300.1092 5/14/2020 STEM - FB 079: Toilet Accessories, EWCs \$1,222 \$0 \$0	300.055	300.1087	4/29/20	20	STEM - FB 083: Acoustic Revisions	\$23,149	\$20,798	Open	06/12/2020	\$0)		
	300.053	300.1090) 5/7/202	⁰ 🕅		\$6,556	\$0	Open	06/12/2020	\$0)		
		300.1092	2 5/14/20	20	STEM - FB 079: Toilet Accessories, EWCs	\$1,222	\$0			\$0)		
Printed on: 7/8/2020 Page 7 of 14	Printed on: 7/8/2020 Page 7 of 14												



Projec	Project # 1318014 Brookline High School										
Chang	e Sum	mary			- Shading identifies CE budget allocation						
AR	CE	Initiated	Out of Scope	f Description	Approximate	Proposed	AR Status	AR Sent	Approved	PCCC No) Executed Date
	300.109	4 5/14/2	⁰²⁰ 🔽	STEM - FB 085 & 085R1: Slab Edge Coordination	\$5,195	\$0			\$	0	
300.059	300.109	5 5/18/2	020	STEM - FB 087: Remove-Replace Beam Smoke Detectors	\$2,206	\$6,151	Submitted	06/19/2020	\$	0	
	300.109	6 5/20/2	⁰²⁰ 🔽	STEM - D/F/H Submittal Comments	\$3,651	\$0			\$	0	
300.032	300.109	7 5/21/2)20	STEM - Disposal of Concrete and Granite in Excavation	\$10,070	\$10,070	Void	05/22/2020	S	0	
	300.110	0 3/20/2	⁰²⁰ 🔽	STEM - FB 063R2: Interior Finishes	\$(764)	\$0			\$	0	
	300.110	2 6/3/20	20	STEM - FB 086: Interior Partitions Toilet Rooms	\$(2,425)	\$0			\$	0	
	300.110	3 6/3/20	20	STEM - FB 082R1: Alternate Relieving Angles	\$3,307	\$0			\$	0	
	300.110	7 6/9/20	20	STEM - FB 089: Slab and Anchorage Existing Connector Option 1	\$13,228	\$0			\$	0	
	300.110	8 6/9/20	20	STEM - FB 092: GWB ilo Metal Panel Bench Front	\$(1,103)	\$0			\$	0	
	300.110	9 6/9/20	20	STEM - FB 091: Add Door in Chem Prep	\$5,512	\$0			\$	0	
	300.111	3 6/16/2	020	STEM - FB 080: Repair Waterproof at Existing Basement Option A	\$253,330	\$0			\$	0	
300.064	300.111	4 6/16/2	020	STEM - FB 088: VESDA System Main Electrical Admin	\$29,764	\$21,925	Submitted	06/29/2020	\$	0	
	300.111	6 6/23/2	020 I	STEM - FB 090 & 090R1: Mechanical Screen Wall	\$11,024	\$0			\$	0	
	300.111	7 6/24/2	⁰²⁰ 🗹	STEM - FB 094: Attic Stock Deletions	\$(3,835)	\$0			\$	0	
	300.111	8 6/25/2)20	STEM - FB 089: Slab and Anchorage Existing Connector Option 2	\$2,206	\$0			S	0	
	300.111	9 6/25/2	⁰²⁰ 🗹	STEM - RFI 278: Basement Corridor/Tunnel Coordination	\$16,536	\$0			\$	0	
	300.112	0 6/30/2	020 🗹	STEM - FB 096: Tile Patterns & Layout	\$0				\$	0	
	300.112	2 7/6/20	20	STEM - Swap Inner Layer of Cement Board to Gypsum	\$0	\$0			\$	0	
	300.112	3 7/6/20	20	STEM - FB 066: Stair Bench Cane Rail, Ramps, Risers, Imbeds	\$0				\$	0	
Printed on: 7/8/2020										Page 8 of 14	



Project # 1318014 Brookline High School													
Chang	- Shadin												
AR	CE	Initiated	Out of Scope	Description	Approximate	Proposed	AR Status	AR Sent	Approved	PCCO No	Executed Date		
	300.1124	4 7/6/202	20 🔽	STEM - FB 095: BDA UL Requirements	\$0				\$	0			
	300.112	5 7/6/202	20	STEM - FB 098: AVB at TWF Splice Only	\$0				\$	0			
	300.112	6 7/8/202	20 N	STEM - FB 093: VRL Machine Room Rating	\$0				\$	0			
	300.112	7 7/8/202	20	STEM - FB 097: 6in San Tie In to Existing Greenough	\$0				S	0			
	310.101	7 8/14/20	¹⁹ 🗹	Enabling - Field Bulletin 001 - Curtain Wall Pricing Set	\$0				\$	0			
	310.102	0 8/14/20	19 🗹	Enabling - Field Bulletin 004 - Structural Coordination	\$0				\$	0			
	310.102	1 8/14/20	¹⁹ 🗹	Enabling - Field Bulletin 005 - Subs/Trades awarded prior to issuance	\$0				\$	0			
	310.1022	2 8/14/20	19 🗹	Enabling - Field Bulletin 005 - Remaining Procurement	\$0				\$	0			
	310.103	0 8/14/20	¹⁹ 🗹	Enabling - Masonry Mockups	\$0				\$	0			
	310.1032	2 8/14/20	19 🗹	Enabling - Changes to CMP Requested by ToB DPW for Project C	\$0	\$	50		\$	0			
	310.103	3 8/14/20	19 🗹	Enabling - Scope revisions to precast concrete during design assist process	\$0				\$	0			
	310.103	5 8/14/20	¹⁹ 🗹	Enabling - Overtime - Changes in Scope	\$0				\$	0			
310.031	310.103	9 8/19/20	¹⁹ 🗹	Enabling - RFI #048: Additional Valves	\$5,000	\$	60 Void	01/06/2020	\$	0			
	310.104	7 8/30/20	¹⁹ 🗖	Enabling - RFI: #100: RTU Curb Relocation	\$0				\$	0			
	310.106	5 9/13/20	19 🗹	Enabling - Fire Door Hold Opens - Owner Request - See CE 310.1074	\$0				S	0			
	310.107	0 9/17/20	¹⁹ 🗹	Enabling - RFI #119: Relocation of Sanitary Vent at H&V	\$0				\$	0			
	310.1072	2 9/18/20	¹⁹ 🗹	Enabling - RFI #117: Covered Walkway Lighting	\$0	\$	60		S	0			
	310.107	5 9/25/20	¹⁹ 🗹	Enabling - RFI #118: Masonry Demolition at Connector - See CE 310.1106	\$0	\$	50		\$	0			
	P	rinted on:	7/8/202	0							Page 9 of 14		



.

ojec	st#13	18014		Brookline High School								
ange	e Sumi	nary										- Shading identifies CE budget alloc
ર	CE	Initiated	Out of Scope	Description	Approximate	Proposed	AR Status	AR Sent	Approved		PCCO No	Executed Date
	310.1076	9/30/20	¹⁹ 🗹	Enabling - RFI #127: H&V Unit Smoke Detector & Testing Requirement	\$0	\$0			:	\$0		
	310.1078	8 10/1/20	19 🗹	Enabling - RFI #112: Existing Attic Sprinklers	\$0	\$0				\$0		
	310.1084	10/2/20	¹⁹ 🗹	Enabling - Field Bulletin 019 - Connector Sawcut Demo - See CE 310.1075 (RFI 118)	\$0					\$0		
	310.1088	8 10/10/20	⁰¹⁹ 🗹	Enabling - RFI #122: Electrical Conduit at 2nd Floor Connector - See CE 310.1091	\$0	\$0			;	\$0		
	310.1089	0 10/13/20	⁰¹⁹ 🗹	Enabling - RFI #130: Relocation of Interior Door at 3rd Floor Egress Stair	\$2,205	\$0			;	\$0		
	310.1090	0 10/13/20	⁾¹⁹ 🗹	Enabling - RFI #133: Soffit at Cafeteria Entrance	\$0	\$0			;	\$0		
	310.1091	10/14/20	⁰¹⁹ 🗹	Enabling - Field Bulletin 021.1 - RFI 122	\$0	\$0				\$0		
	310.1092	2 10/18/20	019 🗹	Enabling - RFI #062: Gas Booster Electrical Scope - Field Bulletin 003	\$0	\$0			:	\$0		
	310.1093	10/21/20	⁾¹⁹ 🗹	Enabling - RFI #092: Waterproofing - Exterior Thickness	\$0	\$0			:	\$0		
	310.1097	10/22/20	⁰¹⁹ 🗹	Enabling - Investigate Existing Kitchen Power	\$1,102	\$0				\$0		
	310.1101	10/25/20	⁰¹⁹ 🗹	Enabling - RFI #124: Unit Heater Relocation	\$2,205	\$0				\$0		
	310.1102	10/25/20)19 🗹	Enabling - RFI #104: Window at Connector - 3rd Floor	\$0	\$0				\$0		
	310.1103	10/25/20	⁰¹⁹ 🗹	Enabling - RFI #105: IMSA Fire Alarm Cable Designation	\$0	\$0				\$0		
	310.1104	10/28/20	⁰¹⁹ 🗹	Enabling - RFI #129: Fire Rating of Rooftop Dog House Duct	\$0	\$0			;	\$0		
	310.1106	5 11/7/20	19 🗹	Enabling - Field Bulletin 019 REV A - Masonry Connector	\$0	\$0			;	\$0		
	310.1112	12/4/20	¹⁹ 🔽	Enabling - Field Bulletin 033 & 033R1 - Patch Concrete at Exist. Bldg Ceiling	\$0	\$0				\$0		
	310.1115	12/23/20)19 🗹	Enabling - RFI #146: Weather Tight - Beam Pockets at Tunnel	\$2,206	\$0			;	\$0		
	310.1116	12/23/20	⁾¹⁹ 🗹	Enabling - Field Bulletin 046 - Beam Pocket Infill -	\$0					\$0		
	P	rinted on:	7/8/202	0								Page 10 of 14



.

Projec	:t # 13	18014		Brookline High Schoo	bl						
Chang	e Sumr	nary									- Shading identifies CE budget allocat
AR	CE	Initiated	Out of Scope	Description	Approximate	Proposed	AR Status	AR Sent	Approved	PCCO No	Executed Date
				Permanent Condition							
	310.1117	12/23/20	¹⁹ 🗖	Enabling - RFI #159: Permanent Condition - Beam Pockets in Tunnel	\$0				\$0		
	310.1119	1/7/202	0 🗹	Enabling - Flett slips - To be allocated or rejected	\$0	\$0			\$0		
	310.1131	2/19/202	20 🗹	Enabling - Allegheny Breakout from CE 310.1049 - Field Bulletin 010	\$1,000	\$0			\$0		
400.009	400.1001	7/29/20	¹⁹ 🗹	MBTA - Delays Associated with MBTA License of Entry	\$11,023	\$35,800	Submitted	03/10/2020	\$0		
400.025	400.1002	6/28/20	N 9	MBTA - OCS & Enabling Field Bulletin # 001	\$316,572	\$205,708	Submitted	03/25/2020	\$0		
400.007	400.1003	7/13/20	¹⁹ 🗹	MBTA - OCS & Enabling Field Bulletin # 002	\$38,109	\$28,176	Submitted	03/20/2020	\$0		
	400.1004	7/17/20	¹⁹ M	MBTA - RFI #017: Electrical Service Cabinet Pad Rebar	\$0				\$0		
	400.1005	8/13/20	¹⁹ 🗹	MBTA - Platform Construction	\$(2,762,740)	\$0			\$0		
	400.1006	8/13/20	¹⁹ M	MBTA - RFI #008: OCS Portal Coatings	\$0				\$0		
	400.1008	8/13/20	¹⁹ 🗹	MBTA - RFI #011: Strutural Streel Coating	\$0				\$0		
	400.1009	8/13/20	19 	MBTA - RFI #012: OCS Portal Foundation Depth	\$0				\$0		
	400.1010	8/13/20	¹⁹ 🗹	MBTA - RFI #014: Changes To Paint Finishes	\$0				\$0		
	400.1011	8/13/20	¹⁹ 🗹	MBTA - RFI #022: FB 2 EDB 1c Routing	\$0	\$0			\$0		
	400.1013	8/15/20	19 M	MBTA - Track Replacement	\$0	\$0			\$0		
	400.1014	8/15/20	¹⁹ 🗹	MBTA - SMP Ammendment (Double Handling Soil)	\$0				\$0		
	400.1015	8/15/20	¹⁹ 🕅	MBTA - Add 4th OCS Portal	\$0				\$0		
	400.1016	9/19/20	¹⁹ 🗹	MBTA - RFI #017: Electric Service Cabinet Pad Rebar	\$0				\$0		
	400.1017	9/19/20	N ⁹	MBTA - Delays Associated with State Building Permit	\$20,000	\$0			\$0		
	400.1018	9/19/20	¹⁹ 🗹	MBTA - Furnish OCS Cable Protection for MBTA	\$110,234	\$0			\$0		
	Pr	rinted on:	7/8/202	0							Page 11 of 14



Projec	ct # 13	18014		Brookline High School							
Chang	e Sumi	nary									- Shading identifies CE budget allocation
AR	CE	Initiated	Out of Scope	Description	Approximate	Proposed	AR Status	AR Sent	Approved	PCCO No	Executed Date
				Work Install by Others							
400.019	400.1021	9/30/20	¹⁹ 🗹	MBTA - OCS & Enabling Field Bulletin # 004 Relocated Pay Station and AFC Hut	\$0	\$24,661	Submitted	03/19/2020	\$)	
400.011	400.1022	2 9/30/20	19 🗹	MBTA - OCS & Enabling Field Bulletin # 005	\$11,023	\$14,520	Submitted	03/12/2020	\$)	
400.012	400.1026	5 10/10/20	⁾¹⁹ 🗹	MBTA - RFI #037: Pay Meter Foundation Revisions	\$2,756	\$8,700	Submitted	03/12/2020	\$)	
400.013	400.1027	7 10/10/20	⁰¹⁹ 🗹	MBTA - RFI #038: Fare Vending Slab Revisions	\$5,512	\$967	Submitted	03/13/2020	\$)	
400.022	400.1029	0 10/17/20	⁾¹⁹ 🗹	MBTA - OCS & Enabling FB 05.5 - Revised Parking Pay Meter Ductbank Routing	\$16,333	\$11,203	Submitted	03/19/2020	\$)	
400.020	400.1030) 10/21/20)19 🗹	MBTA - OCS & Enabling Field Bulletin 005.6 - ToB Meter Cabinet Power	\$10,888	\$16,529	Submitted	03/19/2020	\$)	
400.032	400.1032	2 10/24/20	⁾¹⁹ 🗹	MBTA - Furnish & Install Line Protection not Completed by MBTA	\$10,888	\$7,424	Submitted		\$)	
400.024	400.1033	3 10/25/20)19 🗹	MBTA - OCS & Enabling Field Bulletin 007 - Added OSC Portal	\$250,433	\$308,706	Submitted	03/23/2020	\$)	
400.016	400.1034	10/25/20	⁾¹⁹ 🗹	MBTA - OCS & Enabling Field Bulletin 006 - Sliding MBTA Gate	\$11,279	\$4,566	Submitted	03/13/2020	\$)	
400.015	400.1038	8 11/11/20	⁰¹⁹ 🗹	MBTA - OCS & Enabling Field Bulletin 010 - Fare Collection Hut Foundation	\$5,512	\$9,260	Submitted	03/13/2020	\$)	
	400.1039	0 10/2/20	¹⁹ 🗹	MBTA - Furnish Temporary Line Protection 9/20/19	\$18,740	\$0			\$)	
400.014	400.1042	2 2/11/20	20	Widen Crossing Replaced by Barletta	\$0	\$8,184	Submitted	03/16/2020	\$)	
	400.1043	3 2/11/20	20	MBTA - Field Bulletin 013 Portal Foundation Redesign	\$204,207	\$0			\$)	
400.017	400.1044	4 2/11/20	20	MBTA - West Walkway & Platform Improvements	\$21,777	\$29,587	Submitted	03/16/2020	\$)	
400.021	400.1045	5 2/11/20	20	MBTA - Temporary AFC Connections (Comm & Elec)	\$16,333	\$17,602	Submitted	03/19/2020	\$)	
400.018	400.1046	5 2/11/20	20	MBTA0 OCS & Enabling - Service Conduit Work at Pole #144	\$11,023	\$5,663	Submitted	03/18/2020	\$)	
400.008	400.1048	3 2/11/20	20	MBTA - Temporary Lights along ROW	\$27,559	\$24,615	Submitted	03/13/2020	\$)	

Printed on: 7/8/2020

Page 12 of 14



Project # 1318014 Brookline High School													
Chang	e Sumi	nary									- Shading identifies CE budget allocation		
AR	CE	Initiated	Out of Scope	Description	Approximate	Proposed	AR Status	AR Sent	Approved	PCCO No	Executed Date		
	400.1049	2/11/20	²⁰ 🗹	MBTA - FB 011 - Permit Set Revisions	\$99,211	\$0			\$)			
400.010	400.1050	2/11/20	20	MBTA - Provide Temporary Power to Platform Lighting and Bungalows	\$30,047	\$32,541	Submitted	03/19/2020	\$)			
	400.1051	2/11/20	²⁰ 🗹	MBTA - Remaining Line Protection	\$143,303	\$0			\$	0			
400.027	400.1052	2 3/11/20	20	Relocate Temporary Lights at Closed Platform to New Portals	\$2,178	\$3,120	Submitted	04/08/2020	\$)			
400.026	400.1054	3/13/20	²⁰ 🗹	MBTA - OCS Eversource - Town of Brookline Meter Location Delay	\$7,912	\$7,853	Submitted	04/08/2020	\$)			
400.1055 3/18/2020 MBTA - OCS & Enabling Feeder Fire \$(10,000) \$0 \$0													
400.029 400.1057 3/26/2020 MBTA- OCS & Enabling Grounding MBTA \$8,166 \$5,352 Submitted 04/24/2020 \$0 Bungalows													
	400.1058	3/31/20	20	De-mobilize MBTA Trailer	\$3,811	\$0			\$)			
400.028	400.1059	4/9/202	20 🔽	MBTA OCS & Enabling - Snow Removal Above Allowance 2019-2020 Winter	\$1,796	\$1,793	Submitted	04/09/2020	\$)			
	400.1060	5/6/202	20	MBTA & Enabling - FB 017 Signage Revisions	\$0	\$0			\$)			
	400.1061	5/6/202	20	MBTA & Enabling - FB 018 RFI 059 South East Ramp Layout	\$0	\$0			\$)			
	400.1062	5/6/202	20	MBTA & Enabling - FB 019 Helical Pile Revisions	\$33,070	\$0			\$)			
	400.1063	6/1/202	20	OCS & Enabling Duct Bank Impacts	\$0	\$0			\$)			
	400.1065	6/9/202	20 🔽	MBTA - FB 020 - RFI 064 Helical Pile Potential Obstructions	\$0				\$)			
400.031	400.1066	6/17/20	20	Station: Provide Canopy Shop Splice & MBTA Coatings in Excess of Allowance	\$30,772	\$30,750	Open		\$)			
500.001 500.1002 2/25/2020 Image: Constraint of the state o													
	500.1004	7/6/202	20	DEF MAINT - FB 0100: Replace Elevator Jack at Elev 2	\$0				\$)			
Project Totals for 1318014 - Brookline \$2,600,887 \$2,017,504 \$0													
	High School :												
	Ρ	rinted on:	7/8/202	0							Page 13 of 14		

SKANSKA

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT J: APPROVED PRIME CONTRACT CHANGE ORDERS



Date: 12/12/2019

Prime Contract Change Order Number 001

Brookline High School

Project # 1318014

Skanska USA Building Inc.

To Contractor:	Architect's Project No:
Skanska USA Building Inc.	Contract Date: 7/24/2018
	Contract Number: 1318014

The Contract is hereby revised by the following items:

Approved Authorization Requests 12/12/19

AR	CE	Description	Amount
310.004	310.1002	Enabling - RFI #049: Delete Fire Department Connection Bypass	\$ 0.00
310.005	310.1004	Enabling - RFI #054: FDC Location	\$ 0.00
310.012	310.1009	Enabling - RFI #066: Existing Fire Alarm Devices in Tunnel	\$ 2,248.00
310.009	310.1010	Enabling - RFI #067: Unforeseen Electrical Conditions - Wiring	\$ 7,234.00
310.010	310.1023	Enabling - Field Bulletin 006 - RFI 058, 063, 067 - See CE # 310: 1006 (RFI 058), 1007 (RFI 063), & 1010 (RFI 067)	\$ 0.00
310.002	310.1025	Enabling - Field Bulletin 006.2 - Addt'l Isolation Valves	\$ 3,434.00
310.006	310.1079	Enabling - Field Bulletin 017 - RFI 112 Existing Attic Sprinkler Removal	\$ 5,296.00
200.001	200.1024	CYPRESS - Purchase Line Hose for MBTA	\$ 44,979.00
400.003	400.1025	MBTA - Replenish Line Protection Provided by MBTA	\$ 10,725.00
400.002	400.1036	MBTA - Office Trailer Deliver and Rent	\$ 8,396.00
200.002	200.1046	CYPRESS - Field Bulletin 023 - Water Utility Spec Updates	\$ 5,969.00

For Approval, Refer to Pre-GMP Amendment and Associated AIA G701 with Town of Brookline Signature Page Attached

Printed on: 12/12/2019

Page 1 of 1



Date: 1/9/2020

Prime Contract Change Order Number 002

Brookline High School

Project # 1318014

Skanska USA Building Inc.

To Contractor: Skanska USA Building Inc.

The Contract is hereby revised by the following items:

Approved Authorization Requests 01/09/20

AR	CE	Description		Amount
310.011	310.1005	Enabling - RFI #056: Existing Sanitary Line Discovery	\$	4,542.00
310.007	310.1006	Enabling - RFI #058: Roof Drain Conflict	\$	10,805.00
310.014	310.1008	Enabling - RFI #064: Plaster Ceiling Discovery & Unistrut	\$	20,879.00
310.020	310.1016	Enabling - RFI #075: Unistrut Lateral Bracing	\$	7,467.00
310.017	310.1024	Enabling - Field Bulletin 006.1 - RFIs: 049, 054, 064, & 082 - See CE # , 1004 (RFI 054), 1008 (RFI 064), & 1015 (RFI 082)	310: 1002 (RFI 049) \$	0.00
310.013	310.1038	Enabling - Frontline - T&M contract	\$	0.00
310.015	310.1085	Enabling - Allegheny T&M Contract	(\$	6,240.00)
			TOTAL	\$ 37,453.00

For Approval, Refer to Pre-GMP Amendment and Associated AIA G701 with Town of Brookline Signature Page Attached

Printed on: 1/9/2020

Page 1



Date: 2/6/2020

Prime Contract Change Order Number 003

Brookline High School

Project # 1318014

Skanska USA Building Inc.

To Contractor: Skanska USA Building Inc.

The Contract is hereby revised by the following items:

Approved Authorization Requests 02/06/20

AR	CE	Description		Amount
310.024	310.1014	Enabling - RFI #074: Roberts Wing Demolition Limits / Investigative Work	\$	5,097.00
310.018	310.1028	Enabling - Field Bulletin 008 & 008.1 - Counter in Cafeteria	\$	14,406.00
310.025	310.1034	Enabling - Overtime - Expedite/Accelerate Week Ending 7/13	\$	0.00
310.039	310.1040	Enabling - RFI #077: Lintel Sizing - Crawl Space	-\$	706.00
310.028	310.1042	Enabling - Evacuation Maps	\$	995.00
310.026	310.1046	Enabling - Field Bulletin 009 - RTU Curb Relocation	\$	18,942.00
310.034	310.1051	Enabling - Overtime - Expedite/Accelerate Week Ending 8/3	\$	0.00
310.037	310.1056	Enabling - Safe Relocation	\$	1,455.00
310.022	310.1067	Enabling - RFI #115: Exterior Lighting Not Working	\$	746.00
310.036	310.1071	Enabling - Field Bulletin 013 - Relocate Existing Vent at RTU	\$	5,905.00
310.048	310.1073	Enabling - Field Bulletin 014 - Addt'l Lights at Covered Walkways	\$	7,464.00
400.006	400.1020	MBTA - OCS & Enabling Field Bulletin # 003	\$	0.00
310.042	310.1074	Enabling - ToB Request - Investigate Clock & Fire Alarm Issues	\$	1,213.00
400.004	400.1024	MBTA - Furnish Temporary Line Protection 9/20/19	\$	17,892.00
310.047	310.1081	Enabling - Field Bulletin 020 - Gooseneck Duct Extension	\$	4,274.00
310.021	310.1082	Enabling - RFI #123: Thermostat Questions	\$	1,901.00
310.023	310.1083	Enabling - Field Bulletin 021 - RFI 115 & 123 - See CE 310.1067 (RFI 115) & 310.1082 (RFI 123)	\$	0.00
310.045	310.1094	Enabling - Door Controller/Operator Cut	\$	523.00
310.043	310.1095	Enabling - RFI #093: Tel/Data Aerial Connection	-\$	16,684.00
200.003	200.5011	CYPRESS - Owner Allowance - BP#05A - SOE Obstruction Allowance	\$	0.00
200.004	200.5012	CYPRESS - Owner Allowance - BP#05A - Elimination of Tie Backs Under MBTA Tracks	\$	0.00
310.033	310.1121	Enabling - Griffin OT - Contingency/Acceleration	\$	0.00
400.005	400.1041	MBTA - Replenish Line Protection Provided by MBTA II	\$	1,570.00
			TOTAL	\$ 64,993.00



Date: 4/8/2020

Prime Contract Change Order Number 004

Brookline High School

Project # 1318014

Skanska USA Building Inc.

To Contractor:

Skanska USA Building Inc.

The Contract is hereby revised by the following items:

Approved Authorization Requests 04/08/20

AR	CE	Description		Amount
310.065	310.5000	Enabling - Owner Allowance - Concrete - Fdn for temp stair	-\$	8,815.00
310.052	310.1001	Enabling - RFI #002.1: Foundations for the Urns	\$	5,038.00
310.050	310.1003	Enabling - RFI #052: New Pipe Chase / Addt'l Structural Support	-\$	15,852.00
310.008	310.1007	Enabling - RFI #063: Existing Fire Alarm Panel	\$	42,188.00
310.049	310.1011	Enabling - RFI #069: Unforeseen Electrical Conditions Wiring	\$	34,979.00
310.016	310.1015	Enabling - RFI #082: Level 3 Beams Elimination	\$	940.00
310.001	310.1019	Enabling - Field Bulletin 003 - Gas Booster Deletion	-\$	17,476.00
310.053	310.1026	Enabling - Field Bulletin 006.3 - RFIs: 066, 067, 069, 074, 075, 076, & 081 - See CE # 310: 1009 (RFI (66), 1010 (RFI 067), 1011 (RFI 069), 1014 (RFI 074), 1016 (RFI 075), 1036 (RFI 076), & 1037 (RFI 081)	\$	0.00
310.027	310.1029	Enabling - RFI #059: Changes made to temp. egress stair	\$	11,244.00
310.081	310.1036	Enabling - RFI #076: MC Cable from Level 1 to 2	\$	0.00
310.082	310.1037	Enabling - RFI #081: HWR Reroute Levels 1 - 2	\$	666.00
310.067	310.5001	Enabling - Owner Allowance - Concrete - foundation for temp handicap ramp	-\$	9,201.00
310.085	310.6002	Enabling - Exposure Hold - Concrete - Temp. support of crawl space walls	\$	0.00
310.080	310.5003	Enabling - Owner Allowance - Drywall - Patching	-\$	28,023.00
310.087	310.5004	Enabling - Owner Allowance - Drywall - New ACT & Grid	-\$	8,444.00
310.078	310.6009	Enabling - Exposure Hold - Flooring - Minor Floor Prep	\$	0.00
310.079	310.5005	Enabling - Owner Allowance - Painting - Paint drywall patches	-\$	15,012.00
310.086	310.5007	Enabling - Owner Allowance - Sitework - E&B at temp handicap ramp foundation	-\$	9,021.00
310.032	310.1049	Enabling - Field Bulletin 010 - Temp. Stair Fire Separation	\$	6,467.00
310.041	310.1052	Enabling - Overtime - Expedite/Accelerate Week Ending 8/10	\$	0.00
310.059	310.1054	Enabling - Overtime - Expedite/Accelerate Week Ending 8/24	\$	0.00
310.060	310.1055	Enabling - Overtime - Expedite/Accelerate Week Ending 8/31	\$	0.00
310.063	310.1057	Enabling - Field Bulletin 011 - Existing Foundation Wall Crack	\$	2,568.00
310.035	310.1058	Enabling - Field Bulletin 012 - Temp. Enclosure at Covered Walkway	\$	22,893.00
310.061	310.1061	Enabling - CMP Revisions at 111 Cypress	\$	4,119.00
310.056	310.1068	Enabling - Temp. Handrail Modification	\$	0.00
310.075	310.1077	Enabling - Field Bulletin 015 - Fire Alarm Duct Smoke Detector / ZAM Module	\$	8,033.00
310.044	310.1080	Enabling - Field Bulletin 018 - Added Power at Trap Primer	\$	872.00
310.054	310.1096	Enabling - Reconnect CUH & Elevator power due to sawcut	\$	6,241.00
310.055	310.1098	Enabling - Fire Protection Dry Valve Test - Overtime	\$	0.00
310.030	310.1100	Enabling - Teachers Room	\$	1,572.00
310.077	310.1111	Enabling - Field Bulletin 030 - Relocate DP Sensor	\$	0.00
310.070	310.1114	Enabling - GPRS in Basement	\$	801.00
310.076	310.1118	Enabling - RFI #160 - Enabling Tree Protection	\$	6,206.00
310.057	310.1120	Enabling - Build Dummy Walls - Levels 1 & 2	\$	0.00
310.058	310.1122	Enabling - Sitework Final Clean	\$	0.00
310.091	310.1125	Enabling - Griffin Breakout for CE 310.1003 - RFI #052: New Pipe Chase	\$	0.00
310.066	310.1126	Enabling - Overtime - Expedite/Accelerate Week Ending 6/30	\$	0.00
310.083	310.1127	Enabling - Modifications made to the temp stair during sitewalk	\$	2,154.00
310.088	310.1132	Enabling - Parapet Cut for Demolition	\$	841.00
			TOTAL	\$ 45,978.00

Neither the Contract Price (or eventually the GMP) nor the Contract Time (or eventually the project schedule) upon which said Contract Price (and eventual GMP) is based contemplates any project delays, suspensions, disruptions, cost escalations or other impacts caused, directly or indirectly, by Coronavirus.



Date: 4/29/2020

Prime Contract Change Order Number 005

Brookline High School

Project # 1318014

Skanska USA Building Inc.

To Contractor: Skanska USA Building Inc.

The Contract is hereby revised by the following items:

Approved Authorization Requests 04/29/20

AR	CE	Description		Amount
310.092	310.1013	Enabling - Brokk at Crawl Space Wall	\$	38,357.00
310.051	310.1018	Enabling - Field Bulletin 002 - Misc. Submittal & RFI Conformance	\$	127,815.00
310.062	310.5002	Enabling - Owner Allowance - Masonry - Mockup Masonry Sample Boards	-\$	9,679.00
300.004	300.1007	STEM - Precast Scope Revisions During Design Assist	\$	9,121.00
200.006	200.1009	CYPRESS - Field Bulletin 001 - Landscape Demo Plan	\$	0.00
200.007	200.1010	CYPRESS - Field Bulletin 002 - Updated SMP Boundary	\$	0.00
200.008	200.1011	CYPRESS - Field Bulletin 003 - Curtainwall Updates	\$	0.00
200.009	200.1012	CYPRESS - Field Bulletin 004 - Plaza Updates	\$	0.00
200.010	200.1014	CYPRESS - Field Bulletin 006 - Misc. Concrete and Steel Revisions	\$	0.00
200.011	200.1015	CYPRESS - Field Bulletin 007 - Acoustic Deck and Beam Penetrations	\$	0.00
200.012	200.1016	CYPRESS - Field Bulletin 008 - AREMA Updates	\$	0.00
310.071	310.1113	Enabling - McPhail Over Excavation	\$	13,537.00
200.013	200.1065	CYPRESS - Field Bulletin 049 - Spec Section 260750	\$	0.00
400.023	400.1047	MBTA - MBTA Trailer Set Up	\$	7,800.00
310.073	310.1128	Enabling - Electrical Breakout of Field Bulletin 002	\$	31,532.00
300.006	300.1071	STEM - FB 064: HHW Controls and Sequence	\$	0.00
			TOTAL	\$ 218,483.00

Neither the Contract Price (or eventually the GMP) nor the Contract Time (or eventually the project schedule) upon which said Contract Price (and eventual GMP) is based contemplates any project delays, suspensions, disruptions, cost escalations or other impacts caused, directly or indirectly, by Coronavirus.



Date: 6/3/2020

Prime Contract Change Order Number 006

Brookline High School

Project # 1318014

Skanska USA Building Inc.

To Contractor: Skanska USA Building Inc.

The Contract is hereby revised by the following items:

PCCO 6 Approved Authorization Requests 05/29/20

AR	CE	Description		Amount
310.084	310.5006	Enabling - Owner Allowance - Sitework - E&B at temp stair foundation	-\$	8,012
310.029	310.1043	Enabling - RFI #089 Temporary Wall - Basement	\$	0
310.046	310.1066	Enabling - RFI #114: Wiring for Old Cabinet Unit Heaters	\$	3,751
200.031	200.1017	CYPRESS - Field Bulletin 008A - Steel Brick Support Revisions	\$	0
300.010	300.1010	STEM - FB 001 - Curtainwall Pricing Set	\$	0
200.005	200.1027	CYPRESS - Survey MBTA Track Replacement	\$	4,780
200.032	200.1028	CYPRESS - Field Bulletin 010 - Structural Steel Detail Revisions	\$	0
300.015	300.1017	STEM - FB 025 - Foundation Wall Coordination	\$	0
300.011	300.1020	STEM - FB 027 - Elevator Furring and Hall Buttons	\$	0
300.017	300.1022	STEM - FB 029 - Window Shade Reduction	-\$	2,537
310.094	310.1108	Enabling - RFI #085: Direct Bury Trench - Reroute	\$	14,914
300.018	300.1024	STEM - FB 042 - Stair 3 Dimensional Adjustment	\$	0
300.019	300.1025	STEM - FB 045 - Stair 4 and 5 Dimensional Adjustment	\$	0
300.023	300.1029	STEM - FB 052 - P1 and F49 Conflict with Existing Tunnel RFI 164	\$	16,436
300.024	300.1031	STEM - FB 043 - Sloped Walk Revisions	\$	0
300.025	300.1033	STEM - FB 041 & 041R1 - Repair Leaking Storm Line in Existing Building	\$	20,393
300.021	300.1034	STEM - FB 046 - Beam Pocket Infill Permanent Condition	\$	0
200.035	200.1049	CYPRESS - Field Bulletin 022 - OCS Insert Layout Revisions	\$	0
310.074	310.1123	Enabling - Clean Exposed Trench	\$	0
300.022	300.1038	STEM - Premium Time 01/11/2020 and 01/18/2020	\$	0
300.014	300.1041	STEM - FB 005.5 - AV Specification and Drawings Update	\$	0
200.026	200.1064	CYPRESS - Field Bulletin 040R1 - Shaft Dimensional Adjustment	\$	0
310.090	310.1124	Enabling - Siemens Troubleshooting	\$	0
200.027	200.1071	CYPRESS - Field Bulletin 040R2 - Shaft Dimensional Adjustment	\$	3,181
200.022	200.5022	CYPRESS - Owners Allowance - BP#01 - Grouting of Precast Plank and Voided Slabs	\$	0
200.023	200.6066	CYPRESS - EH - BP#01 - Provide Embed Plates for Safety Stanchions	\$	0
300.026	300.1062	STEM - FB 053: Revise Lab Faucet Type	\$	3,341
300.027	300.1063	STEM - FB 050: Details Around Interior Aluminum Frames	\$	1,417
300.009	300.1066	STEM - RFI 222: Unistrut Rack in Mechanical Trench	\$	6,136
300.028	300.1072	STEM - FB 068: Modify Matt Foundation for Existing Sanitary Line	\$	2,452
200.028	200.1106	CYPRESS - Field Bulletin 069.1 - AHU 8 Revisions - Plumbing Coordination	\$	362
200.030	200.1127	CYPRESS - Field Bulletin 075 - Physics Classroom Faucet Revisions	\$	0
310.095	310.1136	Enabling - Observation #148 - Seal ductwork insulation at doghouse	\$	0
300.029	300.1082	STEM - FB 077: Device Coordination	\$	0
300.030	300.1083	STEM - RFI 245: Soil Classification around Building Footprint	\$	4,079
310.096	310.1138	Enabling - Allegheny - Material Only for CO 003/slip #23980	\$	1,128
				\$ 71,821

Neither the Contract Price (or eventually the GMP) nor the Contract Time (or eventually the project schedule) upon which which said Contract Price (and eventual GMP) is based contemplates any project delays, suspensions, disruptions, cost escalations or other impacts caused, directly or indirectly, by Coronavirus.

SKANSKA

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT K: DIVISION 01 SPECIFICATION MODIFICATIONS

- 1. Refer to attached document redlined and prepared by Hill International for agreed upon modifications to the Division 01 specifications for both the Project C STEM Wing Addition ("Stem") and Project A Cypress Building ("Cypress") projects, based on a collaborative review and agreement by Hill, Skanska and WRA.
- The agreed upon modifications to the Division 01 Specifications are based on the Project C STEM Wing Addition Early Package # 2 specification book as modified and issued with Revision: FB-005 – GMP Bid Set – August 1, 2019.
- 3. The agreed upon modifications assumed that the Division 01 Specifications for Project C STEM Wing Addition GMP Bid Set are identical to the Division 01 Specifications for Project A Cypress Building Field Bulletin # 9 GMP Bid Set. In the case there are discrepancies between the two, the Project C STEM wing specifications shall prevail.
- 4. If the Division 01 Specifications require better quality or greater quantity, the Owner-CM Agreement shall take precedence unless expressly agreed to by the Parties.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

SECTION 011100

SUMMARY OF WORK

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

- A. Attention is directed to Division 00 PROCUREMENT AND CONTRACTING REQUIREMENTS and DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.
- B. Examine all other Sections of the Specifications for requirements that affect work of this Section, whether or not such work is specifically mentioned in this Section.
- C. Coordinate Work with that of all other trades affecting or affected by Work of this Section. Cooperate with such trades to assure the steady progress of all Work under the Contract.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Work covered by the Contract Documents
 - 2. Contract Method
 - 3. Contract Conditions
 - 4. Work under other contracts
 - 5. Work Sequence
 - 6. Owner-furnished products
 - 7. Construction Manager use of premises
 - 8. Permits, inspection and testing required by Governing Authorities
 - 9. Specification formats and conventions.
 - 10. Reference standards.
 - 11. Miscellaneous Provisions.

1.3 WORK UNDER THIS CONTRACT

- A. Project Identification: Brookline High School Expansion Project B Tappan, Stem, Third Floor, Tappan Streetscape, Deferred Maintenance.
- B. Project Location: 111 Cypress Street, Brookline, MA 02445.
- C. Owner: Town of Brookline.
- D. Architect-of-Record: William Rawn Associates Architects, Inc., 10 Post Office Square, Suite 1010, Boston, MA 02109.

REVISION: FB-005 - GMP Bid Set - AUGUST 1, 2019

1.4 CONTRACT METHOD:

Project will be constructed under a single prime contract. This Contract shall be Construction A. Manager at Risk, bid as required by Public Bid Laws.

1.5 CONTRACT CONDITIONS

- Α. This Contract is subject to applicable State and local laws and all amendments thereto. Where any requirements contained herein do not conform to statutes governing the Work of this Contract, the statutes shall govern.
- This Project will be constructed for a political subdivision of the Commonwealth of no tax is paid. Even Β. Massachusetts, and is therefore exempt from State Sales and Use Tax. All bids shall be under tax exempt prepared and purchase of materials for the Project made on the basis of such exemption. After execution of the Contract, the Owner will furnish the Construction Manager with the the department of exemption number to be used.
- C. The provisions of the Federal Occupational Safety and Health Act (OSHA) apply to the execution of the Work of this Contract, in addition to all other laws, ordinances, rules, regulations, and orders of any Federal, State, or local public authority bearing on the performance of the Work.
- D. Each and every provision of law and clause required by law to be inserted in this Contract paragraph. Article shall be deemed to be inserted herein and the Contract shall be read and enforced as though 5.12.1 of Owner CM it were included herein, and if, through mistake or otherwise, any such provision is not inserted, or is not correctly inserted, then upon application of either part the Contract shall required to ascertain forthwith be physically amended to make such insertion or correction.

This does not mean status, certain items are still taxable per revenue guidance.

Exclude this Agreement states that CM is not this, only to notify if variances are made known to the CM.

1.6 WORK UNDER OTHER CONTRACTS

General: Cooperate fully with separate contractors so work on those contracts may be Α. carried out smoothly, without interfering with or delaying work under this Contract. Coordinate the Work of this Contract with work performed under separate contracts.

1.7 WORK SEQUENCE

- General: The Construction Manager's attention is directed toward the critical activities and Α. limitations listed in this Article to highlight unusual conditions present in this Project.
 - 1. The Construction Manager shall be responsible for scheduling the Work accordingly, and in conformance with requirements of all other specifications for the Project.
 - Sequencing requirements shall be clearly identified on all construction schedules re-2. guired under Section 013200 - Construction Progress Documentation.
 - General Sequence of Work: 3.
 - Hazardous Material Procedures. a.
 - Site Enabling. b.
 - Demolition. C.
 - New Construction. d.
 - Sitework and Utilities. e.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- B. Owner Responsibility: Prior to commencement of construction at the site, the Owner will move all loose furnishings out of existing buildings. Owner did not do this
- C. Critical Activities: Each of the following critical activities must be completed prior to other construction activities as indicated:
 - As determined by CM. 1.

1.8 **OWNER-FURNISHED PRODUCTS**

- Owner will furnish products indicated. The Work includes providing support systems to A. receive Owner's equipment and making plumbing, mechanical, and electrical connections.
 - Owner will arrange for and deliver Shop Drawings, Product Data, and Samples to Con-1. struction Manager.
 - 2. Owner will arrange and pay for delivery of Owner-furnished items according to Construction Manager's Construction Schedule.
 - After delivery, Owner will inspect delivered items for damage. Construction Manager 3. shall be present for and assist in Owner's inspection.
 - 4. If Owner-furnished items are damaged, defective, or missing, Owner will arrange for replacement.
 - Owner will arrange for manufacturer's field services and for delivery of manufacturer's 5. warranties to Construction Manager.
 - 6. Owner will furnish Construction Manager the earliest possible delivery date for Ownerfurnished products. Using Owner-furnished earliest possible delivery dates. Construction Manager shall designate delivery dates of Owner-furnished items in Construction Manager's Construction Schedule.
 - Construction Manager shall review Shop Drawings, Product Data, and Samples and re-7. turn them to Architect noting discrepancies or anticipated problems in use of product.
 - 8. Construction Manager is responsible for receiving, unloading, and handling Ownerfurnished items at Project site.
 - 9. Construction Manager is responsible for protecting Owner-furnished items from damage items 7 to during storage and handling, including damage from exposure to the elements.
 - 10. If Owner-furnished items are damaged as a result of Construction Manager's operations, Construction Manager shall repair or replace them.
 - 11. Construction Manager shall install and otherwise incorporate Owner-furnished items into the Work.
- B. Note that items labeled "N.I.C." on the Drawings will be furnished and installed by the Owner under a separate contract after the completion of the Work.
- Refer to demolition drawings and specifications for existing Owner products to be salvaged, C. stored, and reinstalled.

1.9 CONSTRUCTION MANAGER USE OF PREMISES

- Α. General: Construction Manager shall have full use of premises for construction operations, including use of Project site, during construction period.
 - 1. Confine operations at the site to areas permitted by laws, by-laws, permits and contract

Exclude

11

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

limit lines.

- 2. Do not unreasonably encumber the site with materials or equipment.
- Coordinate with Owner and Architect work in connection with adjacent occupied buildings or areas, driveways, walks, and other facilities which would prevent access thereto or interrupt, restrict, or otherwise infringe upon use thereof.
- B. On-Site Work Hours: Refer to Section 005000 Construction Manager's Exhibit B0 General Project Requirements, Section 2 - Work Hours. All requests for extension of Work Hours must Comply with Town of Brookline By-laws which allow for work between the hours of 7:00 AM - 7:00 PM Weekdays and 8:30 AM - 5:00 PM Saturdays, Sundays, and Legal Holidays. Any requested variance to these hours require action by Town Board of Selectmen for approval.
- C. Existing Utility Interruptions: Refer to Section 011400 Work Restrictions.
- D. Construction Manager Parking: Parking of Construction Manager's vehicles and those of his Subcontractors will be allowed only within Limit of Work area located where shown on Drawings. Construction Manager shall be responsible for parking arrangements, regulation and control of such parking and resulting traffic. Each Subcontractor shall make arrangements with Construction Manager for required parking of his vehicles.
 - On-site parking is not-guaranteed available and should not be expected. Contractors behind Tappan are encouraged to carpool or take public transportation when possible. Parking outside and/or other locations the site fence is strictly prohibited. Vehicles parking in the Town of Brookline without a permit parked outside of designated areas such that they disrupt Project activities are subject to towing at the vehicle-owner's expense. Parking of work or personal vehicles outside of the construction fence is strictly prohibited.
- E. On-Site Delivery and Storage of Construction Materials: Do not permit materials and fabricated work to be stacked on, or be transported over, floor and roof construction in such a manner as to stress any construction beyond the designed live loads. Assume full responsibility for protection and safekeeping of products stored on premises. Obtain and pay for use of additional storage or work areas needed for operations. Limit use of site to work and storage of materials for this project.
 - 1. Maintain clean, dry storage areas for construction materials and minimize their exposure to dust. Refer to Section 018119 Indoor Air Quality Requirements and individual Division 2 through 50 Sections for additional requirements.
 - 2. Do not store foamed polystyrene, polyurethane or like materials within the building. Take proper precautionary measures regarding the Storage of such materials outside the building.
 - 3. Similar or worse than any school in the Commonwealth, student and staff drop off Exclude. Deliveries and pick up times congest traffic with vehicles. No deliveries or other construction vehicles are permitted to enter or leave the site between 7:30am and 8:30am specs. and from 2:15pm and 3:15pm on school days. Or as scheduled with School Dept.

F. Construction Manager shall be responsible for adequate site drainage during the entire construction period and shall use any appropriate temporary means that does not adversely affect construction progress or abutting property. A Stormwater Pollution Prevention Plan, approved by DEP, will be implemented at the inception of the project.

G. Construction Manager shall take all necessary safety precautions and maintain an adequate level of fire protection at all times. Only as required by local codes and AHJ's

Exclude. We are not limited to park where shown on drawings. ToB shall provide parking spaces behind Tappan and/or other locations

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

H. Do not use areas outside the Limit of Work area for temporary storage or structures without specific written permission from the Architect and Owner.

1.10 PERMITS, INSPECTION AND TESTING REQUIRED BY GOVERNING AUTHORITIES

- A. If the Contract Documents, laws, ordinances, rules, regulations or orders of any public authority having jurisdiction require any portion of the Work to be inspected, tested, or approved, the Construction Manager shall give the Architect and such Authority timely notice of its readiness so the Designer may observe such inspection and testing.
- B. Prior to the commencement of construction, the Construction Manager shall complete application to the appropriate Building Code enforcement authority for a Building Permit. Such Permit shall be displayed in a conspicuous location at the Project Site.
- C. Payment requirements for this permit fee are waived by the Owner. Waiver of permit fee in this instance shall not be understood to apply to other permit and fee requirements for the Project.

1.11 REFERENCE STANDARDS

- A. For products specified by association or trade standards, comply with requirements of the standard, except when more rigid requirements are specified or are required by applicable codes.
- B. The date of the standard is that in effect as of the bid date, except when a specific date is specified.
- C. Obtain copies of standards when required by Contract Documents. Maintain copy at job sit during progress of the specific work.

1.12 SPECIFICATION FORMATS AND CONVENTIONS

- A. Specification Format: The Specifications are organized into Divisions and Sections using the 50-division format and CSI's "MasterFormat" numbering system.
 - 1. Section Identification: The Specifications use Section numbers and titles to help crossreferencing in the Contract Documents. Sections in the Project Manual are in numeric sequence; however, the sequence is incomplete because all available Section numbers are not used. Consult the table of contents at the beginning of the Project Manual to determine numbers and names of Sections in the Contract Documents.
 - 2. Division 1: Sections in Division 1 govern the execution of the Work of all Sections in the Specifications.
- B. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:
 - 1. Abbreviated Language: Language used in the Specifications and other Contract Documents is abbreviated. Words and meanings shall be interpreted as appropriate. Words

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

implied, but not stated, shall be inferred as the sense requires. Singular words shall be interpreted as plural, and plural words shall be interpreted as singular where applicable as the context of the Contract Documents indicates.

- 2. All instructions in the Specifications are addressed to the Construction Manager unless the responsibility of the Designer or Owner is clearly indicated.
 - a. Where products are listed or described in outline form, the phrase "The Construction Manager shall furnish these products" is implied.
 - b. Where installation instructions or performance criteria are listed or described in outline form, the phrase "The Construction Manager shall perform the Work in accordance with these requirements" is implied.
 - c. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.
- C. Definitions:
 - 1. Indicated: The word "indicated" refers to graphic representations, notes or schedules on Drawings, Paragraphs or schedules in Specifications, and similar requirements in Contract Documents. Terms such as "shown", "noted", "scheduled", and "specified" are used to help locate a reference. No limitation on location is intended except as specifically noted.
 - 2. Directed: Terms such as "directed", "requested", "authorized", "selected", "approved", "required", and "permitted", are hereby defined as "directed by Designer", "requested by Designer", "authorized by Designer", and other like items No implied meaning shall be interpreted to extend the Designer's responsibility into the Construction Manager's area of construction supervision.
 - 3. Approve: The term "approved" when used in conjunction with the Designer's action on the Construction Manager's submittals, applications, and similar requests, is limited to the duties and responsibilities of the Designer as stated in GENERAL CONDITIONS. Such approval shall not release the Construction Manager from responsibility to fulfill Contract requirements unless otherwise provided in the Contract Documents.
 - 4. Furnish: Supply and deliver to the Project Site, ready for unloading, unpacking, assembly, installation, and similar operations.
 - 5. Install: Operations at Project Site, including unloading, unpacking, assembly, erection, placing, anchoring, applying, working to dimension, finishing, curing, protecting, cleaning, and similar operations.
 - 6. Provide: To furnish and install, complete and ready for intended use.
 - 7. Installer: The Construction Manager or entity engaged by the Construction Manager, either as an employee, subcontractor, or sub-subcontractor for performance of a particular construction activity, including installation, erection, application, and similar operations. Installers are required to be experienced in the operations they are engaged to perform.
 - 8. Owner: The Awarding Authority.
 - 9. Authority having Jurisdiction: Any State, Local, or legal authority, as defined by statute.
- D. "Or Equal", "Or Equivalent": clause:
 - 1. Where products or materials are prescribed by manufacture name, trade name or catalogue reference, the word "or approved equal" shall be understood to follow.
 - 2. An item shall be considered equal or equivalent to the named item, if all of the following conditions are met:
 - a. It is at least equal in appearance, quality, durability, strength and design.
 - b. It meets or exceeds all performance requirements specified.
 - c. It performs the function of the item to an equal or superior standard as does the named item.
 - 3. All deviations from products specified shall be submitted as substitutions. For related

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

procedures, refer to Section 013300 - Submittal Procedures.

MISCELLANEOUS PROVISIONS 1.13

- A. Discovery: If during the excavation or other work, articles of unusual value, or of historical or archaeological significance are encountered the ownership of such articles is retained by the Owner, and information regarding their discovery shall be immediately furnished to the Desianer.
 - If the nature of the article is such that the work cannot proceed without danger of dam-1. aging same, work in that area shall be immediately discontinued until the Designer has decided the proper procedure to be followed.
 - Any time lost thereby shall be a condition for which the time of the Contract may be ex-2. tended.
 - 3. All costs incurred after discovery in the salvaging of such articles shall be borne by the Owner.
- B. Refer to Section 013100 Project Management and Coordination, Article 1.4, B. for particular project supervision requirements.
- C. Product and Material Requirements: In addition to product and material requirements as specified throughout the Project Manual, preference shall be given to materials mined or manufactured in Massachusetts first and the United States of America second wherever possible.

D. Owner Change Order Requirements:

Itemized labor and material breakdown: Required for all changes. Failure to include will entire 1. result in immediate rejection of the COP. Invoices for materials substantiating costs section D as the should be included as back-up where applicable and provided in all cases where requested.

Exclude the owner

- Unit Prices: Prior to submission of a change proposal the subcontractor (or sub-agreement 2. subcontractor) shall review the contract documents to determine if Unit Prices covers the dovern. item in auestion.
- Bond and Liability Insurance: This should be broken out separately and is not subject to 3. OH&P. B&L costs of 2% and over (combined) shall be substantiated with the appropriate back-up.
- Labor rates: labor rate should reflect a blended rate of apprentices and journeymen if 4. the former is used to prosecute change order work.
- 5. As-builts: A separate cost for as-built documentation is not reimbursable as a separate cost. This is part of OH.
- Supervision: Supervision costs are NOT acceptable as a separate cost UNLESS it is 6. based on a WORKING foreman.
- Small tools and equipment: Generally, Any equipment rental under \$1000 is not reim-7. bursable as a separate cost. This is part of OH. Small tool costs are not reimbursable as a separate cost.
- 8. Consumables: may be reimbursable as a separate cost (depending on the item) but must be listed separately in order to be considered for reimbursement.
- 9. OH & P: Construction Manager: 5% (combined OH&P) for work performed by subcontractors (labor, equipment, and materials). 10% (combined) for labor work performed by their own forces. 10% (combined) for materials and equipment provided by the CM.
- 10. Subcontractors: 10% combined OH&P for work performed by their own forces. 5% combined for work performed by 2nd tier subcontractors. Additionally, the bottom tier

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

subcontractor is entitled to 10% (combined) OH&P provided that they are performing the work with their own forces. Any tier above the bottom tier (performing the work) shall be entitled to 5% OH&P HOWEVER THE MAX. OH&P CHARGED TO THE OWNER SHALL NOT EXCEEED 20% (COMBINED) IN ANY CASE WHERE SUB-SUBCONTRACTORS ARE INVOLVED IN THE WORK.

- 11. Electrical changes: Use the BNI electrical and the BNI Mechanical Electrical costbooks (as modified by region) as the basis for electrical change order work.
- 12. Sitework: Use the Rental Rate Bluebook (as published by Neslon / Dataquest) for construction equipment rental rates. The Contractor (or subcontractor) shall avail themselves of discount rates for extended periods of rental in order to reduce overall costs incurred by the Owner.
- 13. Home Office Costs: Home Office costs are not reimbursable as a separate cost. This is a part of overhead.
- 14. Time, not extended general condition costs: In the case where the Owner (and / or its agents) deems that a time extension is warranted, the grant of additional time will NOT be accompanied by extended general condition costs.
- E. Proprietary Items: The Town of Brookline has voted and approved certain items to be proprietary as indicated within the Project Manual specifications.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

SECTION 011400

WORK RESTRICTIONS

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

- A. Attention is directed to Division 00 PROCUREMENT AND CONTRACTING REQUIREMENTS and DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.
- B. Examine all other Sections of the Specifications for requirements that affect work of this Section, whether or not such work is specifically mentioned in this Section.
- C. Coordinate Work with that of all other trades affecting or affected by Work of this Section. Cooperate with such trades to assure the steady progress of all Work under the Contract.

1.2 SUMMARY

- A. The Work of this Section includes, but is not limited to, requirements for the following procedures:
 - 1. Construction Documents, Project Electronic Files and graphic reproduction of Contract Documents.
 - 2. Interpretation and modification of Contract Documents.
 - 3. Construction Manager's reports.
 - 4. Cleaning materials
 - 5. Safety and disposal requirements.
 - 6. Conduct of the Work.
 - 7. Existing Utilities.
 - 8. Conduct of construction personnel and noise control.
 - 9. Safety and disposal requirements and accident prevention.
 - 10. Welding and cutting.
 - 11. Fire watch.
 - 12. Municipal police services
 - 13. Storage of materials off-site
 - 14. Dust control.
 - 15. Cleaning during construction.
 - 16. Pollution control.
 - 17. Owner's occupancy requirements
- B. Related work includes, but is not limited to, the following work under other Sections:
 - 1. Section 013200 CONSTRUCTION PROGRESS DOCUMENTATION: Preparation and execution of construction schedule, daily reports, and photography.
 - 2. Section 013100 PROJECT MANAGEMENT AND COORDINATION: Procedures and responsibilities for coordinating the Work.
 - 3. Section 013300 SUBMITTAL PROCEDURES. Submittal procedures.
 - 4. Section 015000 TEMPORARY FACILITIES AND CONTROLS, for additional information on temporary measures required during construction.

REVISION: FB-005 - GMP Bid Set - AUGUST 1, 2019

- 5. Section 015639 TEMPORARY TREE AND PLANT PROTECTION.
- 6. Section 017400 CONSTRUCTION WASTE MANAGEMENT, for removal of nonhazardous debris including provisions for recycling and disposal.
- 7. Section 017700 CLOSEOUT PROCEDURES: Procedures for completing the Work.
- 8. Section 017839– PROJECT RECORD DOCUMENTS: Preparation of record drawings and other documents.
- 9. Division 31 EARTHWORK and Soil Management Plan, for removal of contaminated soils and liquids.

1.3 SUBMITTALS

- A. General: Refer to Section 013300– SUBMITTALS, for submittal provisions and procedures.
- B. Layout of Temporary Construction Facilities: Submit location plan showing trailers and storage layout.
- C. Logistics Plan:
 - 1. Construction Manager shall submit to the Architect, at the Pre-construction Meeting, a detailed Logistics Plan, which shall include:

Town

- a. Delivery Hours and Delivery Routes
- b. Gate location, and wheel washing location.
- c. Hours of Work
- d. Trailer Area, and Layout of trailers
- e. Temp fencing, erosion control, and metering locations
- f. Location for stockpiling of soil
- g. Location for stockpiling plowed snow
- h. Locations for waste management containers.
- i. Protection of existing curbs and walkways.
- j. Lighting Plan
- k. Traffic plan.
- I. Police detail.
- m. Pedestrian safety plan on site.
- n. Protection of Devotion House.
- o. Tree and plant protection.
- 2. Refer to Section 015000 TEMPORARY FACILITIES AND CONTROLS, for specifications for temporary construction and other items to be shown on Logistics Plan.
- 3. No work shall commence until the Logistics Plan has been approved.
- D. Photographs: Progress Prints and videotapes as specified in this Section, and in Section 013200 CONSTRUCTION PROGRESS DOCUMENTATION.
- E. Reports:
 - 1. Documentation of off-site storage facilities.
 - 2. With each Application for Payment, submit the following reports, compiled on a monthly basis:
 - a. Construction Manager's Reports
 - b. Proof of submission of Certified weekly payrolls to Owner.
 - c. Monthly cost projections.

Exclude entire section E. Owner agreement governs monthly reports and cost projections and certified payroll is submitted direct to awarding authority by subs, not by Skanska.

Exclude entire section C. Logistics was provided in proposal and refined over time in conjunction with the Town, DPW, etc. No logistics plans are to be submitted to the Architect

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

1.4 CONSTRUCTION DOCUMENTS

- A. The Construction Manager shall retain copies of the Contract Documents issued to them for bidding purposes.
 - 1. The Owner will furnish to the Construction Manager, without additional charge, an additional ten (10) complete sets of the Contract Documents, including Drawings and Specifications, for use during the construction period.
 - 2. Extra sets returned by bidders and not required for other purposes, as determined by the Owner's Project Manager, will be made available to Construction Manager and Subcontractors for the Work.
- B. All other hard copies of the Contract Documents required by the Construction Manager or subcontractors for use during the construction period shall be purchased by the party requiring same. Owner's Project Manger will furnish approximate costs of such additional copies and will transmit originals to local printing companies with whom he regularly does business, but will not receive bills for such printing through his account. All negotiations for such printing shall be between Construction Manager and Printer.
 - 1. Refer to provisions in this Section, for electronic copies of documents to be made available for the Construction Manager's use during construction.
 - 2. Refer to Section 017839 PROJECT RECORD DOCUMENTS, for additional sets to be provided by the Owner to the Construction Manager for the purpose of maintaining record prints of the Work as construction proceeds.

1.5 PROJECT ELECTRONIC FILES

- A. Definitions:
 - 1. Contract Documents: Printed hard copies of drawings and other documents, as defined in the General Project Requirements and listed in the signed copy of the Form of Agreement between Owner and Construction Manager.
 - a. In case of conflict between the Contract Documents and documents obtained through electronic means, the Contract Documents shall govern.
 - 2. Project Electronic Files: Electronic copies of electronic documents for the Project, comprising drawings listed on Document 011401 – Electronic Release Form.
- B. General Procedures: At the Pre-Construction Meeting, the Architect will present to the Construction Manager one compact disc (CD) with Project Electronic Files, for use in the preparation of coordination and record documents for the Project.
 - 1. Release Forms Required:
 - a. The Construction Manager shall sign a copy of Document 011401 Electronic Release Form, to be filled out and issued by the Architect.
 - b. By signing the release form, the Construction Manager is acting on behalf of all their subcontractors for the Work of this Project.
 - 2. Additional copies of the compact disc with Project Electronic Files will be available from the Architect at an additional cost.
- C. Electronic File Format:
 - 1. Editable Files: Electronic files for drawings listed on Document 011401 Electronic Release Form will be furnished in "*.DWG" format.
 - 2. Printable, Non-Editable Files: Electronic files for all Drawings in the Bid Set and for Drawings issued as Addenda will be furnished in "*.PDF" format (Adobe Acrobat Reader, version 6.0).

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- 3. William Rawn Associates Architects, Inc. does not warrant that these electronic documents are compatible with any software or hardware other than those on which they were produced.
- D. Permitted Use of Project Electronic Files: Use of electronic files by the Construction Manager and Sub-Contractors is limited to the following activities:
 - 1. Project Electronic Files may be used as a guide only for the preparation of Coordination Drawings and Record Drawings to be submitted as a requirement for the Project.
 - 2. Project Electronic Files may be used as a guide only for preparation of shop drawings. Exact copies of Contract Documents will not be accepted if submitted for these purposes, unless specifically permitted by an individual specification Section.
- E. Responsibilities of Construction Manager: Use and reproduction of Project Electronic Documents are subject to the following conditions:
 - 1. The use of Project Electronic Files, reproduced either electronically or by other graphic reproduction methods, does not in any way alter the responsibilities of the Construction Manager for final system coordination. The Construction Manager shall incur all liability in this respect.
 - 2. The Construction Manager and all Subcontractors are responsible for checking the dimensions and completeness of the Project Electronic Files, and for determining any possible errors and omissions, as required by the General Project Requirements.
 - 3. The Construction Manager is responsible for updating Project Electronic Files as necessary to incorporate changes to the Work shown in Addenda and documents issued during construction.
 - 4. In no event shall William Rawn Associates Architects, Inc., or any other Person or Firm for changes made by involved in the creation, production or distribution of the reproducible or electronic documents, be liable to the persons utilizing the documents, on account of any claim for damages. Each Person or Firm utilizing these documents agrees to release, indemnify, provide current hold harmless and defend William Rawn Associates Architects, Inc., its officers, employ-ees and consultants from an against all liability arising out of such firm's use of the electronic or reproduced documents or information referred to herein.
- F. Ownership of Documents: By transferring copies of Project Electronic Files, William Rawn Associates Architects, Inc. and the Owner do not in any way convey the copyright in the designs contained therein, nor do they convey a license to copy or use them for any purpose except as required for the construction of the Project.
- G. License for Software: By transferring copies of Project Electronic Files, William Rawn Associates Architects, Inc. does not in any way convey transfer license to use the software on which the documents were prepared. Each entity using Project Electronic Files is responsible for obtaining licenses as needed for its use of those files.

1.6 GRAPHIC REPRODUCTION OF CONTRACT DOCUMENTS

A. Reproduction of Contract Documents issued for the Project, by graphic reproduction methods, shall be subject to the conditions outlined for reproduction of Project Electronic Files.

CM will not be responsible for determining errors. We will only notify them if we become aware of errors. We will not be responsible for updating the E files for changes made by Addenda, the architect and consultants need to provide current information for coordination purposes.

per Owner-CM Agreement and GMP A&Qs

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

1.7 INTERPRETATION AND MODIFICATION OF CONSTRUCTION DOCUMENTS

- A. Refer to Agreement between Owner and Construction Manager for general information on Change Orders, Work Change Directives, Field Orders and Architect's written amendments and clarifications. The intent of this Article is to provide for additional procedures to be followed during construction.
- B. Requests for Information: Each time the Construction Manager or Subcontractor has a reasonable question on the interpretation of the Contract Documents, they shall submit in writing a Request for Information (RFI) to the Architect for response.
 - 1. The Construction Manager shall examine field conditions carefully and review the Drawings and Specifications thoroughly prior to issuing an RFI.
 - 2. The Construction Manager shall keep a log of RFI's, numbering them in the order in which they are issued.
 - 3. Each RFI shall contain a clear statement of the question, references to relevant Contract Documents and additional background information as needed to facilitate the Architect's review.
 - 4. All requests for information from Subcontractors shall be made through the Construction Manager and addressed to the Architect, and the Architect will distribute them as needed to the appropriate Consultants. A copy of each RFI shall be given to the Clerk of the Works. electronically
 - 5. RFI's shall be issued in a timely manner to permit a thorough review and preparation of a response by the Architect and their Consultants. The Construction Manager shall identify on the RFI form whether the RFI is low, medium or highly critical and shall note the date that the RFI response is due in order not to affect the construction progress schedule.
 - 6. The Architect will prepare a written response to each RFI within **5** 10 workdays, or sooner if the Construction Manager provides a realistic date when the response will be needed.
- C. Proposal Requests: During construction, it may become necessary or desirable to modify the Contract Drawings or Specifications in response to concealed existing conditions, changes in the Owner's program or other unforseen circumstances.
 - 1. Where such a modification may involve a change in the Contract price or time, the Architect will prepare a Proposal Request describing the modification under consideration, including sketches or drawings, specifications and other information to permit pricing by the Construction Manager.
 - 2. Copies of each Proposal Request and its attachments will be distributed to the Owner, Clerk of the Works and Construction Manager.
 - 3. The Construction Manager shall respond in a timely manner with a Proposed Change Order detailing the estimated costs and change in Contract duration, for review by the Architect and approval by the Owner.
 - 4. A Proposal Request will not constitute direction to proceed with the modification unless accompanied by a Work Change Directive and an estimated price.
- D. Change Order Requests: If the Construction Manager is required to perform Work that they consider to represent a change in the cost of the Project, they may submit Change Order Requests for such work in accordance with the General Conditions and Supplementary General Conditions.
 agreement since
 - 1. Each Change Order Request shall be accompanied by a document describing the modification under consideration, including sketches or drawings, specifications and other information to permit review of pricing by the Architect and Owner.

that governs this

process

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- 2. Distribute copies of each Change Order Request and its attachments to the Owner, Clerk of the Works and Architect.
- 3. The Architect and Owner will respond in a timely manner with a Proposed Change Order incorporating the Change Order Request if it is approved.
- 4. Verbal approval of a Change Order Request will not constitute direction to proceed with the modification unless accompanied by a Change Order, or a Construction Change Directive with an estimated price.
- E. Architect Review of Construction Manager-Generated Requests for Information and Change Order Requests: The Architect will review and prepare written responses to the Construction Manager's Requests for Information and Change Order Requests that are submitted in accordance with the requirements of this section.
 - If the Construction Manager submits an excessive number of requests for information that are incomplete, or for which the information requested is available from a careful study and comparison of the Contract Documents, field conditions, other Ownerprovided information, Construction Manager-prepared or other prior Project correspondence or documentation, then the Construction Manager shall be responsible to the Owner for costs for Additional Services of the Architect to review those requests for information.
 - If the Architect determines that the Work covered by a Change Order Request is covered by the scope of the Contract Documents, the Construction Manager shall be responsible to the Owner for costs for Additional Services of the Architect to evaluate proposals and prepare Instruments of Service associated with such Change Order Request.
 - 3. Refer to other paragraphs in this Section for procedures required in cases where Construction Manager is responsible to the Owner for costs for Additional Services of the Architect.

1.8 CONSTRUCTION MANAGER'S REPORTS

A. A daily report summarizing the work performed, weather conditions, number of workers, amount and kinds of equipment, unusual occurrences, and the like shall be compiled and submitted at the end of each week by the Construction Manager's Field Superintendent to the Architect, the Owner's Project Manager, the Clerk of the Works, each working day covering the work performed on the previous working day.

Electronically in Procore

B. Form of the daily report shall be as approved by the Architect.

1.9 CONSTRUCTION MANAGER RESPONSIBILITY TO THE OWNER FOR ARCHITECT'S ADDITIONAL SERVICES means & methods

- A. The Contract between the Owner and the Architect contains provisions for additional services that may be required of the Architect during construction due to unforeseen conditions.
 - 1. Where such additional services become necessary due to the activities of the Construction Manager, as determined by the Owner's Project Manager, costs for such services will be the responsibility of the Construction Manager, and will be deducted from the Contract Amount.

We cannot agree to this, in particular "as determined by the OPM" Would OPM, A&E agree to be responsible for additional costs for our time due to unforeseen conditions?

- B. Additional services for which the Construction Manager is responsible for cost to the Owner may include the following activities of the Architect **and Owner's Project Manager**:
 - 1. Review of Requests for Information and Change Order Requests for work determined to

REVISION: FB-005 - GMP Bid Set - AUGUST 1, 2019

be covered in the Contract Documents. Refer to related Articles in this Section.

- Continuation of construction administration beyond the dates specified for Final Completion of the Work: Refer to Section 013200 – CONSTRUCTION PROGRESS DOCUMENTATION.
- 3. Review of re-submitted submittals and Substitution Requests that have been rejected: Refer to Section 013300 – SUBMITTAL PROCEDURES.
- 4. Re-inspection of incomplete work: Refer to Section 017700 CLOSEOUT PROCEDURES.
- 5. Design services for the resolution of non-conforming work.
- 6. Review and resubmittal of Requisitions for Payment due to incomplete, inaccurate documentation, or errors.

PART 2 - PRODUCTS

2.1 CLEANING MATERIALS

- A. Use only those materials which will not create hazards to health or property and which will not damage surfaces.
- B. Use only those cleaning materials and methods recommended by manufacturer for surface material to be cleaned.
- C. Use cleaning materials only on surfaces recommended by cleaning material manufacturer.
- D. Comply with LEEDv4 requirements, including IAQ plan.

PART 3 - EXECUTION

3.1 CONDUCT OF WORK

- A. The Contract Site shall be as shown on the Drawings, and shall include the entire area bound by the "Contract Limit" or "Limit of Work" lines as well as all areas outside of the Limit of Work Lines when required for performance of work under this Contract.
- B. Due to the proximity of construction activity to existing occupied homes and residential and commercial buildings, extreme care must be taken to minimize the noise, exhaust, and vibration caused during the performance of the Work. Any potential disruptions must be anticipated in advance and scheduling and mitigation measures approved in advance with the Owner's Project Manager.
- C. Construction Manager shall take all steps necessary to protect existing conditions to remain. Damage to existing work caused by Construction Manager's operations under this Contract shall be repaired at Construction Manager's expense.
- D. Any street, paving, curb and/or sidewalk damaged as the result of work under this Contract, whether within or outside the limits of the Work, shall be repaired and/or replaced with new matching construction by the Construction Manager at his expense and in a manner satisfactory to the Architect and authorities having jurisdiction.

WILLIAM RAWN ASSOCIATES, Architects, Inc. 10 Post Office Square, Suite 1010, Boston, MA 02109 Page 136 of 377 within GMP and per Owner Agreement 011400 - 7 of 14

In some cases damage is inevitable and planned for by budgeting repairs. They will no be of CM's/expense unless reinbursed by Owner.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- E. Protection of Curbs and Walkways: Where existing curbs or walks are to remain, or after new curbs or walks are constructed and trucking is required over them, they shall be suitably protected as shown on approved Logistics Plan.
- F. Trenching and other work outside construction limits shall be expedited to the fullest and carried out with minimum of inconvenience to normal operations of Owner and public traffic. Walks, paved or landscaped areas over which temporary walks and driveways cross shall, upon completion of the Work, be restored to their original condition with new construction. Temporary roadways shall be bridged over trenched areas.
- G. Provide continuous, lawful, safe, adequate and convenient access to the site. Construction Manager shall construct and maintain in good, safe, usable condition temporary roads, capable of supporting emergency vehicles, and appurtenances as required, and when no longer required, remove temporary construction and restore such areas to their original condition, or as otherwise specified in the Contract Documents.

3.2 EXISTING UTILITIES

- A. Existing Utility Interruptions: Do not interrupt utilities serving facilities if occupied by Owner, or others unless permitted under the following conditions and then only after arranging to provide temporary utility services according to requirements indicated:
 - 1. Notify Owner not less than four days in advance of proposed utility interruptions.
 - 2. Do not proceed with utility interruptions without Owner's written permission.
- B. Immediately repair any active existing utility lines (cables, conduit, ducts, and piping), damaged during the course of construction. Protect and maintain such active existing utilities in use, until relocation of same has been completed or utilities have been cut, capped, or prepared for new service connections, as applicable. Perform such repair and protection work at no additional cost to the Owner.
- C. If any existing active utility not indicated on the Drawings is unintentionally damaged, and such utility is to remain, immediately repair the damage and restore the utility to its original integrity. Reimbursement of cost for performing such repair will be made by an adjustment in the Contract Price in accordance with the Agreement between Owner and Construction Manager.
- D. Any adjustment as outlined above shall be based on the assumption that the Construction Manager has performed in a prudent manner at the time such damage occurred. If extra expense is incurred in protecting and maintaining any utility line not shown on the Drawings, nor revealed by a "Dig-Safe" inspection, an adjustment in the Contract Price shall be made.
- E. The Owner will cooperate and assist the Construction Manager in locating and identifying underground utilities. Construction Manager shall cooperate and participate in "Dig Safe" programs, notifying proper authorities before proceeding.
- F. If it becomes necessary to interrupt power, water line, sewer, gas or other utilities to adjacent buildings, notify the Architect and Owner's Project Manager at least four (4) days in advance. Schedule such interruptions at such times as will minimize disruption and inconvenience to users. Construction Manager shall be responsible for notification to neighboring properties as required.

EARLY PACKAGE #2: DEMOLITION, ABATEMENT & SITE ENABLING MARCH 1, 2019

BROOKLINE HIGH SCHOOL EXPANSION

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- 3.3 CONDUCT OF CONSTRUCTION PERSONNEL
 - A. All tobacco use on Town property is prohibited by Town Ordinance. Smoking of any substance, including the use of vaporizers, electronic cigarettes, or other smokeless devices, is strictly prohibited on site or adjacent to the site.
 - B. Under no circumstances shall workers on site have interactions with students.
 - C. Use of profanity is prohibited.
 - D. At the sole discretion of the Owner, the Construction Manager shall be prepared to fully cooperate with CORI and SORI checks. Owner agreement only requires CORI

3.4 NOISE CONTROL

Strike we will operate within the by laws of the town.

- A. Develop and maintain a noise-abatement program and enforce strict discipline over all personnel to keep noise to a minimum. Submit noise abatement program to Owner's Project Manager and Architect for review prior to use of noise generating equipment.
 - B. Execute construction work by methods and by use of equipment that will reduce noise and which will provide minimum interference with neighborhood activities.
 - 1. Employ construction methods and equipment that will produce the minimum amount of noise.
 - 2. Equip air compressors with silencers, and power equipment with mufflers.
 - 3. Handle vehicular traffic and scheduling to reduce noise.
 - C. Use of radios, including headphones, and electronic entertainment equipment is strictly prohibited on site.
 - D. Do not run equipment, including idling of vehicles outside of the specified hours of work.

3.5 SAFETY AND DISPOSAL REQUIREMENTS

- A. Standards: Maintain project in accordance with State Building Code and local ordinances.
- B. Hazards Control: Store volatile wastes in covered metal containers and remove from premises. Prevent accumulation of wastes which create hazardous conditions. Provide adequate ventilation during use of volatile and noxious substances.
- C. Disposal: Conduct cleaning and disposal operations to comply with local ordinances and antipollution laws. Do not burn or bury rubbish and waste materials on project site. Do not dispose of hazardous wastes such as solvents, mineral spirits, oil, paint, paint thinner in storm or sanitary drains. Do not dispose of wastes into streams or waterways.

3.6 ACCIDENT PREVENTION

A. Comply with all Federal, State and municipal recommendations and requirements for safety and accident prevention, those of the Associated General Contractors of America and the American National Standards Institute (ANSI Standard A10.2). Conduct regular, frequent

WILLIAM RAWN ASSOCIATES, Architects, Inc. 10 Post Office Square, Suite 1010, Boston, MA 021 Page 138 of Safety standards which are more stringent

WORK RESTRICTIONS 011400 - 9 of 14

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

inspections of the site for compliance with safety regulations.

- B. Neither the Owner nor the Architect will be responsible for providing a safe working place for the Construction Manager, Subcontractors, or their employees, or any individual responsible to them for the Work.
- 3.7 WELDING AND CUTTING

Strike 3.7. Work will be done in compliance with federal, state, town and Skanska requirements, not as written by the Arch.

- A. Where electric or gas welding or cutting work is done above or within ten (10) feet of combustible material or above space that may be occupied by persons, use interposed shields of incombustible material to protect against fire damage or injury due to sparks and/or hot metal.
- B. Place tanks supplying gases for gas welding or cutting at no greater distance from the work than is necessary for safety, securely fastened and maintained in an upright position where practicable. Such tanks, when stored for use, shall be remote from any combustible material and free from exposure to the direct rays of the sun or high temperatures. Storage shall be secured under lock and key, to prevent unauthorized use of gas and equipment.
- C. Maintain suitable fire extinguishing equipment near all welding and cutting operations. When operations cease for the noon hour or at the end of the day, thoroughly wet down the surroundings adjacent to welding and cutting operations. Properly protect any new materials, stored or installed, that are subject to water damage.
- D. Station a worker equipped with suitable fire extinguishing equipment near welding and cutting operations to see that sparks do not lodge in floor cracks or pass through floor to wall openings or lodge in any combustible material. Keep the worker at the source of work which offers special hazards for a minimum of thirty (30) minutes after the job is completed to make sure that smoldering fires have not been started; or longer.
- E. Place a qualified electrician in charge of installing and repairing electric and arc welding equipment.

3.8 FIRE WATCH

- A. Comply with authorities having jurisdiction for fire watch requirements during hot work operations. Hot work shall include but not be limited to welding, torch and open flame work, cutting of steel, and other similar operations. Schedule and pay for fire watch services as required by authorities having jurisdiction. CM shall arrange and pay for all fire watch services as no change to the Contract price.
- B. The Town of Brookline requires welding permit for all hot work, including welding outside. The Town of Brookline requires a Fire Department designated uniformed employee for all Fire Watches. The Town of Brookline Fire Department has a 4-hour minimum shift.
- C. Extend the Worker's Compensation Insurance and Employer's Liability Insurance required under the Agreement between the Owner and Construction Manager to cover Fire Department employees used on the Project.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

3.9 MUNICIPAL POLICE SERVICES

- A. Make all necessary arrangements with the municipal police department in advance of times when regular, off-duty, or reserve police officers will be needed for traffic control or protection due to operations performed under this Contract.
- B. Police detail to be provided on an as needed basis during heavy trucking and work on public roads.
- C. Pay police officers in accordance with rates established by the municipality for such service:
- D. Extend the Worker's Compensation Insurance and Employer's Liability Insurance required under the Agreement between Owner and Construction Manager to cover police used on the Project.

3.10 STORAGE OF MATERIALS OFF SITE

- A. The Construction Manager, Subcontractors and Sub-subcontractors shall obtain prior written approval from the Owner through the Architect for permission to store materials to be incorporated in the Work, for which Progress Payments will be requested, at off-site locations. Any and all charges for storage, including insurance, shall be borne solely by the Construction Manager. Before approval, Owner will require proper proof of insurance and a letter in which is furnished:
 - 1. The names of the Construction Manager and/or Subcontractor or subordinate Subcontractor leasing the storage area.
 - 2. The location of such leased space.
 - 3. Description of the leased area: The entire premises or certain areas of a warehouse giving the number of floors or portions thereof.
 - 4. The date on which the material is first stored.
 - 5. The value of the material stored.
 - 6. Transfer of title for such materials in a form acceptable to the Owner.
- B. Requirements for storage facility at which materials will be stored off-site:
 - 1. The storage facility shall be a bonded warehouse.
 - 2. The Construction Manager shall permit access to the storage facility to the Clerk of the Works upon request.
- C. Construction Manager, Subcontractors and subordinate Subcontractors shall provide prior to the request for payment for such stored materials, adequate advanced notice, to the Architect so that the Owner or Architect can inspect, at their convenience, the materials being stored at any location.
- D. Each sealed carton shall be marked with the Project name, the Owner's name and the Architect's name as they appear in the Agreement.
- E. A perpetual inventory shall be maintained for all materials held in storage for which payment has been requested.
- F. Payment for materials stored off site shall be at the sole discretion of the Owner. Any additional costs to the Owner resulting from storage of material off site for which payment is requested, such as, but not limited to, travel expenses and time for inspectors shall be

Strike entire section, stored material is governed by CM agreement not architect.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

backcharged to, and paid by, the Construction Manager.

3.11 DUST CONTROL

A. Maintain the construction site, stockpiles, access, detour, and haul roads, staging and parking area used for the Work, free of dust which would cause a hazard or a nuisance to those at the site or adjacent sites.

Owner has not authorized the cost of daily street sweeping

1. Streets and sidewalks shall be cleaned regularly to minimize dust accumulations. Street sweeping sweeping shall occur on a daily basis during excavation and foundation operations.

- as needed; refer to GMP GRs

- B. Provide environmentally safe and positive methods and dust control materials to minimize raising dust from construction operations, and provide positive means to prevent air-borne dust from dispersing into the atmosphere.
- C. Wet down dry materials and rubbish to lay dust and prevent blowing dust.
- D. Clean interior spaces prior to the start of finish painting and continue cleaning on an asneeded basis until painting is finished. Construction Clean, not Final Clean for painting.
- E. Schedule operations so that dust and other contaminants resulting from cleaning process will not fall on wet or newly-coated surfaces, including paint, coatings, sealants, caulking, adhesives.
- F. Furnish, erect, and maintain for the duration of the work period, temporary fire-retardant dust proof coverings and partitions as required to prevent the spread of dust beyond the immediate area where work is being performed.
- G. These provisions do not supersede any specific requirements for methods of construction or applicable regulations or general conditions set forth elsewhere in the Contract with regard to performance obligations of the Construction Manager.

3.12 CLEANING DURING CONSTRUCTION

- A. Execute cleaning during progress of work and at Substantial Completion, as required by General Conditions, in accordance with LEEDv4 requirements, and as herein specified. Refer to Section 017400 Cleaning and Waste Management for more information.
- B. Maintain premises and public properties free from accumulations of waste, debris and rubbish caused by operations. At completion of work, remove waste materials, rubbish, tools, equipment, machinery, and surplus materials, and clean all exposed surfaces; leave project clean and ready for occupancy.
- C. Cleaning shall be in addition to cleaning specified under other sections and shall include all surfaces, interior and exterior in which or to which the Construction Manager has had access.
- D. Refer to Sections of the Specifications for cleaning of specific products.
- E. Execute cleaning to ensure that the building, the site, and adjacent properties are maintained free from accumulations of waste materials and rubbish and windblown debris, resulting from construction operations.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- F. Provide on-site containers for collection of waste materials, debris and rubbish.
- G. Remove waste materials, debris and rubbish from the site periodically and dispose of at legal areas off site.
- H. Handle materials in a controlled manner with as little handling as possible. Do not drop or throw materials from heights.
- I. Schedule cleaning operations so that dust and other contaminants resulting from cleaning processes will not fall on wet newly painted surfaces, uncured caulking, sealants, adhesives, and other like items

3.13 POLLUTION CONTROL, GENERAL

- A. Provide methods, means and facilities required to prevent contamination of soil, water and atmosphere by the discharge of noxious substances from construction operations.
- B. Remediation of Spills: Provide equipment and personnel, perform emergency measures required to contain any spillages, and to remove contaminated soils or liquids. Excavate and dispose of contaminated earth off site and replace with suitable uncontaminated compacted fill and topsoil, in accordance with the requirements of Division 31 EARTHWORK.
- C. Take special measures to prevent harmful substances from entering public waters. Prevent disposal of wastes, effluents, chemicals, or other such substances adjacent to streams or in sanitary or storm sewers. Must comply with SWPP requirements.
- D. Provide systems for control of atmospheric pollutants. Prevent toxic concentrations of chemicals. Prevent harmful dispersal of pollutants into the atmosphere.

3.14 OWNER'S OCCUPANCY REQUIREMENTS

A. Owner Occupancy of Completed Areas of Construction: Owner reserves the right to occupy and to place and install equipment in completed areas of building, before Substantial Completion dates, provided such occupancy does not interfere with completion of the Work. Such placement of equipment and partial occupancy shall not constitute acceptance of the total Work.

Strike entire section 3.14, it is governed by the CM Agreement

- 1. Architect will prepare a Certificate of Substantial Completion for each specific portion of the Work to be occupied before Owner occupancy.
- 2. Obtain a Certificate of Occupancy from authorities having jurisdiction before Owner occupancy.
- Before partial Owner occupancy, mechanical and electrical systems shall be fully operational, and required tests and inspections shall be successfully completed. On occupancy, Owner will operate and maintain mechanical and electrical systems serving occupied portions of building.
- 4. On occupancy, Owner will assume responsibility for maintenance and custodial service for occupied portions of building.
- B. If the Project is substantially complete by the specified date for Substantial Completion, the Owner at his election may from time to time, or permanently, occupy the building or any portion thereof as the work is completed to such a degree as will, in the opinion of the Owner,

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

permit the use of the building or other portions of the Project for the purpose for which they are intended.

- C. The Owner will, prior to any such partial occupancy, give notice to the Construction Manager thereof and such occupancy shall be predicated upon the following conditions:
 - 1. In the case of partial occupancy prior to the stipulated completion date, the Owner shall secure endorsement from the Construction Manager's insurance carrier and consent of the surety permitting occupancy of the building or use of the Project during the remaining period of construction.
 - 2. In the case of partial occupancy after the stipulated completion date, the Construction Manager shall extend all the necessary insurance coverage as stipulated until the date of Final Acceptance of the Project. Owner's use and occupancy prior to final Acceptance shall not relieve the Construction Manager of his responsibility to maintain the insurance coverage as required by the Contract Documents.
 - 3. In case of such partial occupancy, the guarantee period called for by the Contract Documents shall commence on the date of Substantial Completion of the Phase containing the guaranteed Work.
 - 4. Occupancy of the building or any portion thereof by the Owner, shall not constitute an acceptance of the Work or of work not performed in accordance with the Contract Documents or relieve the Construction Manager of responsibility to perform any work required by the Contract but not completed at the time of occupancy.
 - 5. If the Owner occupies the building as a result of the Construction Manager's failure to substantially complete the work by the specified date, the Construction Manager shall pay maintenance costs on the portion of the building occupied under this Agreement until Substantial Completion.
 - 6. The Construction Manager shall be required to furnish heat, electricity and water used in the occupied portion of the building, from the time of the occupancy by the Owner until Substantial Completion of the project.
- D. Building systems and components of systems such as, but not limited to, HVAC, will not be considered substantially complete until the entire system functions as specified and to the satisfaction of the Owner.

END OF SECTION

not sure the concern, but whatever was req'd between WRA and Skanska at beginning of the project in order to obtain the e-files must have been rectified and in the past

10 Post Office Sq. Suite 1010 Boston, MA 02109 t. 617.423.3470 www.rawnarch.com

WRA Public CADD Files Disclaimer

Access to WRA BOX site and use of the electronic files is conditioned upon your acceptance of the following.

- The electronic files include drawings, specifications and other documents in electronic form (collectively "data"). The data is the electronic format of the specific file type, and are instruments of service of WRA and its sub-consultants for use solely with respect to the Project for which they were prepared, and shall remain the property of WRA, its sub-consultants, and or the project Owner even if the Project is not completed.
- 2. Your use of the data is strictly limited to that necessary for the services or work you are providing on the Project. All data made available shall not be used for any other projects, for additions to the Project, or for completion of the Project by others.
- 3. The transfer of data shall not be considered a sale. WRA makes no representations expressed or implied regarding the data's merchantability or fitness for a particular purpose or with respect to its quality, adequacy, completeness or sufficiency as to any contained in the data is complete. The data could be changed subsequent to your accessing. Items in the data may not be to scale.
- 4. You acknowledge anomalies and errors can be introduced into the data when it is downloaded, transferred, or used in an incompatible computer environment. By accessing downloading and/or using the data you acknowledge and accept the risks associated with damage to hardware, software or computer systems or networks related to the use of the data. You hereby release WRA, and/or our consultants from losses or damages of any kind resulting from the download, transfer or use of the data.
- 5. You hereby release WRA, and our sub-consultants from losses and damages of any kind resulting from the download, transfer or use of the data. You agree to make no claim and hereby waive, to the fullest extent permitted by law, any claim or cause of action of any nature against us, our officers, employees, agents, or sub-consultants that may arise out of or in connection with your use of electronic files. Furthermore, you shall to the fullest extent permitted by law, indemnify, and hold harmless against all damages, liabilities, or costs, including reasonable attorney's fees and defense costs, arising out of or resulting from your use of these electronic files.
- 6. WRA reserves the right to retain an archival copy of the data which shall be referred to and shall be conclusive in all disputes arising out of the data furnished to you.
- 7. All data is confidential. If you are not the intended or authorized recipient you should not retain, disclose, distribute, or use any information and you should destroy any files received in error.

Please fill in the fields below and send to the WRA project manager on the project.

Project Name: Company Name

Signed: Date:

I have read the above and agree to terms and conditions.

check

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

Ś	Entire s as the S by the c					
SCH	SCHEDULE OF VALUES					
	Owner Agreement takes precedence	agreed review c detail.				

Entire section to be struck as the SOV is governed by the owner agreement, CS section VIII and we use AIA G702 and G703 for format. If that is not agreed to, I will need toreview entire section indatail

1.1 GENERAL PROVISIONS

PART 1 - GENERAL

- A. Attention is directed to Division 00 PROCUREMENT AND CONTRACTING REQUIREMENTS and DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.
- B. Examine all other Sections of the Specifications for requirements that affect work of this Section, whether or not such work is specifically mentioned in this Section.
- C. Coordinate Work with that of all other trades affecting or affected by Work of this Section. Cooperate with such trades to assure the steady progress of all Work under the Contract.

1.2 SUMMARY

- A. The Work of this Section includes requirements for the following procedures:
 - 1. Preparation and submittal of the Preliminary and Final Schedule of Values
- B. Related work includes, but is not limited to, the following work under other Sections:
 - 1. Requirements for construction schedules: Section 013200 Construction Progress Documentation.
 - 2. General procedures for submittals: Section 013300 Submittal Procedures.

1.3 DEFINITIONS

A. Schedule of Values: A statement furnished by Construction Manager allocating portions of the Contract Sum to various portions of the Work and used as the basis for reviewing Construction Manager's Applications for Payment.

1.4 SUBMITTALS

- A. Prepare and submit the following submittals in accordance with the requirements of Section 013300 Submittal Procedures.
- B. Schedule of Values:
 - 1. Schedule of Values shall be typewritten on 8-1/2 by 11 inch white paper.
 - 2. Submit to the Architect one (1) copy of each Schedule of Values within 7 days of receipt

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

of Notice to Proceed for GMP Number 1 and for the Notice to Proceed for the Final GMP. Electronic submission is acceptable.

- 3. Provide Schedule of Values in AIA-G702 and G703 format.
- C. List of Subcontractors and Sub-subcontractors: Attached to the Preliminary Schedule of Values shall be a list of the names, addresses (and whether individual, partnership or corporation) of each Subcontractor or Sub-Subcontractor who is to perform all or any part of each subdivision. In the event any Subcontractors, or Sub-subcontractors are not known at the time said schedule is prepared, an amended or supplementary list containing the names of the Subcontractors and Sub-Subcontractors involved and indicating their division of the Work shall be furnished to the Architect as soon as the information is available. A code number for identification on requisitions shall be used to identify the Construction Manager, each of the Subcontractors and subordinate Subcontractors, and shall be shown in each requisition where any part of the Work performed by the Construction Manager, such Subcontractor, Sub-Subcontractors or material supplier is incorporated in the amount of the requisition for which payment is requested.
- D. Monthly Updates: Submit to the Owner's Project Manager with the Schedule of Values on a monthly basis such schedules of quantities and costs, payrolls, reports, estimates, records, and other data as the Owner's Project Manager may request concerning work performed or to be performed under this Contract. The Schedule of Values shall be submitted at the same time as the updated CPM Schedule showing the current status of the work, as required under Section 013200 Construction Progress Documentation.

1.5 SCHEDULE REQUIREMENTS

- A. General: Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Coordinate with the Project CPM Schedule. Provide line items for principal subcontract amounts, where appropriate, and for portions of the work designated in this Section.
- B. Format and Content: Use the Project Manual table of contents as a guide to establish line items for the Schedule of Values. Provide at least one line item for each Specification Section. Identify each line item by Specification Number and Title, and by portion of the Work of that Section where the Work of a Section is allocated to more than one line item.
- C. The Schedule of Values shall be arranged in vertical columns identified with titles, including Names Of Items; Original Amounts, Percent Completed To Date; Previous Payments; Current Requests; and Balance Not Yet Requested. A summary of the total amount due to date and the amount of the five percent retained shall be included in the statement which shall be signed by the Construction Manager. A separate sheet shall be included with each requisition showing status of work covered by approved Change Orders. The Schedule of Values shall be revised if later found by the Architect to be inaccurate.
- D. In preparing the Schedule, each sub-division or classification of the Work shall be identified by code number referring to each individual Section (or Sub-Section where applicable) of the Specifications. The Schedule of Values shall be prepared in accordance with AIA Documents G702 and G703.
- E. Initial values will be recognized to be an accurate accounting of the value of the work. Upon request by the Architect, support values given with data that will substantiate their

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

correctness.

- F. Identify quantities of designated materials or materials stored on which payment is expected to be made.
- G. Use monthly submissions of Schedule of Values only as basis for Construction Manager's Application for Payment.
- 1.6 PREPARING SCHEDULE OF VALUES
 - A. General Procedures:
 - 1. Prepare Preliminary Schedule of Values for review by Architect and Owner's Project Manager.
 - 2. Incorporate requested modifications to produce a Final Schedule of Values, which will become the basis for documenting the progress of the Work with each Application for Payment.
 - 3. Update Final Schedule of Values as necessary to reflect changes in the Work.
 - B. Itemize separate line item cost for each of the general cost items as specified in this Section. Each line item must be \$50,000 or less unless the cost is for a single piece of equipment.

C.	Brea		on a case-by-case basis, SOV	
			value might exceed these	
	1.	Delivered cost of product	amounts which will be reviewed	
	2.	Total installation cost, with overhead and profit.	with Owner and OPM	

- 3. Construction phase.
- 4. Note that the Owner is exempt from Sales and Use Tax for all materials incorporated into the Work.
- D. For each line item which has installed value of more than \$20,000.00 breakdown costs to list major products, components, or operations under each line.
- E. Sum of costs of all items listed in schedule shall be equal to total Contract Sum.
- F. Each item shown on an Application for Payment Schedule of Values shall also appear on the CPM Schedule.

1.7 LINE ITEMS FOR SCHEDULE OF VALUES

- A. Work Covered in Division 1: Itemize separate line item cost for each of the following cost items:
 - 1. Performance and Payment Bonds for Construction Manager and Trade contractors.
 - 2. Field engineering; photographic documentation.
 - 3. Coordination; project management.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- 4. Coordination drawings.
- 5. Preparation of construction schedule and periodic updates.
 - a. If periodic updates of schedule are not performed in a timely manner, the amount shown on the Schedule of Values for this line item shall be forfeited.
- 6. Weather protection; temporary fence.
- 7. Temporary heat, water, power and lighting.
- 8. Temporary office facilities; temporary sanitary facilities.
- 9. Construction aids, including staging, scaffolding, shoring.
- 10. Project sign.
- 11. Indoor air quality provisions.
- 12. Construction waste management.
- 13. Cutting and patching.
- 14. Final cleaning.
- 15. Punchlist preparation and response.
- 16. Maintenance of as-built documents for architectural and site work; preparation of closeout documents.
- 17. Commissioning coordination activities.
- 18. Overhead.
- 19. Sustainable Design Provisions.
- 20. Other items of work as requested by the Architect or Owner.
- B. Work Covered in Divisions 2 through 50: Provide at least one separate line item for each Section of the Specifications. Section line items shall be further subdivided into separate line items as follows:
 - 1. Subdivide each line item into separate line items for individual floors of the project where applicable or in accordance with Owner's requirements and approved format.
 - 2. Identify material costs separately from labor costs.
 - 3. Provide separate line items for the following where applicable:
 - a. Submittals
 - b. Maintenance of as-built documents for mechanical and electrical work
 - c. Preparation of closeout documents
 - d. Operations and Maintenance Manuals;
 - e. Training
 - f. Attic stock.
 - g. Other items of work as requested by the Architect or Owner.
 - 4. For mechanical and electrical work, provide the following additional separate line items where applicable:
 - a. Commissioning coordination activities other than demonstration of FPT to the Commissioning Firm
 - b. Commissioning coordination activities associated with demonstration of FPT to the Commissioning Firm

REVISION: FB-005 - GMP Bid Set - AUGUST 1, 2019

5. For each line item which has installed value of more than \$20,000.00 break down costs to list major products, components, or operations under each line.

PART 2 - PRODUCTS [NOT USED]

PART 3 - EXECUTION [NOT USED]

END OF SECTION

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

	SECTION 012500	Entire section to be struck
	PAYMENT PROCEDURES	as payment procedure is governed by the owner agreement, GCs section VIII and we use AIA G702 and G703 for format.
1 - GENERAL		that is not agreed to, I will
GENERAL PROVISIONS	Owner Agreement takes precedence	need to review entire section in detail.

- A. Attention is directed to Division 00 PROCUREMENT AND CONTRACTING REQUIREMENTS and DIVISION 01 GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.
- B. Examine all other Sections of the Specifications for requirements that affect work of this Section, whether or not such work is specifically mentioned in this Section.
- C. Coordinate Work with that of all other trades affecting or affected by Work of this Section. Cooperate with such trades to assure the steady progress of all Work under the Contract.

1.2 SUMMARY

PART

1.1

- A. Section includes administrative and procedural requirements necessary to prepare and process Applications for Payment.
- B. Related Requirements:
 - 1. Section 012200 UNIT PRICES for administrative requirements governing the use of unit prices.
 - 2. Section 012600 CONTRACT MODIFICATION PROCEDURES for administrative procedures for handling changes to the Contract.
 - 3. Section 013200 CONSTRUCTION PROGRESS DOCUMENTATION "Construction Progress Documentation" for administrative requirements governing the preparation and submittal of the Contractor's construction schedule.

1.3 DEFINITIONS

A. Schedule of Values: A statement furnished by Contractor allocating portions of the Contract Sum to various portions of the Work and used as the basis for reviewing Contractor's Applications for Payment.

1.4 SCHEDULE OF VALUES

CM has provided separate acceptable cost/resource analysis for Owner's use

- A. Coordination: Coordinate preparation of the schedule of values with preparation of Contractor's construction schedule. Cost-loaded Critical Path Method Schedule may serve to satisfy requirements for the schedule of values.
 - 1. Coordinate line items in the schedule of values with items required to be indicated as separate activities in Contractor's construction schedule.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- 2. Submit the schedule of values to Architect through Construction Manager at earliest possible date, but no later than seven days before the date scheduled for submittal of initial Applications for Payment.
- 3. Subschedules for Phased Work: Where the Work is separated into phases requiring separately phased payments, provide subschedules showing values coordinated with each phase of payment.
- 4. Subschedules for Separate Elements of Work: Where the Contractor's construction schedule defines separate elements of the Work, provide subschedules showing values coordinated with each element.
- 5. Subschedules for Separate Design Contracts: Where the Owner has retained design professionals under separate contracts who will each provide certification of payment requests, provide subschedules showing values coordinated with the scope of each design services contract, as described in Section 011000 SUMMARY
- B. Format and Content: Use Project Manual table of contents as a guide to establish line items for the schedule of values. Provide at least one line item for each Specification Section.
 - 1. Identification: Include the following Project identification on the schedule of values:
 - a. Project name and location.
 - b. Name of Architect.
 - c. Architect's Project number.
 - d. Contractor's name and address.
 - e. Date of submittal.
 - 2. Arrange schedule of values consistent with format of AIA Document G703.
 - 3. Arrange the schedule of values in tabular form, with separate columns to indicate the following for each item listed:
 - a. Related Specification Section or Division.
 - b. Description of the Work.
 - c. Name of subcontractor.
 - d. Name of manufacturer or fabricator.
 - e. Name of supplier.
 - f. Change Orders (numbers) that affect value.
 - g. Dollar value of the following, as a percentage of the Contract Sum to nearest onehundredth percent, adjusted to total 100 percent. Round dollar amounts to whole dollars, with total equal to Contract Sum.
 - 1) Labor.
 - 2) Materials.
 - 3) Equipment.
 - 4. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Provide multiple line items for principal subcontract amounts in excess of five percent of the Contract Sum.
 - 5. Provide a separate line item in the schedule of values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.
 - a. Differentiate between items stored on-site and items stored off-site.
 - 6. Purchase Contracts: Provide a separate line item in the schedule of values for each purchase contract. Show line-item value of purchase contract. Indicate Owner payments or deposits, if any, and balance to be paid by Contractor.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- 7. Overhead Costs: Include total cost and proportionate share of general overhead and profit for each line item.
- 8. Closeout Costs. Include separate line items under Contractor and principal subcontracts for Project closeout requirements in an amount totaling five percent of the Contract Sum and subcontract amount.
- 9. Schedule of Values Revisions: Revise the schedule of values when Change Orders or Construction Change Directives result in a change in the Contract Sum. Include at least one separate line item for each Change Order and Construction Change Directive

1.5 APPLICATIONS FOR PAYMENT

to be reflected only under each Sub/Trade reqs

- A. Each Application for Payment following the initial Application for Payment shall be consistent with previous applications and payments as certified by Architect and Construction Manager and paid for by Owner.
- B. Payment Application Times: The date for each progress payment is indicated in the Agreement between Owner and Contractor. The period of construction work covered by each Application for Payment is the period indicated in the Agreement.
- C. Payment Application Times: Submit Application for Payment to Architect by the last of the month. The period covered by each Application for Payment is one month, ending on the last day of the month.
 - 1. Submit draft copy of Application for Payment seven days prior to due date for review by Architect.
- D. Application for Payment Forms: Use AIA Document G702 and AIA Document G703 as form for Applications for Payment.
 - 1. Other Application for Payment forms proposed by the Contractor shall be acceptable to Architect, Construction Manager and Owner. Submit forms for approval with initial submittal of schedule of values.
- E. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Construction Manager will return incomplete applications without action.
 - 1. Entries shall match data on the schedule of values and Contractor's construction schedule. Use updated schedules if revisions were made.
 - 2. Include amounts for work completed following previous Application for Payment, whether or not payment has been received. Include only amounts for work completed at time of Application for Payment.
 - 3. Include amounts of Change Orders and Construction Change Directives issued before last day of construction period covered by application.
 - 4. Indicate separate amounts for work being carried out under Owner-requested project acceleration.
- F. Tools and Equipment: All tools and equipment purchased for construction of the project and requisitioned for payment shall be tracked on a log indicating what was purchased, the cost, and the requisition number the payment is being made in. The log shall be included in any payment requisition that contains a request for payment for tools and equipment by the CM. Tools and equipment purchased for the project are to be turned

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

over to the Owner at completion, and accepted or discarded at that time pursuant to the Owner's discretion.

- G. Stored Materials: Include in Application for Payment amounts applied for materials or equipment purchased or fabricated and stored, but not yet installed. Differentiate between items stored on-site and items stored off-site.
 - 1. Provide certificate of insurance, evidence of transfer of title to Owner, and consent of surety to payment for stored materials.
 - 2. Provide supporting documentation that verifies amount requested, such as paid invoices. Match amount requested with amounts indicated on documentation; do not include overhead and profit on stored materials.
 - 3. Provide summary documentation for stored materials indicating the following:
 - a. Value of materials previously stored and remaining stored as of date of previous Applications for Payment.
 - b. Value of previously stored materials put in place after date of previous Application for Payment and on or before date of current Application for Payment.
 - c. Value of materials stored since date of previous Application for Payment and remaining stored as of date of current Application for Payment.
- H. Transmittal: Submit **four** three signed and notarized original copies of each Application for Payment to Architect by a method ensuring receipt within 24 hours. One copy shall include waivers of lien and similar attachments if required.
 - 1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.
- I. Waivers of Mechanic's Lien: With each Application for Payment, submit waivers of mechanic's lien from subcontractors, sub-subcontractors, and suppliers for construction period covered by the previous application.
 - 1. Submit partial waivers on each item for amount requested in previous application, after deduction for retainage, on each item.
 - 2. When an application shows completion of an item, submit conditional final or full waivers.
 - 3. Owner reserves the right to designate which entities involved in the Work must submit waivers.
 - 4. Submit final Application for Payment with or preceded by conditional final waivers from every entity involved with performance of the Work covered by the application who is lawfully entitled to a lien.
 - 5. Waiver Forms: Submit executed waivers of lien on forms acceptable to Owner.
- J. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:
 - 1. List of subcontractors.
 - 2. Schedule of values.
 - 3. Contractor's construction schedule (preliminary if not final).
 - 4. Combined Contractor's construction schedule (preliminary if not final) incorporating Work of multiple contracts, with indication of acceptance of schedule by each Contractor.
 - 5. Products list (preliminary if not final).
 - 6. Sustainable design action plans, including preliminary project materials cost data.
 - 7. Schedule of unit prices.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- 8. Submittal schedule (preliminary if not final).
- 9. List of Contractor's staff assignments.
- 10. List of Contractor's principal consultants.
- 11. Copies of building permits.
- 12. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
- 13. Initial progress report.
- 14. Report of preconstruction conference.
- 15. Certificates of insurance and insurance policies.
- 16. Performance and payment bonds.
- 17. Data needed to acquire Owner's insurance.
- K. Application for Payment at Substantial Completion: After Architect issues the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.
 - 1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.
 - 2. This application shall reflect Certificate(s) of Substantial Completion issued previously for Owner occupancy of designated portions of the Work.
- L. Final Payment Application: After completing Project closeout requirements, submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:
 - 1. Evidence of completion of Project closeout requirements.
 - 2. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
 - 3. Updated final statement, accounting for final changes to the Contract Sum.
 - 4. AIA Document G706.
 - 5. AIA Document G706A.
 - 6. AIA Document G707.
 - 7. Evidence that claims have been settled.
 - 8. Final meter readings for utilities, a measured record of stored fuel, and similar data as of date of Substantial Completion or when Owner took possession of and assumed responsibility for corresponding elements of the Work.
 - 9. Final liquidated damages settlement statement.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

END OF SECTION

Specification Section 012600a Change Order Form 15 Documents

Attached form is outdated and does not reflect the form that Skanska and Hill agreed to use on 9/24/19 acknowledged we will continue to use that version/template

ATTACHMENT NO. 1 (# Pages)

Skanska USA Building Inc.

Change Request #001

To: Ray Masak Project Manager 333 Washington Street, 6th Floor Brookline. MA 02445 Date: 2/21/2019 Project #: Project: Brookline High School Expansion Project

Description:		Proposed Amount
Item Description		Amount
Item X		\$0.00
Item Y		\$0.00
Fee		
General Liability		included above
Payment and Performance Bonds		\$0.00
	Total :	\$0.00

Type: Schedule Impact: Overtime: Notes: Lump Sum This change will add ${\bf X}$ day(s) to the contract completion date. Project OT (Is / Is Not) Required

By:

Date:

PROJECT NAME:	Brookline High School	PROJECT NO.		CM: Skanska USA Building Inc.		
PCO NUMBER:		PCO DESCRIPTION:				
PCO DATE:						
SKA PCO NUMBER:						
	CONSTRUCTION MANAGER CHANGE REQUEST SUMMARY					

CONSTRUCTION MANAGER CHANGE REQUEST SUMMARY

1. LABOR: CONSTRUCTION MANAGER'S SELF-PERFORMED WORK

		Regular Hours	Overtime (1.5x) Hours	Double Time (2x)		be taken from the R er its approval by the	ate Approval Sheet, CM.		
Trade	Classification	Worked	Worked	Hours Worked	Regular Time Rate (Cost/hour)	Overtime Rate (Cost/Hour)	Double Time Rate (Cost/Hour)		Total Labor Cost
					(cost/nour)	(cost/fibul)	(cost/fibur)		
		I			1			TOTAL LABOR COST	\$0

2. MATERIALS: CONSTRUCTION	MANAGER'S SELF PERFORMED WORK				
	Material Description	Quantity	Unit	Cost per Unit	Total
					C
					(
					(
					C
					C
					C
					(
					(
					C
					0
					C
					C
			T	OTAL MATERIALS COST	ŚC

PROJECT NAME:	Brookline High School	PROJECT NO.			CM: Skanska USA	Building Inc.	
PCO NUMBER:		PCO DESCRIPTION:					
PCO DATE:							
SKA PCO NUMBER:		J					
		CONSTRUCTION MANAGER CHANGE	REQUEST SUMMARY				
3. EQUIPMENT: CONST	TRUCTION MANAGER'S SELF PERFO	Equipment Description		Qty	Unit	Cost Per Unit	Total
		4 · F · · · · · · · · · · · · · · · · ·					(
							(
						TOTAL EQUIPMENT CO	
							· · · · ·
4. MISC. LUMP SUMP	SERVICES PROVIDED TO CONSTRU	CTION MANAGER (POLICE DETAIL, UTILITIE Description of Miss	S, ETC.): cellaneous Lump Sum Service				Total
		Description of white	centrate ous camp sum service				Total
				то	TAL MISC. LUMP SU	IM SERVICES COST:	\$0
5. SUBTOTAL COSTS F	OR CONSTRUCTION MANAGER LI	NE ITEMS 2., 3., AND 4.				SUBTOTAL:	\$0
6. OVERHEAD AND PR	OFIT OF CONSTRUCTION MANAG	FR LINE ITEM 5				10% X Line 5:	\$0
	permitted 10% of total actual cos					10/07/ Line 5.	, v
	5. & 6. FOR CONSTRUCTION MAN	IACED:			TOTAL COST OF M	ORK SELF-PERFORMED BY C.	
7. TOTAL OF LINES 1.,	S. & C. FOR CONSTRUCTION MAN	AGER.			TOTAL COST OF W	URK SELF-PERFORIVIED BT C.	M. \$0
8. TOTAL COST OF WC	ORK PERFORMED BY SUBCONTRAC	CTORS:		Total of	line 11 costs for eac	h attached subcontractor fo	rm \$0
9. OVERHEAD AND PR	OFIT FOR SUBCONTRACTOR WOR	<u>:K:</u>			(5	5% Fee applied to line 8 abov	ve) (
10. SUBTOTAL LINES 7	., 8., AND 9.						\$0
11. CM PAYMENT AND	D PERFORMANCE BOND					0.00% x ITEM 10:	
12. CM PAYMENT AND PERFORMANCE BOND 0.00% × ITEM 7:							
13. TOTAL COST OF CH	ANGE ORDER TO OWNER						\$0

PROJECT NAME:	Brookline High School	PROJECT NO.	CM: Skanska USA Building Inc.
PCO NUMBER:		PCO DESCRIPTION:	
PCO DATE:			
SKA PCO NUMBER:			
		FORMAT FOR SUBMISS	SION OF CHANGE ORDER
CHECK HERE IF SECO	ND-TIER SUB		(Submit separate form for Subcontractor and each Sub-subcontractor)

NAME OF FIRM SUBMITTING CHANGE ORDER

1. LABOR: THIS SUBCONTRACTOR:

Use only CM Approved Rated as established per the Laborer Rate Submission Form. Rates are inclusive of all overhead, profit, health, welfare, annuity and excess fringes. It is the Trade's responsibility to submit and maintain current Change Order Labor Rate Forms. All changes in previously approved rates shall be submitted for CM approval via an amendec Labor Rate Submission Form prior to appearing on this sheet.

		Regular Hours	Overtime (1.5x) Hours	Double Time (2x)	These values shall	be taken from the Ra	ate Approval Sheet,	Fee Included in Hourly	
Trade	Classification	Worked	Worked	Hours Worked	Regular Time Rate	Overtime Rate	Double Time Rate	rate (from approval	Total Labor Cost
		WORKED	WOIKEd	Hours worked	(Cost/hour)	(Cost/Hour)	(Cost/Hour)	form)	

1.A

TOTAL LABOR COST FEE (INCLUDED IN LABOR COST ABOVE)

\$O

2. MATERIALS: THIS SUBCONTRACTOR:

(For extensive material lists, attached details backup and enter as a lump sum below)

Material Description	Quantity	Unit	Cost per Unit	Total
				0
				0
				0
				0
				0
				0
				0
				0
				0
				0
				0
				0
		Т	OTAL MATERIALS COST	\$0

PROJECT NAME:	Brookline High School	PROJECT NO.	CM: Skanska USA Building Inc.
PCO NUMBER: PCO DATE:		PCO DESCRIPTION:	
CHECK HERE IF SECOND-TIER SUB			SION OF CHANGE ORDER (Submit separate form for Subcontractor and each Sub-subcontractor)
NAME OF FIRM SUE	BMITTING CHANGE ORDER		

3. EQUIPMENT: SUBCONTRACTOR: (For extensie equipment lists, attach detailed backup and enter as a lump sum below):

Equipment Description	Qty	Unit	Cost Per Unit	Total
				0
				0
				0
TOTAL EQUIPMENT COST:				

4. MISC. LUMP SUMP SERVICES PROVIDED TO THIS SUBONTRACTOR (POLICE DETAIL, UTILITIES, ETC.):

Description of Miscellaneous Lump sum Service			Total
	TO'	TAL MISC. LUMP SUM SERVICES COST:	\$0
5. SUBTOTAL COSTS FOR THIS SUBONTRACTOR LINE ITEMS 2., 3., AND 4.		SUBTOTAL:	\$0
6. OVERHEAD AND PROFIT OF THIS SUBCONTRACTOR LINE ITEM 5:		10% X Line 5:	\$0
Construction Manager permitted 10% of total actual cost of Item 5.		10% A Life 5.	οÇ
······			
7. TOTAL OF LINES 1., 5. & 6. FOR THIS SUBCONTRACTOR:	TAL COST OF W	ORK SELF-PERFORMED BY THIS SUBCONTRACTOR.	\$0
8. TOTAL COST OF WORK PERFORMED BYLOWER TIER SUBCONTRACTORS:	of line 11 costs f	or each attached Second_Tier subcontractor form	
9. OVERHEAD AND PROFIT FOR LOWER TIER SUBCONTRACTOR WORK:		(5% Fee applied to line 8 above)	0
The total of all Subcontractor and Lower-Tier Subcontractor markups may not exceed an aggregate 15% of Co	ost of Work, regardless of the number of tiers invo		0
10. ACTUAL PREMIUM PAID FOR BOND	(enter approved rate as a percentage)	0.00% x ITEM 7:	\$0.00
11. TOTAL COST OF WORK DUE SUBCONTRACTOR, Including bond cost			\$0
NOTE: ALL change order proposals and invoices from the SUBCONTRACTOR must include a cover letter on co	mnany letterhead identifying the PCO number a	description of the scope of work and total cost of	the proposed change
	, include the second state of the second state	contraction of the second seco	p

PROJECT NAME: Brookline High School - Brookline, MA

Date Effective Beginning: Contractor Name: Effective Until

LABOR RATE SUBMISSION FORM

This form must be completed, submitted and approved prior to the submission of any change order price proposals. Complete the below for every Trade and Classification that is likely to work the project. If any contractor seeks to utilize a total hourly wage rate (wages plus benefits) for change order pricing that is in excess of the applicable published prevailing wage rate, then this form must be completed, submitted (with backup documentation - i.e. union agreement) and approved prior to the submission of any change order price proposals. The information supplied below must be consistent with certified payroll submissions. SUBCONTRACTOR TO FILL OUT ONLY THE BLANK BOXES.

DIRECT LABOR COSTS SUBCONTRACTOR PROPOSED RATES FOR APPROVAL Classification Classification Classification Classification Classification Trade Description Classification (Foreman. (Foreman. (Foreman. (Foreman. (Foreman. (Carpenter, Pipefitter, Journeyman, Journeyman, Journeyman, Journeyman Journeyman, (Foreman, Journeyman, Electrician, etc.) Apprentice) Apprentice) Apprentice) Apprentice) Apprentice) Apprentice) Trade Description/Classification Prevailing Wage Rate Hourly Base Wage Rate Health & Welfare Pension/Annuity **Direct Hourly Labor Cost** Workmen's Compensation Insurance Liability Insurance Federal Social Security Massachusetts Unemployment Compensation Subtota or 30% of Hourly Base Wage Rate OHP = 10% of Direct Hourly Labor Cost Excess Fringes Total Hourly Labor Cost (with A) 0 Total Hour Labor Cost (with B) 0 0 0 0 0

NOTES:

>Contractor may utilize rate of 30% for insurance/taxes without providing documentation. If a rate in excess of 30% is requested, documentation must be provided and only the four items listed above may be included.

>Attached all relevant supporting documentation such as union wage rate sheets, Insurance carrier verification letters, workers compensation rate tables, etc

>Excess fringes are the actual direct additional premium costs and expenses incurred as results of collective bargaining agreements or other agreements between organized labor and employers (apprentice training, education fund, legal, travel, etc.) If any dollar value is claimed under Excess Fringes, provide all necessary supporting documentation. Note that the following benefits are explicitly not allowed: Tools of the Trade.

PROJECT C – STEM WING ADDITION

BROOKLINE HIGH SCHOOL EXPANSION

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

Exclude: See CM Agreement SECTION 012600

CONTRACT MODIFICATION PROCEDURES

Entire section to be struck as change procedure is governed by the owner agreement, GCs section VII

PART 1 - GENERAL

- 1.1 GENERAL PROVISIONS
 - A. Attention is directed to Division 00 PROCUREMENT AND CONTRACTING REQUIREMENTS and DIVISION 01 GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.
 - B. Examine all other Sections of the Specifications for requirements that affect work of this Section, whether or not such work is specifically mentioned in this Section.
 - C. Coordinate Work with that of all other trades affecting or affected by Work of this Section. Cooperate with such trades to assure the steady progress of all Work under the Contract.
- 1.2 SUMMARY
 - A. Section includes administrative and procedural requirements for handling and processing Contract modifications.
 - B. Related Requirements:
 - 1. Section 013300 SUBSTITUTION PROCEDURES for administrative procedures for handling requests for substitutions made after the Contract award.

1.3 MINOR CHANGES IN THE WORK

A. Architect will issue through Construction Manager supplemental instructions authorizing minor changes in the Work, not involving adjustment to the Contract Sum or the Contract Time, on AIA Document G710.

1.4 PROPOSAL REQUESTS

- A. Owner-Initiated Proposal Requests: Construction Manager will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.
 - 1. Work Change Proposal Requests issued by Construction Manager are not instructions either to stop work in progress or to execute the proposed change.
 - 2. Within time specified in Proposal Request after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
- b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
- c. Include costs of labor and supervision directly attributable to the change.
- d. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
- e. Quotation Form: Use forms acceptable to Architect.
- B. Contractor-Initiated Proposals: If latent or changed conditions require modifications to the Contract, Contractor may initiate a claim by submitting a request for a change to Architect.
 - 1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.
 - 2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 - 3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
 - 4. Include costs of labor and supervision directly attributable to the change.
 - 5. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
 - 6. Comply with requirements in Section 012500 "Substitution Procedures" if the proposed change requires substitution of one product or system for product or system specified.
 - 7. Proposal Request Form: Use form acceptable to Architect.

1.5 ADMINISTRATIVE CHANGE ORDERS

A. Unit-Price Adjustment: See Section 012200 - UNIT PRICES for administrative procedures for preparation of Change Order Proposal for adjusting the Contract Sum to reflect measured scope of unit-price work.

1.6 CHANGE ORDER PROCEDURES

A. On Owner's approval of a Work Change Proposal Request, Architect will issue a Change Order for signatures of Owner and Contractor on AIA Document G701CMa.

1.7 CONSTRUCTION CHANGE DIRECTIVE

A. Construction Change Directive: Architect may issue a Construction Change Directive on AIA Document G714CMa. Construction Change Directive instructs Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- 1. Construction Change Directive contains a complete description of change in the Work. It also designates method to be followed to determine change in the Contract Sum or the Contract Time.
- B. Documentation: Maintain detailed records on a time and material basis of work required by the Construction Change Directive.
 - 1. After completion of change, submit an itemized account and supporting data necessary to substantiate cost and time adjustments to the Contract.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

END OF SECTION

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

SECTION 013300

SUBMITTAL PROCEDURES

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

- A. Attention is directed to Division 00 PROCUREMENT AND CONTRACTING REQUIREMENTS and DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.
- B. Examine all other Sections of the Specifications for requirements that affect work of this Section, whether or not such work is specifically mentioned in this Section.
- C. Coordinate Work with that of all other trades affecting or affected by Work of this Section. Cooperate with such trades to assure the steady progress of all Work under the Contract.

1.2 SUMMARY

- A. The Work of this Section includes, but is not limited to, requirements for the following procedures:
 - 1. Submittal schedule
 - 2. Product data
 - 3. Shop drawings
 - 4. Samples
 - 5. Colors and finishes
 - 6. Calculations
 - 7. Informational submittals
 - 8. Action on submittals.
 - 9. Substitution requests.
- B. Related work includes, but is not limited to, the following work under other Sections:
 - 1. Availability and restrictions for use of electronic copies of Contract Document: Section 011400 Work Restrictions.
 - 2. Specific requirements for submittal of construction schedules: Section 013200 Construction Progress Documentation.
 - 3. Specific requirements for submittal of schedule of values: Section 012400 Schedule of Values.
 - 4. Requirements for submittal of coordination drawings: Section 013100 Project Management and Coordination.
 - 5. Submittal of final record drawings and other documents: Section 017839 Project Record Documents.
 - 6. Submittal of product and procedural documentation: Section 018110 Sustainable Design Requirements; 018119-Indoor Air Quality Requirements.
 - 7. Waste management documentation: Section 017400 Cleaning and Waste Management.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

1.3 DEFINITIONS

- A. Action Submittals: Written and graphic information that requires Architect's responsive action. Action submittals include product data, shop drawings and samples.
- B. Informational Submittals: Written information that does not require Architect's responsive action. Submittals of this kind may be required by the Architect to confirm the Construction Manager's compliance with submittal requirements. Submittals may be rejected for not Informational submittals include calculations and other complying with requirements. informational submittals described in this Section.
- C. Substitutions: Changes in products, materials, equipment and methods of construction from those required by the Contract Documents, as proposed by the Construction Manager and not considered "or equal".
- D. Or equal: Construction Manager proposed products, materials, and equipment that comply with specified material and performance requirements, but are not one of the named manufacturer's, suppliers, and distributors. Equal products, materials, and equipment shall identically match the physical appearance of specified items.

1.4 SUBMITTALS

- Submittal Schedule: Α.
 - 1. Within 45 days after signing the Agreement, to be submitted with the CPM Schedule, prepare and submit for the Architect's approval a schedule of Shop Drawings, Product Data and Samples required to be submitted for the Work.
 - The schedule shall indicate by trade the date by which final approval of each item a. must be obtained, and shall be revised as required by conditions of work, subject to the Architect's approval.
 - b. The schedule shall be derived from the Construction Manager's CPM Schedule, but shall be submitted as a separate document, in addition to being part of the CPM line items.
 - 2. The Architect's review, including Consultant's review period, will not exceed 21 calendar days from the date on which the Architect receives the submission or the date that is provided on the Construction Manager's submittal schedule, whichever is the latest. Construction Manager shall strictly adhere to the established dates set forth by the Schedule of Submittals specified above in paragraph 2.01 A. On a weekly basis, the Construction Manager is responsible for identifying, in writing, priority submissions to assist the Architect in facilitating an efficient review process that is in accordance with the As needed to meet schedule requirements for manufacture Construction Manager's CPM schedule.

and delivery for install dates, and subject to release dates of

- approved RTA's and GMP from the Owner. Each submittal shall be made no later than 60 calendar days prior to the time that the 3. CPM shows requirement for incorporation of the item into the Work, or earlier under the following conditions:
 - As required to furnish and deliver to the site the specific item or items required, with a. sufficient time to allow proper examination and review of such submittals.
 - If the item in question is to be incorporated in the work prior to the expiration of 60 b. calendar days from the time of execution of the Contract, the aforesaid written notice shall be submitted to the Architect immediately following the execution of the

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

Contract.

- c. Substitutions/ Or Equal: Each request for a substitution shall be made no later than 90 calendar days prior to the time for incorporation of the item into the Work.
- 4. No item, material, article, system or piece of equipment requiring approval of the Architect shall be ordered or installed until such approval has been obtained.
- B. Product List for Color Selection: To facilitate the preparation of the color schedule, the Construction Manager shall, along with the CPM, submit within forty-five (45) calendar days following signing the Agreement, unless otherwise extended by the Architect, a list of the names of the manufacturers whose products he proposes to use.
 - 1. List products for which color, finish, pattern, texture, or other related information is a consideration, including, but not limited to the following:
 - a. Exterior materials: Face brick; metal wall panels and siding; exterior concrete masonry units; factory-finished metal siding; factory finish for doors, windows and louvers; and curtain wall.
 - b. Millwork and Casework finishes: Solid and veneer wood with transparent finish; plastic laminate; solid surfacing.
 - c. Wood door finishes.
 - d. Acoustic wall panels.
 - e. Interior finishes: Ceramic tile, acoustical ceiling tile, resilient flooring, carpet, paint.
 - f. Specialties available in a choice of colors: Toilet partitions; lockers; operable panel finishes.
 - g. Other items for which the above properties affect the design.
 - 2. Products listed shall be as specified, unless substitution has been approved.
- C. Substitution and Or Equal Requests: Submit three copies of each request for consideration. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
 - 1. Substitution and Or Equal Request Form: Use facsimile of form provided at end of Section.
 - 2. Documentation: Show compliance with requirements for substitutions listed on the Substitution / Or Equal Request form, and additional requirements as may be requested by the Architect or as otherwise applicable. Submit specified product or system and clearly demonstrate in a side-by-side comparison the similarities and differences between the specified and proposed Substitution or Or Equal product or system. Absent this documentation, the request will not be reviewed by the Architect and be sent back rejected.
- D. Product Data, Shop Drawings, Samples, Schedules and other Submittals: Refer to individual Specification Sections for submittals required.
- E. Confirmation of contract between Construction Manager and printing company for reproduction of shop drawings as specified in this Section.

REVISION: FB-005 - GMP Bid Set - AUGUST 1, 2019

PART 2 - PRODUCTS

2.1 SUBMITTAL PREPARATION, GENERAL

We use Skanska's transmittal from Procore

- A. Preparation of Submittals: To receive consideration by the Architect, each submittal shall be accompanied with the Submittal Transmittal Form at the end of this section.
 - 1. Submittal packages shall contain all required information in accordance with the submittal requirements of each specification section. Incomplete submittals will be returned without review.
- B. Each submittal cover sheet shall contain a clear space approximately 80 square inches for stamps and Architect's comments. Each drawing shall contain a similar space as an additional border on the right or bottom.
 - 1. Include Product Data / Sustainability Attributes Reporting Form if applicable for reporting of required sustainable documentation as required. See each specification section.
- C. Distribution:
 - 1. CM shall electronically deliver submittals to the Architect and its consultants, OPM, Clerk, and CxA (when applicable) in a format acceptable to the Architect. via procore
 - 2. (Eor submittals that are 11x17 and larger) simultaneously, CM shall deliver 1 hard copy via procore print each to the Architect and its consultants and one hard copy print to the clerk.
 - 3. Architect and consultants will review submittals, and the Architect will post reviewed submittals on web-based file transfer service specified herein. via procore
 - 4. CM is responsible for distribution to all trades.
 - 5. CM to deliver 1 hard copy of "Reviewed" and "Approved and Furnish as Corrected" submittals to Clerk. via procore
 - 6. Drawings submitted directly from Subcontractors, manufacturers or vendors, or directly to the Architect's consultants, will be returned to the Construction Manager without action.
- D. Web-Based Construction Administration Database:
 - 1. For the entire Construction Period Construction Manager shall provide, manage and maintain a High-Band Width Electronic File Transfer Service that is accessible via the Internet by a Web Browser such as Internet Explorer or Mozilla Fire Fox. The Construction Manager shall process submittals electronically, through one of the three following web-based construction administration database services:
 - a. Prolog Converge.
 - b. Submittal Exchange.
 - c. Newforma.
 - d. Procore.
 - e. Or equal.
 - 2. The Construction Manager shall provide licensed seats/access to, and training on said database, for all of the Architect's, Architect's Consultant's and OPM's CA Team Members, to facilitate electronic transmittal of all of Construction Documentation including, but not limited to Project submittals, RFI's and Change Order Requests, Architect Directives, Sketches, Meeting Minutes, and Architect Field Reports.
 - 3. All of the Project documentation compiled in this CA database, shall be made completely accessible to the Architect & Owner, for the entire duration of the Project, and then be submitted (in PDF form) to, and become the property of the Owner, similar to all other Closeout documentation related to this Project.

Sustainability reports may not be concurrent with initial submittals. Architect is responsible to only specify compliant products, so this should not be an issue.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

2.2 PRODUCT DATA

- A. Manufacturers' Product Literature: For standard manufactured items, submit manufacturer's catalog sheets with illustrated cuts of the items to be furnished.
 - 1. Include scale details, sizes, dimensions, performance characteristics, capacities and other pertinent information.
 - 2. Each submittal of product data shall be accompanied by an appropriate transmittal form with specific reference to the applicable paragraph in the Specifications.
 - 3. Indicate clearly on such printed matter which of several items is being submitted for approval.
- B. Sustainable Submittals: For products requiring sustainable attributes as described in 018110 or other related sections; include recycled content percentage (both pre-consumer and postconsumer), proof of relevant indoor air quality certifications as required by LEED, and proof of FSC certification when applicable.
- C. If catalog cuts of standard manufactured items show different types, options, finishes, performance requirements, or other variations, those features that the Construction Manager proposes to furnish shall be clearly circled or otherwise indicated, and all irrelevant diagrams, notes, or other information deleted or canceled.
 - 1. If any variations from the catalog description are proposed or required, such variations shall be clearly noted on the cut by the Construction Manager.
 - 2. Wiring diagrams shall be produced to address specific project requirements. Catalog cuts of wiring diagrams will not be acceptable.

2.3 SHOP DRAWINGS

- A. The Construction Manager shall prepare shop drawings showing such features as required by the Technical Specifications Sections, to demonstrate an understanding of the particular conditions unique to this Project.
 - 1. Prepare shop drawings at a scale of at least twice the scale of contract drawings showing the same work.
 - 2. Reproduction of Contract Documents in any form will not be accepted for use as Shop Drawings, unless specifically allowed in writing by the Architect for a particular portion of the Work.
 - 3. Refer to Section 011400 –WORK RESTRICTIONS for permissible use of electronic documents for the purpose of preparation of shop drawings. Use of Project Electronic Files for shop drawing preparation will be subject to the requirements specified in that Section.
- B. Shop Drawings related to various units comprising a proposed assembly shall be submitted simultaneously so that such units may be checked individually and as an assembly.
- C. Each drawing shall have a clear space approximately 80 square inches as an additional border on the right or bottom for stamps and Architect's comments.
- D. Shop Drawings shall clearly indicate all details, sectional views, arrangements, working and erection dimensions, kinds and quality of materials and their finishes, and other information

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

necessary for proper checking and for fabrication and installation of the items, and shall include all information required for making connections to other work and/or adjacent materials.

E. If any information on previously submitted Shop Drawings, aside from notations made by the Architect is revised in any way, such revision shall be circled or otherwise graphically brought to the Architect's attention. If approved Drawings are subsequently revised, they shall be resubmitted to the Architect with all revisions clearly marked for the Architect's attention. Whenever drawings are revised, the latest revisions shall be circled or otherwise indicated to distinguish them clearly from all previous revisions (and from the information on the original drawing).

2.4 SAMPLES

- A. Submit samples as required under the various Sections of the Specifications. Each sample shall be accompanied by a transmittal and cover sheet as required for all submittals.
- B. Before submitting samples, consult with Architect to determine whether samples are to be submitted to Architect's office, field, or other location.
- C. Samples shall be submitted in triplicate, with a fourth sample to be submitted to the Clerk for Owner review, unless otherwise specified or directed by the Architect.
- D. Samples may be submitted to Architect directly from manufacturers, vendors, suppliers, Subcontractors, or others, but a separate transmittal letter shall be submitted through the Construction Manager in each such case.
- E. Approved samples of major or expensive items or assemblies, if in good condition and meeting all requirements of the Contract, may be properly marked for identification and used in the Work, provided that all shipping and handling charges are paid by the Construction Manager.
- F. Each sample shall have a label indicating the material represented, its place of origin, and the names of the producer, the Architect, the Construction Manager, the Subcontractor and the building or Work for which the material is intended. Samples shall be marked to indicate the Drawing numbers or Specification Paragraph requiring the materials represented.
- G. Approval of samples for color, texture, and other aesthetic qualities shall not be construed as approval of other characteristics.
- H. Approved samples, unless specifically stated by the Construction Manager as slated for incorporation in the Work, will be kept on file (and accessible for inspection) by the Architect until Final Acceptance of the Project. Any sample not reclaimed by the Construction Manager within thirty (30) days after Substantial Completion of the Project will be considered unclaimed material, and may be disposed of by the Architect.

2.5 COLORS AND FINISHES

A. The Architect will prepare a master color schedule indicating the required color, finish, pattern, material, texture, and other pertinent information in connection with interior and

REVISION: FB-005 - GMP Bid Set - AUGUST 1, 2019

exterior finishes.

Current schedule does not have this time built in. It could be added.

- B. Color chips shall be submitted for all items having color unless otherwise directed or approved by the Architect. Upon the expiration of such 45-day period, the Architect will proceed with color selection and preparation of final color selection.
- C. The Architect will select the colors and finishes of a manufacturer within the framework of the Specifications, for each item where the Construction Manager fails to submit the name of a specific manufacturer within the allotted time, and the Construction Manager shall provide such materials without additional compensation.

2.6 CALCULATIONS

- A. Calculations Based on Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Construction Manager by the Contract Documents, submit calculations demonstrating that products and systems comply with specific performance and design criteria indicated.
 - 1. If criteria indicated are not sufficient to perform services or certification required, submit a written request for additional information to Architect.
- B. Certification: In addition to Shop Drawings, Product Data, and other required submittals, submit three copies of a statement, signed and sealed by the responsible design professional, for each product and system specifically assigned to Construction Manager to be designed or certified by a design professional.
 - 1. Indicate that products and systems comply with performance and design criteria in the Contract Documents.
 - 2. Include list of codes, loads, and other factors used in performing these services

2.7 INFORMATIONAL SUBMITTALS

- A. General: Informational submittals comprise written information that does not require Architect's responsive action.
- B. Informational submittals required for the Work include, but are not limited to, the following:
 - 1. Calculations for Construction Manager-engineered work, as specified in particular specification sections in Divisions 2 through 50.
 - 2. Research/evaluation reports and test data as specified in particular specification sections in Divisions 2 through 50.
 - 3. Certifications and other qualification data, as specified in particular specification sections in Divisions 2 through 50.
 - 4. Maintenance data, as specified in particular specification sections in Divisions 2 through 50.
 - 5. Confirmation of contract with printing company as specified in this Section.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

2.8 SUBMITTAL REQUIREMENTS FOR COMMISSIONING

- A. Submittals:
 - 1. Submit digital copy of applicable submittals for equipment to be commissioned to Commissioning Authority (CxA).
 - CxA will review and approve submittals applicable to systems being commissioned for compliance with commissioning needs, concurrent with Architect's and Construction Manager's review.
 - 3. Provide copy of the Design Team's review comments to the CxA. By WRA
 - 4. Repeat this process for any resubmissions.
- B. Data for Commissioning: The following information shall be included in all submittals of commissioned equipment and systems.
 - 1. Detailed manufacturer's installation and start-up procedures.
 - 2. Operating, troubleshooting, and maintenance procedures.
 - 3. Fan and pump curves.
 - 4. Full warranty information, with responsibilities of Owner to keep warranty in force clearly defined.
 - 5. Installation and checkout materials actually shipped inside equipment and actual field checkout sheet forms to be used by factory or field technicians.
- C. CxA will request specific information needed about each piece of commissioned equipment or system. Information requested includes, but is not limited to:
 - 1. Full details of Owner-contracted tests, if any.
 - 2. Full factory testing reports, if any.
- D. CxA may request additional documentation necessary for commissioning process. Requests by CxA may precede, be concurrent with, or follow normal submittals.
- E. Construction Manager's responsibility for deviations in submittals from requirements of Contract Documents is not relieved by CxA's review.

PART 3 - EXECUTION

3.1 CONSTRUCTION MANAGER ACTION ON SUBMITTALS

- A. Should the Architect in checking shop drawings or other submittals make changes which the Construction Manager deems will increase the Contract Price, the **Architect shall issue a Proposal Request, Construction Change Directive, or Field Order to provide notice of the change and revise the contract documents accordingly. The Construction Manager shall respond to the change in accordance with the General Conditions of their Agreement.** Construction Manager shall so inform the Architect and OPM in writing within fourteen (14) calendar days following receipt of the checked submittals and prior to starting fabrication of the item or items. Failing this, the Construction Manager shall be deemed to have waived all claims for extra compensation for the work involved.
- B. Notes or other information on submittals that are contrary to provisions of the Contract

Can be provided by subs, but all of this will not be provided with initial product data and shop drawings for approval

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

Documents shall be deemed to be addressed to the applicable Construction Manager, Subcontractor, material supplier or other parties involved, and shall have no force or effect with respect to this Contract, even though the Shop Drawing or Sample involved is approved by the Architect. In particular the terms "By Others", "N.I.C." or words of similar meaning and import on submissions shall not be deemed to imply that the referenced items are to be omitted from this Contract.

- C. The Construction Manager shall obtain and distribute copies of approved Shop Drawings and other Submittals to his subcontractors and material suppliers needing such information, at no additional cost to the Owner.
- D. The Construction Manager shall keep on the site, in good order, a complete up-to-date set of all approved Shop Drawings and other Submittals. Electronic only via procore
- E. Construction Manager shall assume full liability for delay attributed to insufficient time for delivery and/or installation of material or performance of the Work when approval of pertinent Shop Drawings is withheld due to failure of the Construction Manager to submit, revise, or resubmit Shop Drawings in adequate time to allow the Architect reasonable time, not to
 14 exceed twenty-one (21) calendar days for normal checking and processing of each submission and resubmission. The Architect will not be limited to twenty-one (21) calendar days when the Submittal Schedule has not been submitted or is not current.

3.2 ARCHITECT ACTION ON SUBMITTALS

- A. Product Data and Shop Drawings: After reviewing product data submittals, the Architect will mark each submittal with one of the following responses
 - 1. The Architect will annotate all submittals digitally, applying a stamp including the following information: "Reviewed as required by the Construction Contract Documents and approved, but only for conformance to the design concept of the Work, and subject to further limitations and requirements contained in the Contract Documents."
 - 2. "Rejected". A digital copy of Rejected submittals will be uploaded into the CA Database. Rejected submittals shall be resubmitted in the same manner until approval is obtained.
 - 3. The stamp will also contain notes indicating possible actions, namely; "rejected"; "revise and resubmit"; and "furnish as corrected". Architect will check one of the actions.
 - 4. Corrections or comments made on the submittals during this review shall not relieve Construction Manager from compliance with requirements of the Contract Drawings and Specifications. This check is only for review of general conformance with the design concept of and general conformance with the information given in the Contract Documents. The Construction Manager is responsible for confirming and correlating all quantities and dimensions; selecting fabrication processes and techniques of construction; coordinating his work with that of all other trades; and performing his work in a safe and satisfactory manner.

Electronic documentati on only

5. For all Submittals, the Construction Manager will have prints made from the annotated digital submittals at the Construction Manager's expense. Such prints shall be used for record purposes and for comparison with subsequent resubmissions. One will be retained by the Architect, and one furnished to the applicable consultants. Such procedures shall be followed until the Shop Drawing is marked "Furnish as Corrected", or "Reviewed as required by the Construction Contract Documents and approved, but only for conformance to the design concept of the work, and subject to further limitations and requirements contained in the Contract Documents."

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- 6. Submittals marked "Furnish as Corrected" shall be treated in the same manner as Drawings marked "Reviewed as required by the Construction Contract Documents...and requirements contained in the Contract Documents." The Architect's comments shall be considered part of the original Drawings. Should the Construction Manager disagree with such comments, he shall so notify the Architect in writing within fourteen (14) days after receipt of such Drawings and before commencing work on the items in question. Failing this, the Construction Manager shall be deemed to have accepted full responsibility for implementing such comments at no additional cost to the Owner.
- 7. For documents with the comment "Reviewed as required by the Construction Contract Documents..." or "Furnish as Corrected", the Construction Manager will have made at the Construction Manager's expense, four (4) prints of the corrected original for the Architect's and Owner's use.
- B. Informational Submittals: Architect will review each informational submittal and will review it for general compliance with submittal requirements
 - 1. Architect will process and digitally distribute each informational submittal as for other submittals.
 - 2. Compliant informational submittals will be marked "Reviewed" and a stamped digital copy will be distributed to Owner's Project Manager, Clerk of the Works and Construction Manager.
 - 3. Informational submittals that do not comply with submittal requirements specified herein and in the section whose work they cover will be returned "rejected". Re-submittal will be required.

3.3 SUBSTITUTIONS/ OR EQUALS

- A. Conditions: Architect will consider Construction Manager's request for substitution when the following conditions are satisfied. If the following conditions are not satisfied, Architect will return requests without action, except to record noncompliance with these requirements:
 - 1. Substitution is requested by completing a copy of Form 013301 SUBSTITUTION / OR EQUAL REQUEST FORM, attached to the end of this Section.
 - Requested substitution offers Owner a substantial advantage in cost, time, energy conservation, or other considerations, after deducting additional responsibilities Owner must assume. Owner's additional responsibilities may include compensation to Architect for redesign and evaluation services, increased cost of other construction by Owner, and similar considerations.
 - 3. Requested substitution/ or equal does not require extensive revisions to the Contract Documents.
 - 4. Requested substitution is consistent with the Contract Documents and will produce indicated results.
 - 5. Substitution request is fully documented and properly submitted.
 - 6. Requested substitution will not adversely affect Construction Manager's Construction Schedule.
 - 7. Requested substitution has received necessary approvals of authorities having jurisdiction.

Page 174 of 377

- 8. Requested substitution is compatible with other portions of the Work.
- 9. Requested substitution has been coordinated with other portions of the Work.
- 10. Requested substitution provides specified warranty.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- 11. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.
- 12. Requested substitution does not affect LEED v4 requirements.
- 13. Any additional cost, or any loss or damage arising from the substitution of any material or any method for those originally specified shall be borne by the contractor, notwith-standing approval or acceptance of such substitution by the Owner or Architect.
- B. Architect's Action: Architect will request additional information or documentation for evaluation within 7 calendar days of receipt of a request for substitution. Architect will notify Construction Manager of acceptance or rejection of proposed substitution within 21 calendar days of receipt of request, or 7 calendar days of receipt of additional information or documentation, whichever is later.
 - 1. Use product specified if Architect cannot make a decision on use of a proposed substitution within time allocated.
- C. Review of Substitution / Or Equal Requests: The Architect will review Substitution Requests that are submitted in accordance with the requirements of this section, and are shown to be of benefit to the Project.
- D. Form of Acceptance of Substitution: Change Order

END OF SECTION

REVISION: FB-005 - GMP Bid Set - AUGUST 1, 2019

SECTION 013100

PROJECT MANAGEMENT AND COORDINATION

PART 1 - GENERAL

1.1 **GENERAL PROVISIONS**

- Attention is directed to Division 00 PROCUREMENT AND CONTRACTING Α. REQUIREMENTS and DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.
- Β. Examine all other Sections of the Specifications for requirements that affect work of this Section, whether or not such work is specifically mentioned in this Section.
- C. Coordinate Work with that of all other trades affecting or affected by Work of this Section. Cooperate with such trades to assure the steady progress of all Work under the Contract.

1.2 SUMMARY

- A. The Work of this Section includes, but is not limited to, requirements for the following procedures:
 - Responsibility for coordination of the Work. 1.
 - 2. Surveying and engineering.
 - Coordination Drawings. 3.

N/A doesn't exist

- B. Related work includes, but is not limited to, the following work under other Sections:
 - Survey information available to bidders: Section 003100 AVAILABLE PROJECT 1. INFORMATION.
 - General requirements for submittals: Section 013300 SUBMITTAL PROCEDURES.

1.3 SUBMITTALS

- Prepare and submit documentation in accordance with Section 013300 SUBMITTAL A. PROCEDURES.
- B. Drawings:
 - Survey of vertical floor for each floor level of the 1913 Building to remain following the 1. selective demolition work and prior to any new work.
 - Survey of base plate elevations and anchor bolt locations. 2.
 - 3. Survey of as-built conditions: Certified survey showing all as-built dimensions, locations, angles and elevations of construction, to be submitted at Substantial Completion of the Work. This service/survey was not included within the Survey RTA or GMP as Div. 1 can be added as an additional service if required, or final survey by Owner. Survey of location and elevations of tiebacks left on-site. was excluded at the time.
 - 4.
 - Coordination Drawings as described in this Section. 5.
- C. Certifications required for Work described in this Section:

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

1. Field Engineering: Submit name and address of surveyor and professional engineer to Architect. Hired lowest qualified

bidder per Owner agreement and OPM authorization

1.4 COORDINATION

- A. General: The Construction Manager shall be responsible for the proper fitting of all work and the coordination of the operations of all trades, Subcontractors, material installers and equipment engaged upon the Work. He shall perform or cause Subcontractors to perform all cutting, fitting, adjusting and patching necessary to make the several parts of the Work come together properly and to fit the Work to receive or be received by that of other contractors.
- B. Project Supervision: The Construction Manager shall give his personal supervision to the Work and shall assign site staff for the Project as stipulated in the Agreement between the Owner and Construction Manager.
- C. Coordination with Subcontractors: The Construction Manager shall be in charge of the entire Work and shall be responsible for the prompt coordination of all trades, including his own forces and his various Subcontractors, and shall become fully familiar with all work required under the Contract.
 - 1. The above notwithstanding, each Subcontractor shall assume responsibility for the correctness and adequacy of his work. Each Subcontractor shall be responsible for and pay for all damage done by his work and his workers.
 - 2. No Subcontractor shall be permitted on the site without the Superintendent present to supervise the Work.
- D. Care shall be given to the proper scheduling, delivery, and installation of items to be built into rough construction which will affect the latter portions of the Work, such as anchors, pipe sleeves, inserts, conduit, pipes, lugs, clips, brackets, braces, hangers, bolts, miscellaneous metal, and similar items. These items are not necessarily specified under the trade Section under which they are to be installed. The Construction Manager shall ascertain that all are properly installed in their correct locations at the proper time, so as to prevent cutting and patching of finished work.
- E. The Construction Manager shall be fully responsible for coordination of general construction work with that of Subcontractors for PLUMBING, ELECTRICAL, HEATING AND VENTILATING and all other specialized trades. He shall investigate, together with the Subcontractors involved, the routing of pipe, ductwork, and conduit with particular attention to interference of structural members, other pipes, ducts, and conduit cuts, headroom conditions, door and window openings and swings, pipe chases, and similar features of the building which may affect installation and proper functioning of such items.
- F. Changes in design locations which may be necessary in the routing of pipes and ducts, or in the location of any mechanical, electrical or other equipment or in the location of other building elements, shall be anticipated and made prior to installation. Additional compensation will not be allowed for costs incurred as a result of the Construction Manager's failure to anticipate the necessity for such changes.
- G. There shall be no change or variation in ceiling height, wall layout, shaft, chase, furring or other dimensions shown on Drawings without the specific written approval of the Architect.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

H. The Construction Manager's responsibility for the coordination of all work under the Contract shall be complete, and shall extend to all modifications in the Work, whether or not such modifications entail a change in the Contract Price. Where the Contract Documents allow an optional material or method of performing a portion of the Work, or where the Construction Manager is ultimately allowed or directed to perform a part of the Work using a substitute material or method, the Construction Manager shall provide all other coordination and additional work that such change necessitates, without any additional cost to the Owner.

1.5 SURVEYING AND ENGINEERING, GENERAL

No, done by hired consultant, not employee of CM

Α.

The Construction Manager shall employ a project engineer who is a qualified land surveyor registered to practice in the State the project is located in, who shall establish and maintain grades and levels and permanent bench marks. In addition, the Construction Manager shall designate one person from within his organization, with engineering experience, who shall do the usual engineering work required, including leveling, checking, and verifying wall and partition lines, elevations, and other like items.

- B. Prior to commencement of any excavation or filling work on the site, the project engineer shall check locations of all structures and other fixed items with regard to property lines and other existing conditions. The Construction Manager shall be fully responsible for reporting to the Architect discrepancies between the dimensions and/or locations indicated on the Contract Drawings and those as they actually exist on the site.
- After verification of all dimensions and locations, the Construction Manager shall submit to the Architect such verification in written form bearing the professional stamp of the surveyor.
 Failure to do so shall mean that the Construction Manager assumes responsibility for all corrective measures required at no addition to the Contract amount.
- D. The Construction Manager shall lay out the Work and shall be responsible for all lines, elevations, and measurements of the building, grading, paving and other work under the Contract. He shall exercise proper precaution to verify the dimensions shown on the Drawings before laying out the Work and will be held responsible for any error resulting from his failure to exercise such precaution.

1.6 FIELD ENGINEERING REQUIREMENTS

- A. General: Provide professional field engineering services, establish grades, lines and levels, by use of recognized engineering survey practices.
 - 1. Submit surveys and documentation as described herein.
 - . Scope of Field Engineering:
 - 1. Site features:
 - a. Existing grades, including grades immediately adjacent to existing building.
 - 2. Structural elements: For each column, a precise base plate elevation and horizontal location shall be established. After the anchor bolts have been set in the foundations and leveling plates have been set in grout, the top surface of each leveling plate shall be surveyed to determine the following locations. Submit survey data to the Architect forreview and approval prior to fabrication of structural steel.
 - a. Elevation of top surface of each leveling plate.
 - b. Precise position of the center of each anchor bolt in each leveling plate.

Exclude B.1. We hired surveyor for layout of new buildings, not to check existing conditions.

2 and 3 are bought from subs.

4 we did with A plus

B cclude all of B and C.

Exclude all of B and C. We hired surveyor for layout of new buildings, not to check existing conditions.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- 3. Survey of location and elevations of tiebacks left on-site.
- 4. Vertical floor survey for each floor level of the 1913 Building to remain following the selective demolition work and prior to commencement of new work.
- C. Qualifications of Surveyor or engineer: Qualified engineer or registered land surveyor, acceptable to Architect and the Owner.
 - Registered professional engineer of the discipline required for the specific service on the 1. Project, licensed in the State the project is located in.
- D. Survey Reference Points:
 - Datum: Location of control datum to be used as reference point for horizontal and verti-1. cal survey measurements is shown on Drawings.
 - 2. Locate and protect control and reference points prior to starting sitework, and preserve all permanent reference points during construction.
 - Make no changes or relocations of control points without prior written notice to Ara. chitect.
 - In the event that any reference point is lost or destroyed, or requires relocation due to 3. necessary changes in grades or construction, perform the following actions without delay:
 - Report change to Architect immediately. a.
 - Replacement of reference point shall be performed by surveyor, as directed by Arb. chitect.
 - **Project Survey Requirements:** 4.
 - a. Establish a minimum of two permanent benchmarks on the site, referenced to data established by survey control points.
 - Establish lines and levels, locate and lay out by instrumentation and other approprib. ate means.
 - Verify layouts periodically using the same means as those by which they were es-C. tablished.

E. Records:

- 1. Maintain a complete, accurate log of all control and survey work as it progresses.
- 2. Prepare and submit a survey of existing conditions and a final survey of as-built conditions containing all relevant horizontal and vertical dimensions and reference point data.
- 1.7

N/A

BOW DING ENVELOPE COORDINATION DRAWINGS have not included resources or costs to produce

Strike entire section 1.7. We have included participation in envelope commissioning but coordination drawings.

- Building Envelope Coordination Meeting: The CM shall coordinate a pre-construction meeting Α. on site with all of the building envelope Subcontractors, the OPM, Clerk, Commissioning Agent, and Architect. Envelope systems and work includes, but is not limited to:
 - 1. Masonry, Air/ Vapor Barrier Systems, Waterproofing Systems, Windows, Curtainwall, Louvers, Roofing Systems, Metal Siding Systems, Exterior Frame Systems.
- B. CM shall coordinate and produce color coded coordination drawings of each system showing interface between each building envelope system.
- C. Coordination drawings shall include, but not be limited to:
 - 1. Foundation Conditions
 - 2. Footing Conditions
 - 3. Edge of floor slab conditions

4.

5.

6. 7.

8. 9.

F.

BROOKLINE HIGH SCHOOL EXPANSION

Openings in roof.

coordination drawings.

Roof Edge Conditions Roof to Wall Conditions

Expansion Joint Conditions

Interface of existing and new construction.

Opening Conditions (i.e. Window, Curtainwall & Louver)

1.8 MECHANICAL COORDINATION DRAWINGS

A. The Construction Manager shall be responsible for the coordination of all mechanical and electrical work with architectural requirements including ceiling layouts. Well in advance of commencing work in any area and before materials are fabricated or work begun, he shall submit to the Architect complete Coordination Drawings in the form of colorized PDF's, submitted electronically with 1 hard copy print to the Architect, and 1 hard copy print to the Engineer, in a scale not less than 1/4" = 1'-0". Congested areas and sections through shafts shall be at a scale not less than 3/8" = 1'-0".

D. Coordination drawings must be completed prior to system application on the mock-up(s).

E. Coordination Drawings shall be reviewed and signed off by each building envelope trade.

Refer to additional applicable requirements specified herein below for mechanical

- 1. Coordination Drawings are considered Informational Submittals. Refer to Section 013300 SUBMITTALS for requirements for preparation and submittal of Informational Submittals.
- B. Coordination Drawings shall indicate the necessary offsets for all ductwork, piping, conduit, and other items to clear the work of all other trades, and structure, and to maintain the required ceiling height, ceiling layout and partition layout.
- C. Prepare Coordination Drawings as follows: Provide PDF's and 1 hard copy print to the Architect and Engineer concurrently with each trade's additions, and with clearly marked
 C. conflicts and guestions on said PDF's and prints.
 - 1. The background for coordination drawings shall show the reflected ceiling plan.
 - 2. Construction Manager shall require HEATING AND VENTILATING Subcontractor to prepare original Drawings showing all ductwork, hot water and other heating lines, based on approved Sheet Metal Fabrication Drawings and related mechanical submittals.
 - 3. Construction Manager shall distribute them to the Architect and the Plumbing Subcontractor for the next step.
 - 4. Construction Manager shall then require PLUMBING Subcontractor to indicate all his equipment and plumbing lines on these.
 - 5. Construction Manager shall then require FIRE PROTECTION Subcontractor to indicate his equipment and piping on these.
 - 6. Construction Manager shall require the ELECTRICAL Subcontractor to indicate his equipment and conduit lines on the same Drawings.
 - 7. Construction Manager shall resolve conflicts and then submit in PDF and 1 hard copy to the Architect for review.
 - 8. Submit complete final set of coordination drawings for record purposes in PDF and 1 hard copy.


Exclude entire section C. A says coordination is CMs responsibility, so coordination process is dictated by Skanska's documents in Subcontracts not this section

Qualify electronic only,

no hard copy.

Are we OK with them being information only or

are they for approval?



REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- D. Coordination Drawings shall bear the signature of all subcontractors involved indicating that all space conditions have been satisfactorily resolved. In addition, the Drawings shall bear the Construction Manager's stamp bearing the notation "Drawings Have Been Checked and Coordinated with all Trades". Drawings without these notations, or Drawings submitted more than 120 days after the execution of the Contract, will not be accepted or reviewed by the Architect.
- E. If any space conflicts cannot be resolved by the Construction Manager, he shall immediately notify the Architect.
- F. Coordination Drawings are for the Construction Manager's and Architect's use during construction and shall not be construed as replacing any Shop, "As-Built", or other Record Drawings required elsewhere in these Contract Documents.
- G. Architect's review of Coordination Drawings shall not relieve Construction Manager from his overall responsibility for coordination of all work performed pursuant to the Contract or from any other requirements of the Contract.
- H. Access panel coordination: Show locations and sizes of all access panels for all trades on Coordination Drawings.
- I. Refer to Section 011400 Work Restrictions for Project Electronic Files to be made available for use by the Construction Manager in the preparation of Coordination Drawings.

PART 2 - PRODUCTS [NOT USED]

PART 3 - EXECUTION [NOT USED]

END OF SECTION

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

SECTION 013119

PROJECT MEETINGS

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

- A. Attention is directed to Division 00 PROCUREMENT AND CONTRACTING REQUIREMENTS and DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.
- B. Examine all other Sections of the Specifications for requirements that affect work of this Section, whether or not such work is specifically mentioned in this Section.
- C. Coordinate Work with that of all other trades affecting or affected by Work of this Section. Cooperate with such trades to assure the steady progress of all Work under the Contract.

1.2 SUMMARY

- A. The Work of this Section includes, but is not limited to, requirements for the following procedures:
 - 1. Organizational meetings.
 - 2. Project meetings.
 - 3. Pre-Installation conferences
 - 4. Post-construction meetings
- B. Related work includes, but is not limited to, the following work under other Sections:
 - 1. Requirements for construction schedules: Section 013200 Construction Progress Documentation.

PART 2 - PRODUCTS

2.1 ORGANIZATIONAL MEETINGS

- A. General: The Owner's Project Manager will schedule pre-construction organizational meetings, periodic Project meetings, specially called meetings throughout the progress of the Work, and post-construction meetings. Representatives of the Construction Manager shall attend all such meetings. Subcontractors shall attend only if requested by the Architect or the Owner's Project Manager.
- B. Pre-Construction Meeting: Immediately following award of Contract, the Architect will call one or more preliminary organizational meetings, during which detailed procedures will be worked out for submission and review of Shop Drawings and samples, format and extent of the Progress Schedule and Schedule of Values, format and methods for progress payment requisitions, channels of communication between Owner, the Owner's Project Manager,

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

Architect's and Construction Manager's personnel, and other routines to be followed during construction. The Architect will then issue a directive summarizing such procedures.

2.2 PROJECT MEETINGS

- A. The Architect shall schedule and meet regularly with the Owner, the Owner's Project Manager and the Construction Manager at the site of the Work during the course of the Contract for the purpose of progress review, coordination of Shop Drawing schedules, sample submittals, and other items of work requiring such coordination. The dates of such meetings shall be as mutually agreed upon between the Owner, the Owner's Project Manager, Construction Manager and the Architect. Construction Manager shall require Subcontractors to attend such meetings if requested by the Architect.
- B. The Construction Manager shall take minutes of such meetings and shall distribute copies of the minutes to all concerned.
- C. Construction Manager's and Subcontractor's representatives attending such meetings shall include the job superintendent or other responsible party approved by the Architect. Such representatives shall be empowered to make, at these meetings, definite decisions binding upon their respective employers regarding all matters pertaining to work under this Contract.
- D. The Construction Manager shall furnish the Owner, the Owner's Project Manager and the Architect, in writing, the names, addresses, and telephone numbers of Construction Manager's and principal Subcontractors' personnel to be contacted in the event of an out-of-hours emergency at the building site. He shall also maintain a similar list readily visible from the outside of the field office.
- E. The CM shall provide a 3-week lookahead schedule. Where activities on this schedule are included in the complete and detailed construction schedule, they should be referenced by the same name and activity numbers. This schedule shall also include the look ahead from the previous week's schedule for confirmation/realization of construction schedule dates.

2.3 PREINSTALLATION CONFERENCES

- A. Pre-Installation Conferences: Conduct pre-installation conferences at site prior to construction activities that require coordination.
 - 1. Schedule the conference to occur after submittals have been approved for the materials or systems.
 - 2. Installers, manufacturer's representatives, and fabricators of materials or systems affected shall be required to attend. Advise Architect of scheduled meeting dates.
 - Do not allow affected work to proceed if the conference cannot be successfully concluded. Initiate actions necessary to resolve impediments to performance of the work and reconvene the conference at the earliest feasible date.
 - 4. The Construction Manager shall take minutes of such meetings & shall distribute copies of the minutes to all concerned.
- B. Work for which pre-installation conferences will be required include the following. Additional pre-installation conferences may be required by specifications in Sections 2 through 50, and

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

by the Owner or Architect during the progress of the Work:

- 1. Concrete work including finishes.
- 2. Steel erection.
- 3. Air barrier system.
- 4. Roofing.
- 5. Daylight dimming system.
- 6. Masonry.
- 7. Metal siding.
- C. Refer to individual specifications sections for additional requirements.

2.4 POST-CONSTRUCTION MEETINGS

- A. Not less often than every three months, starting with the date of Substantial Completion and continuing for one year thereafter, representatives of the Construction Manager and the Subcontractors for FIRE PROTECTION, PLUMBING, HVAC, and ELECTRICAL Work shall meet with the Architect and Owner's Project Manager at the site in accordance with an agreed-upon schedule in order to inspect the Work and to plan correction of any deficiencies or failures discovered during this period.
- B. Representatives of the Construction Manager and Subcontractors attending such meetings shall be the same persons, or shall have the same powers and authority, as those attending job meetings prior to the date of Substantial Completion.
- C. Post-Warranty Meeting: Coordinate with Owner and attend meeting to be held with Commissioning Agent.

D. The Construction the minutes to all of VI.7

The Construction Manager shall take minutes of such meetings & shall distribute copies of the minutes to all concerned.

END OF SECTION

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

SECTION 013200

CONSTRUCTION PROGRESS DOCUMENTATION

PART 1 - GENERAL

- 1.1 GENERAL PROVISIONS
 - A. Attention is directed to Division 00 PROCUREMENT AND CONTRACTING REQUIREMENTS and DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.
 - B. Examine all other Sections of the Specifications for requirements that affect work of this Section, whether or not such work is specifically mentioned in this Section.
 - C. Coordinate Work with that of all other trades affecting or affected by Work of this Section. Cooperate with such trades to assure the steady progress of all Work under the Contract.

1.2 SUMMARY

- A. The Work of this Section includes, but is not limited to, requirements for the following procedures:
 - 1. Time for Completion and Liquidated Damages.
 - 2. Sequencing requirements.
 - 3. Requirements for scheduling closeout activities.
 - 4. Critical Path Method Schedule preparation and submission.
 - 5. Photographic documentation of construction.
- B. Related work includes, but is not limited to, the following work under other Sections:
 - 1. Section 011100 SUMMARY OF WORK: Hours of work and related scheduling criteria.
 - Section 012400 SCHEDULE OF VALUES: Allocation of portions of the Work as line items in applications for payment.
 - 3. Section 013100 PROJECT MANAGEMENT AND COORDINATION: Construction Manager responsibility for coordinating the Work.
 - 4. Section 013119 PROJECT MEETINGS: Scheduling construction-related meetings.
 - 5. Section 013300 SUBMITTAL PROCEDURES: Coordination of submittal schedule with construction.
 - 6. Section 014000 QUALITY REQUIREMENTS: Special sequencing requirements required for inspection of building components prior to concealment.
 - 7. Section 017700 CLOSEOUT PROCEDURES: Requirements for Substantial Completion and Final Completion.

1.3 A to C should be struck, it is governed by section VI of GCs to owner agreement.

1.3 SUBMITTALS

A. Preliminary Construction Schedule and Schedule Narrative: Within 10 calendar days following re-

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

ceipt of the Notice to Proceed for GMP Number 1, submit a CD containing an electronic copy (PRX) and two paper copies for review by the Owner, Project Manager and the Architect. This preliminary schedule and schedule narrative shall include the project contract dates, milestones, long lead items, major work activities and a critical path to completion.

- 1. Acceptance of the Preliminary Construction Schedule by the Owner's Project Manager and Architect shall be a prerequisite to certification of the first Application for Payment.
- B. Complete and Detailed Construction Schedule: Within 60 calendar days following receipt of the Notice to Proceed of the Final GMP submit a CD containing an electronic copy(PRX) and two paper copies of the complete and detailed schedule to show entire schedule for entire construction period.
 - Acceptance of the Complete and Detailed Construction Schedule by the Owner, Project Manager and Architect shall be a prerequisite to certification of the second Application for Payment.
 - 2. The Complete and Detailed Construction Schedule shall be the project baseline target schedule from which future schedule progress will be compared and measured.
 - 3. The Complete and Detailed Construction Schedule shall be the basis for monthly updates and three week look ahead schedules for the weekly meetings.
- C. Monthly Schedule Update: By the end of the first week of the month submit a schedule update of the accepted Complete and Detailed Construction Schedule accompanied by a written narrative reporting on the progress of the Work for the prior month and a CD containing an electronic copy (PRX) and two paper copies of the Monthly Schedule Update.
 - 1. Acceptance of the Updated Schedule each month by the Owner's Project Manager and Architect shall be a prerequisite to payment of the monthly Application for Payment.
 - The schedule report and updates shall be submitted in the following formats: Milestone summary showing baseline start and finish dates. Full schedule sorted by early start and by area.
- D. Daily Construction Field Reports: Submit one copy of the current week's field reports to the Owner's Project Manager and the Architect at the end of each week. (Electronic submission is acceptable)

within 1 week

- E. Special Reports: Submit one copy of special reports of unusual events at the site directly to Owner's Project Manager and a copy to the Architect, on the day of the occurrence. Distribute additional copies of report to parties affected by the occurrence. (Electronic submission is acceptable)
- F. Qualification Data: For Scheduling Consultant requirements, see paragraph 1.7.
- G. Photographs:
 - 1. Photographic documentation of construction as specified herein.
 - 2. Copies of prints: Submit electronic prints of each photographic view within seven days of taking photographs. Field Office Prints: Retain electronically one set of prints of progress photographs in the field office at Project site, available at all times for reference. Identify photographs same as for those submitted to Architect. Photos are taken daily and posted to

procore, thats it, no hard copies or separate files, they are in procore.

Strike entire sectin 1.4, its governed

by owner agreement.

BROOKLINE HIGH SCHOOL EXPANSION

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- 3. Identification: On each print file, provide the following information: Name of Project. Date photograph was taken if not date stamped by camera. Unique sequential identifier.
- 4. Key Plan: Submit key plan of Project site and building with notation of vantage points marked for location and direction of each photograph. Indicate elevation or story of construction. Include same label information as corresponding set of photographs.

1.4 **TIME FOR COMPLETION AND LIQUIDATED DAMAGES**

- A. It is understood and mutually agreed, by and between the Construction Manager and the Owner, that the date of commencement and the time for completion for each phase are essential conditions of this Contract, and it is further mutually understood and agreed that the Work embraced in this Contract shall be commenced by the date specified therein.
- B. The Construction Manager agrees that said Work shall be prosecuted regularly, diligently, and uninterruptedly at such rate of progress as will insure full completion thereof within the time specified. It is expressly understood and agreed, by and between the Construction Manager and the Owner, that the time for the completion of the Work in each phase described herein is a reasonable time for the completion of the same, taking into consideration the usual industrial and climatic conditions prevailing in this locality.
- C. It is further agreed that time is of the essence of each and every portion of the Contract and of the Contract Documents wherein a definite and certain length of time is fixed for the performance of any act whatsoever; and where under the Contract an additional time is allowed for the completion of any work, the new limit fixed by such extension shall be of the essence of this Contract. Provided, that the Construction Manager shall not be charged with liquidated damages for any excess cost when the delay in completion of the Work is due:
 - 1. To any preference, priority, or allocation order duly issued by the Awarding Authority.
 - 2. To unforeseeable causes beyond the control and without the fault or negligence of the Construction Manager, including, but not restricted to: Acts of God, or of the public enemy; acts of the Owner; acts of another Construction Manager in the performance of a Contract with the Owner; fires, floods, epidemics, quarantine restrictions, strikes, and freight embargoes.
 - 3. To any delays of Subcontractors or suppliers occasioned by any of the clauses specified.
- D. Provided, further, that the Construction Manager shall, within ten (10) days from the beginning of such delay, unless the Owner shall grant a further period of time prior to the date of final settlement of the Contract, notify the Owner, in writing, of the causes of the delay, who shall ascertain the facts and extent of the delay and notify the Construction Manager within a reasonable time of its decision in the matter.
- E. If the Construction Manager shall neglect, fail or refuse to substantially complete the Work within the time herein specified or any proper extension thereof granted by the Owner, the Construction Manager does hereby agree, as part of the consideration for the awarding of this Contract, to pay to the Owner the amount specified in the Agreement (or if not specified, then actual damages amount), not as a penalty but as liquidated damages for such breach of contract as herein set forth, for each and every calendar day that the Construction Manager shall be in default after the time stipulated in the Contract for completing the Work.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- F. The said amount is fixed and agreed upon by and between the Construction Manager and the Owner because of the impracticability and extreme difficulty of fixing and ascertaining the actual damages the Owner would in such event sustain, and said amount is agreed to be the amount of damages which the Owner would sustain and said amount shall be retained from time to time by the Owner from current periodic estimates. This remedy to the Owner shall be cumulative to the remedies available to the Owner under law.
- G. Work Executed after Substantial Completion: The Architect will continue to execute their administrative responsibilities for the Contract, as provided in the General Conditions, beyond the specified date of Final Completion.
 - If, due to delays on the Construction Manager's part in the completion of the Work, the Architect and Owner's Project Manager is required to continue in this role beyond the specified date for Final Completion, the Construction Manager shall be responsible to the Owner for costs for Additional Services of the Architect and Owner's Project Manager to perform additional administration duties, until the Work is complete.
 - 2. Refer to Section 011400 Work Restrictions, for procedures required in cases where Construction Manager is responsible to the Owner for costs for Additional Services of the Architect.
- H. Liquidated Damages: Refer to the OWNER/ CONSTRUCTION MANAGER AGREEMENT, as amended, for provisions for, and amounts of, Liquidated Damages.

1.5 SEQUENCING REQUIREMENTS

- A. Exterior Envelope Construction and Inspection: Schedule the installation of materials comprising the exterior walls and roofs to minimize exposure of construction materials to damage by ultraviolet light, wind and weather. Notify the Architect prior to concealment of air barrier, to permit inspection and testing. Refer to Section 014000 – QUALITY REQUIREMENTS, and individual technical specification sections for specific requirements.
- B. Indoor Air Quality Provisions: Refer to Section 018119 INDOOR AIR QUALITY REQUIREMENTS, for the following activities that will have an impact on scheduling:
- strike, there are multiple ways to achieve LEED IAQ requirements and flush out may not be mandated.
- 1. Sequencing required to minimize adsorption of airborne contaminants on new surfaces.
- Sequence of building flush-out with respect to completion, testing and balancing of mechanical systems. Flush-out shall be complete prior to substantial completion.
- C. Commissioning: Refer to the Owner's commissioning agent, for inspections, testing and related activities to be performed by Commissioning Agent during and after construction.

1.6 SCHEDULING REQUIREMENTS FOR CLOSEOUT

A. General: Closeout scheduling shall be carefully coordinated with activities required for Commissioning and the approved Indoor Air Quality Management Plan. The following sequence of activities is a summary of requirements of many trades. Refer to other Division 1 Sections and Technical Sections for additional information as indicated.

REVISION: FB-005 - GMP Bid Set - AUGUST 1, 2019

В.	Initial Closeout Activities:	
Strike, will be done per CX specs. CX agent is responsible for scheduling meetings.	 Commissioning Coordination Meeting: Schedule meeting well in advance of anticipated date for start-up of mechanical and electrical systems. At this meeting, the Commissioning Firm will distribute Pre-Functional Performance Test (PFPT) checklists, and scheduling require- ments will be reviewed. Refer to Section 013119 – PROJECT MEETINGS. Confirmation of Completion of Finishes, Casework and Cleaning: The Construction Manager submit a letter confirming that all major finishes have been applied, all casework is installed and final cleanup has been completed. 	
C.	System Start-Up, Building Flush-out and Testing and Balancing.	
strike, there are multiple ways to achieve LEED IAQ requirements and flush out may not be mandated.	Befer to Section 230000 – Heating Ventilating and Air Conditioning for additional require-	
	 ments for system operation. Flush-out shall be complete prior to substantial completion. 3. Testing and Balancing: After the building flush-out is complete, replace HVAC system filters, adjust HVAC system for normal operation and conduct tests for balancing the system. 	
strike, this will be D. done per owner agreement	Substantial Completion: When system start-up and the related activities specified above have been completed on all mechanical and electrical systems, notify the Architect that the Project is Substantially Complete. Refer to Section 017700 –CLOSEOUT PROCEDURES, for additional requirements for Substantial Completion.	
1.7	QUALIFICATIONS OF PERSONNEL FOR CPM SCHEDULING with in house employees and have not included the cost to hire aconsultant.	
A.	The Construction Manager will engage, at the Construction Manager's own expense, a qualified CPM Scheduling Consultant (hereinafter "Scheduling Consultant"), approved by the OPM, to assist in the preparation and production of the CPM Schedule. The Construction Manager may perform these services with the Construction Manager's own organization if the qualifications of assigned staff are approved by the Owner.	o, specs ready
part-time; B. refer to	The Scheduling Consultant, or the Construction Manager's assigned staff, shall meet the state following criteria:	ates you re able to o this
GCs	1. Has at least one tall time employee skilled in the application of computerized CPM network in- techniques to construction projects of the magnitude and complexity of this project.	
	2. Has available computer equipment and software for the production of the required CPM network and reports.	
C.	Prior to engaging a Scheduling Consultant or commencing the performance of the Work required under this Section with the Construction Manager's own staff, the Construction Manager shall submit to the OPM for acceptance:	
	 The name and address of the proposed Scheduling Consultant, if used. Information sufficient to show that the proposed Scheduling Consultant, or the Construction Manager's own organization, has staff and computer facilities meeting the criteria specified in this Section. 	

PROJECT C – STEM WING ADDITION

EARLY PACKAGE #2: DEMOLITION, ABATEMENT & SITE ENABLING MARCH 1, 2019

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

3. A list of prior projects for which the proposed Scheduling Consultant, the Scheduling Consultant's organization, or the Construction Manager's staff has performed services similar to those required by this Contract.

PART 2 - PRODUCTS

- 2.1 CRITICAL PATH METHOD SCHEDULE (CPM) GENERAL
- A. The purpose of the Critical Path Method (CPM) Progress Schedules (hereinafter "CPM Schedule") shall be to:
 - 1. Assure adequate planning, scheduling and reporting during execution of the work by the Construction Manager.
 - 2. Assist the Construction Manager, Architect, Project Manager and Owner in monitoring the progress of the work and evaluating proposed changes to the Contract and the Construction schedule;
 - 3. Assist the Owner, Project Manager, Architect and the Construction Manager in the preparation and evaluation of the Construction Manager's monthly progress payments. CX schedule to be provided by CX agent then we can
 - 4. Ensure that the progress of any aspect of the project is reflected in the forecasted project completion date for the project as a whole. The CPM shall be fully integrated with all aspects of the project such as: detailed design, procurement, construction, and commissioning.
- B. The Construction Schedules shall employ the Critical Path Method (CPM) for the planning, scheduling and reporting of the work to be performed under the contract and shall meet the following requirements:
 - The schedule shall be developed and maintained utilizing the most current version of Primavera P6 Project Planner software system or alternative software program, at the Owner's discretion, and the data fully transferable to Primavera Project Planner.
 - 2. The Schedule shall be used by both the Construction Manager and the Owner with access granted to the Owner. The Schedule shall be reviewed and agreed to by the Owner and Construction Manager.
 - 3. For informational purposes only and to establish approximate values, the Complete and Detailed Construction Schedule will be accompanied by a monthly cash flow projection and a monthly man-hour projection. Planned billings and man-hours will be tracked against actual on a monthly basis.
 - 4. Provide Activity Logic Report with the submittal of the CPM schedule.
 - 5. The schedule and monthly updates shall also be furnished in its native electronic file format.
 - 6. Construction activity duration shall be in units of whole working days and shall be limited to a minimum of one (1) and a maximum of twenty (20) working days for each activity.
 - 7. The schedules and the corresponding completion dates shall meet the contract duration (remaining contract duration for the monthly updates) of the project. A CPM Schedule show-ing completions later that those specified shall be addressed in the Recovery schedule. Failure by the Construction Manager to include any element of work required for performance of the Contract shall not excuse the Construction Manager from completing all work

We may not be on most current platform. Program used is SKA discretion not owner.

Skanska has provided this w/GMP

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

within the Contract Time. Under no circumstances, shall the Construction Manager be entitled to an equitable adjustment in the event of failing to achieve an early completion schedule.

- 8. The Construction Manager shall review the planned activity coding and activity ID format with the Project Manager prior to the development of the Detailed Construction Schedule. At a minimum, the Project Manager will require the following coding: Area, Location/Phase, Work Type/Trade, and a separate code for each subcontractor.
- 9. The CPM shall be created and maintained with the following requirements:
 - 10. A unique activity identification number and description including all design activities, procurement activities, **submittal preparation and review activities**, **construction of mock-ups**, construction activities, startup and commissioning activities, turn-over and close-out activities.
 - b. Activity start and finish dates
 - c. Calendar ID: calendars will be reviewed and approved by all parties
- 11. Proposed durations assigned to each activity shall be the Construction Manager's best estimate of time required to complete the activity considering the scope and resources planned for the activity, utilizing the appropriate workday calendar.
- 12. Seasonal weather conditions shall be considered and included in the planning and scheduling of all work influenced by high or low ambient temperatures and/or precipitation to ensure completion of all work within the Contract time. Seasonal weather conditions shall be determined by an assessment of average historical climatic conditions based upon the preceding ten (10) year records published for the locality by the National Ocean and Atmospheric Administration (NOAA).
- 13. The OPM's acceptance of the Construction Schedule shall not relieve the Construction Manager of responsibility for timing, planning and scheduling of the Work, nor impose any duty on the Architect or Owner with respect to the timing, planning or scheduling of the Work. Neither the review nor acceptance of the Construction Manager's CPM Schedule or other data submitted by the Construction Manager pursuant to this Section, nor any other action on the part of the Owner under this section shall in any way be deemed as a representation by the OPM that the Construction Manager can or will be permitted to follow a particular schedule or sequence of operations or that, by following any such schedule or sequence, he can or will complete the Work by the time(s) required by the Contract or by any other time(s). Nor shall the acceptance of any CPM Schedule or other such data relieve the Contractor of his obligation to complete the Work by the time(s) required in the Contract, even though such CPM schedule approved may be inconsistent with such completion.

C. Strike, owner agreement governs

No action on the part of the Construction Manager pursuant to this Section shall be construed as a request for an extension of the time(s) for completion required by the Contract. A request for an extension of time shall be deemed made only if it complies with the requirements of Division 1 of these specifications. No extension of the time(s) for completion shall be inferred because of any action, failure to act, or statement on behalf of the Owner pursuant to this Section.

D. The CPM Schedule developed by the Construction Manager may indicate an acceleration of the time(s) required for completion of the Contract. No acceleration of the time(s) for completion shall be construed as a request for an increase in the Contract Sum. Failure of the Construction Manager to meet an accelerated schedule shall not relieve the Construction Manager's obligation to perform all the Work by time(s) required by the Contract and in accordance with all other provisions of the Contract. Failure of the Construction Manager to meet an accelerated schedule shall not relieve the Contract Sum.

we currently have not included **12.** weather days, they would be treated as owner change. We could add them if desired.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

2.2 PRELIMINARY CONSTRUCTION SCHEDULE AND SCHEDULE NARRATIVE

- A. Within 10 calendar days following receipt of Notice to Proceed for GMP Number 1, prepare and submit for review prints and CD of the Preliminary Construction CPM Schedule and schedule narrative covering the first one hundred fifty (150) days following the Award of Contract. The schedule shall be neatly organized and plotted, time-scaled from left to right on standard size sheets. The Preliminary Construction Schedule and schedule narrative shall cover the following phases and/or activities:
 - 1. Proposed mobilization, procurement and planned construction within the first 150 days after Notice To Proceed.
 - 2. Include a summary bar for major areas of the remainder of the Work.
 - 3. Show the critical path for the project, indicating in the narrative, the major milestones and long-lead activities on the project.
- B. The Preliminary Schedule shall be incorporated into the Complete and Detailed Schedule including all revisions directed by the Owner, Project Manager and Architect.

2.3 COMPLETE AND DETAILED CONSTRUCTION SCHEDULE

Prepare and submit a comprehensive, fully developed Complete and Detailed CPM Construction Schedule within 60 days after Notice to Proceed of the Final GMP.

- 1. The Complete and Detailed schedule shall incorporate the accepted Preliminary Construction Schedule with the Owner/Project Manager/Architect's comments
- 2. Schedule shall be neatly organized and plotted time scaled from left to right on Project standard size sheets with suitable notation relating the interface points among sheets.
- 3. The Construction Manager's Schedule shall consist of, but not be limited to, the following:
 - a. Proposed procurement, submittal preparation, submittal review, fabrication & delivery, construction, testing, commissioning, and permitting activities.
 - b. Proposed durations for activities.
 - c. Proposed sequencing of activities (predecessors & successors).
 - d. Milestone events as agreed to by the Owner/CM including, but not limited to, Building Enclose, Permanent Power, Substantial Completion, and Final Completion.
- 4. The following shall be depicted on the Schedule for each activity:
 - a. Concise description of the work represented by the activity (maximum forty-eight (48) characters). The work related to each activity shall be limited to one work trade and one area.
 - b. In developing the Schedule, the Construction Manager shall be responsible for assuring that subcontractor and supplier work at all tiers, as well as its own work, is included in the Schedule. It shall be the Construction Manager's responsibility to obtain each Subcontractor's written approval and/or concurrence with the CPM Schedule.
 - c. The Schedule as developed shall show the sequence and interdependence of activities required for complete performance of the work. The Construction Manager shall be responsible for assuring that all work sequences are logical and the Schedule shows a coordinated plan of the work.
 - d. Each activity shall have only one responsible party and will be coded accordingly.
- 5. For the purposes of utilizing schedule targets, activity ID's shall not be modified.
- 6. Any change in logic shall be documented and presented for review by the Owner in the Monthly Schedule Update Report.

A. understood Owner Agreement takes precedence but these sections might still elaborate requirements of the CM

Strike 2.2 and 2.3. its

deverned by

agreement.

owner

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- 7. Any float suppression techniques identified shall be corrected by the Construction Manager.
- 8. The Construction Manager shall utilize logic, durations, and appropriate calendar assignment to forecast dates, not activity constraints.

2.4 MONTHLY SCHEDULE UPDATE REPORTS

Governed by monthly report section of owner agreement.

understood

precedence but

requirements of

these sections

might still elaborate

the CM

Owner Agreement

takes

Strike 2.4

- A. Monthly Schedule Update Report: Evaluate the status of the work each month to show actual progress and to identify problem areas. Update the Complete and Detailed Construction schedule and print a schedule summary. The update shall include a narrative of the changes from the previous version. Include approved Change Orders and Construction Change Directives within the updated schedule. The Construction Manager shall certify that both the CPM Schedule and Monthly Schedule Update Report submittal correctly represent the sequence, means, methods, techniques and procedures in which he/she plans to execute the Work, and the actual execution of the Work. All proposed sequencing changes shall be addressed and detailed within the narrative.
- B. Schedule review meetings shall be conducted on a monthly basis. The Construction Manager shall send the updated schedule to the Owner in advance of the update meetings.
- C. The Construction Manager is responsible for obtaining and validating all subcontractors' progress in terms of installed quantities and to ensure adherence to the schedule while identifying potential risks and their impacts. The monthly status submission shall not be submitted with "out of sequence" logic.
- D. The Construction Manager shall furnish sufficient forces, offices, facilities and equipment at no additional cost to the Owner, and shall work such hours as necessary, within any local restrictions or agreements incorporated into the Contract, to ensure the prosecution of the work in accordance with the current monthly Project Schedule Update. At weekly job meetings, documented in meeting notes, the CM shall review with the Owner the schedule progress and discuss mitigation of any delays. Should the monthly update show that the Critical Path is fourteen (14) or more calendar days behind the approved CPM schedule, the Construction Manager shall prepare a Recovery Schedule at no additional cost to the Owner explaining and displaying how the Construction Manager intends to reschedule the work in order to regain compliance with the contract. The provision of this paragraph may include the Construction Manager increasing the hours of work, the number of shifts, overtime operations and/or the amount of construction plant and equipment or working on Saturdays, Sundays and holidays, within agreed working hours or variance granted, provided the Construction Manager gives reasonable notice to the Owner.
- E. Tasks and activities on updates shall be referenced on weekly 3-week look ahead schedules.

2.5 RECOVERY SCHEDULE

Strike 2.5. A. Governed by owner agreement VI. When directed by the Project Manager/Architect, the Construction Manager shall develop a Recovery Schedule with a detailed narrative for all the remaining work based on the last accepted Monthly Schedule Update. The Recovery Schedule shall represent the Contractors current work sequence plan and shall forecast completion of the remaining work within remaining contract durations. The Recovery Schedule narrative shall enumerate the Construction Manager's work plan including increases to crew sizes and/or extended shifts to complete work with in remaining contract

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

durations. The Recovery Schedule shall conform to requirements set forth in Paragraph 1.04 (Complete and Detailed Construction Schedule).

B. Should the updates indicate that the project is falling behind schedule, or the Construction Manager's actual physical progress is falling behind schedule when compared with the current project schedule, the Construction Manager shall promptly take action to create a recovery plan. Following the update meeting where the schedule and or progress delays were made known to the Owner the Construction Manager shall submit a schedule recovery plan within a reasonable timeframe relative to the mitigation plan complexity. The recovery schedule and associated narrative shall be submitted as a proposed revision to the project schedule. The recovery schedule and narratives shall be submitted in accordance with all previous schedules and disclose any schedule and cost implications of the recovery plan. In the case of slippage which constitutes an emergency, the Construction Manager shall use all appropriate expediency measures to present the recovery plan to the Owner in advance of the above minimum requirements.

understood Owner Agreement takes precedence but these sections might still elaborate requirements of the CM

Strike 2.6. Governed by

agreement VI.

owner

The Construction Manager shall anticipate, avoid, and mitigate the effects of all delays, whether or not such delays involve Activities with positive float. The Construction Manager shall be responsible to develop mitigation measures for all delays, regardless of the responsibility for the delays, and to identify all time and cost impacts to the work associated with those mitigation measures. Whenever it is possible for the Construction Manager to mitigate delay without added cost, the Construction Manager shall do so. The Construction Manager shall mitigate all delays as efficiently and economically as possible, with the objective of minimizing both the time and cost impact of the delay.

D. Unless circumstances otherwise require, the Construction Manager shall not pursue mitigation action for which it expects the Owner/Architect to be liable, prior to notifying the Owner/Architect and receiving Owner/Architect authorization to proceed with the mitigation action. Any action taken by the Construction Manager prior to receiving approval from the Owner/Architect shall be at the Construction Manager's risk.

2.6 TIME IMPACT ANALYSIS FOR CHANGES, DELAYS AND CONTRACTOR REQUESTS

A. When changes are initiated or delays are experienced, or the Construction Manager desires to revise the CPM Schedule, the Construction Manager shall submit to the OPM and Architect a written Time Impact Analysis illustrating the influence of each change, delay, or Construction Manager request on any Milestone. Each Time Impact Analysis shall include Fragmentary Network (Network Analysis) demonstrating how the Contractor proposes to incorporate the change, delay, or Construction Manager request into the CPM Schedule. The Time Impact Analysis shall demonstrate the time impact to each and every affected Activity in the CPM Schedule utilizing the most recent CPM Schedule Update as the basis for the Analysis. The date of the most recent CPM Schedule shall be a date prior to the date the change is given to the Construction Manager, the date the delay occurred, or the date the Construction Manager submits the request for a change. The event time used in the Time Impact Analysis shall be included in the most recent CPM Schedule Update or as adjusted by mutual agreement. The Time Impact analysis shall include an electronic submittal which shall contain the details of the change including, but not limited to, added, changed, or deleted data for Activities, logic restraints, resources or costs.

B. Any and all claims for delay must be substantiated by proving an impact to the critical path based on the approved schedule. The schedule must show any activity items creating a delay that may be beyond the Owner's control and are concurrent in developing the Time Impact Analysis. Fail-

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

ure to submit a Time Impact Analysis will result in forfeiture for any claim arising thereof.

- C. Activity delays shall not necessarily mean that an extension of any Milestone is warranted or due the Contractor. A change or delay may not affect existing critical Activities or cause non-critical Activities to become critical. A change or delay may result in only absorbing a part of the available total float that may exist within an Activity chain of the Network, thereby not causing any effect on any Milestone.
- D. Total float is defined as the amount of time between the early start date and the late start date, or the early finish date and the late finish date, for each and every activity in the CPM Schedule. Float is not for the exclusive use or benefit of either the Owner (or its agents) or the Construction Manager or Subcontractors. Float will be used on a "first come, first serve" basis, provided that the claim for use is legitimate and proven by a Time Impact Analysis as defined herein.
- E. One copy of each Time Impact Analysis shall be submitted within 10 calendar days after the commencement of a delay or the notice of direction for a change is given to the Construction Manager.
- F. In cases where the Construction Manager does not submit a Time Impact Analysis within 10 calendar days, or make the Owner aware that the Time Impact Analysis will not be submitted within 10 calendar days, the Construction Manager agrees that the particular change, delay or Contractor request does not require an extension of time to a Milestone and the Construction Manager hereby waives its right to subsequently request a time extension.
- G. Acceptance or rejection of each Time Impact Analysis by the Owner shall be made within 10 calendar days after receipt unless subsequent meetings and negotiations are necessary. Upon acceptance, a copy of the Time Impact Analysis signed by the Owner shall be returned to the Construction Manager, and incorporated into the CPM Schedule at the next monthly CPM Schedule Update. The Time Impact Analysis shall be incorporated into and attached to any relevant Change Order(s).

2.7 DAILY CONSTRUCTION REPORTS

- A. (Prepare a daily construction report, recording events at the site. Report the following information, as applicable.)
 - 1. List of subcontractors at the site, and approximate count of personnel.
 - 2. High and low temperatures, general weather conditions (when exterior work is in progress)
 - 3. Meetings and significant decisions.
 - 4. Accidents, unusual events, and emergency procedures.
 - 5. Stoppages, delays, shortages, losses.
 - 6. Services connected, disconnected.
 - 7. Orders and requests of governing authorities.
 - 8. Equipment or system tests and start-ups.
 - 9. Partial Completions, occupancies.
 - 10. Substantial Completions authorized.
- B. At the end of each week, compile the daily reports. Have the Construction Manager's Superintendent sign the daily reports. Submit 1 copy to the Owner/Owner's Project Manager and place 1 copy in the Project Record Documents file. stored daily

on procore, no hard copy

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

2.8 3 WEEK LOOK-AHEAD

A. Provide a bar chart type, 3 week look-ahead schedule to review with the Owner's Project Manager and Architect during progress meetings. The 3 week look-ahead schedule furnished at the weekly meeting shall include the previous week look ahead for reference and record of realized items.

2.9 CONSTRUCTION PHOTOGRAPHS

- A. Digital Images: Provide images in JPG format, produced by a digital camera with minimum sensor size of 8 megapixels, and at an image resolution of not less than 3200 by 2400 pixels.
- B. General: Take photographs using the maximum range of depth of field, and that are in focus, to clearly show the Work. Photographs with blurry or out-of-focus areas will not be accepted.
 - 1. Maintain key plan with each set of construction photographs that identifies each photographic location.
- C. Digital Images: Submit digital images exactly as originally recorded in the digital camera, without alteration, manipulation, editing, or modifications using image-editing software.
 - 1. Date and Time: Include date and time in file name for each image.
 - 2. Field Office Images: Maintain one set of images accessible in the field office at Project site, available at all times for reference. Identify images in the same manner as those submitted to Architect and Owner.
- D. Preconstruction Photographs: Before starting construction, take photographs of Project site and surrounding properties, including existing items to remain during construction, from different vantage points, as directed by Architect.
 - 1. Take adequate photographs, minimum of 100, or provide video, to show existing conditions adjacent to property before starting the Work.
 - 2. Take adequate photographs, minimum of 100, or provide video, of existing buildings either on or adjoining property to accurately record physical conditions at start of construction.
 - 3. Take additional photographs as required to record settlement or cracking of adjacent structures, pavements, and improvements.
- E. Periodic Construction Photographs: Take 20 photographs monthly, with timing to coincide with the cutoff date associated with each Monthly Schedule Update Report. Select vantage points, in cooperation with the Clerk of the Works, to show status of construction and progress since last photographs were taken.
- F. Final Completion Construction Photographs: Take 20 color photographs after date of Substantial Completion for submission as project record documents. Architect and Owner will inform photographer of desired vantage points. The photographer is Skanska project

The photographer is Skanska projecteam member, professional photos have not been included.

See prior comments regarding daily photos and procore

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

PART 3 - EXECUTION

3.1 SCHEDULING THE WORK

- A. The Construction Manager will coordinate, review and at all times be up to date with all aspects of the schedule and in so doing will:
 - 1. Highlight any areas of potential risk
 - 2. Confirm that the agreed interim milestones and target dates for completion can either be achieved, be improved upon or require corrective action.
 - 3. Be proactive in identifying delays and or lack of progress and in identifying prudent cost-effective means of addressing such delays and or progress issues.

END OF SECTION

acceptable that Procore form is being used i.l.o. WRA example Spec can be deleted. We are using forms produced by Procore.

Specification Section 013302 Submittal Transmittal

SUBMITTAL REVIEW TRANSMITTAL

Submittal No.: (GC Insert Submittal Number)

Project:	Brookline High School Expansion	Contract For: New Construction
Prepared By:	(GC Insert General Contractor's Project Manager & Company Name)	To: William Rawn Associates, Architects, Inc.
Subcontractor:	(GC Insert Subcontractor's Contact & Company Name)	Contractor's Reference (GC Insert Date) Date from Submittal Schedule:
Specification Reference:	(GC Insert Section and paragraph number)	Date Due Back to (GC Insert Date) Contractor from Submittal Schedule:
Submittal Type:	(GC Select - Product Data, Certification, Test Report, Shop Drawing, Sample, etc.)	Date Received by Architect: (Arch Insert Date)
Submittal Title:	(GC Insert Submittal Name)	Date Returned to (Arch Insert Date) Contractor:

General Contractor Review Comments:

(GC provide stamp and any applicable comments or notations in this box)

Architect/Consultant Review Comments:

(Architect/consultant provide stamp and any applicable comments or notations in this box)

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

SECTION 014000

QUALITY REQUIREMENTS

PART 1 - GENERAL

- 1.1 GENERAL PROVISIONS
 - A. Attention is directed to Division 00 PROCUREMENT AND CONTRACTING REQUIREMENTS and DIVISION 01 GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.
 - B. Examine all other Sections of the Specifications for requirements that affect work of this Section, whether or not such work is specifically mentioned in this Section.
 - C. Coordinate Work with that of all other trades affecting or affected by Work of this Section. Cooperate with such trades to assure the steady progress of all Work under the Contract.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for
 - 1. Quality assurance
 - 2. Quality control
- B. Testing and inspecting services are required to verify compliance with requirements specified or indicated. These services do not relieve Construction Manager of responsibility for compliance with the Contract Document requirements.
 - 1. Specific quality-assurance and -control requirements for individual construction activities are specified in the Sections that specify those activities. Requirements in those Sections may also cover production of standard products.
 - 2. Specified tests, inspections, and related actions do not limit Construction Manager's other quality-assurance and -control procedures that facilitate compliance with the Contract Document requirements.
 - 3. Requirements for Construction Manager to provide quality-assurance and -control services required by Architect, Owner, or authorities having jurisdiction are not limited by provisions of this Section.
 - 4. A pre-construction "kickoff" meeting regarding testing requirements shall be scheduled and shall be attended by: the GC or CM and all applicable Trade/Sub Construction Managers, the Testing Agency, the Architect, OPM/Clerk of the Works, Structural Engineer, Geotechnical Engineer.

1.3 DEFINITIONS

A. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work to guard against defects and deficiencies and substantiate that proposed

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

construction will comply with requirements.

- B. Quality-Control Services: Tests, inspections, procedures, and related actions during and after execution of the Work to evaluate that actual products incorporated into the Work and completed construction comply with requirements. Services do not include contract enforcement activities performed by Architect.
- C. Mockups: Full-size, physical assemblies that are constructed on-site. Mockups are used to verify selections made under sample submittals, to demonstrate aesthetic effects and, where indicated, qualities of materials and execution, and to review construction, coordination, testing, or operation; they are not Samples. Approved mockups establish the standard by which the Work will be judged.
- D. Laboratory Mockups: Full-size, physical assemblies that are constructed at testing facility to verify performance characteristics.
- E. Preconstruction Testing: Tests and inspections that are performed specifically for the Project before products and materials are incorporated into the Work to verify performance or compliance with specified criteria.
- F. Product Testing: Tests and inspections that are performed by a nationally recognized testing laboratory (NRTL) according to 29 CFR 1910.7; a testing agency accredited according to NIST's National Voluntary Laboratory Accreditation Program (NVLAP), or a testing agency qualified to conduct product testing and acceptable to authorities having jurisdiction, to establish product performance and compliance with industry standards.
- G. Source Quality-Control Testing: Tests and inspections that are performed at the source, i.e., plant, mill, factory, or shop.
- H. Field Quality-Control Testing: Tests and inspections that are performed on-site for installation of the Work and for completed Work.
- I. Testing Agency: An entity engaged to perform specific tests, inspections, or both. Testing laboratory shall mean the same as testing agency.
- J. Installer/Applicator/Erector: Construction Manager or another entity engaged by Construction Manager as an employee, Subcontractor, or Sub-subcontractor, to perform a particular construction operation, including installation, erection, application, and similar operations.
 - 1. Using a term such as "carpentry" does not imply that certain construction activities must be performed by accredited or unionized individuals of a corresponding generic name, such as "carpenter." It also does not imply that requirements specified apply exclusively to tradespeople of the corresponding generic name.
- K. Experienced: When used with an entity, "experienced" means having successfully completed a minimum of five previous projects similar in size and scope to this Project; being familiar with special requirements indicated; and having complied with requirements of authorities having jurisdiction.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

1.4 CONFLICTING REQUIREMENTS

Strike. Governed by Owner agreement order of precedence

- A. General: If compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent requirement. Refer uncertainties and requirements that are different, but apparently equal, to Architect for a decision before proceeding.
- B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Architect for a decision before proceeding.

1.5 SUBMITTALS

- A. Qualification Data: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.
- B. Testing and Inspection Log: Submit updated copy of log each month with the Application for Payment. Log is kept on Procore and available for everyone, every day. It will not be submitted monthly with pay app.
- C. Reports: Prepare and submit certified written reports that include the following:
 - 1. Date of issue.
 - 2. Project title and number.
 - 3. Name, address, and telephone number of testing agency.
 - 4. Dates and locations of samples and tests or inspections.
 - 5. Names of individuals making tests and inspections.
 - 6. Description of the Work and test and inspection method.
 - 7. Identification of product and Specification Section.
 - 8. Complete test or inspection data.
 - 9. Test and inspection results and an interpretation of test results.
 - 10. Record of temperature and weather conditions at time of sample taking and testing and inspecting.
 - 11. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.
 - 12. Name and signature of laboratory inspector.
 - 13. Recommendations on retesting and reinspecting.
- D. Permits, Licenses, and Certificates: For Owner's records, submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents, established for compliance with standards and regulations bearing on performance of the Work.

1.6 QUALITY ASSURANCE

A. General: Qualifications paragraphs in this Article establish the minimum qualification levels required; individual Specification Sections specify additional requirements.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- B. Installer Qualifications: A firm or individual experienced in installing, erecting, or assembling work similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful in-service performance.
- C. Manufacturer Qualifications: A firm experienced in manufacturing products or systems similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.
- D. Fabricator Qualifications: A firm experienced in producing products similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.
- E. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or product that are similar to those indicated for this Project in material, design, and extent.
- F. Specialists: Certain sections of the Specifications require that specific construction activities shall be performed by entities who are recognized experts in those operations. Specialists shall satisfy qualification requirements indicated and shall be engaged for the activities indicated.
 - 1. Requirement for specialists shall not supersede building codes and regulations governing the Work.
- G. Testing Agency Qualifications: An NRTL, an NVLAP, or an independent agency with the experience and capability to conduct testing and inspecting indicated, according to ASTM E 329; and with additional qualifications specified in individual Sections; and where required by authorities having jurisdiction, that is acceptable to authorities.
 - 1. NRTL: A nationally recognized testing laboratory according to 29 CFR 1910.7.
 - 2. NVLAP: A testing agency accredited according to NIST's National Voluntary Laboratory Accreditation Program.
- H. Factory-Authorized Service Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.
- I. Preconstruction Testing: Where testing agency is indicated to perform preconstruction testing for compliance with specified requirements for performance and test methods, comply with the following:
 - 1. Construction Manager responsibilities include the following:
 - a. Provide test specimens representative of proposed products and construction.
 - b. Submit specimens in a timely manner with sufficient time for testing and analyzing results to prevent delaying the Work.
 - c. Provide sizes and configurations of test assemblies, mockups, and laboratory mockups to adequately demonstrate capability of products to comply with performance requirements.
 - d. Build site-assembled test assemblies and mockups using installers who will perform same tasks for Project.
 - e. Build laboratory mockups at testing facility using personnel, products, and methods of

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

construction indicated for the completed Work.

- f. When testing is complete, remove test specimens, assemblies, mockups, and laboratory mockups; do not reuse products on Project.
- 2. Testing Agency Responsibilities: Submit a certified written report of each test, inspection, and similar quality-assurance service to Architect, with copy to Construction Manager. Interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from the Contract Documents.
- J. Mockups: Before installing portions of the Work requiring mockups, build mockups for each form of construction and finish required to comply with the following requirements, using materials indicated for the completed Work:
 - 1. Build mockups in location and of size indicated or, if not indicated, as directed by Architect.
 - 2. Mock-ups shall be constructed by same personnel assigned to the project construction.
 - 3. Coordinate the work of multiple subcontractors as needed to build complete mockups of multi-component systems.
 - 4. Notify Architect seven days in advance of dates and times when mockups will be constructed.
 - 5. Demonstrate the proposed range of aesthetic effects and workmanship.
 - 6. Perform field tests on mock-up panels to show compliance with requirements as specified in individual sections. At a minimum, perform air leakage and water infiltration testing.
 - 7. Obtain Architect's approval of mockups before starting work, fabrication, or construction. a. Allow seven days for initial review and each re-review of each mockup.
 - 8. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.
 - 9. Demolish and remove mockups when directed, unless otherwise indicated.
- K. Laboratory Mockups: Comply with requirements of preconstruction testing and those specified in individual Sections in Divisions 2 through 50.

1.7 QUALITY CONTROL – OWNER RESPONSIBILITIES

- A. General: Where quality-control services are indicated as Owner's responsibility in individual specification sections, Owner will engage a qualified testing agency to perform these services.
 - 1. Testing, inspections and commissioning performed by the Owner or the Owner's agents in no way reduces the responsibility of the Construction Manager to meet performance requirements, descriptive criteria and all other requirements of the specifications, nor do these activities on the part of the Owner relieve the Construction Manager from performing Quality Assurance and Quality Control measures specified.
- B. Tests and Inspections: The Owner reserves the right to employ consultants and testing agencies to test the performance of the Work and to inspect the Work for conformance with the Contract Documents.
 - 1. Notice for Testing: The Construction Manager shall give the Owner a minimum 24-hour notice when installations that require testing are ready for testing or inspection.
 - a. Earlier notice shall be given where specified in a given technical section of the Specifications.
 - b. If the Owner's testing agency arrives at the site to test the performance of the work, and

Specific colors as selected by Architect, not range. No testing on mock ups, only for constructibilit y and quality standard.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

determines that the installation is not ready for testing or inspections, then the Construction Manager shall be responsible for the costs of the testing agency's site visit

- 2. Availability of Test Results: The results of such tests and inspections will be made available to the Architect and Construction Manager.
- 3. Correction of Work:
 - a. Where results demonstrate deficiencies in the Work, the Construction Manager shall take all actions necessary to correct the Work in a timely manner at their own expense.
 - b. When the Construction Manager considers the Work to be corrected, further tests and inspections will be performed by the Owner's consultants and testing agencies at the Construction Manager's expense.
- C. Owner will furnish Construction Manager with names, addresses, and telephone numbers of testing agencies engaged and a description of types of testing and inspecting they are engaged to perform.
- D. Costs for retesting and reinspecting construction that replaces or is necessitated by work that failed to comply with the Contract Documents will be charged to Construction Manager, and the Contract Sum will be adjusted by Change Order.

1.8 QUALITY CONTROL – CONSTRUCTION MANAGER RESPONSIBILITIES

- A. Tests and inspections not explicitly assigned to Owner are Construction Manager's responsibility. Unless otherwise indicated, provide quality-control services specified and those required by authorities having jurisdiction. Perform quality-control services required of Construction Manager by authorities having jurisdiction, whether specified or not.
 - 1. Where services are indicated as Construction Manager's responsibility, engage a qualified testing agency to perform these quality-control services.
 - a. Construction Manager shall not employ same entity engaged by Owner, unless agreed to in writing by Owner.
 - 2. Notify testing agencies at least 24 hours in advance of time when Work that requires testing or inspecting will be performed.
 - 3. Where quality-control services are indicated as Construction Manager's responsibility, submit a certified written report, in duplicate, of each quality-control service.
 - 4. Testing and inspecting requested by Construction Manager and not required by the Contract Documents are Construction Manager's responsibility.
 - 5. Submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.
 - B. Manufacturer's Field Services: Where indicated, engage a factory-authorized service representative to inspect field-assembled components and equipment installation, including service connections. Report results in writing as specified in Division 1 Section "Submittal Procedures."
 - C. Retesting/Reinspecting: Regardless of whether original tests or inspections were Construction Manager's responsibility, provide quality-control services, including retesting and reinspecting, for construction that replaced Work that failed to comply with the Contract Documents.
 - D. Testing Agency Responsibilities: Cooperate with Architect and Construction Manager in

Page 205 of 377

Other than our own QAQC manual and project staff, we have not included costs for any testing and inspection. We could add that cost and service to the GMP if desired.

REVISION: FB-005 - GMP Bid Set - AUGUST 1, 2019

performance of duties. Provide qualified personnel to perform required tests and inspections.

- 1. Notify Architect and Construction Manager promptly of irregularities or deficiencies observed in the Work during performance of its services.
- 2. Determine the location from which test samples will be taken and in which in-situ tests are conducted.
- 3. Conduct and interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from requirements.
- 4. Submit a certified written report, in duplicate, of each test, inspection, and similar qualitycontrol service through Construction Manager.
- 5. Do not release, revoke, alter, or increase the Contract Document requirements or approve or accept any portion of the Work.
- 6. Do not perform any duties of Construction Manager.
- E. Associated Services: Cooperate with agencies performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as requested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:

Labor is NIC unless WRA can specify what that is and we can price it and add to GMP

- 1. Access to the Work.
- 2. Incidental labor and facilities necessary to facilitate tests and inspections.
- 3. Adequate quantities of representative samples of materials that require testing and inspecting. Assist agency in obtaining samples.
 - 4. Facilities for storage and field curing of test samples.
- 5. Delivery of samples to testing agencies.
- 6. Preliminary design mix proposed for use for material mixes that require control by testing agency.

Coordination: Coordinate sequence of activities to accommodate required quality-assurance and

-control services with a minimum of delay and to avoid necessity of removing and replacing

Security and protection for samples and for testing and inspecting equipment at Project site.

Need WRA or ToB to provide a schedule for this

for this work now

or exclude. Schedule times for tests, inspections, obtaining samples, and similar activities.

construction to accommodate testing and inspecting.

- G. Schedule of Tests and Inspections: Prepare a schedule of tests, inspections, and similar qualitycontrol services required by the Contract Documents. Submit schedule within 30 days of date established for the Notice to Proceed.
 - 1. Distribution: Distribute schedule to Owner, Architect, testing agencies, and each party involved in performance of portions of the Work where tests and inspections are required.
- PART 2 PRODUCTS (Not Used)
- PART 3 EXECUTION

7.

F.

- 3.1 TEST AND INSPECTION LOG
 - A. Prepare a record of tests and inspections. Include the following:
 - 1. Date test or inspection was conducted.

Only for tests and inspections by CM. ToB/WRA to keep log of tests and inspections they are responsible for.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- 2. Description of the Work tested or inspected.
- 3. Date test or inspection results were transmitted to Architect.
- 4. Identification of testing agency or special inspector conducting test or inspection.
- B. Maintain log at Project site. Post changes and modifications as they occur. Provide access to test and inspection log for Architect's reference during normal working hours.

3.2 REPAIR AND PROTECTION

- A. General: On completion of testing, inspecting, sample taking, and similar services, repair damaged construction and restore substrates and finishes.
 - 1. Provide materials and comply with installation requirements specified in other Specification Sections. Restore patched areas and extend restoration into adjoining areas with durable seams that are as invisible as possible.
 - 2. Comply with the Contract Document requirements for Section 017329 CUTTING AND PATCHING.
- B. Protect construction exposed by or for quality-control service activities.
- C. Repair and protection are Construction Manager's responsibility, regardless of the assignment of responsibility for quality-control services. We can't agree to this for testing done by others unless ToB/WRA can provide a scope for us to price and include in GMP

END OF SECTION

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

SECTION 014200

REFERENCES

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

- A. Attention is directed to Division 00 PROCUREMENT AND CONTRACTING REQUIREMENTS and DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.
- B. Examine all other Sections of the Specifications for requirements that affect work of this Section, whether or not such work is specifically mentioned in this Section.
- C. Coordinate Work with that of all other trades affecting or affected by Work of this Section. Cooperate with such trades to assure the steady progress of all Work under the Contract.

1.2 DEFINITIONS

- A. General: Basic Contract definitions are included in the Conditions of the Contract.
- B. "Approved": When used to convey Architect's action on Contractor's submittals, applications, and requests, "approved" is limited to Architect's duties and responsibilities as stated in the Conditions of the Contract.
- C. "Directed": A command or instruction by Architect. Other terms including "requested," "authorized," "selected," "required," and "permitted" have the same meaning as "directed."
- D. "Indicated": Requirements expressed by graphic representations or in written form on Drawings, in Specifications, and in other Contract Documents. Other terms including "shown," "noted," "scheduled," and "specified" have the same meaning as "indicated."
- E. "Regulations": Laws, ordinances, statutes, and lawful orders issued by authorities having jurisdiction, and rules, conventions, and agreements within the construction industry that control performance of the Work.
- F. "Furnish": Supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.
- G. "Install": Operations at Project site including unloading, temporarily storing, unpacking, assembling, erecting, placing, anchoring, applying, working to dimension, finishing, curing, protecting, cleaning, and similar operations.
- H. "Provide": Furnish and install, complete and ready for the intended use.
- I. "Project Site": Space available for performing construction activities. The extent of Project site is shown on Drawings and may or may not be identical with the description of the land on which Project is to be built.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

1.3 INDUSTRY STANDARDS

- A. Applicability of Standards: Unless the Contract Documents include more stringent requirements, applicable construction industry standards have the same force and effect as if bound or copied directly into the Contract Documents to the extent referenced. Such standards are made a part of the Contract Documents by reference.
- B. Publication Dates: Comply with standards in effect as of date of the Contract Documents unless otherwise indicated.
- C. Copies of Standards: Each entity engaged in construction on Project should be familiar with industry standards applicable to its construction activity. Copies of applicable standards are not bound with the Contract Documents.
 - 1. Where copies of standards are needed to perform a required construction activity, obtain copies directly from publication source.
- D. Abbreviations and Acronyms for Standards and Regulations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the organizations responsible for the standards and regulations.

1.4 ABBREVIATIONS AND ACRONYMS

- A. Industry Organizations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities indicated in Thomson Gale's "Encyclopedia of Associations" or in Columbia Books' "National Trade & Professional Associations of the U.S."
- PART 2 PRODUCTS (Not Used)
- PART 3 EXECUTION (Not Used)

END OF SECTION 014200

BROOKLINE, MASSACHUSETTS

JANUARY 15, 2019

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

SECTION 014330

MOCKUPS

PART 1 - GENERAL

- 1.1 GENERAL PROVISIONS
 - A. Attention is directed to Division 00 PROCUREMENT AND CONTRACTING REQUIREMENTS and DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.
 - B. Examine all other Sections of the Specifications for requirements that affect work of this Section, whether or not such work is specifically mentioned in this Section.
 - C. Coordinate Work with that of all other trades affecting or affected by Work of this Section. Cooperate with such trades to assure the steady progress of all Work under the Contract.

1.2 SUMMARY

- A. General: Provide and coordinate mock-up assemblies at Project site for Architect's review and acceptance, in accordance with requirements of the Contract Documents. Refer to individual Specification Sections for mock-up requirements.
- B. Freestanding Mock-Up Schedule:
 - 1. Freestanding **constructability** mock-up of exterior wall, for visual and performance.
 - 2. Freestanding brick mockups, number as required by Architect for determination of final approved blend.
 - 3. Typical guardrail/handrail with steel channel provide one 2'-0" long section of the typical guardrail/handrail configuration for Stairs 1&2. Guardrail/handrail shall include steel channel stringer profile.
 - 4. (10) Total Paint color mockups (on 4'X4' square of drywall) for in-field review in order to facilitate selection of final paint colors.
- spec'd in Div 9 5. Terrazzo see sample review process in spec section 096620.
 - 6. Epoxy floor see sample review process in spec section 096710.
 - 7. Metal wall panels (interior) see sample review process in spec section 097813.
 - 8. Reception desk corner 3 linear feet
 - 9. New books millwork One 5 foot diameter piece
 - C. In-Place Mock-Up Schedule:
 - 1. Typical classroom fully finished (paint, flooring, ceiling, millwork, door, glazing, whiteboards, tack boards)
 - 2. Typical guardrail/handrail at Stair 1 or 2: provide in-place review of the first section installed in field, for review and approval prior to proceeding with the remainder of the installation.

BROOKLINE, MASSACHUSETTS

JANUARY 15, 2019

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- 3. Typical Level 01 Perimeter Bench provide in-place review of the first section of perimeter bench installed in the field (minimum 8ft long section). The finished mockup shall include all components of the perimeter bench and associated systems, including but not limited to the supply air ductwork, radiant heating element, structural supports, enclosure construction, and finish materials. This mockup shall be reviewed and approved prior to proceeding with the remainder of the installation.
- 4. Interior butt-glazed walls typical head condition. Provide in-place review of the first (2) panels of butt-glazed walls. In place mockup shall include the base and head track (including embedment of the track within the gypsum soffit walls) the interior glazing panels, and sealant joint between them. The mockup shall be reviewed and approved prior to proceeding with the remainder of the installation.
- 5. Paint (all colors) (4'x4' area) of final preferred colors.
- 6. Terrazzo 10'x10' square area of first work, for review and approval prior to proceeding with the remainder of the installation.
- 7. Porcelain floor tile and ceramic wall tile approximately 10sf area of first work, for review and approval prior to proceeding with the remainder of the installation.
- 8. Large format porcelain wall tile; (3) continuous full-height panels, for review and approval prior to proceeding with the remainder of the installation.
- 9. Full height markerboard panels; (3) continuous full-height panels, for review and approval prior to proceeding with the remainder of the installation.
- 10. ACM-1 and ACM-3 Ceiling Panels; (4) continuous hung panels, for review and approval prior to proceeding with the remainder of the installation. One of the (4) panels must include cut-out and installation of an F27 light fixture.
- D. It shall be the responsibility of the Contractor to coordinate the work of the related Specification Sections so that each mock-up meets the specified requirements.
- E. Sustainable Design Intent: Comply with project requirements intended to achieve certification, measured and documented according to the LEED Green Building Rating System, of the US Green Building Council. Refer to Section 018110 SUSTAINABLE DESIGN REQUIREMENTS, for certification level and certification requirements.
- F. Related Work: The following items are not included in this Section and are specified under designated Sections:
 - 1. Section 033000 Cast-in-place Concrete for constructability mockup foundation

1.3 DEFINITIONS

A. Freestanding Mock-Ups: Full-size, physical assemblies that are constructed on-site in a protected location.

Schedule does not permit changes to CD's as a result of mock ups.

- Freestanding mock-ups are not part of the final construction. Freestanding mock-ups will be used to verify selections made under sample submittals, to demonstrate aesthetic effects, qualities of materials and execution, and to review construction, coordination, testing, and operation.
- 2. Approved freestanding mock-ups establish the standard by which the Work will be judged.
 - 3. Approved freestanding mock-ups remain on site during the balance of construction and are demolished and removed from site at completion of the Work they represent.

BROOKLINE, MASSACHUSETTS

JANUARY 15, 2019

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- B. In-Place Mock-Ups: Full-size, physical assemblies that are constructed in-place and remain part of final construction.
 - 1. In-place mock-ups will be used to verify selections made under sample submittals, to demonstrate aesthetic effects, qualities of materials and execution, and to review construction, coordination, testing, or operation.
 - 2. Approved in-place mock-ups establish the standard by which the Work will be judged.
 - 3. Approved mock-ups remain part of the completed Work.
 - 4. Remove rejected work based on workmanship issues and rebuild mock-up at no additional cost to the Owner.

1.4 SUBMITTALS

- A. Schedule: Construction Manager shall submit a schedule of mock-up construction, including dates for mock-up review by the Architect.
 - 1. Mock-up schedule shall be reviewed at each progress meeting, revised and resubmitted as required.
 - 2. Schedule shall allow sufficient time for mock-ups which are not accepted to be reconstructed and reviewed until accepted by the Architect.
- B. Shop Drawings of Mock-Ups: Provide large scale shop drawings for fabrication, installation and erection of all parts of each mock-up. Provide plans, elevations, and details of anchorage, connections and accessory items.
- C. Photographs of Mock-Ups: Submit photographs of mock-ups after completion of installation and acceptance of each mock-up.
- D. Submittal Samples: Refer to individual Specification Sections for submittal requirements of mock-up components and coordinate accordingly.

1.5 QUALITY ASSURANCE

A. Design Modifications: Make design modifications to work only as required to meet performance requirements and to coordinate the work. Indicate proposed design modifications on shop drawings. Maintain original design concept without altering profiles and alignments indicated.

PART 2 - PRODUCTS

2.1 MATERIALS AND PRODUCTS

A. Provide materials, components, and products for mock-ups as specified in individual Specification Sections.

PART 3 - EXECUTION

3.1 GENERAL

A. Refer to PART 3, EXECUTION portions of the various Specification Sections for specific requirements regarding condition of surfaces, erection, and erection tolerances.

BROOKLINE, MASSACHUSETTS

JANUARY 15, 2019

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

3.2 FIELD MOCK-UP OF EXTERIOR WALL

- A. Provide a field mock-up of the exterior wall at location and in configuration indicated on Drawings. The exterior wall mock-up shall include the veneer systems and backup, one window and all related flashings and sealants, etc. Obtain Architect's acceptance of visual qualities prior to commencing work that individual mock-up is intended to represent. Protect and maintain approved mock-ups throughout the work of the Contract. Locate mock-ups at the Project site as directed by the Architect.
 - 1. Refer to Drawings for extent of the field mock-up.
 - 2. Provide modifications to mock-up as required until Architect's approval has been received.

3.3 FIELD MOCK-UP OF INTERIOR CONSTRUCTION

- A. Provide a field mock-up of the interior construction items at locations and in configuration indicated on Drawings or as otherwise directed. Obtain Architect's acceptance of visual qualities prior to commencing work that individual mock-up is intended to represent. Protect and maintain approved mock-ups throughout the work of the Contract. Locate mock-ups at the Project site as directed by Architect.
 - 1. Refer to Drawings for extent of the field mock-up.
 - 2. Provide modifications to mock-up as required until Architect's approval has been received.
- B. Interior Construction Mock-ups: Provide mock-ups of various interior construction as indicated or as specified in the applicable Specification Sections, as directed by the Architect.

3.4 INDIVIDUAL MOCK-UPS

- A. Provide individual mock-ups of types and sizes required by individual Specification Sections to evaluate and set the standard of quality for that work. Obtain Architect's acceptance of visual qualities prior to commencing work that individual mock-up is intended to represent. Protect and maintain approved mock-ups throughout the work of the Contract. Locate mock-ups at the Project site as directed by the Architect.
 - 1. Provide as many mock-ups as required until Architect's approval has been received.
 - 2. When indicated in individual Specification Sections, approved mock-ups may be incorporated into the finish work.

3.5 REPAIR AND PROTECTION

- A. General: On completion of testing, inspecting, sample taking, and similar services, repair and restore substrates and finishes.
 - 1. Provide materials and comply with installation requirements specified in other Specification Sections. Restore patched areas and extend restoration into adjoining areas with durable seams that are as non-visible as possible.

We can't agree to this for testing done by others unless ToB/WRA can provide a scope for us to price and include in GMP

B. Protect construction exposed by or for guality-control service activities.

BROOKLINE, MASSACHUSETTS

JANUARY 15, 2019

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

3.6 REMOVAL AND DISPOSAL

A. Demolish and remove mock-ups from site at the completion of the Project. Legally dispose of demolished mock-up materials. Comply with requirements of Section 017400 – CONSTRUCTION WASTE MANAGEMENT.

END OF SECTION

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

SECTION 015000

TEMPORARY FACILITIES AND CONTROLS

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

- A. Attention is directed to Division 00 PROCUREMENT AND CONTRACTING REQUIREMENTS and DIVISION 01 GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.
- B. Examine all other Sections of the Specifications for requirements that affect work of this Section, whether or not such work is specifically mentioned in this Section.
- C. Coordinate Work with that of all other trades affecting or affected by Work of this Section. Cooperate with such trades to assure the steady progress of all Work under the Contract.

1.2 SUMMARY

- A. The Work of this Section includes, but is not limited to, requirements for the following:
 - 1. Temporary facilities and services.
 - 2. Temporary water.
 - 3. Weather protection
 - 4. Temporary heating and ventilating
 - 5. Temporary humidity control.
 - 6. Temporary electricity and lighting
 - 7. Temporary telephone
 - 8. Temporary sanitary facilities
 - 9. Temporary fire protection
 - 10. Temporary stairs and ladders
 - 11. Temporary hoists and chutes
 - 12. Staging and scaffolding
 - 13. Temporary use of elevators
 - 14. Temporary enclosures
 - 15. Protection of work, property and the public
 - 16. Security of the work
 - 17. Rodent control.
 - 18. Water control
 - 19. Snow and ice control
 - 20. Construction fence
 - 21. Project signs
 - 22. Temporary offices

1.3 SUBMITTALS

A. General: Refer to Section 013300 – SUBMITTAL PROCEDURES, for submittal provisions

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

and procedures.

- B. Informational Submittals: Submit the following plans for temporary protection and facilities as specified in this Section:
 - 1. Weather protection plan
 - 2. Temporary humidity control procedures
 - 3. Temporary heating plan
 - 4. Temporary fire protection plan.

1.4 TEMPORARY FACILITIES AND SERVICES

- A. Construction Manager shall be responsible for arranging and providing temporary facilities and general services at the site as specified herein and as otherwise required for proper and expeditious prosecution of work. Except as otherwise specified, the Construction Manager shall pay costs for all temporary facilities and general services until Final Acceptance of the Work and shall remove same at completion of the Work.
- B. All such services and facilities shall comply with applicable Federal, State and local regulations.
- C. Construction Manager shall make all connections to existing services and sources of supply, shall provide all necessary installations, labor, materials, and equipment, in a manner subject to the approval of the Architect and the Owner, shall remove temporary installations and conditions when no longer required, and shall restore the services and sources of supply to proper operating condition as approved by the Architect.
- D. Discontinuance of any temporary service prior to the completion of any portions of the Work shall not render the Owner liable for any additional cost resulting therefrom.
- E. Should a change in location of any temporary equipment be necessary in order for the Work to progress properly, Construction Manager shall remove and relocate such equipment as required without additional cost to the Owner.
- F. Temporary Lot for Trailers: Construct temporary trailer lot shown on approved Logistics Plan for temporary use of Owner and Construction Manager during construction. Demolish temporary lot and restore area for permanent use as shown on Drawings.

1.5 TEMPORARY WATER

- A. Furnish potable water for construction purposes for trades at a point within 10 feet of building being constructed. Make arrangements and pay charges for water service installation, maintenance, and removal thereof, and pay costs of water for all trades. Table A states that water and sewer connection and usage is paid by ToB
- B. After installation, permanent water supply and distribution system may be used as source of water for construction purposes, provided that the Construction Manager pays applicablemunicipal water costs and assumes responsibility for damage to water distribution system and pays costs of restoration of system where so damaged.
- C. Temporary pipe lines and connections from the permanent service line, either outside or

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

within the building, necessary for the use of the Construction Manager and his Subcontractors shall be installed, protected and maintained at the expense of the Construction Manager.

- D. In addition to temporary lines and connections, the Construction Manager shall at the Construction Manager's expense install a temporary meter in a frostproof box in such location and in such manner as may be approved by the Architect. Per table A, by ToB. We can add the cost?
- E. Provide an adequate supply of drinking water from approved sources of acceptable quality, satisfactorily cooled, for Construction Manager's employees and those of his Subcontractors. Where required, furnish drinking water in suitable containers and provide single-service cups for use of employees. Drinking water dispensers shall be conveniently located in building where work is in progress.
- F. At completion of construction work, temporary water service equipment and piping shall be removed by Construction Manager.

1.6 WEATHER PROTECTION

- A. It is the intent of these Specifications to require the Construction Manager to provide temporary enclosures and heat to permit construction work to be carried on during the months of October through April and in compliance with Local General Laws. These Specifications are not to be construed as requiring enclosures or heat for operations that are economically infeasible to protect in the judgment of the Architect. Included in this category, without limitation, are such items as site work, excavation, pile driving, steel erection, erection of certain exterior wall panels, roofing, and similar operations.
- B. "Weather Protection" shall mean the temporary protection of that work adversely affected by moisture, wind and cold, by covering, enclosing and/or heating. This protection shall provide adequate working areas during the months of October through April consistent with the approved construction schedule to permit the continuous progress of all work necessary to maintain an orderly and efficient sequence of construction operations. The Construction Manager shall furnish and install all "weather protection" material and be responsible for all costs, including heating required to maintain temperature of 40 degrees F. at the working surface. This provision does not supersede any specific requirements for methods of construction, curing of materials or to performance obligations of the Construction Manager.

weather protection is means and methods.

- C. Within 30 calendar days after award of Contract, the Construction Manager shall submit in writing to the Architect for approval, three (3) copies of his proposed methods for weather protection.
- D. Installation of weather protection shall comply with all safety regulations including provisions for adequate ventilation and fire protection.
- E. Determination of extent of work to be performed during winter months shall be by the Construction Manager, with Owner's approval provided that work shall proceed at such a rate as to insure Substantial Completion on or before the stipulated date in accordance with the Progress Schedule.
- F. Be responsible for providing protection against damage to materials and work installed in freezing weather by providing special heat and coverings to prevent damage by the

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

elements. Protect the ground surfaces under footings, under pipelines, under masonry, under concrete and other work subject to damage, against freezing or ice formation. If low temperature makes it impossible to continue operations safely in spite of cold weather precautions, cease work, and so notify the Architect.

1.7 TEMPORARY HEATING AND VENTILATING

- Means and methods A. Within thirty (30) calendar days after commencement of work under this Contract, the Construction Manager shall submit in writing to the Architect for approval, three (3) copies of his method and time schedule for heating during construction, which shall concur with his general Progress Schedule.
 - B. Temporary weather-tight enclosures and temporary heating shall be provided by the Construction Manager as required during construction to make the building weather-tight and to protect work from freezing and frost damage. All costs of closing in buildings, and all costs of temporary heat shall be paid for by the Construction Manager until Substantial Completion.
 - C. Construction Manager shall provide for temporary heating and shall pay fuel costs for heating directly to the utility company. In areas of building where work is being conducted, temperature shall be continuously maintained as specified in Sections of Specifications but not less than 50 degrees F. nor more than 75 degrees F.
 - D. Furnish and install one accurate recording Fahrenheit thermometer at a place designated by the Owner, located as directed by the Owner in order to determine that the specified temperatures are being maintained.
 - E. When work has progressed sufficiently for installation of glazing, Construction Manager may, if approved by Architect, use glazed windows or curtainwall in place of temporary enclosures. Permanent glazing shall be protected against damage from mortar, cement, plaster, and other like items, and from damage by other trades; and upon completion of work shall be thoroughly cleaned, damaged component parts including glass shall be satisfactorily repaired or replaced, and windows and curtainwall left in perfect condition, prior to Substantial Completion.
 - F. Where building systems are inoperable, temporary heating shall be by smokeless portable unit heaters, steam generators or forced warm air heaters (UL, Factory Mutual, Fire Marshall approved), located outside building or vented to the outside. Construction Manager shall pay for fuel, maintenance and attendance required in connection with temporary heat. Surfaces, interior or exterior, damaged by use of these space heaters shall be replaced by new materials or be refinished to the satisfaction of the Architect without additional cost to the Owner. Use of oil burning "salamanders" is forbidden and nonvented open flame heaters will not be permitted inside after the building is closed in. Do not use propane-fueled heaters inside building or near stockpiles of combustible materials.
 - G. Make periodic inspections of the equipment and controls to insure proper operation of the system, as conditions require, and report any failings. Installation and operation of weather protection and heating devices shall comply with all safety regulations including provisions for adequate ventilation and fire protection.
 - H. Upon conclusion of temporary heating period, Construction Manager shall remove temporary piping, temporary radiators, other equipment and pay costs in connection with repairing

utility costs are allowances

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

damaged caused by installation or removal of temporary heating equipment and shall thoroughly clean and recondition those parts of permanent heating system used for temporary service.

- I. Provide adequate ventilation as required to keep temperature of building within 10 degrees of ambient outdoor temperature when such ambient temperature exceeds 70 degrees F., and to prevent accumulation of excess moisture in building. Refer to Section for Indoor Air Quality Control, for additional requirements for ventilation during construction
- 1.8 TEMPORARY HUMIDITY CONTROL
- GMP includes Allowance

A. Humidity Control of Enclosed Building: The Construction Manager shall install the following equipment to monitor and regulate relative humidity as required for the installation of all interior products. Humidity control equipment shall include, but not be limited to, the following:

- 1. Hygrometer: Provide one device to measure temperature and relative humidity in each construction area.
- 2. Dehumidifier, as required to maintain humidity of enclosed areas below 70%:
- 3. Fans: As required to eliminate significant variation in humidity levels within enclosed spaces.
- B. Schedule for Humidity Control: Relative humidity shall be maintained within the limits set by manufacturers of all interior materials and equipment. Refer to individual specification sections in Divisions 6, 9, 10, 11 and 12 for additional environmental requirements. No interior construction product shall be installed or applied prior to enclosure of building and installation of temporary humidity control measures.
- C. Within 30 calendar days after award of Contract, the Construction Manager shall submit in writing to the Architect for approval, three (3) copies of his proposed methods for humidity control.

1.9 TEMPORARY ELECTRICITY AND LIGHTING

- GMP includes Allowance
- A. Make arrangements as required with local electric company for temporary electric service, pay expenses in connection with installation, operation, and removal thereof, and pay cost of energy consumed by all trades until Substantial Completion of the building. Construction Manager shall make payments for electrical service directly to the electric company.
 - B. Take care not to overload equipment and lines. Provide and relocate temporary electric meters as required.
 - C. Power: Provide power distribution as required throughout new structure 120/208 volt, 3 phase, 60 cycle AC. Termination of power distribution shall be at one location in each major section of building, approximately at center. Termination shall be provided complete with circuit breakers, disconnect switches and other electrical devices as required to protect power supply system. Submit plan showing electrical distribution locations for Architect's approval.
 - D. Lighting: Temporary lighting system shall be furnished, installed and maintained by Construction Manager as required to satisfy minimum requirements of safety and security.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

Temporary lighting system shall afford general illumination in building areas and supply not less than one (1) watt per square foot of floor area for illumination in areas of building where work is being performed. Provide adequate outdoor lighting to illuminate staging, stockpiles, trenches, projections, office trailers and other like items, to the satisfaction of the Architect and Owner, and general illumination throughout adequate for watchmen and emergency personnel.

- E. Safety: All temporary equipment and wiring for power and lighting shall be furnished and installed in conformity with the National Electrical Code and in accordance with local ordinances and requirements of the municipal power authority. All temporary wiring and accessories shall be maintained in a safe manner and utilized so as not to constitute hazard to persons or property and shall be removed after they have served their purposes.
- F. When permanent electrical power and lighting systems are in operating condition, they may be used for temporary power and lighting for construction purposes, provided that Construction Manager obtains written approval of Architect and Owner. If permanent lighting fixtures are used in temporary light, provide new lamps for fixtures used for temporary light before Substantial Completion of the Work. In addition, provide the following:
 - 1. Replace lamps that burn-out.
 - 2. Replace lamps that get damaged.
 - 3. Limit hours of use of the lights as acceptable to Architect.
 - 4. Clean light fixtures during final cleaning. Lighting protective plastic wrap shall remain on light fixtures to the extent possible, until final cleaning.
- G. At completion of construction work, or at such time as Construction Manager makes use of permanent electrical installation, temporary wiring, lighting and other temporary electrical equipment and devices shall be removed by Construction Manager.

1.10 TEMPORARY TELEPHONE AND HIGH SPEED INTERNET

- A. Arrange with local telephone company to provide direct line telephone service at each construction site. Provide: At office trailers only
 - 1. One direct line instrument in Field Office for the Construction Manager with electronic answering machine.
 - Two direct line instruments in Field Office of the Clerk of the Works/OPM equipped with electronic answering machine; plus one direct line for facsimile machine in office. Turn over keys to Clerk of the Works, OPM and Architect.
 - 3. High Speed internet access, 6.0 Mbps minimum downstream speed, modem to accept the appropriate service provided, and wireless router via DSL, Broadband, Cable, or equal with unlimited internet access to the Field offices of the Construction Manager and Clerk of the Works/OPM.
 - 4. Other instruments at the option of the Construction Manager, or as required by regulations.
 - 5. Each Subcontractor shall make his own arrangements for telephone service.
- B. Pay for installation and removal of temporary telephones and facsimile lines and for all calls and fixed charges in connection therewith; including unlimited long-distance calling.
- C. Temporary telephone services shall be maintained until Final Completion of the Work.

REVISION: FB-005 - GMP Bid Set - AUGUST 1, 2019

1.11 TEMPORARY SANITARY FACILITIES

- A. Construction Manager shall provide an adequate number of toilet facilities with chemical type toilets and temporary lighting rented from and serviced by an approved company, as necessary for all persons engaged on the Work. Provide separate facilities for male and female workers.
- B. Toilets shall be erected in location approved by the Architect and Owner, shall be maintained by the Construction Manager in a clean and orderly condition in compliance with all local and State health requirements, and shall be removed at Substantial Completion of the Work.
- C. Permanent toilet facilities shall not be used by the Construction Manager, Subcontractors or any persons engaged by them during the course of work under this Contract

— without owner approval

1.12 TEMPORARY FIRE PROTECTION

To be provided in **A**. compliance with federal, state, local, osha and Skanska standards.

. Provide and maintain adequate temporary fire protection in the form of barrels of water with buckets, fire bucket tanks, fire extinguishers, or other effective means of extinguishing fire, ready for instant use, distributed around the Project and in and about temporary inflammable structures during construction of the Work. Provide one fire extinguisher for every 3,000 SF of the building area.

- B. Within 30 calendar days after award of Contract, the Construction Manager shall submit in writing to the Architect, three (3) copies of his proposed methods for fire protection that have been reviewed and approved by the local Fire Department. Post a copy of the approved fire protection plan in the Field Office for reference.
- C. Gasoline and other flammable liquids shall be stored in and dispensed from UL listed safety containers in conformance with National Board of Fire Underwriter's recommendations. Storage shall not be within building.
- D. Make arrangements for periodic inspection by local fire protection authorities and insurance underwriter's inspectors. Cooperate with said authorities and promptly carry out their recommendations.
- E. Tarpaulins used during construction work shall be made of material that is resistant to fire, water, and weather. Tarpaulins shall have UL approval and comply with FS-CCC-D-746.
- F. Torch-cutting and welding operations performed by Subcontractors shall have approval of Construction Manager before such work is started and chemical extinguisher shall be available within sight and not over ten (10) feet from location where such work is in progress.
- G. Do not light fires in or about premises.
- H. Comply with requirements in Section 011400 Work Restrictions.
- 1.13 TEMPORARY STAIRS AND LADDERS
 - A. Each trade shall provide its own ladders.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

B. All such apparatus, equipment and construction shall meet all requirements of Federal, State and local laws applicable thereto.

1.14 TEMPORARY LIFTS AND HOISTS

- A. Each trade shall provide its own lifts, hoists, including associated rigging, and conveyance apparatus.
- B. Construction, maintenance and operation of material hoists shall conform to applicable requirements of the "Standard Safety Code for Building Construction", ANSI; to AGC "Manual" requirements, OSHA, and to State and local regulations.
- C. Temporary lifts and hoists required for proper execution of work shall be properly maintained. Hoists shall be so constructed as to prevent damage, staining and marring of permanent work.
- D. Provide openings in slabs, roofs, walls and partitions, where required, for moving in large pieces of equipment. Close and restore openings and finish them after equipment is in place. Structural modification, shall be subject to prior written approval by the Architect.

1.15 TEMPORARY CHUTES

- A. The Construction Manager shall provide chutes for use by all trades.
- B. Temporary chutes, and similar items required for proper execution of Construction Manager's work and that of his Subcontractors shall be properly maintained. Use of such facilities by other contractors, subcontractors and trades shall be permitted as required by construction schedule. Chutes shall be so constructed as to prevent damage, staining and marring of permanent work.
- C. No materials, rubbish or debris, shall be permitted to drop free, but shall be removed by the use of material hoist and/or fully enclosed rubbish chute.

1.16 STAGING AND SCAFFOLDING

A. Responsibility for Staging:

The sub that provides it or the sub that uses someone else's is responsible

1. Each trade shall provide staging and scaffolding required for its work.

each Sub/Trade

- B. Construction Requirements for Staging: The Construction Manager is responsible for safety of staging and scaffolding, including but not limited to the following requirements:
 - 1. Staging shall be of approved design, erected and removed by experienced stage builders, and shall comply with all applicable OSHA standards.
 - 2. Provide accident prevention devices required by State and local laws.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

1.17 TEMPORARY USE OF ELEVATOR

Construction manager

- A. Trades shall make arrangements with Elevator Subcontractor for temporary use of elevator, during construction period, and for normal use by all trades and Subcontractors.
- B. Make arrangements for provision of temporary cab enclosure, car, car switches, gate contacts, power, signaling devices, temporary hoistway openings, protection of permanent hoistway entrances and other installed finished work, and pay for all such other items as are necessary to permit temporary operation in accordance with local, State and national codes.
- C. Arrange with Elevator Subcontractor for all necessary maintenance of elevator during period of temporary operation and for restoration of elevators to their original, perfect condition with guarantees as specified. All costs in connection with temporary operation of elevator shall be paid by the Construction Manager.
- D. Do not abuse, overload or otherwise damage elevators in temporary use for construction purposes.
- E. Elevator will be made available to the Owner for use during installation of FF&E, IT and Owner materials at no cost to the Owner. within the 3 months of elevator operation ca

1.18 TEMPORARY ENCLOSURES

within the 3 months of elevator operation carried in the GMP, during regular hours, as construction schedule allows and to be coordinated with CM.

- A. Provide temporary weathertight enclosure of exterior walls and roof openings as necessary to provide acceptable working conditions, provide weather protection for interior materials, allow for effective temporary heating, and to prevent entry of unauthorized persons.
- B. Sequence the work to avoid damage to materials. Where not possible, provide weatherproof enclosures. Materials and equipment delivered in weather resistant packaging should remain in that packaging until required for installation.
- C. Provide temporary exterior doors with self-closing hardware and padlocks. Permanent door enclosures shall not be used as temporary enclosures. Other enclosures shall be removable as necessary for work and for handling of materials.
- D. Refer to Section INDOOR AIR QUALITY CONTROL, for requirements for temporary interior partitions to enclose portions of the work where required for protection of indoor air quality.
- E. Relocate temporary enclosures as required by progress of construction, by operations of the building, or work requirements, and to accommodate legitimate requirements of Owner and Subcontractors employed at the site.
- F. Completely remove temporary materials, equipment and services when enclosure needs can be met by use of permanent construction and at completion of the Project.

1.19 PROTECTION OF WORK, PROPERTY AND THE PUBLIC

A. Furnish, erect, and maintain, until such time as removal is approved by the Architect, temporary fencing and barricades to extent recommended by OSHA and as otherwise required for the protection of life and property during operations under the Contract.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- B. Construct barricades and protective facilities in accordance with local and State regulations. Furnish and install all signs, lights, reflectors, and all such protection facilities as may be required.
- C. Construction Manager shall save the Owner harmless from all claims arising from the use of public streets, sidewalks, and adjoining premises for construction purposes.
- D. Keep all access roads and walks clear of debris, materials, construction plant and equipment during building operation. Repair streets, drives, curbs, sidewalks, fences, poles and the like where disturbed in building operation and leave them in as good condition after completion of the Work as before operations started.
- E. Protect all planting, landscaping, trees and site improvements to remain. Refer to requirements in Section 015639 TREE AND PLANT PROTECTION.

As req'd by DPW and approved CMP F. The Construction Manager shall be responsible for the maintenance of construction barriers and traffic barriers in order to maintain traffic around the Work with the maximum of safety and practical convenience to such traffic during the life of the Contract, and whether or not work has been suspended temporarily. He shall take all precautions for preventing injuries to persons or damage to property on or about the Work.

- G. Work shall be carried on and barriers erected in such a manner as to provide safe passage at all times for public travel and with least obstruction to traffic. The Construction Manager shall provide and maintain at his own expense in a safe and passable condition such temporary bypasses created by the barriers as may be necessary to accommodate both pedestrian and vehicular traffic.
- H. Whenever gale or high winds are forecast, take proper measurements to secure all loose material, equipment or other items that could blow about and be damaged or cause damage to other work. No such loose items shall be left unsecured at end of working day. Particular attention shall be taken with scaffolding and items placed or stored on roofs or within the structure prior to being enclosed.

Remove all snow and ice which may impede work, damage the finishes or materials, be detrimental to workers, or impede trucking, delivery, or moving of materials at the job site, or prevent adequate drainage of the site or adjoining areas. Maintain sidewalk on Harvard Street adjacent to project site to be clear of all snow and ice.

Be responsible for all breakage of glass from the time construction operations commence until the Project is occupied by the Owner. Unless glass has been broken by the Owner or his representatives, or by other separate prime contractors, the cost of glass replacement shall be borne by Construction Manager.

1.20 SECURITY OF THE WORK We have provided a temporary fence. We don't have any cameras, security

- A. The Construction Manager shall be responsible for providing any and all security precautions necessary to insure adequate protection of his and the Owner's interests.
- B. Take all required measures to protect the Work at all times against fire, storm, theft, vandalism and other losses.

We have snow removal on the site. Have not included adjacent streets, sidewalks, parking lots, bike lanes, etc. Where is this street??

insurance as appropriate.

BROOKLINE HIGH SCHOOL EXPANSION

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- C. The Construction Manager shall be wholly responsible for patrolling and protecting the work under construction and the materials stored on the site; and shall reimburse the Owner for any losses, damage or injury not compensated by insurance, except those directly caused by the Owner, his agents or his employees.
- D. The Construction Manager shall rebuild, repair, restore and make good all damage to any portion of the Work occasioned by any of the above causes before completion and written acceptance of the completed Work, and shall bear the expense thereof. No extension of time will be allowed in such cases.
- E. Should the Construction Manager fail to take prompt action whenever conditions make it necessary, the Owner may make emergency repairs or cause the same to be made, with the stipulation that the costs for such repairs shall be charged against the Construction Manager and deducted from monies due to him.

1.21 RODENT CONTROL

- A. Pest Control: Engage pest-control service to recommend practices to minimize attraction and harboring of rodents and to perform extermination and control procedures at regular intervals so Project will be free of rodents and their residues at Substantial Completion.
 - 1. Obtain extended warranty for Owner. NIC
 - 2. Perform control operations lawfully, using environmentally safe materials.

1.22 WATER CONTROL

- A. Take over responsibility for site drainage in work areas upon entering the premises and maintain such drainage during the life of this Contract in a manner approved by the Architect and so as not to adversely affect adjacent areas or abutting property.
- B. During the progress of the Work, provide and maintain all required pumps, suction and discharge lines, and power in sufficient number and capacity to keep all excavations, pits, trenches, foundations, and the entire property area free from accumulation of water from any source whatsoever, at all times, and under any and all circumstances and contingencies that may arise.

1.23 SNOW AND ICE CONTROL

- A. De-icing Materials:
 - 1. General: Comply with state and local regulations.
- B. Snow Storage:
 - 1. General: Comply with state and local regulations.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

PART 2 - PRODUCTS

2.1 CONSTRUCTION FENCE

- A. Furnish, install, maintain, and pay for temporary fencing and other protection required for the safety of the Work and of stored materials and equipment. Provide temporary construction fence as required for public safety and protection around entire construction area at the Limit of Work line, as shown on Drawings.
- B. Construction fence shall be eight (8) feet high and of chain link construction with 6 gauge wire at the top and the bottom of the fencing material, erected in a substantial manner, straight, plumb and true and with scrim.

Using movable fence panels, not gates

- C. Gates shall be built into fence at such approved locations as are necessary, well crossbraced and hung on heavy strap hinges with proper post and hook for double gates. Provide heavy hasps and padlocks for each gate. Provide keys to Owner to facilitate emergency access by Owner's Security Forces and local Police and Fire Department. Gates shall be double-locked to include a Knox padlock for emergency access.
- D. All fencing shall be in accordance with local ordinances and shall be removed at such time before Final Acceptance as the Architect directs. Restore site to acceptable condition after removing fence.

2.2 PROJECT SIGNS

A. Provide in a location designated by the Architect one (1) sign, 4 feet by 8 feet in size, with three 4-inch by 4-inch post supports. Sign shall be fabricated from 3/4 inch thick medium density overlaid exterior plywood, edged continuously with 3/4 inch square pine banding. Apply one coat of exterior primer and two coats of exterior gloss enamel to all surfaces of sign and supports.

- B. Sign shall be professionally produced and shall indicate: (1) the name of the Project, (2) the name of the Owner, (3) the name of the Construction Manager, (4) names and addresses of the Architect and Consulting Engineers, and (5) the phrase "This Project Funded in Part by the Massachusetts School Building Authority". Graphic images and lettering, including type size, style and colors, will be provided by the Architect prior to beginning of construction. Architect will provide layout in electronic disc format or printed copy for sign production.
- C. Provide directional signs as required to properly control construction traffic at each site.
- D. No other signs or advertisements will be allowed on building or premises.

2.3 TEMPORARY OFFICES

- A. Provide, maintain, and pay all costs in connection with temporary offices; including but not limited to office furniture, office equipment, and exhaustible office supplies.
 - 1. Provide 4 trailers, one for the Owner's Project Manager and three for storage.

Please provide desired graphics and we can make it We have not included

any costs for Owner,

OPM, clerk offices.

BROOKLINE HIGH SCHOOL EXPANSION

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- B. In addition to his own requirements, the Construction Manager shall provide and bear all costs for completely enclosed weathertight structure equal to Williams Scotsman Model MO3512; not less than 35-0" x 12'-0" in area for use of the Owner's Project Manager, the Architect, and their representatives. The trailer shall have two offices and a conference room, a reasonable amount of natural light, adjustable natural ventilation, and two exterior doors with OSHA approved stairs and dead bolt locks accessible and keyed from the outside. In addition include the following equipment:
 - 1. Heat during cold weather below 60 degrees F.
 - 2. Two desks (30x60 standard double pedestal steel desks with plastic laminate tops, two-drawer letter hanging file on one side, three drawer pedestal on the other side, center pencil drawer. Drawers shall lock; furnish two keys per desk.) and desk chairs (swivel type upholstered chair with arms, fully adjustable seat heights and variable back rests; five caster bases with wheels) in separate offices. One desk and one desk chair in the main area. Include one spring-mounted desk light per desk.
 - 3. One conference table, 72 by 30 inches, with plastic laminate top.
 - 4. Eight straight back folding chairs with cushioned seats.
 - 5. Three Fireproof metal file cabinets (4 drawers each) with locks, hanging frame inserts, hanging file holders and folders (50 per drawer). Drawers shall lock; furnish each cabinet with three keys.
 - 6. One closet.
 - 7. Two sloped surface plan review tables, 42 by 72 inches each, with raised lip at low edge.
 - 8. Two portable plan rack units on casters; 12 stick capacity each. Include twelve 3 knob sticks per unit.
 - 9. Two desk-type telephones with speakerphone feature.
 - 10. One electronic telephone answering machine.
 - 11. One coat rack, consisting of wall mounted panel equipped with eight coat hooks, two 20 gallon wastepaper baskets.
 - 12. One exterior high quality mercury thermometer.
 - 13. Air conditioning during weather above 75 degrees F.
 - 14. 12-inch deep steel wall-mounted shelving, 12 to 15 linear feet.
 - 15. Sufficient number of electric lights (50 fc at desk level over entire area) and outlets.
 - 16. One Dell MFP3115cn Printer/Copier/Scanner/Fax, or equal as approved by OPM. Provide letter, legal and 11 x 17 paper supply and required printer ink cartridges for the duration of the work. Include cable connections to USB port and service program with 3 years parts and labor warranty with 3 years onsite service with response time within 24 hours of notice. Provide technician to setup printer and printer capabilities (print, scan, fax, and other like items) on up to four owner rep/ clerk computers.
 - 17. One dedicated telephone line for fax.
 - 18. Supplies: Office supplies, including toners for all equipment, ten hard hats, four safety glasses, four safety vests and two raincoats.
 - 19. One water-cooler: Provide dispenser which holds bottled water and furnishes instant hot as well as cold water, supply with flat bottom paper cups, and weekly bottle replacement for the duration of the project.
 - 20. One refrigerator, two door, 3.3 cu ft capacity.
 - 21. One microwave, 0.9 cu ft capacity counter top model.
 - 22. One industrial quality wall-mounted first aid kit sized and supplied for 10 people.
 - 23. One automatic coffee machine equal to 2011-02 Keurig B140 Brewing System including coffee for the duration of the project.
 - 24. One UPS backup power unit, 20 minute capacity, auto shutdown on power failure.
 - 25. Power strip with surge protector, and dust covers for all equipment; provide three..

TEMPORARY FACILITIESAND CONTROLS 015000 - 13 of 14

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- 26. Electronic labeling system: desktop model, Brother # PT2700 or equal. Furnish with tape and other supplies for duration of project.
- C. Heat and Air Conditioning shall be maintained to provide an indoor air temperature of 76 degrees F at 72 inches above the floor and throughout the space during the cooling season and 70 degrees F at 30 inches above the floor during the heating season.
- D. Electrical Convenience Power: Provide convenience outlets for at least 2400 watts and at least 2 convenience circuits independent of the lighting, equipment power, and heating needs.
- We have not included this, but could add to GMP?

E. Offices shall be located in location approved by the Architect, shall be maintained by the Construction Manager in a clean and orderly condition, and shall be removed at Substantial Completion. The Construction Manager shall provide a weekly cleaning service in each office, with monthly waxing. Construction Manager shall maintain pathways to trailers from construction site and parking area free of water, snow and ice.

- F. Provide routine emergency service for office equipment specified and reasonable quantities of expendable supplies as required for job related use. Consumables include:
 - 1. Fax machine, copiers, printer: toner and paper.
 - 2. Drinking Water: Provide bottled spring water for water dispenser in 6 gallon bottles, delivered as necessary to avoid running out, coffee for machine, and continuous stock of flat bottom cups.
 - 3. Lamps: bulbs and fluorescent lamps of appropriate types and wattage for the trailer fixtures.

All Skanska's G equipment may not be new, it only goes to owner if part of GR's be relocated to within the school district by a professional moving company at the completion and we have not included a moving company for the

clerk/OPM.

PART 3 - EXECUTION (NOT USED])

END OF SECTION

requiring canopy pruning to allow for building staging and will utilize CM contingency for

We bought what was shown in the Civil Drawings. This entire spec section should be excluded or we can get pricing to comply.

REVISION: FB-005 - GMP BID SET - AUGUST 1, 2019

this instance only. Balance of this specification is excluded.

SECTION 015639

TEMPORARY TREE AND PLANT PROTECTION

- Landscape dwgs show select ETR trees to be protected and states they PART 1 GENERAL may require pruning as directed, 1.1 SUMMARY therefore should not be excluded Protection of existing trees and plants from damage as a result of the Contractor's operations including, but not limited to: Α. be maintained as installed. Item 4 Root Pruning, construction pruning and vista pruning for view improvement has not been included. Skanska is aware of one tree on the 1. Protection of existing natural woodlands. Cypress project along Cypress Street adjacent to the sidewalk which is potentially

 - 2. Marking of clearing limits.
 - Tree protection fencing. 3.
 - 4. Root pruning, construction pruning and vista pruning to improve views from the new Only as specified in landscaping specs building. bought from subs, or we can add to GMP

1.2 SUSTAINABLE DESIGN REQUIREMENTS

Does this apply to A. temporary materials like plant protection?

The Owner's sustainability requirements for this Project includes participation in the LEED™ (Leadership in Energy and Environmental Design) Program for "LEEDv4-SC Silver" Certification under the United States Green Building Council's LEED Rating System, LEED for SCHOOLS, Version 4.

Β. Materials, products and procedures within this Section shall contribute to the Project's sustainable design goals, including those defined by the USGBC's LEED V4 Green Building Design and Construction Reference Guide and Section 018110 (Sustainable Design Requirements). Refer to Section 018110 (Sustainable Design Requirements) for the project's target certification level and specific certification requirements. The Contractor shall ensure that the requirements related to the project's sustainability design goals are implemented to the fullest extent. Substitutions, or other changes to the work proposed by the Contractor or their Subcontractors, shall not be allowed if such changes compromise the aforementioned environmental goals and LEED certification.

1.3 RELATED REQUIREMENTS

- Α. Examine Contract Documents for requirements that affect work of this Section. Other Specification Sections that directly relate to work of this Section include, but are not limited to:
 - 1. Section 018110, SUSTAINABLE DESIGN REQUIREMENTS
 - 2. Section 017400. CONSTRUCTION WASTE MANAGEMENT
 - 3. Section 024113, SELECTIVE SITE DEMOLITION AND REMOVALS: Clearing and grubbing.
 - 4. Section 312000, EARTH MOVING; Establishment of subgrade elevation.
 - 3. Section 329300, PLANTING: New plant material.

1.4 **REFERENCED STANDARDS**

Α. Comply with applicable requirements of the following standards. Where these standards conflict with other specified requirements, the most restrictive requirements shall govern.

1. American National Standards Institute (ANSI):

Z133.1

Safety Requirements for Pruning, Trimming, Repairing, Maintaining and Removing Trees, and for Cutting Brush.

2. International Society of Arboriculture (ISA):

Guide Guide for Establishing Values of Trees and Other Plants

3. National Arborist Association (NAA):

Ref. 1 Pruning Standards for Shade Trees

1.5 SUBMITTALS

Trees to be protected **A**. and details of such are in drawings, SKA is not proposing these items. **B**.

Provide a drawing indicating all trees scheduled to be protected for Architect's approval.

Proposed methods, and schedule for effecting tree and plant protection shall be submitted for approval.

C. Proposed methods, materials, and schedule for root pruning, construction pruning, and tree fertilization shall be submitted for approval.

1.6 DAMAGE PENALTIES

A. If any trees or shrubs designated to be saved are damaged and replacement is required, a number and diameter of trees or shrubs of the same species and variety, as specified by the Owner and Architect, shall be furnished and planted by the Contractor. The total inch diameter of the replacement trees or shrubs shall equal the diameter of the tree or shrub to be replaced. The Contractor shall not be liable for any loss or damage which occurs while the Contractor is complying with instructions given by the Owner, Architect, or arborist working on the Project.

1.7 SPECIAL SITE LIMITATIONS

Where are there natural woodlandds?

- ³⁷ The Contractor's attention is called to the fact that certain areas on the site exist as natural woodland spaces and are to remain as natural woodlands. Therefore, all construction operations must be performed in such a manner which will preserve these existing natural environments as wood preserves.
- B. Designated areas of trees, understory, and wildflowers are to remain untouched and unharmed.
- C. Construction activities in the wooded preserve areas are prohibited.
- D. Clearly mark all clearing limits in the field and accompany Architect on a joint review of clearing limits before clearing operations have commenced. Limit of clearing is generally defined as the limit of grading.

- E. No objects are permitted to be attached to trees protected without written authorization by the Architect.
- 1.8 QUALITY ASSURANCE
 - A. Selective pruning and feeding methods shall conform to the applicable requirements of ANSI Z133.1.
 - B. Work of this section shall be completed by a professional ISA Certified Arborist with a minimum five years experience, who has successfully completed an exam and education program equal to the International Society of Arboriculture (ISA) Certification Program, sponsored by the International Society of Arboriculture 2009, P.O. Box 3129, Champaign, IL 61826 (217) 355-9411; Email: isa@isa-arbor.com.
 - C. Arborist shall have the following minimum qualifications:
 - 1. Membership in:
 - a. NAA National Arborist Association
 - b. ISA International Society of Arborists
 - 2. Meet state requirements for insurance.
 - 3. Licenses for application and use of pesticides.

PART 2 PRODUCTS

- 2.1 LEED MATERIAL REQUIREMENTS
 - A. Products and materials in this Section shall meet performance criteria and contribute to sustainable design requirements, as specified in Section 018110 (Sustainable Design Requirements). These contributions include, but are not limited to, preconsumer and postconsumer recycled content percentages, regional content percentages, FSC Certified wood, and product VOC content limits.
 - B. Recycled Content: Products and materials shall comply with minimum recycled content percentages as specified in 018110 (Sustainable Design Requirements).
- 2.2 TREE PROTECTION FENCING
 - Orange plastic fencing, "Nordic Plus II Snow Fence", manufactured by TENAX Corporation, 4800 East Monument Street, Baltimore, Maryland 21205, USA; (p) 410-522-7000 (t) 800-356-8495 (f) 410-522-7015, or approved equal.
 - 1. Plastic fence shall be 4 ft. high minimum, with wood or steel posts, spaced approximately 4 ft. apart bound together with at least 13 gauge galvanized steel wire.
 - 2. Posts for fencing shall be 6 ft. painted steel posts, driven a minimum of 2 ft. into the ground.
 - 3. For fencing within the drip line of trees, surface mounted post anchors may be acceptable. Review with Architect and arborist and obtain written approval prior to installing. Post installation shall not damage tree root systems.
 - B. Provide laminated "Keep Out" signage as indicated on the Drawings.

- C. Mulch: Pine bark mulch.
- D. Tree Wound Paint: Bituminous based paint of standard manufactuere specifically formulated for protection of tree wounds from moisture and insect invasion.
- 2.3 ROOT PRUNING
 - A. Mulch materials shall be as specified under Section 329300, PLANTING.
 - B. Liquid fertilizer to be applied to root pruned and construction pruned trees shall be Peters M 77 Sequestered-Chelated Soluble Fertilizer manufactured by W.R. Grace and Co., Cambridge, MA 02140, Gold Start Liquid Fertilizer, manufactured by Nutra-Flo Company, 1919 Grand Ave, Sioux City, IA 51106-5708; Phone: 712-277-2011; 800-831-4815; Fax: 712-279-1946; Agro- Culture Liquid Fertilizer, manufactured by Agro-Culture Liquid Fertilizers, 3055 W. M-21, P.O. Box 150, St. Johns, Michigan 48879; 1-800-678-9029, or approved equal. Liquid fertilizer shall be approved by Certified Arborist.
 - C. Dormant oil spray shall be a dormant miscible spray equal to Sunspray' Scalecide' or Volck Oil.
 - D. Insecticide shall be Isotox manufactured by Ortho; QuickPRO, manufactureed by Monsanto; LESCO Sevin Brand SL, #019106, manufactured by LESCO, or approved equal. Insecticide shall be approved by Certified Arborist.

PART 3 EXECUTION

- 3.1 INSTALLATION OF FENCING
 - A. Prior to start of demolition work and clearing and grubbing operations, tree protection fencing shall be installed in accordance with the following:
 - 1. Fencing shall be installed at the tree protection areas indicated on the Drawings.
 - 2. Fencing shall be installed a minimum of 15 ft. beyond the drip line of trees to be protected, unless otherwise approved by the Architect.
 - B. Post installation must avoid underground utilities. Tree protection fencing located over steam tunnel/vault locations shall be installed using surface anchors. No poles or stakes shall be driven into the ground at these locations.
- 3.2 PROTECTION FOR EXISTING TREES TO BE PRESERVED:
 - A. All trees to be preserved on the property shall be protected against damage from construction operations.
 - 1. Includes associated understory.
 - B. Only those trees located within the limits of improvements to be constructed as indicated, shall be removed.
 - 1. All trees to remain shall be flagged for review after the location of improvements to be constructed are staked in the field.

- 2. Any tree to be removed shall be reviewed by the Architect and Owner for approval prior to removal.
- 3. Trees to be preserved are represented by a solid line. Trees to be removed are represented by a dashed or ghosted line. Trees to be planted are graphically differentiated from existing trees.
- 4. Obtain approval of installation of tree fencing from Owner and Architect prior to the initiation of any removal of vegetation and construction.
- C. Erect fencing and armor protection prior to beginning any clearing, demolition or construction activity, and unless otherwise instructed, maintain in place until construction is completed.
 - 1. Obtain approval of installation of tree fencing from Owner and Architect prior to the initiation of any removal of vegetation and construction.
 - 2. Tree protection fencing shall be erected at the edge of the dripline where possible; in extreme circumstances and with the approval of the Architect, fencing may be located at the edge of the root protection zone.
 - a. For trees 10 inch caliper and less, the minimum distance the barrier shall be erected is ten (10) feet from the trunk of tree or clump of trees.
 - 3. Trees immediately adjacent to and within one hundred feet (100) of any construction activities are to be protected by fencing; subject to approval of the Architect and Owner.
 - 4. Trees exposed to construction activity within the dripline or within twenty-five (25) feet of any construction activity are to have trunks protected with tree armor in addition to fencing.
 - 5. The tree protection fencing shall be placed before any excavating or grading is begun and maintained in repair for the duration of the construction work unless otherwise directed.
 - 6. No material shall be stored or construction operation shall be carried on within the tree protection barricade.
 - 7. Tree protection fencing shall remain until all work is completed.
 - 8. Remove tree protection fencingat commencement of finish grading.
- D. Protect trees that are to remain, whether within fencing or not, from the following:
 - 1. Compaction of root area by equipment or material storage; construction materials shall not be stored closer to trees than the farthest extension of their limbs (dripline).
 - 2. The proposed finished grade within the root protection zone of any preserved tree shall not be raised or lowered more than three (3) inches.
 - a. Retaining methods can be used to protect and/or provide lateral support to the area outside the root protection zone.
 - 3. Trunk damage by moving equipment, material storage, nailing or bolting.
 - 4. Strangling by tying ropes or guy wires to trunks or large branches.
 - 5. Poisoning by pouring solvents, gas, paint, etc., on or around trees and roots.
 - 6. Cutting on roots by excavating, ditching, etc.
 - a. Prior to excavation within the tree drip lines or the removal of trees adjacent to other trees that are to remain, make a clean cut between the disturbed and undisturbed root zones with a rock saw or similar equipment to minimize root damage.
 - b. Refer to EXCAVATION AROUND TREES paragraph for additional information.
 - 7. Damage of branches by improper pruning.
 - 8. Drought from failure to water or by cutting or changing normal drainage pattern past roots. Contractor shall provide means as necessary to ensure positive drainage.

- 9. Changes of soil pH factor by disposal of lime base materials such as concrete, plaster, lime treatment at pavement subgrade, etc. When installing concrete adjacent to the root zone of a tree, use a minimum 6 mil. plastic vapor barrier behind the concrete to prohibit leaching of lime into the soil.
- 10. Do not cut roots 3/4" in diameter or over without approval of Owner's Representative. All excavation and earthwork within the RPZ of trees shall be done by hand.
- 11. Protect all existing trees near areas to be stabilized from underground contaminations by placing a 6 mil. Plastic film barrier along exposed vertical cut extending a minimum 12" into undisturbed subgrade below depth of stabilization.
- 12. No vehicular traffic shall occur within the drip line of any tree; including parking of vehicles.
- 13. No soil shall be spread, spoiled or otherwise disposed of under any tree within the RPZ.
- E. Any damage done to existing tree crowns or root systems shall be repaired by the Arborist to the satisfaction of the Architect and Owner's Representative.
 - 1. Broken branches shall be cut cleanly.
 - 2. Any roots cut shall be cut cleanly with a saw other means approved by the Architect and Owner's Representative.
- F. Damages to trees caused through negligence of Contractor or his employees will be assessed by Owner and Project Arborist as described in Paragraph 1.5.
- 3.3 ROOT PROTECTION ZONE:
 - A. The root protection zone (RPZ) is measured with a radius from the trunk 10'.
 - 1. No disturbance shall occur closer to the tree than one-half the radius of the RPZ or within five (5) feet of the tree whichever is greater.
- 3.4 ROOT PROTECTION ZONE IMPACTS:
 - A. Those trees to remain which have some encroachment on their root protection zone shall have the following maximum allowable impacts:
 - 1. Minimum Protection Criteria 'A': No disturbance of natural grade, e.g. trenching or excavation, can occur closer to the tree than one-half the radius of the RPZ or within five (5) feet of the tree whichever is greater.
 - 2. Minimum Protection Criteria 'B': No cut or fill greater than three (3) inches will be located closer to the tree trunk than ½ the RPZ radius distance.
 - B. Trees impacted shall have a minimum of a six (6) inch layer of mulch placed and maintained over the root protection zone and the undisturbed area within the dripline.
 - 1. Immediate pruning and fertilization shall occur per the pruning and fertilization sections of this specification.
 - 2. Provide water in a slow drip manner to impacted trees as approved by the Architect and Owner's Representative.
 - 3. Provide water to apply equivalent to 1 inch once per week to deeply soak in over the area within the dripline of the tree during periods of hot, dry weather.
 - 4. Spray tree crowns periodically to reduce dust accumulation on the leaves.

3.5 EXCAVATING AROUND TREES

- A. Excavate within the dripline of trees only where required and when absolutely necessary.
 - 1. Any excavation within the RPZ of trees shall be under the direction of the Arborist.
 - 2. Arborist shall be at site at all times while excavation is occurring within the RPZ.
 - 3. Air spade all removals within the RPZ.
 - 4. Refer to ROOT PROTECTION ZONE (RPZ).
- B. When excavating for new construction is required within the RPZ, air spade and hand excavate to minimize damage to root systems.
 - 1. Use narrow tine spading forks and comb soil to expose roots.
 - 2. Relocate roots back into backfill areas wherever possible.
 - 3. If large main lateral roots are encountered, expose beyond excavation limits as required to bend and relocate without breaking.
 - 4. If root relocation is not practical, clean cut roots using sharp ax approximately three (3) inches back from new construction.
- C. Where existing grade is above new finish grade, carefully excavate within the dripline to the new finish grade.
 - 1. Carefully hand excavate an additional six (6) inches below the finish grade.
 - 2. Use narrow tine spading forks to comb the soil to expose the roots, and prune the exposed root structure as recommended by the Arborist.
 - 3. Keep the exposed roots damp.
 - 4. Treat the cut roots as specified and as recommended by the Arborist.
 - 5. After pruning and treatment of the root structure is complete, backfill to finish grade with eight (8) inches of approved plant mix, or structural soil.
- D. Where noted on plan, use airspade to expose roots for required cutting to accomidate hardscape elements. Architect to verify all cuts prior to proceeding.
- E. Temporarily support and protect roots against damage until permanently relocated and covered with recommended landscape material.

3.6 ROOT PRUNING

- A. Where construction will be in close proximity to existing trees designated to remain, roots shall be pruned. Proximity shall be as determined in the field by the Architect.
- B. Root pruning is the physical cutting of tree roots to minimize root damage and promote healing. Suitable means for root pruning include trenching, vibrating plow, stump grinder. Any method which tears roots or disturbs the soil beyond the grading limit is unacceptable.
- C. Tree to be root pruned shall be root pruned to a depth of 24 in. by means of a trencher or other approved means.
- D. Backfill root pruning trench with existing soil mixed with peat moss or well-rotted sawdust to a mixture of approximately 75% soil and 25% humus. Tamp lightly to set soil

E. Apply mulch to a depth of 4 in. to 6 in. at minimum 10 ft. to 15 ft. radius around tree to reduce compaction of roots.

3.7 GOVERNING STANDARDS

- A. Work procedures will be guided by the current provisions of the American National Standard Institute. Complete detail of the provisions are to be found in the references listed. The two basic objectives of the pruning operation shall include:
 - 1. Hazard Reduction Pruning: Hazard reduction pruning shall be completed to remove visible hazards in a tree. Hazard pruning shall consist of one or more of the maintenance pruning types.
 - 2. Maintenance Pruning: Maintenance pruning shall be completed to maintain and improve tree health and structure and includes hazard reduction pruning.

3.8 MAINTENANCE PRUNING TYPES

- A. Both hazard reduction pruning and maintenance pruning shall consist of one or more of the following pruning types:
 - 1. Crown Cleaning: Crown cleaning shall consist of the selective removal of one or more of the following items: dead, dying, or diseased branches, weak branches, water sprouts and stubbed branches.
 - 2. Crown Thinning: Crown thinning shall consist of the selective removal of branches to increase light penetration, air movement, and reduce weight.
 - 3. Crown Raising: Crown raising shall consist of the removal of the lower branches of a tree to provide clearance.
 - 4. Crown Reduction, or Crown Shaping: Crown reduction shall consist of decreasing the height and/or spread of a tree.
 - 5. Vista Pruning: Vista pruning shall consist of selective thinning of framework limbs or specific areas of the crown.
 - 6. Crown Restoration: Crown restoration pruning shall improve the structure, form and appearance of a tree which has been severely headed, vandalized, storm damaged or improperly pruned.

3.9 UTILITY PRUNING

- A. Utility pruning shall consist of one or more of the following items:
 - 1. Trees Underneath: Pruning trees growing directly under and growing into the facility/utility space.
 - 2. Trees Along Side: Pruning of trees growing directly along side and growing into or toward the facility/utility space.

3.10 SCHEDULE

- A. All of the pruning type(s) as applicable are required at each tree. All pruning shall be completed to remove branches/laterals 1/8 inch and greater. All prunning to be completed before commencement of demolition.
 - 1. Height clearance:

- a. Pedestrian Areas: 8 feet height clearance from grade unless directed otherwise by Architect and Owner.
- b. Vehicular Areas: 13'-6" height clearance from top of paving unless directed otherwise by Architect and Owner.

3.11 CROWN IMPACTS

- A. Trees impacted by construction shall be limited to a maximum of 30 percent of the viable portion of a tree's crown removed as approved by the Architect and Owner's Representative. Removal of more than 30 percent of the viable portion of a tree's crown will necessitate the tree's removal and replacement at the Contractor's expense.
 - 1. Replacement shall be governed at the ratio of 1 inch of new tree per inch of tree removed up to trees of size less than 24" caliper. For trees 24" caliper and greater the ratio shall be 3 inches per new tree per inch of tree removed.
 - 2. Replacement trees are to have a one (1) year warranty; refer to Section 329300, PLANTING.

3.12 APPROVAL

A. No major limbs or structure will be cut or removed without prior approval of the Architect and Owner's Representative.

3.13 STERILIZATION

- A. All tools used will be sterilized with Clorox Bleach, or approved equal, prior to use and between each tree.
- B. Residue from sterilization operation shall be diluted so as not to damage any vegetation.
- C. At trees known to be diseased and where there is danger of transmitting that disease, tools are to be disinfected after each cut.
- 3.14 PAINT CUTS
 - A. Paint cuts more than 1 inch in diameter with an approved tree wound paint on trees.
 - 1. Paint cuts within 30 minutes after cutting.

3.15 FERTILIZATION OF PRESERVED TREES

- A. All existing trees to be reserved impacted by construction activities taking place within the dripline, including but not limited to trenching and grading, shall be fertilized.
- B. Feeding of existing trees to be impacted by construction shall be accomplished in accordance with the following specifications:
 - 1. Feeding shall be completed prior to construction of permanent improvements adjacent to all trees including site fill or paving including trenching operations.
 - 2. Liquid tree fertilizer applied with a standard hydrant sprayer at a pressure of 100 to 200 psi shall be injected in slightly slanted holes approximately twelve (12) inches in depth.

- 3. Concentration of suspension to be forty (40) pounds of fertilizer for trees in each 100 gallons of water. Application rate: six (6) pounds of actual nitrogen per 1,000 square feet of area under drip-line.
- 4. Holes are to be made in concentric circles and 3' on center around the tree with the last ring located at the dripline of the foliage of the trees.
- 5. Area beneath the dripline of the trees is to be well watered after the fertilization is placed.

3.16 MULCH

- A. Mulch base of all existing trees four (4') feet radius with 3 " deep mulch layer.
 - 1. If existing trees are grouped, the entire area is to be mulched in between the trees.
- B. Mulch base of all existing trees impacted by construction activities within RPZ with 3" deep mulch layer.
 - 1. If existing trees are grouped, the entire area is to be mulched in between the trees.

3.17 CLEANUP

- A. Wood and debris shall become property of the Contractor and shall be removed from the site. Cost of disposal to be paid by Contractor.
- B. If acceptable to Owner, wood from tree removal and pruning activities can be double shredded/grinded and used on site as mulch at locations as approved by Architect and Owner.
- 3.18 REMOVAL OF PROTECTION
 - A. All protection shall remain in place throughout the construction period. Remove protection devices only after written permission has been granted by the Architect.

END OF SECTION

PROJECT C – STEM WING ADDITION

SECTION 017400

CONSTRUCTION WASTE MANAGEMENT

PART 1 - GENERAL

- 1.1 GENERAL PROVISIONS
 - A. Attention is directed to Division 00 PROCUREMENT AND CONTRACTING REQUIREMENTS and DIVISION 01 GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.
 - B. Examine all other Sections of the Specifications for requirements that affect work of this Section, whether or not such work is specifically mentioned in this Section.
 - C. Coordinate Work with that of all other trades affecting or affected by Work of this Section. Cooperate with such trades to assure the steady progress of all Work under the Contract.

1.2 SUMMARY

- A. This Section includes requirements for the Contractor's implementation of waste management controls and systems for the duration of the Work.
- B. Sustainable Design Intent: Comply with project requirements intended to achieve certification, measured and documented according to the LEED Green Building Rating System, of the US Green Building Council. Refer to Section 018110 - SUSTAINABLE DESIGN REQUIREMENTS, for certification level and certification requirements.
 - 1. LEED MRp2, Construction and Demolition Waste Management Planning: Develop a waste management plan, quantifying material diversion by either weight or volume to recycle and/or salvage non-hazardous construction and demolition debris.
 - a. Exclude excavated soil and land-clearing debris from calculations.
 - b. Diverted waste includes recycled, salvaged, reused, and donated materials.
 - c. Include materials destined for alternative daily cover (ADC) in the calculations as waste (not diversion).
 - d. Include wood waste converted to fuel (bio-fuel) in the calculations as diversion. Other types of waste-to-energy are not considered diversion for this credit.
 - 2. LEED MRc5, Construction and Demolition Waste Management: Comply with one of the following paths, as directed by the LEED Checklist:
 - a. Option 1, Diversion:
 - 1) Path 1: Divert at least 50 percent and three material streams of nonhazardous construction and demolition debris.
 - 2) Path 2: Divert at least 75 percent and four material streams of nonhazardous construction and demolition debris.
 - b. Option 2, Reduction of Total Waste Material: Do not generate more than 2.5 pounds of construction waste per square foot (12.2 kilograms of waste per square meter) of the building's floor area.

TGE Comment: Per the CA kick off meetings and follow up CA check-in meetings, Skanska has developed a draft construction waste management plan and has a strategy to sort some waste on site and provide a breakdown of at least 5 project specific waste streams. Construction waste tracking is underway on the construction sites. CWM management tracking is required to be submitted to the City at the end of construction.

EARLY PACKAGE #2: DEMOLITION, ABATEMENT & SITE ENABLING MARCH 1, 2019

5 – GMP Bid Set – AUGUST 1, 2019

Section and are specified under the

Section 911000 - GENERAL REQUIRENTS for general submittal requirements. Section 924100 - DEMOLITION for demolition, salvage, and reuse requirements.

The Owner and Architect have established that this Project shall generate the least amount of waste practical and that processes that ensure the generation of as little waste as possible due to error, poor planning, breakage, mishandling, contamination, or other factors shall be employed.

With regard to these goals the Contractor shall develop, for the Architect's review, a Waste Management Plan (WMP) for this Project.

a. Final Waste Management Plan shall be submitted for LEED certification.

- Each Subcontractor shall be responsible for segregating their own waste into different dumpsters as directed by the Contractor.
- Source Separation, Definition: Source separated construction or demolition waste materials that are sorted into separate bins on the project site (aka on-site).
 - a. This waste strategy often isolates waste materials targeted for reuse, donation, or recycling programs.
 - b. Typically, sorted materials on-site include metals, wood, ceiling tiles, furniture, and concrete.
- B. Contractor shall be responsible for ensuring that debris will be disposed of at appropriately designated licensed solid waste disposal facilities, as defined by local authorities having jurisdiction or Massachusetts General Laws (MGL) Chapter 111, Section 150A.
- C. Hazardous Wastes: Any unforeseen hazardous wastes shall be separated, stored, and disposed of according to local regulations and as directed by the Owner. Hazardous wastes shall not be included in diversion calculations.

1.4 SUBMITTALS

2.

R

1.3

A.

INTENT

- A. Construction and Demolition Waste Management Plan (WMP): Submit within 21 calendar days after receipt of Notice to Proceed, in a format acceptable to the Owner and in compliance with USGBC requirements. Demolition shall not begin until WMP has been approved.
 - 1. Establish waste diversion goals for the project by identifying at least seven materials (both structural and nonstructural) targeted for diversion. Approximate a percentage of the overall project waste that each material represents.
 - 2. Construction and Demolition Handling Facilities:
 - a. Indicate the name(s) of the facilities where construction and demolition waste will be delivered and the applicable tipping fees.
 - b. Furnish Contractor's statement of verification that facilities proposed for use are licensed for types of waste to be delivered and have sufficient capacity to receive waste from this project.
 - 3. Material Handling Procedures, at Construction and Demolition Handling Facilities:

submitted. Due to space constraints on site, C&D debris will be comingled on site and seperated off site. Little or no on site source separation will take place.

018110 1.02.A

documentation

will not be

states

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- a. Indicate annual recycling rates and material streams, as defined by local authorities having jurisdiction or MassDEP.
- b. Specify which materials shall be source separated or commingled and describe the diversion strategies planned for the project. Describe where the materials will be taken and how the recycling facilities will process the materials.
- 4. Alternatives to Landfilling: A list of each material proposed to be salvaged or recycled during the course of the Project. Include the following and any additional items proposed:
 - a. Cardboard and paper products.
 - b. Clean dimensional wood. If means of diversion is Wood Derived Fuel (WDF) refer to submittal requirements below.
 - c. Beverage containers and employee food containers.
 - d. Concrete.
 - e. Slurry wall materials.
 - f. Bricks and masonry.
 - g. Asphalt.
 - h. Metals from framing, banding, stud trim, ductwork, piping, rebar, roofing, other trim, steel, iron, galvanized sheet steel, stainless steel, aluminum, copper, zinc, lead, brass, and bronze.
 - i. Mechanical and electrical equipment.
 - j. Building components which can be removed relatively intact from existing construction.
 - k. Packaging materials, including cardboard, boxes, plastic sheet and film, polystyrene packaging, wood crates, and plastic pails.
 - I. Glass.
 - m. Scraps from new gypsum wall board (drywall).
 - n. Carpet and pad.
 - o. Acoustical ceiling panels.
 - p. Plastics, including plastic pails, polyethylene sheet, and bubble wrap.
 - q. Rigid foam.
- 5. Meetings: A description of the regular meetings to be held to address waste management.
- 6. Materials Handling Procedures, at Project Site: A description of the means by which any waste materials identified above will be protected from contamination, and a description of the means to be employed in recycling the above materials consistent with requirements for acceptance by designated facilities.
 - a. Indicate which material streams shall be source separated and which shall be commingled.
- 7. Transportation: A description of the means of transportation of the recyclable materials (whether materials will be site-separated and self-hauled to designated centers, or whether mixed materials will be collected by a waste hauler and removed from the site) and destination of materials.

Bi-monthly

- B. Waste Management Progress Reports: Concurrent with each Application for Payment, submit a written Waste Management Progress Report in the same format as required for Final Report.
 - 1. Provide updated LEED v4 Construction and Demolition Waste Calculator with each progress report.
- C. Waste Management Final Report: Prior to Substantial Completion, submit a written Waste Management Final Report summarizing the types and quantities of materials recycled and

REVISION: FB-005 - GMP Bid Set - AUGUST 1, 2019

disposed of under the Waste Management Plan. Include the name and location of disposal facilities. Quantity may be measured by either weight or volume; be consistent in calculations. Include the following:

- 1. Material category, including source separated material streams.
- 2. Generation point of waste.
- 3. Total quantity of waste, by weight.
- 4. Quantity of waste salvaged, both estimated and actual.
- 5. Quantity of waste recycled, both estimated and actual.
- 6. Total quantity of waste diverted (salvaged plus recycled).
- 7. Total quantity of waste diverted (salvaged plus recycled) as a percentage of total waste.
- D. Other Submittals:
 - 1. Records of Donations: Indicate receipt and acceptance of salvageable waste donated to individuals and organizations. Indicate whether organization is tax exempt.
 - 2. Records of Sales: Indicate receipt and acceptance of salvageable waste sold to individuals and organizations. Indicate whether organization is tax exempt.
 - 3. Recycling and Processing Facility Records: Indicate receipt and acceptance of recyclable waste by recycling and processing facilities licensed to accept them. Include manifests,

TGE Comment: Per the CA kick off meetings and follow up CA check-in meetings, Skanska has developed a draft construction waste management plan and has a strategy to sort some waste on site and provide a breakdown of at least 5 project specific waste streams.

6.

E.

Records: Indicate receipt and acceptance of waste by licensed to accept them. Include manifests, weight

y: Signed by refrigerant recovery technician responsible that all refrigerant that was present was recovered and ording to EPA regulations. Include name and address of is recovered.

m	\cap
> Due to space	2
constraints on	4
Č site, multiple on	3
site waste	2
Streams will be	4
Co-mingled on	3
Site and	2
separated off	2
č site.	3
ann	1

- Specific LEED v4 Submittals:
 - a. Provide completed LEED v4 Construction and Demolition Waste Calculator for LEED MRp2 and MRc5.
 - b. Provide final report detailing waste streams generated, including tipping slips, disposal rates, and diversion rates.
- Commingling Waste Vendor Submittals: Provide annual report from local or state government authority and summary attachment of diverted materials with the average annual recycling rate. Figures in the summary must be derived from the annual reports in concise clear language.
 - 1. Commingling waste shall be considered one material stream.
 - 2. Provide tipping invoices for commingled waste and the following:
 - a. Vendor's most recent annual report from local or state government authority.
 - b. Vendor's annual report summary attachment of diverted materials in tonnage, with the average annual recycling rate.
 - 3. If Wood Derived Fuel (WDF) was listed as a diverted material in the above, vendors shall furnish a letter from the biomass plant stating their DOE operating permit number and that WDF was received from vendor, for the same year as the annual report.

PART 2 - PRODUCTS [Not Used]

Per CA kick-off and regular check-ins, construction waste is being tracked. Waste tickets will be obtained and weights will be reported on the LEED CWM management calculator.

EARLY PACKAGE #2: DEMOLITION, ABATEMENT & SITE ENABLING MARCH 1, 2019

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

PART 3 - EXECUTION

Some waste may go direct to transfer stations and will be segregated after transfer from there.

Β.

PLAN IMPLEMENTATION

General: Implement Waste Management Plan as approved by the Architect. Provide containers, storage, signage, transportation, and other items as required to implement WMP for the entire duration of the Contract.

Deliver waste directly to construction and demolition handling facilities. Do not deliver to transfer stations.

Commingling Waste: Commingling waste at the job site may be allowed, provided that the following conditions are met:

1. Comminglers shall be included in the Waste Management Plan (WMP).

Ν

2. Additional comminglers must be pre-approved by the Architect via WMP addenda, prior to tipping on the job site.

3.2 WASTE MANAGEMENT PLAN IMPLEMENTATION

- A. Manager: The Contractor shall designate an on-site person responsible for instructing workers and overseeing and documenting results of the Waste Management Plan for the Project.
- B. Distribution: The Contractor shall distribute copies of the Waste Management Plan to the Job Site Foreman, each Subcontractor, the Owner and the Architect.
- C. Instruction: The Contractor shall provide on-site instruction of appropriate separation, handling, and recycling, salvage, reuse, and return methods to be used by all parties at the appropriate stages of the Project.
- D. Separation Facilities: The Contractor shall lay out and label a specific area to facilitate separation of materials for recycling, salvage, reuse, and return. Recycling and waste bin areas are to be kept neat and clean and clearly marked in order to avoid contamination of materials. Location shall be acceptable to the Architect.

allowed.

1. Commingling: Waste commingling shall be approved prior to jobsite tipping, per requirements of this Section.

END OF SECTION

REVISION: FB-005 GMP BID SET – AUGUST 1, 2019

SECTION 017700

CLOSEOUT PROCEDURES

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

- A. Attention is directed to Division 00 PROCUREMENT AND CONTRACTING REQUIREMENTS and DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.
- B. Examine all other Sections of the Specifications for requirements that affect work of this Section, whether or not such work is specifically mentioned in this Section.
- C. Coordinate Work with that of all other trades affecting or affected by Work of this Section. Cooperate with such trades to assure the steady progress of all Work under the Contract.
- D. Track acquisition, review, and transmittal of record documents in a log.

1.2 SUMMARY

- A. The Work of this Section includes, but is not limited to, requirements for the following procedures:
 - 1. Final cleaning
 - 2. Temporary and trial usage
 - 3. Warranties and bonds
 - 4. Closeout requirements
 - 5. Inspection and Submittals for Substantial Completion
 - 6. Monetized Punch List Inspections
 - 7. Final Inspection and Submittals
 - 8. Final application and certificate for payment
 - 9. Post-construction inspection
- B. Related Work includes, but is not limited to, the following Work under other Sections:
 - 1. Dates for Substantial Completion and Final Completion: Division 00.
 - 2. Procedures related to Architect's additional services to complete closeout of Project: Section 011400 – WORK RESTRICTIONS
 - 3. Construction schedule requirements: Section 013200 CONSTRUCTION PROGRESS DOCUMENTATION.
 - 4. Verification of performance of mechanical and electrical systems: Section 019113 GENERAL COMMISSIONING REQUIREMENTS.
 - 5. Temporary facilities to be removed at the end of the Project: Section 015000 TEMPORARY FACILITIES AND CONTROLS.
 - 6. Documents to be submitted as part of Closeout Requirements: Section 017839 PROJECT RECORD DOCUMENTS

1.3 SUBMITTALS

- A. Warranties and Bonds: As specified herein.
- B. Punch Lists: As specified herein.
- C. Submittals for Substantial Completion: As specified herein.
- D. Final Submittals: As specified herein.

PART 2 - PRODUCTS

- 2.1 CLEANING MATERIALS
 - A. Refer to Section 011400 WORK RESTRICTIONS for cleaning materials.

PART 3 - EXECUTION

3.1 FINAL CLEANING

- A. Before final inspection, thoroughly clean the entire exterior and interior areas of the building where construction work has been performed, the immediate surrounding areas, and corridors, stairs, halls, storage areas, temporary offices, and toilets.
 - 1. Allow adequate time in Construction Schedule to perform thorough final cleaning of entire Project.
- B. Refer to Section 011400 WORK RESTRICTIONS for general requirements for cleaning and for cleaning products, and refer to individual specification sections for cleaning requirements for particular products.
- C. Employ professional cleaners for final cleaning operations.
- D. Remove all construction facilities, debris, and rubbish from the Owner's property and legally dispose of same beyond site limits.
- E. Broom clean exterior paved surfaces, and rake clean other surfaces of the grounds.
- F. Sweep, dust, wash, and polish all finished surfaces. This includes cleaning of the Work of all finished trades where needed, whether or not cleaning for such trades is included in their respective Sections.
- G. Remove grease, mastic, adhesives, dust, dirt, stains, fingerprints, labels, and other foreign materials from exposed interior and exterior surfaces.
- H. Leave pipe and duct spaces, chases, and furred spaces thoroughly clean.
- I. Wash and polish-all new glass on both sides, such Work shall be performed by a contractor

REVISION: FB-005 GMP BID SET - AUGUST 1, 2019

specializing in a window cleaning work.

- J. Clean all ceilings, wall surfaces, floors, window and door frames, hardware, metal work, glass, glazing, enameled metals, and the like.
- K. Repair, patch and touchup marred surfaces to specified finish, to match adjacent surfaces.
- L. Each Subcontractor for mechanical and electrical work, including Plumbing, HVAC, Fire Protection, and Electrical Work shall clean materials and equipment for which they are responsible, leaving the Work in a finished and clean state.
- M. For each mechanical unit that has been in operation during construction, Construction Manager shall clean permanent filters and replace disposable filters with new filters as specified for that mechanical unit, and shall also clean ducts, blowers and coils associated with that unit.
- N. Prior to final completion, Construction Manager shall conduct an inspection of sight-exposed interior and exterior surfaces and all work areas, to verify that the entire Work is clean.
- O. Owner will assume responsibility for cleaning as of time designated on Certificate of Substantial Completion for Owner's acceptance of Work or portion thereof.
- P. Include stripping, sealing, and waxing per Owner's requirements. Refer to technical specifications for additional requirements.

3.2 TEMPORARY AND TRIAL USAGE

- A. Temporary or trial usage by Owner of any mechanical device, machinery, apparatus, equipment, or any Work or materials supplied under the Contract before final completion and written acceptance by the Architect shall not be construed as evidence of acceptance as same.
- B. The Owner reserves the privilege of such temporary or trial usage for such reasonable time as required to properly test such item. Claims for damages due to injury to or breaking of any parts of such Work, when the determined cause is weakness or inaccuracy of structural parts, defective material or workmanship, will not be allowed.
- C. If the Owner so requests, place an approved person or persons to instruct and assist in such trial usage and bear the costs therefor.

3.3 WARRANTIES AND BONDS

A. Compile specified warranties and -bonds, review to verify compliance with Contract Documents, and submit to Architect for review and subsequent transmittal, if approved, to the Owner.

One

B. Assemble two original signed copies of warranties, bonds and service and maintenance contracts executed by Officers of each of the respective manufacturers, suppliers and subcontractors.

REVISION: FB-005 GMP BID SET – AUGUST 1, 2019

- C. Neatly type Table of Contents in orderly sequence. Provide complete information for each item:
 - 1. Product or work item identification.
 - 2. Manufacturing or supplying firm, with name of principal, address and telephone number.
 - 3. Scope of work and of warranty provided.
 - 4. Date of beginning of warranty, bond or service and maintenance contract. Commence upon date of Substantial Completion for each phase.
 - 5. Duration of warranty, bond or service maintenance contract. (In no case less than one (1) year).
 - 6. Information for Owner's personnel:
 - a. Proper procedure in case of failure.
 - b. Instances which might affect validity of warranty or bond.
 - 7. Construction Manager, name of responsible principal, address and telephone number.
- D. Form of Submittals: Prepare in duplicate packets and in the following format:
 - 1. Size: 8-1/2" x 11". Punch sheets for 3-ring binder. Z-Fold larger sheets to fit into binders.
 - 2. Cover: Identify each packet with types or printed title "WARRANTIES AND BONDS". List Title of Project, Date and Name of Construction Manager.
 - 3. Binders: Commercial quality, three-"D"-ring, with durable and cleanable plastic covers.
- E. Time of Submittals:
 - 1. For equipment or component parts of equipment put into service during progress of construction, submit documents within ten (10) days after inspection and acceptance. Otherwise, make submittals before Date of Substantial Completion.
 - 2. For items of Work where acceptance is delayed materially beyond the Date of Substantial Completion, provide updated submittal within ten days after acceptance, listing the date of acceptance as the start of the warranty period.
- F. Submittals Required: Submit warranties, bond, service and maintenance contracts as specified in the respective Sections of the Specifications.

3.4 CLOSEOUT REQUIREMENTS

- A. Punch List: When the Construction Manager submits a complete list of items to be completed or corrected in accordance with subparagraph 9.8.2 of the GENERAL CONDITIONS and the Architect receives the list, the Architect will make an inspection to determine whether the Work or designated portion is substantially complete. The Construction Manager shall submit a schedule indicating when each item will be completed.
- B. If the Architect determines that the Construction Manager's list is not complete, the Architect will notify the Construction Manager. The Construction Manager shall provide a complete list before the Architect will complete his inspection.
- C. If the Architect's inspection discloses any item whether or not included on the Construction Manager's list, which is not in accordance with the requirements of the Contract Documents, the Architect will add the item to the list and will issue a punch list of items to be completed or

REVISION: FB-005 - GMP BID SET – AUGUST 1, 2019

corrected before final payment will be made. Such punch list shall not be construed as allinclusive of the work which the Construction Manager will be required to perform before final payment.

D. Substantial Completion: Architect will prepare and issue a Certificate of Substantial Completion, AIA G704, complete with signatures of Owner and Construction Manager, accompanied by list of items to be completed or corrected, as verified and amended by the Architect. Architect will not issue certificates of Substantial Completion until the items listed below in Articles 3.05 and 3.06 have been completed and submitted.

completion and testing certs for all life safety systems, at a min., will be required for WRA to issue final affidavits in order for CM to obtain TCO

3.5 INSPECTION FOR SUBSTANTIAL COMPLETION

- A. In preparation for Substantial Completion, the Construction Manager shall submit written certification that:
 - 1. Contract Documents have been reviewed.
 - 2. Work has been inspected for compliance with Contract Documents.
 - 3. Work has been completed in accordance with Contract Documents.
 - 4. Equipment and systems have been tested in presence of Owner's Representative and are operational **as designed as a complete system**.
 - 5. Work is completed, and ready for inspection. will be coordinated well in advance
- B. Architect will begin inspection within seven (7) days after receipt of above referenced Construction Manager's Certification. schedule requires this to happen immediately, not in 7 days. We could add 7 days to schedule if its a must
- C. Should the Architect consider the Work is substantially complete in accordance with requirements of Contract Documents, the Architect will request Construction Manager to make Project Closeout submittals.
- D. Should the Architect consider that the Work is not substantially complete:
 - 1. The Architect will notify Construction Manager, in writing, stating reasons.
 - 2. Construction Manager shall take immediate steps to remedy the stated deficiencies, and send second written notice to the Architect certifying that the Work is complete.

3.6 SUBMITTALS FOR SUBSTANTIAL COMPLETION

A. Construction Manager shall track submittals for Substantial Completion in a log similar to the construction submittal log

- B. Construction Manager shall submit the following items at Substantial Completion:
 - 1. Operating and Maintenance Data.
 - 2. Schedule for training and instruction on new mechanical and electrical systems.
 - 3. Guarantees and Warranties.
 - 4. Keys and keying schedule.
 - 5. Spare Parts and Maintenance Materials.
 - 6. Roofing Guarantee and Flashing Endorsement.
 - 7. Evidence of Compliance with requirements of governing authorities.
 - 8. Punch list with schedule.
 - 9. Final Record Documents.
 - 10. Flush-out documentation including ATC hourly trending reports.

WILLIAM RAWN ASSOCIATES, Architects, Inc.

10 Post Office Square, Suite 1010, Boston, MA 02109 Page 248 of 377

REVISION: FB-005 GMP BID SET – AUGUST 1, 2019

- B. Evidence of compliance with authorities' requirements shall include:
 - 1. Certificates of compliance for flame and smoke, and fire rating.
 - 2. Certificates of Inspection:
 - a. Mechanical
 - b. Electrical
 - 3. Certificate of Occupancy
- C. Submit Certificate of Insurance for products and completed operations.
- D. Instructions: Instruct Owner's personnel in the operation of all systems, mechanical, electrical and other equipment.

3.7 ATTIC STOCK

A. Construction Manager shall track the requirements, acquisition, and transmittal of Attic Stock to the Owner.

3.8 TOOLS AND EQUIPMENT TO THE OWNER

Strike. Owner A. agreement governs Construction Manager shall track all equipment and tools requisitioned for payment through the project on a log that will be furnished to the Owner as requested. The CM shall turn over the tools and equipment at the conclusion of the project. The cost of tools and equipment not returned may be deducted from the final requisition as determined by the Owner.

3.9 MONETIZED PUNCHLIST INSPECTIONS

CM has been providing a log to date. it's incumbent upon CM to continue to maintain tracking of the whereabouts and conditions of these items and periodically communicate to Owner so any concerns can get resolved during the project.

- A. Within 30 days of Substantial Completion, the Architect will produce a Monetized Punch List that assigns a monetary value to each item remaining incomplete or incorrect.
- B. The Construction Manager may request two inspections by the Architect after receipt of the Monetized Punch List, for the purpose of documenting progress toward completion of items on the List.

3.10 FINAL INSPECTION

- A. The Construction Manager shall complete or correct all remaining items on the Monetized Punch List in accordance with the time limits stated in the General Conditions.
- B. Certification of Final Completion: When the Construction Manager considers that all of the items on the Monetized Punch List have been completed or corrected, the Construction Manager shall submit written certification that the items on the Monetized Punch List have been completed and corrected. This certification shall include a copy of the Monetized Punch List with the following information added:
 - 1. Indicate beside each item the date when the item was completed or corrected and,
 - 2. In the case of items completed by subcontractors or sub-subcontractors, the name of the Subcontractor or Sub-subcontractor. schedule requires this to happen immediately, not in 7

days. We could add 7 days to schedule if its a must

C. The Architect will begin inspection within seven (7) days after receipt of such certification, to determine whether items on the Punch List have been completed.

WILLIAM RAWN ASSOCIATES, Architects, Inc.

10 Post Office Square, Suite 1010, Boston, MA 02109

CLOSEOUT PROCEDURES will be coordinated well in advance of 7

- 3.11 FINAL SUBMITTALS
 - A. Construction Manager's Affidavit of Payment of Debts and Claims, AIA G706.
 - B. Construction Manager's Affidavit of Release of Liens, AIA G706A, with:
 - 1. Consent of Surety to Final Payment: AIA G707.
 - 2. Construction Manager's release or waiver of liens.
 - 3. Separate releases or waivers of liens for subcontractors, suppliers and others with lien rights against property of Owner, together with list of those parties.
 - C. All submittals shall be duly executed before delivery to the Architect.

3.12 FINAL APPLICATION AND CERTIFICATE FOR PAYMENT

- A. Construction Manager shall submit final application for payment in accordance with requirements of the GENERAL CONDITIONS. within the Owner's Agreement.
- B. Architect will issue final certificate in accordance with provisions of Conditions of the Contract.
- C. Prior to issuance of the Certificate for Final Payment by the Architect, all requirements contained in this Paragraph entitled "Closeout Requirements" and other requirements of the Conditions of the Contract shall be executed, received and approved by the Architect.

3.13 POST-CONSTRUCTION INSPECTION

- A. 10 months after Date of Substantial Completion, the Owner's Project Manager will make visual inspection of Work in company with Owner and Construction Manager to determine whether correction of Work is required, in accordance with provisions of GENERAL CONDITIONS AND SUPPLEMENTARY GENERAL CONDITIONS.
- B. For guarantees beyond one year, the Owner's Project Manager will make inspection at request of Owner after notification to Construction Manager.
- C. Owner's Project Manager will promptly notify Construction Manager in writing of any observed deficiencies.

END OF SECTION

Strike. Owner agreement governs

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

SECTION 017839

PROJECT RECORD DOCUMENTS

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

- A. Attention is directed to Division 00 PROCUREMENT AND CONTRACTING REQUIREMENTS and DIVISION 01 GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.
- B. Examine all other Sections of the Specifications for requirements that affect work of this Section, whether or not such work is specifically mentioned in this Section.
- C. Coordinate Work with that of all other trades affecting or affected by Work of this Section. Cooperate with such trades to assure the steady progress of all Work under the Contract.
- D. Track completion and submittal of training films and records on a log.

1.2 SUMMARY

- A. The Work of this Section includes, but is not limited to, requirements for the following procedures:
 - 1. Record prints
 - 2. Final record drawings
 - 3. Operations and maintenance submittals and instructions.
 - 4. School Dude product and equipment database information.
- B. Related work includes, but is not limited to, the following work under other Sections:
 - 1. Availability and restriction for use of project electronic files: Section 011400 Work Restrictions.
 - 2. Photographic documentation of construction: Section 011400 Work Restrictions.
 - 3. Availability of electronic files for preparation of record documents: Section 011400 Work Restrictions.
 - 4. Surveying and field engineering: Section 013100 Project Management and Coordination.
 - 5. General requirements for submittals: Section 013300 Submittal Procedures.
 - 6. Other submittals required at the completion of the Work: Section 017700 Closeout Procedures.
 - 7. Sustainable design requirements: Section 018110 Sustainable Design Requirements.
 - 8. Indoor air quality requirements: Section 018119 Indoor Air Quality Requirements.

1.3 DEFINITIONS

A. Record Prints are full sets of black-line of Contract Drawings, kept at the Project Site and marked regularly to record as-built conditions as specified herein.

REVISION: FB-005 - GMP Bid Set - AUGUST 1, 2019

- B. Final Record Drawings: Electronic files in DWG format prepared from completed and approved Record Prints.
- C. Final Record Coordination Drawings: Electronic files in DWG format prepared from updated prints of approved coordination drawings, to record as-built conditions.

1.4 SUBMITTALS

- A. Record Prints: Periodic submittal of prints of Drawings marked to indicate Work completed and changes in the Work, as specified in this Section:
 - 1. **Record Prints**
 - 2. **Coordination Drawing Record Prints**

We can provide a print out of the redlined drawings that we keep in Procor. Changes to architectural backgrounds would have to be provided by WRA.

- Final Record Drawings: Reproducible drawings, as specified in this Section: Β.
 - **Final Record Drawings** 1.
 - 2. **Final Record Coordination Drawings**

For final record dwgs, see above, no DWG's.

For final coordination drawings, aren't these the same as as built drawings from subs involved in MEP Coord?



1. Maintenance Manuals

C. Operations and Maintenance Submittals:

- 2. Schedule of Training and Instruction for mechanical and electrical systems.
- School Dude product and database information. D.
- E. **Record Finishes Manual**
- PART 2 PRODUCTS
- 2.1 RECORD DOCUMENTS, GENERAL
 - The Construction Manager shall maintain Record Prints of site plans, landscape drawings, Α. architectural drawings, and structural drawings.
 - Trade-Contractors shall maintain Record Prints of the Work of the following Sections: Β.
 - 1. Section 210001 - Fire Protection.
 - Section 220001 Plumbing. 2.
 - Section 230001 Heating, Ventilating, and Air Conditioning. 3.
 - Section 260001 Electrical Work. 4

2.2 **RECORD PRINTS**

This is done by the subs for progress payments

During the progress of the Work, the Construction Manager shall keep on file at all times one Α. (1) complete set of black line prints of the entire set of Contract Drawings. The set shall be updated daily to record the following information:

Page 252 of 377

Status of Work: The set shall be used to indicate the progress of the Work installed by 1.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

coloring in the various pipelines, ducts, and apparatus as erected.

- 2. Revisions: Accurately and promptly update with colored inks, daily as the Work progresses, to accurately record all revisions to the Work, including, but not limited to, the following:
 - a. Fire Protection, Plumbing, Heating and Ventilating, and Electrical Work, wherever Work was installed other than as shown on the Contract Drawings or described in the Specifications
 - b. Locations, elevations, sizes, and other like items of all concealed and buried utilities, ducts, and services, including exterior utility and storm drainage lines.
 - c. The Construction Manager shall be responsible for assuring that the various revisions are delineated by the specific trades involved.
- 3. The set shall be kept available at all times for use and inspection by the Architect and the Owner.
- 4. Schedule monthly meetings to review the progress of record prints with the Architect. The progress set must be approved by the Architect in order to be included in the monthly pay application.

Refer to Section 011400 Work Restrictions for Project Electronic Files to be made available for use by the Construction Manager in the preparation of Final Record Drawings.

Transfer all information from the updated Record Prints to the electronic files at least once every three months.

- 1. For each submission, submit a preliminary electronic set for the Architect's review. Once approved, submit three prints of each updated drawing to the Architect at least three times during construction: when the work is approximately 1/4, 1/2, and 3/4 complete.
- 2. When roughing in for any particular area is completed, it shall be shown on the Record Prints and a copy submitted for Architect's review.

2.3 FINAL RECORD DRAWINGS Can't do this if work isn't complete, as builts will be provided upon completion of the work

- A. Before completion of the Work, and when directed by the Architect, the Construction Manager and all indicated subcontractors shall perform the following:
 - 1. Transcribe all previously recorded information from Record Prints onto the electronic files.
 - 2. Make all final changes and corrections to the electronic files for the Final Record Drawings.
 - 3. Signatures Required: The Construction Manager or Trade-Contractor shall sign each drawing for which they are responsible, as certification that the work was installed as shown.
 - 4. Deliver signed, completed Final Record Drawings to Architect.

This may delay occupancy if there is not Sub B. Compl.

Acceptance by the Architect of the completed Final Record Drawings shall be a prerequisite for Substantial Completion.

- C. Shop Drawings will not be acceptable as Final Record Drawings for the Project.
- D. The Architect shall be the sole judge of the acceptability of Final Record Drawings.
- E. Special Requirements for Final Record Drawings of Site Work:

CM must ensure on-going as-builts are being kept throughout construction phase, and not wait until end of the project, by individual Subs/Trades and will make available to Owner or Design Team to periodically review them.

> We have not included any dwg record drawings.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- 1. Record Drawings for exterior utilities and other items below grade shall include accurate locations of the following:
 - a. The points where such items enter the building and property lines.
 - b. All turns, offsets, and other changes in direction below grade.
 - c. All valves and other appurtenances.
- 2. Indicate locations of these items using dimensions to adjacent permanent benchmarks or structures as approved by the Architect. Reliance on scale only to locate any temporary or concealed construction will not be acceptable.
- 3. Final Record Drawings for work below grade shall be submitted immediately upon completion of utility line installation and prior to concealment of the work
- 4. Refer to Division 31/32/33 Sections for additional requirements for Final Record Drawings of site work.

2.4 RECORD COORDINATION DRAWINGS

- A. Record progress of the Work and modifications and corrections on a set of prints of approved coordination drawings. Follow procedures as for Record Prints.
- B. Final Record Coordination Drawings shall be prepared using information from approved record copies of coordination drawings as for Final Record Drawings.

2.5 MAINTENANCE MANUALS

- A. Upon Substantial Completion of the Work, submit maintenance schedules, maintenance manuals, and all approved Shop Drawings, presenting full details for care and maintenance of visible surfaces and all equipment furnished and installed under the Contract.
- B. Maintenance manuals shall consist of manufacturer's catalog cuts with descriptive information, lubricating and maintenance instructions, parts lists, usage instructions, names, addresses and telephone numbers where replacement parts and service can be quickly obtained, and all other information required for the Owner to use, maintain, and service the items properly.
- C. Additional Requirements for Operations and Maintenance Manuals:
 - 1. All O&M's are subject to approval by The Owner as well as the Architect and Consultants.
 - 2. All O&M's are to include a list of common parts used for routine maintenance.
 - 3. All O&M's are to be broken down into .pdf files with a table of contents to be submitted for approval.
 - 4. All O&M are to reference the corresponding submittal number and equipment type on the contract drawings.
 - 5. HVAC O&M shall include a matrix on an excel spreadsheet for equipment type (AHU's exhaust fans, etc) and list the number of belts, part # for belts, filter size, filter part number (if available), and filter quantity.
 - 6. School dude schedules see example Equipment Data Retrieval Spreadsheet at the end of this Section.
 - 7. Include training sign-in sheets.
 - 8. Contact information (including emergency contact information).

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

9. Maintenance schedules.

D. Upon Architect's approval of drafts, submit two (2) corrected copies properly bound in a logical and well arranged order, with index, to the Architect for transmittal to the Owner.

2.6 SCHOOL DUDE DATABASE SUBMITTALS

- A. Upon Substantial Completion of the Work, submit information according to Template Guide included at the end of this section.
- B. The Contractor or the specific equipment vendor shall complete the Data Retrieval Spreadsheet as part of project closeout of the mechanical, electrical, plumbing and fire protection. See sample attachment at end of this section of the Data Retrieval Spreadsheet for Brookline High School's Equipment Data Retrieval Spreadsheet. The Construction Manager and trade contractor are responsible for this task during the submittal, installation and O&M manual phases of the project.
- C. The MEP Coordinator for the Construction Manager shall compile the information gathered by the Trades in the collection of required asset information. This information will be compiled into the Brookline High School's Equipment Data Retrieval Spreadsheet. Information gathered will be used to compile the Computerized Maintenance Management Systems (CMMS).
- D. Upon Architects approval, submit hard and digital copy to Owner.

2.7 SCHOOL DUDE DATABASE SUBMITTALS

- A. Upon Substantial Completion of the Work, submit information according to Template Guide included at the end of this section.
- 2.8 RECORD FINISHES MANUAL
 - A. Upon Substantial Completion of the Work, submit a finishes manual in PDF format documenting products installed in the project. Include the following:
 - 1. Specification name and number
 - 2. Product name, manufacturer and manufacturer's product number, installing subcontractor, and contact information.
 - 3. Manufacturer's maintenance recommendations.

PART 3 - EXECUTION

3.1 TRAINING AND INSTRUCTIONS

A. The Construction Manager shall arrange for instruction for the Owner's employees, to insure proper operation of the equipment furnished.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- 1. It is the intent of this paragraph to require the Construction Manager and the applicable Subcontractors to furnish as much detailed instruction as is necessary to educate the Owner's on-site personnel in the proper use of the equipment.
- 2. This instruction shall be provided by a qualified trainer who is also a manufacturer's certified technician with expertise with the specific system or equipment for which training is required. In some cases, this may require more than one visit to the Project by those responsible for the instruction.
- 3. The Construction Manager and, in particular, the Plumbing, Heating and Ventilating, and Electrical Subcontractors shall not assume that the Owner's employees possess special expertise or have had any previous experience whatsoever in the operation and maintenance of sophisticated mechanical and electrical equipment.
- 4. Submit the schedule and draft agenda for instructional sessions to the Owner. Do not proceed with instruction until Owner has approved schedule.
- 5. Refer to specific technical sections for additional requirements specific to particular equipment and systems.
- B. For major items of mechanical and electrical equipment, instructions and demonstrations shall be performed during the initial start-up period and during one or more return visits as may be required.
- C. Videotape: Instruction sessions and demonstrations shall be video-recorded by professional videographers in DVD format, using tripods, broadcast-quality video cameras and proper lighting. Close-ups of items being demonstrated shall be included. Sound recording shall be clear and perfectly intelligible. Video shall be edited as required to provide a permanent reference. Each session and demonstration shall be included, except where waived by the Architect, and all DVDs shall be properly labeled as to date, subject, and presenter. Provide two (2) copies of each DVD.

ATTACHED: Equipment Data Retrieval Spreadsheet - Brookline High School's Data Collection Database

END OF SECTION

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

SECTION 017900

DEMONSTRATION AND TRAINING

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

- A. Attention is directed to Division 00 PROCUREMENT AND CONTRACTING REQUIREMENTS and DIVISION 01 GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.
- B. Examine all other Sections of the Specifications for requirements that affect work of this Section, whether or not such work is specifically mentioned in this Section.
- C. Coordinate Work with that of all other trades affecting or affected by Work of this Section. Cooperate with such trades to assure the steady progress of all Work under the Contract.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for instructing Owner's personnel, including the following:
 - 1. Instruction in operation and maintenance of systems, subsystems, and equipment.
 - 2. Demonstration and training video recordings.

1.3 INFORMATIONAL SUBMITTALS

may or may not be available depending on each manufacturer; otherwise Subs/Trades will provide live recording onsite

- A. Instruction Program: Submit outline of instructional program for demonstration and training, including a list of training modules and a schedule of proposed dates, times, length of instruction time, and instructors' names for each training module. Include learning objective and outline for each training module.
 - 1. Indicate proposed training modules using manufacturer-produced demonstration and training video recordings for systems, equipment, and products in lieu of video recording of live instructional module.
- B. Qualification Data: For instructor.
- C. Attendance Record: For each training module, submit list of participants and length of instruction time.
- D. Evaluations: For each participant and for each training module, submit results and documentation of performance-based test.

requires clarification of expectation

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

1.4 CLOSEOUT SUBMITTALS

- A. Demonstration and Training Video Recordings: Submit two copies within seven days of end of each training module.
 - 1. Identification: On each copy, provide an applied label with the following information:
 - a. Name of Project.
 - b. Name and address of videographer.
 - c. Name of Architect.
 - d. Name of Construction Manager.
 - e. Name of Contractor.
 - f. Date of video recording.
 - 2. Transcript: Prepared in PDF electronic format. Include a cover sheet with same label information as the corresponding video recording and a table of contents with links to corresponding training components. Include name of Project and date of video recording on each page.
 - 3. At completion of training, submit complete training manuals for Owner's use

1.5 QUALITY ASSURANCE

- A. (Facilitator Qualifications: A firm or individual experienced in training or educating maintenance personnel in a training program similar in content and extent to that indicated for this Project, and whose work has resulted in training or education with a record of successful learning performance.
- B. Instructor Qualifications: A factory-authorized service representative, complying with requirements in Section 014000 "Quality Requirements," experienced in operation and maintenance procedures and training.
- C. Videographer Qualifications: A professional videographer who is experienced photographing demonstration and training events similar to those required.
- D. Preinstruction Conference: Conduct conference at Project site to comply with requirements in Section 013100 "Project Management and Coordination." Review methods and procedures related to demonstration and training including, but not limited to, the following:
 - 1. Inspect and discuss locations and other facilities required for instruction.
 - 2. Review and finalize instruction schedule and verify availability of educational materials, instructors' personnel, audiovisual equipment, and facilities needed to avoid delays.
 - 3. Review required content of instruction.
 - 4. For instruction that must occur outside, review weather and forecasted weather conditions and procedures to follow if conditions are unfavorable.

1.6 COORDINATION

- A. Coordinate instruction schedule with Owner's operations. Adjust schedule as required to minimize disrupting Owner's operations and to ensure availability of Owner's personnel.
- B. Coordinate instructors, including providing notification of dates, times, length of instruction time, and course content.

Page 258 of 377

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

C. Coordinate content of training modules with content of approved emergency, operation, and maintenance manuals. Do not submit instruction program until operation and maintenance data have been reviewed and approved by Architect.

1.7 INSTRUCTION PROGRAM

- A. Program Structure: Develop an instruction program that includes individual training modules for each system and for equipment not part of a system, as required by individual Specification Sections.
- B. Training Modules: Develop a learning objective and teaching outline for each module. Include a description of specific skills and knowledge that participant is expected to master. For each module, include instruction for the following as applicable to the system, equipment, or component:
 - 1. Basis of System Design, Operational Requirements, and Criteria: Include the following:
 - a. System, subsystem, and equipment descriptions.
 - b. Performance and design criteria if Contractor is delegated design responsibility.
 - c. Operating standards.
 - d. Regulatory requirements.
 - e. Equipment function.
 - f. Operating characteristics.
 - g. Limiting conditions.
 - h. Performance curves.
 - 2. Documentation: Review the following items in detail:
 - a. Emergency manuals.
 - b. Systems and equipment operation manuals.
 - c. Systems and equipment maintenance manuals.
 - d. Product maintenance manuals.
 - e. Project Record Documents.
 - f. Identification systems.
 - g. Warranties and bonds.
 - h. Maintenance service agreements and similar continuing commitments.
 - 3. Emergencies: Include the following, as applicable:
 - a. Instructions on meaning of warnings, trouble indications, and error messages.
 - b. Instructions on stopping.
 - c. Shutdown instructions for each type of emergency.
 - d. Operating instructions for conditions outside of normal operating limits.
 - e. Sequences for electric or electronic systems.
 - f. Special operating instructions and procedures.
 - 4. Operations: Include the following, as applicable:
 - a. Startup procedures.
 - b. Equipment or system break-in procedures.
 - c. Routine and normal operating instructions.
 - d. Regulation and control procedures.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- e. Control sequences.
- f. Safety procedures.
- g. Instructions on stopping.
- h. Normal shutdown instructions.
- i. Operating procedures for emergencies.
- j. Operating procedures for system, subsystem, or equipment failure.
- k. Seasonal and weekend operating instructions.
- I. Required sequences for electric or electronic systems.
- m. Special operating instructions and procedures.
- 5. Adjustments: Include the following:
 - a. Alignments.
 - b. Checking adjustments.
 - c. Noise and vibration adjustments.
 - d. Economy and efficiency adjustments.
- 6. Troubleshooting: Include the following:
 - a. Diagnostic instructions.
 - b. Test and inspection procedures.
- 7. Maintenance: Include the following:
 - a. Inspection procedures.
 - b. Types of cleaning agents to be used and methods of cleaning.
 - c. List of cleaning agents and methods of cleaning detrimental to product.
 - d. Procedures for routine cleaning.
 - e. Procedures for preventive maintenance.
 - f. Procedures for routine maintenance.
 - g. Instruction on use of special tools.
- 8. Repairs: Include the following:
 - a. Diagnosis instructions.
 - b. Repair instructions.
 - c. Disassembly; component removal, repair, and replacement; and reassembly instructions.
 - d. Instructions for identifying parts and components.
 - e. Review of spare parts needed for operation and maintenance.

1.8 PREPARATION

- A. Assemble educational materials necessary for instruction, including documentation and training module. Assemble training modules into a training manual organized in coordination with requirements in Section 017823 "Operation and Maintenance Data."
- B. Set up instructional equipment at instruction location.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

1.9 INSTRUCTION

- A. Facilitator: Engage a qualified facilitator to prepare instruction program and training modules, to coordinate instructors, and to coordinate between Contractor and Owner for number of participants, instruction times, and location. By CM or Sub/Vendor
- B. Engage qualified instructors to instruct Owner's personnel to adjust, operate, and maintain systems, subsystems, and equipment not part of a system.
 - 1. Architect will furnish an instructor to describe basis of system design, operational requirements, criteria, and regulatory requirements.
 - 2. Owner will furnish Contractor with names and positions of participants.
- C. Scheduling: Provide instruction at mutually agreed-on times. For equipment that requires seasonal operation, provide similar instruction at start of each season.
 - 1. Schedule training with Owner through Construction Manager, with at least seven days' advance notice.
- D. Training Location and Reference Material: Conduct training on-site in the completed and fully operational facility using the actual equipment in-place. Conduct training using final operation and maintenance data submittals.
- E. Evaluation: At conclusion of each training module, assess and document each participant's mastery of module by use of a demonstration]performance-based test.
- F. Cleanup: Collect used and leftover educational materials and give to Owner. Remove instructional equipment. Restore systems and equipment to condition existing before initial training use.

1.10 DEMONSTRATION AND TRAINING VIDEO RECORDINGS by CM or Sub/Trade representative

- A. General: Engage a qualified commercial videographer to record demonstration and training video recordings. Record each training module separately. Include classroom instructions and demonstrations, board diagrams, and other visual aids, but not student practice.
 - 1. At beginning of each training module, record each chart containing learning objective and lesson outline.
- B. Digital Video Recordings: Provide high-resolution, digital video in MPEG format, produced by a digital camera with minimum sensor resolution of 12 megapixels and capable of recording in full HD mode with vibration reduction technology.
 - 1. Submit video recordings on CD-ROM or thumb drive.
 - 2. File Hierarchy: Organize folder structure and file locations according to Project Manual table of contents. Provide complete screen-based menu.
 - 3. File Names: Utilize file names based on name of equipment generally described in video segment, as identified in Project specifications.
 - 4. Contractor and Installer Contact File: Using appropriate software, create a file for inclusion on the equipment demonstration and training recording that describes the following for each Contractor involved on the Project, arranged according to Project Manual table of contents:

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- a. Name of Contractor/Installer.
- b. Business address.
- c. Business phone number.
- d. Point of contact.
- e. Email address.
- C. Recording: Mount camera on tripod before starting recording, unless otherwise necessary to adequately cover area of demonstration and training. Display continuous running time.
 - 1. Film training session(s) in segments not to exceed 15 minutes.
 - a. Produce segments to present a single significant piece of equipment per segment.
 - b. Organize segments with multiple pieces of equipment to follow order of Project Manual table of contents.
 - c. Where a training session on a particular piece of equipment exceeds 15 minutes, stop filming and pause training session. Begin training session again upon commencement of new filming segment.
- D. Light Levels: Verify light levels are adequate to properly light equipment. Verify equipment markings are clearly visible prior to recording.
 - 1. Furnish additional portable lighting as required.
- E. Narration: Describe scenes on video recording by audio narration by microphone while video recording is recorded. Include description of items being viewed.
- F. Transcript: Provide a transcript of the narration. Display images and running time captured from videotape opposite the corresponding narration segment.
- G. Preproduced Video Recordings: Provide video recordings used as a component of training modules in same format as recordings of live training.

PART 2 - PRODUCTS

PART 3 - EXECUTION

END OF SECTION

PROJECT C – STEM WING ADDITION

BROOKLINE HIGH SCHOOL EXPANSION

EARLY PACKAGE #2: DEMOLITION, ABATEMENT & SITE ENABLING MARCH 1, 2019

GENERAL NOTE: Skanska assumes that

compliance with any and all LEED requirements have been specifically included in the Contract Documents in the trade specific specification

sections required to obtain compliance. Should a product be listed in the trade specific specification section that conflicts with Division 1 Sustainable Design Requirements, we have

included the product as identified in the trade specific specifications. It is the Architect's responsibility to specify products that comply with the Sustainable Design Requirements.

REVISION: FB-005 - GMP Bid Set - AUGUST 1, 2019

SECTION 018110

SUSTAINABLE DESIGN REQUIREMENTS

PART 1 - GENERAL

- 1.01 GENERAL PROVISIONS
 - A. Attention is directed to Division 00 PROCUREMENT AND CONTRACTING REQUIREMENTS and DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.
 - B. Examine all other Sections of the Specifications for requirements that affect work of this Section, whether or not such work is specifically mentioned in this Section.
 - C. Coordinate Work with that of all other trades affecting or affected by Work of this Section. Cooperate with such trades to assure the steady progress of all Work under the Contract.
- 1.02 SUMMARY
 - A. The Project is required to meet the Town of Brookline LEED Certifiable requirements. LEED credits and data will be collected and reported to the Owner and Architect, but will not be submitted to LEED or LEED-online.
 - B. Section includes general requirements and procedures for compliance with certain prerequisites and credits needed for Project to obtain "LEED Version 4 for Building Design and Construction Schools" (LEED v4 BD+C Schools) Silver certification based on USGBC's LEED v4 BD+C Schools.
 - 1. Specific requirements for LEED are also included in other Sections.
 - Some LEED prerequisites and credits needed to obtain LEED certification depend on product selections and may not be specifically identified as LEED requirements. Compliance with requirements needed to obtain LEED prerequisites and credits may be used as one criterion to evaluate substitution requests and comparable product requests.
 - 3. A copy of the LEED Project checklist is attached at the end of this Section for information only.
 - a. Some LEED prerequisites and credits needed to obtain the indicated LEED certification depend on aspects of Project that are not part of the Work of the Contract.
 - 4. Definitions included in the "LEED Version 4 for Building Design and Construction" (LEED v4 BD+C) Reference Guide and online amendments apply to this Section.
 - C. Related Work: The following items are not included in this Section and are specified under the designated Sections:
 - 1. Section 013300 SUBMITTAL PROCEDURES for general submittal requirements.
 - 2. Section 017400 CONSTRUCTION WASTE MANAGEMENT.
 - 3. Section 018119 CONSTRUCTION INDOOR AIR QUALITY (IAQ) MANAGEMENT.

1.03

BROOKLINE HIGH SCHOOL EXPANSION

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- 4. Section 019113 GENERAL COMMISSIONING REQUIREMENTS.
- Divisions 01 through 49 Sections for LEED requirements specific to the work of each of these Sections. Requirements may or may not include reference to LEED.
- DEFINITIONS See general note on page 1. All individual spec sections must reference pertinent LEED requirements. This is particularly important with 149A Trade Contract bids.
- A. Bio-Based Materials: Materials that meet the Sustainable Agriculture Network's Sustainable Agriculture Standard. Bio-based raw materials shall be tested using ASTM D 6866 and be legally harvested, as defined by the exporting and receiving country.
- B. CDPH Standard Method v1.1: California Department of Public Health (CDPH) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers, v. 1.1–2010, for the emissions testing and requirements of products and materials.
- C. Chain-of-Custody (COC): A procedure that tracks a product form the point of harvest or extraction to its end use, including all successive stage of processing, transformation, manufacturing, a distribution.
- D. Chain-of-Custody Certificates: Certificates signed by manufacturers and fabricators certifying that wood used to make products was obtained from forests certified by an FSC-accredited certification body to comply with FSC STD-01-001.
- E. Composite Wood and Agrifiber: Products made of wood particles and/or plant material pressed and bonded with adhesive or resin such as particleboard, medium density fiberboard (MDF), plywood, wheatboard, strawboard, panel substrates, and door cores.
- F. Corporate Sustainability Report: A third-party verified report that outlines the environmental impacts of extraction operations and activities associated with the manufacturer's product and the product's supply chain.
- G. Environmental Product Declaration (EPD): An independently verified report based on life-cycle assessment studies that have been conducted according to a set of common rules for each product category and peer-reviewed.
 - 1. Product-Specific Declaration: A product with a publicly available, critically reviewed lifecycle assessment conforming to ISO 14044 that has at least a cradle to gate scope.
 - 2. Industry-Wide (Generic) EPD: Provide products with third-party certification (Type III), including external verification, in which the manufacturer is explicitly recognized as a participant by the program operator. EPD must conform to ISO 14025, 14040, 14044, and EN 15804 or ISO 21930 and have at least a cradle to gate scope.
 - 3. Product-Specific Type III EPD: A product with a third-party certification, including external verification, in which the manufacturer is explicated recognized by the program operator. EPD must conform to ISO 14025, 14040, 14044, and EN 15804 or ISO 21930 and have at least a cradle to gate scope.
- H. Extended Producer Responsibility (EPR): Measures undertaken by the maker of a product to accept its own and sometimes other manufacturers' products as postconsumer waste at the end of the products' useful life.
- I. Health Product Declaration Open Standard (HPD): A standard format for reporting product content and associated health information for building products and materials.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- J. Indoor Air Quality (IAQ) Management Plan: Plan developed by the Contractor to provide a healthy indoor environment for workers and building occupants during construction. Plan must meet or exceed the recommendations of the Sheet Metal and Air Conditioning Contractors National Association (SMACNA) "IAQ Guidelines for Occupied Buildings Under Construction."
- K. Leadership Extraction Practices: Products that meet at least one of the responsible extraction criteria, which include: extended producer responsibility; bio-based materials; FSC wood products; materials reuse; recycled content; and other USGBC approved programs.
- L. Material Cost: The dollar value of materials being provided to the site, after Contractor markups, including transportation costs, taxes, fees, and shop labor, but excluding field equipment and field labor costs.
- M. Materials Reuse: Reuse includes salvaged, refurbished, or reused products.
- N. Multi-Attribute Optimization: Third party certified products that demonstrate impact reduction below industry average in at least three of the following six categories: global warming potential; stratospheric ozone depletion; acidification; eutrophication; tropospheric ozone creation; nonrenewable resource depletion.
- O. Passive (As Related to MEP): Not part of the active portions of the Mechanical, Electrical, and Plumbing systems, for example piping, pipe insulation, ducts, duct insulation, conduit, plumbing fixtures, faucets, showerheads, and lamp housings.

LEED CA credit documentation is required by the City to be submitted prior to CoO. Per LEED CA kick-off meetings and regular check-in meetings, it is understood that LEED tracking spreadsheets and backup documentation will be provided by Skanksa. This work and regular LEED CA meetings are underway.

R

04

Strike, 1.02.A

will not be

submitted.

states documentation

A.

В.

1.

cled content is the sum of postconsumer recycled content plus one-half d content, based on cost.

naterial is defined as waste material generated by households or by trial, and institutional facilities in their role as end users of the product, er be used for its intended purpose.

aterial is defined as material diverted from the waste stream during the cess. Excluded is reutilization of materials, such as rework, regrind, or n a process and capable of being reclaimed within the same process

Q. Regional Materials: Materials that are extracted, harvested, recovered, and manufactured within a radius of 100 miles from the Project site.


Volatile Organic Compounds (VOC) Emissions Test: Refer to CDPH Standard Method v1.1 definition.

ADMINISTRATIVE REQUIREMENTS

Work of this project includes completed building and application for LEED certification. Work is not complete until Owner has accepted USGBC's final review of LEED certification.

Provide documentation required by LEED and LEED review.

Provide materials and procedures necessary to obtain LEED prerequisites and credits required in this Section. Other Sections may specify requirements that contribute to LEED prerequisites and credits. Refer to other sections for additional materials and procedures necessary to obtain LEED prerequisites and credits.



REVISION: FB-005 - GMP Bid Set - AUGUST 1, 2019

- c. Materials Reuse: Receipts for salvaged and refurbished materials used for Project, indicating sources and costs.
- Recycled Content: Product data and certification letter from product d. manufacturers, indicating percentages by weight of postconsumer and preconsumer recycled content for products having recycled content. Include statement of costs.
- 6. MRc4, Building Product Disclosure and Optimization, Material Ingredients: Option 1, Material Ingredient Reporting.
 - a. Material ingredient reports for products that comply with LEED requirements for material ingredient reporting, including but not limited to the following:
 - Manufacturer Inventory. 1)
 - 2) Health Product Declaration.
 - 3) Cradle to Cradle certifications.
 - Declare product labels. 4)
 - UL Product Lens certifications. 5)

7. EQp2/EQc3/EQc4, Indoor Air Quality: Comply with submittal requirements of Section 018119 - CONSTRUCTION INDOOR AIR QUALITY (IAQ) MANAGEMENT. provided for MRc3.

> EQc2, Low-Emitting Materials: Product data, indicating VOC content and emissions testing documents showing compliance with requirements for low-emitting materials, for the following materials:

- Paints and coatings. a.
- Adhesives and sealants. b.
- Flooring. C.

8.

Cost data will be

That work is

Cost date will be provided on

Complete

. submitted

complete. preliminary

action plans will not be.

once

plans will be

individual material reporting forms 06

Α.

В.

C.

underway

d. Products containing composite wood or agrifiber products or wood glues.

INFORMATIONAL SUBMITTALS

Qualification Data: For LEED coordinator.

Project Materials Cost Data: Provide statement indicating total cost and shop labor for materials used for Project. Costs exclude site labor, overhead, and profit. Include breakout of costs for the following categories of items:

- Wood construction materials.
- 2. Furniture.

1.

- Passive plumbing materials. 3.
- 4. Passive mechanical (HVAC) materials.
- Passive electrical materials. 5.
- 6. Earthwork and exterior improvements, hard costs.

LEED Action Plan Components: Provide preliminary submittals within 30 days of date established for commencement of the Work indicating how the following requirements will be met:

1. MRp2/MRc5, Waste management plan, complying with Section 017419 -CONSTRUCTION WASTE MANAGEMENT.

at the

work.

BROOKLINE HIGH SCHOOL EXPANSION

REVISION: FB-005 - GMP Bid Set - AUGUST 1, 2019

- 2. EQp2/EQ3/EQ4, Indoor air quality plan, complying with Section 018119 -CONSTRUCTION INDOOR AIR QUALITY (IAQ) MANAGEMENT. **Bi-monthly** D. LEED Progress Reports: Goncurrent with each Application for Payment, submit reports comparing actual construction and purchasing activities with LEED action plans for the Strike, Except following: MRp2, per general note, 1. MRp2/MRc5, Waste reduction progress reports complying with Section 017419 all products CONSTRUCTION WASTE MANAGEMENT. are specified as compliant so progress 2 MRc2, Building product disclosure and optimization - environmental product reports are not declarations. required. We will submit for record 1 time 3. MRc3, Building product disclosure and optimization – sourcing of raw materials. completion of General: Manufacturing locations. a. Option 2: b. Bio-based materials. 1) 2) Certified wood products. 3) Materials reuse. 4) Recycled content. MRc4, Building product disclosure and optimization – material ingredients. 4 Progress reports on LEED tracking is aterials. required. Per the CA kick off meetings terials Tracking Sheet monitoring the project's progress towards and regular follow up CA check-in ndoor Environmental Quality Credits. Tracking Sheet to be meetings underway, LEED tracking is nstruction meetings. underway and progress updates are y, during construction, complying with Section 018119 being provided by Skanska. Materials OOR AIR QUALITY (IAQ) MANAGEMENT. requirements listed in Part 2 Products must be tracked and documented. ware assessment, complying with Section 018119 - CONSTRUCTION INDOOR AIR QUALITY (IAQ) MANAGEMENT. QUALITY ASSURANCE 1.07 Α. LEED Coordinator: Engage an experienced LEED-Accredited Professional to coordinate LEED requirements. LEED coordinator may also serve as waste management coordinator. GENERAL NOTE: Skanska assumes that compliance with any and all LEED requirements have been specifically included in the Contract Documents in the trade specific specification sections required to obtain compliance. Should a product be listed in the trade specific PART 2 - PRODUCTS specification section that conflicts with Division 1 Sustainable Design Requirements, we have included the product as identified in the trade specific specifications. It is the MATERIALS, GENERAL Architect's responsibility to specify products that comply with the Sustainable Design 2.01 Requirements. Α. Provide products and probedures necessary to obtain LEED credits required in this Section.
 - Although other Sections may specify some requirements that contribute to LEED credits, the Contractor shall determine additional materials and procedures necessary to obtain LEED credits indicated. Contractor to determine a combination of credit options best suited for achieving credits required.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

1. Exclusions: Special equipment, such as elevators, escalators, process equipment, and fire suppression systems, is excluded from the credit calculations. Also excluded are products purchased for temporary use on the project, like formwork for concrete.

2.02 BUILDING PRODUCT DISCLOSURE AND OPTIMIZATION

- A. MRc2, Building Product Disclosure and Optimization, Environmental Product Declarations (EPD). Option 1. Provide at least 20 permanently installed products (sourced from at least 5 different manufacturers) which meet one of the disclosure criteria:
 - 1. Product-Specific Declaration: Valued as one quarter (1/4) of a product.
 - 2. Industry-Wide (Generic) EPD: Valued as one half (1/2) of a product.
 - 3. Product-Specific Type III EPD: Valued as one whole product.
- B. MRc3, Building Product Disclosure and Optimization, Sourcing of Raw Materials: Option 2, Leadership Extraction Practices. Provide products that meet at least one of the responsible extraction criteria below for at least 25%, by cost, of the total value of permanently installed building products in the project:
 - 1. Bio-based materials
 - 2. Certified Wood: Wood-based materials include, but are not limited to, the following materials when made from wood, engineered wood products, or wood-based panel products:
 - a. Rough carpentry.
 - b. Miscellaneous carpently.
 - c. Heavy timber construction.
 - d. Wood decking.
 - e. Metal-plate-connected wood trusses.
 - f. Structural glued-laminated timber.
 - g. Finish carpentry.
 - h. Architectural woodwork.
 - i. Wood paneling.
 - j. Wood veneer wall covering.
 - k. Wood flooring.
 - I. Wood lockers.
 - m. Wood cabinets.
 - 3. Recycled content.
 - a. Exceptions: Do not include furniture, fire protection, operational plumbing, operational mechanical, and operational electrical components, and specialty items, such as elevators and equipment, in the calculation.
- C. MRc4, Building Product Disclosure and Optimization, Material Ingredients: Option 1, Material Ingredient Reporting.
 - 1. Use at least 20 different permanently installed products from at least five different manufacturers that use any of the following programs to demonstrate the chemical inventory of the product to at least 0.1% (1000 ppm), which meet one of the following disclosure criteria:
 - a. Manufacturer Inventory.
 - b. Health Product Declarations (HPDs).

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- c. Cradle to Cradle (C2C) certifications.
- d. Declare product labels.
- e. UL Product Lens certifications.

2.03 LOW-EMITTING MATERIALS

- A. EQc2, Low-Emitting Materials, General Emissions Requirements: Products must demonstrate they have been tested and determined compliant in accordance with California Department of Public Health, (CDHP), Standard Method v1.1-2010, using the applicable exposure scenario. Manufacturer's documentation demonstrating compliance must state the range of total VOCs (tVOC) after 14 days measured as specified in the CDPH Standard Method v1.1 as follows:
 - 1. 0.5mg/m3 or less,
 - 2. between 0.5 and 5.0 mg/m3 or,
 - 3. 0.50 mg/m3 or more.
- B. EQc2, Low-Emitting Materials, Paints and Coatings: For field applications that are inside the weatherproofing system, use paints and coatings that comply with the limits for VOC content when calculated according to the California Air Resources Board (CARB) 2007, Suggested Control Measure (SCM) for Architectural Coatings, or the South Coast Air Quality Management District (SCAQMD) Rule 1113, effective June 3, 2011.

Product Type:	Allowable VOC Content (g/L):
Bond Breaker	350
Clear wood finishes - Varnish	275
Clear wood finishes – Sanding Sealer	275
Clear wood finishes - Lacquer	275
Colorant – Architectural Coatings, excluding IM	50
coatings	
Colorant – Solvent Based IM	600
Colorant - Waterborne IM	50
Concrete – Curing compounds	100
Concrete – Curing compounds for roadways & pridges	350
Concrete surface retarder	50
Driveway Sealer	50
Dry-fog coatings	50
Faux finishing coatings - Clear topcoat	100
Faux finishing coatings – Decorative Coatings	350
Faux finishing coatings - Glazes	350
Faux finishing coatings - Japan	350
Faux finishing coatings – Trowel applied coatings	50
Fire-proof coatings	150
Flats	50
Floor coatings	50
Form release compounds	100
Graphic arts (sign) coatings	150
Industrial maintenance coatings	100
Industrial maintenance coatings – High temperature IM	420
coatings	
Industrial maintenance coatings – Non-sacrificial anti-	100
graffiti coatings	
Industrial maintenance coatings – Zinc rich IM primers	100

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

Magnesite cement coatings	450
Mastic coatings	100
Metallic pigmented coatings	150
Multi-color coatings	250
Non-Nat coatings	50
Pre-treatment wash primers	420
Primers, sealers and undercoaters	100
Reactive penetrating sealers	350
Recycled coatings	250
Roof coatings	50
Roof coatings, aluminum	100
Roof primers, bituminous	350
Rust preventative opatings	100
Stone consolidant	450
Sacrificial anti-graffiti opatings	50
Shellac- Clear	730
Shellac – Pigmented	550
Specialty primers	100
Stains	100
Stains, interior	250
Swimming pool coatings – repair	340
Swimming pool coatings – other	340
Traffic Coatings	100
Waterproofing sealers	100
Waterproofing concrete/masonry sealers	100
Wood preservatives	350
Low solids coatings	120

- C. EQc2, Low-Emitting Materials, Paints and Coatings: For field applications that are inside the weatherproofing system, paints and coatings shall comply with the requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- D. EQc2, Low-Emitting Materials, Adhesives and Sealants: For field applications that are inside the weatherproofing system, use adhesives and sealants that comply with the limits for VOC content when calculated according to South Coast Air Quality Management District (SCAQMD) Rule #1168, requirements in effect on July 1, 2005, and rule amendment date January 7, 2005:

Architectural Applications:	Allowable VOC Content (g/L):
Indoor carpet adhesives	50
Carpet pad adhesives	50
Outdoor carpet adhesives	150
Wood flooring adhesives	100
Rubber floor adhesives	60
Subfloor adhesives	50
Ceramic tile adhesives	65
VCT and asphalt tile adhesives	50
Dry wall and panel adhesives	50
Cove base adhesives	50
Multipurpose construction adhesives	70
Structural glazing adhesives	100
Single ply roof membrane adhesives	250

REVISION: FB-005 - GMP Bid Set - AUGUST 1, 2019

Specialty Applications:	
PVC welding	510
CPVC welding	490
ABS welding	325
Plastic cement welding	250
Adhesive primer for plastic	550
Computer diskette manufacturing	350
Contact adhesive	80
Special purpose contact adhesive	250
Tire retread	100
Adhesive primer for traffic marking tape	150
Structural wood member adhesive	140
Sheet applied rubber lining operations specialty	850
Top and Trim adhesive	250
Substrate Specific Applications:	
Metal to metal substrate specific adhesives	30
Plastic foam substrate specific adhesives	50
Porous material (except wood) substrate specific adhesives	50
Wood substrate specific adhesives	30
Fiberglass substrate specific adhesives	80
Sealants:	
Architectural sealant	250
Marine deck sealant	760
Nonmember roof sealant	300
Roadway sealant	250
Single-ply roof membrane sealant	450
Other sealant	420
Sealant Primers:	
Architectural non-porous sealant primer	250
Architectural porous sealant primer	775
Modified bituminous sealant primer	500
Marine deck sealant primer	760
Other sealant primer	750
Other	
Other adhesives, adhesive bonding primers, adhesive	250
primers or any other primers	

- 1. Exception: The provisions of SCAQMD Rule 1168 do not apply to adhesives and sealants subject to state or federal consumer product VOC regulations.
- E. EQc2, Low-Emitting Materials, Adhesives and Sealants: For field applications that are inside the weatherproofing system, adhesives and sealants shall comply with the requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- F. EQc2, Low-Emitting Materials, Flooring: Flooring shall comply with the requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- G. EQc2, Low-Emitting Materials, Composite Wood: Composite wood, agrifiber products, and adhesives shall be made using ultra-low-emitting formaldehyde (ULEF) resins as defined in the

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

California Air Resources Board's "Airborne Toxic Control Measure to Reduce Formaldehyde Emissions from Composite Wood Products" or shall be made with no added formaldehyde.

- H. Additional Low-Emitting Requirements:
 - 1. If the applicable regulation requires subtraction of exempt compounds, any content of intentionally added exempt compounds larger than 1% weight by mass (total exempt compounds) must be disclosed.
 - 2. If a product cannot reasonably be tested as specified above, testing of VOC content must comply with ASTM D2369-10; ISO 11890, part 1; ASTM D6886-03; or ISO 11890-2.
 - 3. Methylene chloride and perchloroethylene may not be intentionally added in paints, coatings, adhesives, or sealants.
- 2.04 INDOOR WATER USE REDUCTION
 - A. WEp2, Indoor Water Use Reduction, Appliances: Provide US EPA ENERGY STAR labeled or performance equivalent appliances, where applicable.
 - B. WEp2/WEc2, Indoor Water Use Reduction, Plumbing Fixtures: Do not exceed water flow requirements indicated in Division 22 PLUMBING.
 - 1. Provide US EPA WaterSense labeled plumbing fixtures, where applicable.

PART 3 - EXECUTION

- 3.01 NONSMOKING BUILDING By Owner, not construction
 - A. EQp2, Environmental Tobacco Smoke Control: Smoking is not permitted within the building or within 25 feet (8 m) of entrances, operable windows, or outdoor-air intakes.
 - 1. Refer to Section 018119 CONSTRUCTION INDOOR AIR QUALITY (IAQ) MANAGEMENT.
- 3.02 CONSTRUCTION WASTE MANAGEMENT
 - A. MRp2/MRc5, Construction and Demolition Waste Management: Comply with Section 017419 CONSTRUCTION WASTE MANAGEMENT.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- 3.03 CONSTRUCTION INDOOR-AIR-QUALITY MANAGEMENT
 - A. EQc3/EQc4, Construction Indoor Air Quality Management Plan: Comply with Section 018119 CONSTRUCTION INDOOR AIR QUALITY (IAQ) MANAGEMENT.
- 3.04 LEED V4 FOR SCHOOLS SCORECARD
 - A. Refer to Section 018111.
- 3.05 LEED V4 MATERIALS REPORTING FORM
 - A. Refer to Section 018112.

END OF SECTION

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

SECTION 018119

CONSTRUCTION INDOOR AIR QUALITY (IAQ) MANAGEMENT

PART 1 - GENERAL

- 1.1 GENERAL PROVISIONS
 - A. Attention is directed to Division 00 PROCUREMENT AND CONTRACTING REQUIREMENTS and DIVISION 01 GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.
 - B. Examine all other Sections of the Specifications for requirements that affect work of this Section, whether or not such work is specifically mentioned in this Section.
 - C. Coordinate Work with that of all other trades affecting or affected by Work of this Section. Cooperate with such trades to assure the steady progress of all Work under the Contract.

1.2 SUMMARY

- A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:
 - 1. LEED EQp1, Environmental Tobacco Smoke Control: Prevent exposure of building systems to environmental tobacco smoke during construction.
 - 2. LEED EQc3, Construction Indoor Air Quality Management Plan: Requirements for minimum indoor air quality (IAQ) performance standards during the construction period.
 - 3. LEED EQc4, Indoor Air Quality Assessment: Requirements for assessment of minimum indoor air quality (IAQ) performance standards through either building flush-out or air testing before occupancy
- B. Sustainable Design Intent: Comply with project requirements intended to achieve certification, measured and documented according to the LEED Green Building Rating System, of the US Green Building Council. Refer to Section 018110 - SUSTAINABLE DESIGN REQUIREMENTS, for certification level and certification requirements.
- C. Related Work: The following items are not included in this Section and are specified under the designated Sections:
 - 1. Section 013200 CONSTRUCTION PROGRESS DOCUMENTATION: Scheduling requirements for building flush-out.
 - 2. Section 013300 SUBMITTAL PROCEDURES for general submittal requirements.
 - 3. Section 015000 TEMPORARY FACILITIES AND CONTROLS for temporary construction facilities, protection, and controls.
 - 4. Section 017419 CONSTRUCTION WASTE MANAGEMENT for demolition and construction waste management.
 - 5. Section 018119 SUSTAINABLE DESIGN REQURIEMENTS: Sustainable design requirements
 - 6. Section 075400 THERMOPLASTIC MEMBRANE ROOFING: Sealing of air intakes during roofing installation.

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

- 7. Division 23 HVAC: For coordination with HVAC requirements, temporary and permanent filters, and other provisions for air handling systems
- 8. Divisions 02 through 49 Specification Sections for specific requirements relating to indoor air quality.

1.3 PERFORMANCE REQUIREMENTS

- A. LEED EQp1, Environmental Tobacco Smoke Control: At a minimum, take the following measures:
 - 1. Comply with Owner's Non-Smoking Campus Policy.
 - 2. Do not allow smoking in enclosed portions of the project site, on the rooftop, or in construction trailers.
 - a. This prohibition includes electronic cigarettes.
 - 3. Locate exterior designated smoking areas at least 25 feet away from entries, outdoor air intakes, and operable windows. Provide signage for designated smoking areas, located within 10 feet of each entry. Provide ash receptacles and clean areas daily.
- B. LEED EQc3, Construction Indoor Air Quality Management Plan: During construction, comply with the following requirements:
 - 1. Coordinate with Owner's current IAQ management plans and procedures.
 - 2. Meet or exceed the minimum requirements of the recommended Control Measures of the Sheet Metal and Air Conditioning National Contractors Association (SMACNA) IAQ Guidelines for Occupied Buildings Under Construction, Second Edition, November 2007, Chapter 3.
 - 3. If permanently installed air handlers are used during construction, filtration media with a Minimum Efficiency Reporting Value (MERV) of 8 shall be used at each return air grille, as determined by ASHRAE 52.2-2007. Replace filtration media immediately prior to occupancy, according to Division 23 HVAC.
- C. LEED EQc4, Indoor Air Quality Assessment: Comply with one of the following requirements:
 - 1. Option 1: Perform a building flush-out with outside air, either before occupancy or during occupancy. Schedule does not support performing prior to

occupancy. Flush out has not been included.

1.4 SUBMITTALS

C says one of following,

but only 1 is listed? Not

sure

schedule

supports

flush out

- A. LEED EQc3, Construction Indoor Air Quality Management Plan: Within 21 calendar days after receipt of Notice to Proceed, the Contractor shall submit Construction IAQ Management Plan.
 - 1. Construction IAQ Management Plan: Include, but do not limit to, the following:
 - a. HVAC Protection.
 - b. Source Control.
 - c. Pathway Interruption.
 - d. Housekeeping.
 - e. Scheduling.
 - 2. Product Data: Submit for each type of filtration media used during construction and installed immediately prior to occupancy, with MERV values clearly identified.
- B. LEED EQc4, Indoor Air Quality Assessment:

REVISION: FB-005 – GMP Bid Set – AUGUST 1, 2019

Not specifically bought from HVAC sub? 1. Option 1, Flushout: Signed statement describing the building air flush-out procedures, including the dates when flush-out was begun and completed and statement that filtration media was replaced after flush-out. a. Product Data: Submit for filtration media used during flush-out and occupancy, with

. Product Data: Submit for filtration media used during flush-out and occupancy, with MERV values clearly identified.

PART 2 - PRODUCTS

- 2.1 FILTRATION MEDIA
 - A. Filtration Media: Comply with ASHRAE 52.2-2007 and provide MERV as required.
- PART 3 EXECUTION
- 3.1 CONSTRUCTION IAQ MANAGEMENT PLAN IMPLEMENTATION
 - A. IAQ Manager: The Contractor shall designate an on-site person responsible for instructing workers and overseeing and documenting results of the Construction IAQ Management Plan for the Project.
 - 1. Distribution: The Contractor shall distribute copies of the Construction IAQ Management Plan to the Job Site Foreman, each subcontractor, the Owner, and the Architect.
 - 2. Instruction: The Contractor shall provide on-site instruction of appropriate procedures and methods to be used by all parties at the appropriate stages of the Project.
 - B. Preconditioning: Allow products, which have odors and significant VOC emissions, to off-gas in a dry, well-ventilated space for sufficient period to dissipate odors and emissions prior to delivery to Project.
 - 1. Remove containers and packaging from materials prior to conditioning to maximize offgassing of VOCs.
 - 2. Condition products in ventilated warehouse or other building.
 - C. Ventilation: Ventilate interior spaces directly to the exterior to minimize accumulation of odors and VOC emissions during construction.
 - D. Coordinate Construction IAQ Management Plan with construction cleaning as indicated in Section 015000 TEMPORARY FACILITIES AND CONTROLS and with final cleaning as indicated in Section 017700 CONTRACT CLOSEOUT.
- 3.2 INDOOR AIR QUALITY (IAQ) ASSESSMENT
 - A. LEED EQc4, Indoor Air Quality Assessment: Option 1, Flush-Out:
- Exclude, cannot be achieved in current schedule 1. After construction ends, prior to occupancy and with all interior finishes installed, perform a building flush-out by supplying a total volume of 14,000 cu. ft. of outdoor air per sq. ft. of floor area while maintaining an internal temperature of at least 60 deg F and a relative humidity no higher than 60 percent.
 - a. Operating Requirements: Refer to Division 23 HVAC.

current

BROOKLINE HIGH SCHOOL EXPANSION

REVISION: FB-005 - GMP Bid Set - AUGUST 1, 2019

2. If occupancy is desired prior to flush-out completion, the space may be occupied following delivery of a minimum of 3500 cu. ft. of outdoor air per sq. ft. of floor area to the Exclude, space. Once a space is occupied, it shall be ventilated at a minimum rate of 0.30 cfm per cannot be achieved in sq. ft. of outside air or the design minimum outside-air rate, whichever is greater. During each day of the flush-out period, ventilation shall begin a minimum of three hours prior to schedule occupancy and continue during occupancy. These conditions shall be maintained until a total of 14,000 cu. ft./sq. ft. of outside air has been delivered to the space.

> Operating Requirements: Refer to Division 23 - HVAC. a.

END OF SECTION

SECTION 019113

COMMISSIONING

PART 1 - GENERAL

1.1 GENERAL PROVISIONS AND GOALS

- A. Attention is directed to the Contract, General Conditions, and all sections within Division 1 General Requirements that are hereby made part of this Section of the Commissioning Plan/Specifications.
- B. Examine all Sections of the Specifications for requirements that affect work under this Section and in particular, Divisions 1, 14, 21, 22, 23, 26, 27 and 28.
- C. This Section of the Contract is set aside to incorporate current Commissioning contract requirements and to be the document by which this Section of the Contract will be built into the Final Commissioning Report.
- D. The Final Commissioning Report will be that document by which LEED, Additional Commissioning Point Criteria compliance is met.
- E. Commissioning Goal: Commissioning is a systematic process of ensuring that all building systems perform interactively according to the design intent and the Owner's operational needs. This is achieved by beginning in the Design Phase and documenting design intent and continuing through construction, acceptance and the warranty period with actual verification of performance. The commissioning process encompasses and coordinates the traditionally separate functions of system documentation, equipment start-up, automatic control system calibration, testing, adjusting, and balancing (TAB), electrical systems, plumbing systems, fire protection systems, HVAC systems, process, electrical, and performance testing and training.
- F. Commissioning Goal: To have the Contractor complete a comprehensive system readiness process followed by system demonstration to the Commissioning Team with the CA providing the documentation/verification of the building systems that they perform in accordance with the requirements of the contract documents. In addition, the commissioning process may be in compliance with the Energy & Atmosphere prerequisite credit 1 (EAp1) and additional enhanced commissioning credit (EAc1) in compliance with LEED certification.
- G. Abbreviations found in this specification:
 - 1. Commissioning Agent CA
 - 2. Pre-functional Performance Checklist PFPC
 - 3. Functional Performance Test FPT
 - 4. Testing, Adjusting and Balancing TAB
- 1.2 COMMISSIONING PLAN
 - A. The Commissioning Plan outlines the contract requirements once authorization-to-proceed with construction has been given and the plan extends into the Warranty Phase

- B. The Owner shall champion the commissioning process with the CA to commission the building systems to the quality standards and procedures specified herein and as documented on the contract drawings and to LEED Certification compliance.
- C. As information to the Commissioning Team joining in the commissioning process at the Construction Phase the CA completed the following in the Design Phase:
 - 1. Created the Commissioning Plan
 - 2. Review the development of the Owner's Project requirements (OPR).
 - 3. Review the Design Engineer's Basis of Design (BOD).
 - 4. Included within the Commissioning Specification sample of the suggested PFPC checklists, Commissioning Test Plan & Schedule template, and draft FPT narrative for Contractor understanding of commissioning process and contract requirements.
- D. The following activities will be completed by the Commissioning Team per the contract documents and also in accordance with the Fundamental and Enhanced Commissioning criteria for LEED Commissioning Credit starting in the Design Phase:
 - 1. Review the OPR throughout the project including the following OPR issues.
 - a. Owner and User Requirements.
 - b. Environmental and sustainability goals.
 - c. Energy efficiency goals.
 - d. Indoor environmental and quality requirements.
 - e. Equipment and system expectations.
 - f. System training goals.
 - g. Building Occupant and O&M Personnel Requirements.
 - 2. CA shall complete a Summary Commissioning Report per LEED Credits EAp1 and EAc1 at the end of the project.
 - 3. Design Team shall assist in the Owners development of the OPR and keep their Basis of Design (BOD) documents current throughout the Construction Phase. Both documents are to be included in the Final Commissioning Report and are part of the LEED certification process per LEED v4 Credits EAp1 and EAc1.
 - 4. Commissioning Team shall utilize the Commissioning Plan per LEED Credits EAp1 and EAc1. The following are integral parts of the Commission Plan and are imbedded into this Section of the specification:
 - a. Commissioning Program Overview
 - 1) Goals and objectives
 - 2) General Project Information
 - 3) Systems to be commissioned
 - b. Commissioning Team
 - 1) Team members, roles and responsibilities.
 - 2) Communication protocol, coordination, meetings, field visits, and overall commissioning project management.
 - c. Description of Commissioning Process Activities
 - 1) Documenting the Owner's Project Requirements.
 - 2) Preparing the Basis of Design.
 - 3) Developing systems Functional Performance Test (FPT) procedures.

- 4) Prepare systems for FPT demonstration to the Commissioning Team.
- 5) Verifying systems performance.
- 6) Reporting deficiencies and the resolution process.
- 7) Accepting the building systems.
- d. Project is pursuing the Enhanced Commissioning Credit (EAc1) to include the following commissioning process activities:
 - 1) Documenting the Commissioning Review Process.
 - 2) Review of Contractor submittals.
 - 3) Compile the Systems Manual.
 - 4) Verification of training of operations personnel.
 - 5) Reviewing building operation after final acceptance.
- 5. CA shall review Contractor submittals applicable to systems being commissioned per LEED Credit EAc1.
- 6. CA shall verify the installation and performance of commissioned systems per LEED Credits EAp1 and EAc1.
 - a. Installation Observation.
 - b. Systems Performance Testing.
 - c. Evaluation of Results compared to OPR/BOD.
- 7. CA shall assist the development with the Commissioning Team of a Systems Manual for the commissioned systems per LEED Credit EAc1. The Systems Manual provides future operating staff the information needed to understand and optimally operate the commissioned systems. A Systems Manual is in addition to the O&M Manuals submitted by the Contractors. The Systems Manual requires the following for each commissioned system:
 - a. Final version of the Basis of Design (provided by the Design Team).
 - b. System single-line diagrams (provided by the Design Team and may include the TAB system flow diagrams and the CAs system flow diagrams).
 - c. As-built sequences of operations, control drawings and original set points (provided by the ATC Contractor and each Equipment Manufacturer's ATC submittal for pre-packaged ATC).
 - d. Operating instructions for integrated building systems (provided by the Contractor).
 - e. Recommended schedule of maintenance requirements and frequency requirements and frequency, if not already included in the project O&M Manuals (provided by the Contractor).
 - f. Recommended schedule for retesting of commissioned systems with blank test forms from the original Commissioning Plan (provided by the CA).
 - g. Recommended schedule for calibrating sensors and actuators (provided by the ATC Contractor and each Equipment Manufacturer's ATC submittal for prepackaged ATC).
 - h. PFPC documents from the System Manual specified herein (provided by the Contractor).
- 8. CA shall verify that the requirements for training are completed by the Construction Manager/GC and their team per LEED Credit EAc1 and Contract Documents.
- 9. CA shall review building operation within 10-months after substantial completion per LEED Credits EAc1.

- 10. CA shall complete a Summary Commissioning Report per LEED Credits EAp1 and EAc1.
- E. In the Construction Phase, the Contractor shall work closely with the CA in establishing and maintaining the schedule of commissioning events for the commissioning of systems and activities noted here based on the draft Commissioning Test Plan & Schedule.
- F. Commissioning of the selected systems shall consist of documentation of system readiness prior to demonstration using the PFPC checklists followed by demonstration of the system using the FPTs.
- G. The PFPCs shall be developed and provided to the Contractor by the CA and shall be used in concert with the addition of Equipment Manufacturer start-up checklists, Contractor's own "static inspection" checklists, Pre-TAB checklists, ATC System Graphics, and Control Contractor (both the ATC firm and each Equipment Manufacturer providing packaged ATC) point-to-point checkout check lists as part of Contract equipment and system start-up system readiness process. In addition, the ATC contractor(s) shall provide a minimum of 16 hours system trending prior to the FPT system demonstrations continuing on with a minimum of 40 additional hours of system trending.
- H. These PFPC documents shall be included in an on-site 3-ring binder(s) and kept current by the Contractor during the Construction Phase. This binder shall become an integral part of the Systems Manual at the end of the project.
- I. The CA shall complete random installation observation per contract documents and shall include in each commissioning Field Report, the associated equipment and distribution Observation Checklists.
- J. Commissioning of the selected systems shall consist of demonstration of the interactive system operation through the use of finalized FPT narratives. The FPT narratives shall be completed with input during the Construction Phase from the Contractor and Design Team and used to verify operation per design intent through all modes and conditions. Facility staff shall participate and receive on-the-job training during the system demonstration.
- K. Prior to Project Closeout, the Contractor, with the assistance of the CA shall compile the Systems Manual LEED Credit EAc1.
- L. In the Post-Construction Phase, the CA shall facilitate a 10-month Warranty/Project Closeout meeting, as well as facilitate a seasonal/deferred system demonstration (i.e., FPT for heating system in heating season) per LEED Credit and EAc1.

1.3 SYSTEMS TO BE COMMISSIONED

- A. Systems include all interconnected components and are not limited to the equipment listed within this specification.
 - 1. HVAC Systems: Heating, ventilating and air conditioning systems, and mechanical equipment forming a part of these systems including, but not limited to, air handler systems, boilers, chillers, direct expansion refrigeration equipment, fuel storage, pumps, fans, exhaust systems, ventilation systems, variable frequency drives, and heat recovery systems. Terminal equipment such as but not limited to, VRF system, VAV boxes with reheat Coils, VAV return/exhaust boxes, finned tube radiation, radiant heating panels, unit heaters and cabinet unit heaters will be commissioned at 25%, randomly selected.

- 2. Building Automation, Temperature Controls and Energy Management systems and all equipment forming a part of these systems including, but not limited to, the interface of these systems with HVAC systems, plumbing electrical, fire alarm and security systems.
- 3. Plumbing Systems and all equipment forming a part of these systems including, but not limited to, potable and non-potable water systems, water pressure booster systems, service water heating systems, sanitary waste and vent systems, grey water systems, laboratory waste and acid neutralization systems, storm water systems including rain water reclamation systems, natural gas systems, and compressed air systems.
- 4. Electrical Power Systems and all equipment forming a part of these systems including, but not limited to, electrical supply and distribution systems, emergency and standby power systems including automatic transfer switching systems, uninterrupted power supplies, lighting and lighting control systems, low voltage systems, grounding and bonding systems, and interfaces to automated temperature/building automation control systems.
- 5. Life Safety Systems and all equipment forming a part of these systems including, but not limited to, security and surveillance systems, fire alarm systems, fire protection and suppression systems and egress lighting.
- B. Commissioning Activities
 - 1. Construction Phase
 - a. Facilitate a Commissioning Team Kick-off Meeting with handouts referencing Commissioning Test Plan & Schedule and the Systems Manual Table of Content to provide a Commissioning Education Platform to the Commissioning Team.
 - b. Participate in regularly scheduled commissioning field coordination meetings facilitated by the CA at intervals based on meetings with the Contractor, TAB Firm, installing Trade Sub-Contractors, Control Contractor (both the ATC firm and each Equipment Manufacturer providing packaged ATC) and Owner facility manager representative. The purpose of the meetings will be to review the status of commissioning activities, schedule future activities, and resolve commissioning process issues.
 - c. Respond to comments on submittals that have been reviewed for commissionability per LEED Credit EAc1.
 - 1) Review for conformance with the OPR and basis of design.
 - 2) Fulfilling Operation and Maintenance Requirements.
 - 3) Facilitating performance testing.
 - d. Coordinate and schedule the pre-functional and functional performance activities, as well as the TAB and other trade activities.
 - e. Review the following in the shop drawing phase:
 - 1) Equipment submittals for equipment/systems to be commissioned.
 - 2) TAB submittal including the TAB Plan and associated system flow diagrams indicating design data at pertinent test points in the air and water systems.
 - 3) Equipment and System Training Plan submittal.
 - 4) ATC submittal (both the ATC firm and each Equipment Manufacturer providing packaged ATC).
 - 5) Systems Manual Table of Content.
 - 6) O&M Manuals at end of Submittal Phase.
 - f. Review and respond to pertinent RFIs and change orders associated with the commissioning process.

- g. Respond to comments on mechanical and electrical field coordination drawings that have been reviewed for commission-ability.
- h. Observe and document PFPCs for systems being commissioned per LEED Credits EAp1 and EAc1.
- i. Observation of Installation per contract documents all major systems and randomly selected support equipment to be commissioned using Observation Checklists.
- j. Observe and document randomly observed equipment manufacturer's startup for systems being commissioned.
- k. Review of the Systems Manual as it is developed during the Construction Phase.
- I. Facilitate and document FPTs for systems being commissioned per LEED Credits EAp1 and EAc1.
- m. Maintaining and resolving Corrective Action Log issues.
- n. Participate in System Education/Training.
- 2. Post-Construction Phase:
 - a. Perform seasonal/deferred FPT demonstration.
 - b. Facilitate in a Warranty/Project Closeout meeting at month 10 per LEED Credit EAc1.
 - c. Complete Final Commissioning Report document per LEED Credits EAp1 and EAc1.
 - d. Complete LEED compliance within Final Commissioning Report per LEED Credits EAp1 and EAc1 as well as Letter of Certification Hard Copy and On-Line requirements.
 - e. Final Report to include Systems Manual as well as Letter of Certification per LEED Credit EAc1.

PART 2 - PRODUCT

2.1 COMMISSIONING TEAM

- A. The Commissioning Team shall consist of representatives from the following parties involved in the design and construction of this facility:
 - 1. Owner's Project Manager
 - 2. Owner's Facility Operator and/or Manager
 - 3. Commissioning Firm
 - 4. Design Team Professionals (associated with system to be commissioned)
 - 5. Contractor
 - 6. Testing Adjusting & Balancing (TAB) Contractor
 - 7. Automatic Control Contractor
 - 8. LEED Accredited Professional Consultant
 - 9. Trade Contractors (associated with system to be commissioned).
 - 10. Equipment Manufacturers (associated with system to be commissioned).
 - 11. Equipment Manufacturer's Automatic Control Engineer (associated with equipment furnished with pre-packaged automatic controls as part of systems to be commissioned).
 - 12. Independent Testing Agencies (associated with system to be commissioned).
 - 13. Regulatory Agency (as needed)
- 2.2 SYSTEMS MANUAL
 - A. The Systems Manual Table of Content shall be the initial cover sheet document that will begin the process of compiling all pertinent documentation associated with each system readiness. Other check lists to be included shall be the following on a system-by-system basis:

AUGUST 1, 2019

- 1. Trade Contractor's static inspection (punch list) checklist
- 2. Manufacturer's equipment startup checklist
- 3. ATC point-to-point checklist
- 4. ATC graphics & programming documents
- 5. Pre-TAB equipment checklists & draft of each system's balancing report along with associated system flow diagram (design-to-actual).
- 6. Trending graphs
- 7. Dry-run FPT sign-off document
- B. Using the enhanced PFPC checklists, the Trade Contractor (i.e., for HVAC, the associated ATC and TAB firms, etc.) shall complete the Pre-Functional Test documents and submit the completed signed forms and other appropriate start-up sheets. Trade Contractor shall submit the completed forms, initialed by the technician in-charge and attach other appropriate start-up sheets including but not limited to documents noted above prior to the start of the demonstration of the FPT Demonstration(s) to the Owner.
- C. Each step in the PFPC process shall be initially scheduled within the Commissioning Test Plan & Schedule and updated as work is completed and each step shall be completed with a document indicating the work completed.

2.3 TRAINING

- A. The Construction Manager/GC shall submit the Training Plan in a three-ring binder in the Submittal Phase based on the specification herein. Each Trade Contractor shall include within this binder, their training plan and class handouts. Once Training Plan is reviewed by the Construction Manager/GC, and approved by CA, they shall coordinate the following classes leading up to the final Training.
 - 1. Introduction to the Training Plan at end of Submittal Phase (approximately 2 hr session).
 - 2. Progress training with walk-thru of site once major equipment has been installed (approximately 4 hour session).
 - 3. System Training when commissioning of systems (FPT) occurs.
 - 4. Final Training as within specifications.

2.4 OBSERVATION OF INSTALLATION CHECKLISTS

- A. Using the Observation of Installation Checklist, the CA will visit the project site and randomly perform a system-readiness on systems being commissioned. The CA will use these sheets in concert with the construction documents specified herein. In addition, the approved submittals and RFIs that are on record will be referenced to ensure all field installation/design changes are noted on the completed observation sheet prior to distribution to the Commissioning Team.
- B. All Observation Deficiencies will be noted in a Corrective Action Log and distributed to the Contractor and Design Engineer for corrective measures.
- C. All deficiencies noted on the Observation Corrective Action Log shall be corrected by the appropriate responsible Trade, given to the Contractor who will provide the completed Corrective Action Log updates to the CA prior to system FPT demonstration to Owner.

2.5 FUNCTIONAL PERFORMANCE TEST NARRATIVES

A. The Contractor along with the rest of the Commissioning Team members (particularly the design engineer) shall review and comment on the FPT narratives specified herein and edit

them based on the approved sequence of operation submittals and return documents to the CA prior to system commissioning for final FPT narratives.

- B. The CA shall revise the FPT narratives during the Construction Phase to incorporate any changes required to comply with the approved submittals and any contract document changes. The revised FPT narratives shall be issued as Final and Approved for executed documents.
- C. The Contractor shall use the FPT narratives to test the systems prior to demonstrating the FPT to the Owner, Facility Manager, and Commissioning Firm. The Contractor shall submit a completed and signed Final FPT form to the CA as evidence that the Contractor and associated Trade Contractors have dry-run tested the systems. All deficiencies noted by the Contractor during the dry-run, will be corrected and noted on the signed off/completed FPT document prior to the CA scheduling the demonstration of the systems to the Owner. This document shall be filed in the Systems Manual.
- D. The Contractor shall make available, during the testing phase, the manufacturer's representative/technician to execute sequences of operation that cannot be demonstrated by the Contractor to the Owner and CA due to their being part of an packaged unit not under their control.
- E. The Contractor shall use the Final FPT narrative format to commission the building systems demonstrating the Functional Performance to the Owner and the CA. During the Owner demonstration all deficiencies that can be corrected within 10 minutes, may be completed. Any corrective measures that will require more than a 10-minute corrective measure will be documented by the CA in a Corrective Action Log for re-testing by the trades at a later, scheduled date.
- F. The Contractor shall respond to the Commissioning Firm's Corrective Action Log depicting noncompliant system demonstration items to be corrected within (3) business days after receipt of Corrective Action Log.
- PART 3 EXECUTION
- 3.1 COMMISSIONING TEAM MEMBER RESPONSIBILITIES.
 - A. The responsibilities of the various parties in the commissioning process are provided in this section. The responsibilities of the mechanical contractor (included TAB), BMS Contractor and the electrical contractor are included herein. The Design Engineer, Owner's Project Manager or Owner's Representative are also part of the Commissioning Team.
 - B. All Parties
 - 1. Attend commissioning scoping meeting and additional meetings as necessary.
 - C. Owner Project Manager shall:
 - 1. Champion the commissioning process.
 - 2. Participate in the development of the Owner's Project Requirement (OPR) document.
 - 3. Review and comment on any revisions to the Basis of Design (BOD) document.
 - 4. Attend commissioning specific coordination meetings.
 - 5. Participate in Pre-Functional Checklist observation.
 - 6. Participate in Functional Performance Testing.
 - 7. Participate in system education/training.

- D. Owner Facility Operator and/or Manager shall:
 - 1. Periodically visit the construction site to become familiar with the project equipment/system installation.
 - 2. Attend commissioning coordination meetings.
 - 3. Review equipment, system and control submittals for Basis of Design (BOD).
 - 4. Work with other the Construction Manager/GC and Contractors to review completion of the Data Retrieval Sheet and the development of the Asset Collection Database.
 - 5. Work with other Commissioning Team members with system education/training.
 - 6. Witness and, to the greatest extent possible, participate in the following commissioning activities:
 - a. Initial equipment startup
 - b. Testing, adjusting and balancing
 - c. ATC point-to-point checkout
 - d. PFPCs
 - e. FPTs
 - 7. Work with the Commissioning Team with interface of automatic control systems with existing building automation system.
 - 8. Work with Commissioning Team to develop the Systems Manual.
 - 9. Review commissioning progress and deficiency reports.
 - 10. Arrange for facility operating personnel and maintenance personnel to attend various field commissioning activities and field training sessions.
 - 11. Assist the CA as necessary in the seasonal or deferred testing and deficiency corrections required by the specifications.
 - 12. Participate in any seasonal or deferred testing and any deficiency issues resolution.
- E. Commissioning Agent shall:
 - 1. The CA is not responsible for design concept, design criteria, compliance with codes, design or general construction scheduling, cost estimating, or construction management. The CA may assist with the problem solving of non-conformance or deficiencies, but ultimately that responsibility resides with the individual trade contractors and the design team. The primary role of the CA is to develop and coordinate the execution of the testing plan, observe and document performance that systems are functioning in accordance with the documented design intent and in accordance with the Contract Documents. The Contractors will provide all tools or use of tools to start, check-out and functionally test the equipment. The CA does not touch the equipment, run the equipment of manipulate the building automation system.
 - 2. Facilitate commissioning meetings with the Commissioning Team.
 - 3. Coordinate and direct the commissioning activities in a logical, sequential and efficient manner using consistent protocols and forms, centralized documentation, clear and regular communications and consultations with all necessary parties, frequently updated timelines and scheduled and technical expertise.
 - 4. Coordinate the commissioning work and, with the Construction Manager/GC, onto the Commissioning Test Plan & Schedule.
 - 5. Request and review additional information required to perform commissioning tasks, including O&M Materials, contractor start-up and check-out procedures.
 - 6. Before start-up, gather and review the current control sequences and interlocks and with the contractors and design engineers until sufficient clarity has been obtained, in writing, to be able to write detailed testing procedures.
 - 7. Review and approve normal Contractor submittals applicable to systems being commissioned for compliance with commissioning needs, concurrent with A/E and Construction Manager/GC reviews.

- 8. Receive and review construction documentation (Requests for Information, Bulletins, Change Orders etc.) for impact on commissioning process.
- 9. Maintain Pending Issues Log
- 10. Review commissioned equipment, system and control submittals for OPR and BOD compliance.
- 11. Monitor the collection of the O&M Manuals by the Contractor immediately following the individual approval of equipment submittals and in compliance with LEED Credits EAc1.
- 12. Work with other Commissioning Team members with system education/training and monitor that training was conducted for all commissioning features and systems. Training program needs to address all training/education aspects as per LEED certification compliance. LEED Credits EAc1.
- 13. Complete random installation observation according to contract documents for system readiness assessment and complete each site visit with a Field Visit Report and record of any deficiencies.
- 14. Monitor the Contractor's development of the Systems Manual on-site. Pre-Functional Checklists will be completed by the installing contractors and signed-off and collected by the CA prior to testing of systems.
- 15. Randomly observe startup and checkout of equipment completed by the Contractor and documented per the manufacturer's instructions and contract documents. The CA shall apply a sampling method of start-up observation for systems to be commissioned.
- 16. With assistance of the design engineer and installing contractors, write the FPT procedures for equipment and systems.
- 17. Provide final "draft" FPT procedures to installing contractors for their use in "dry-run" of systems prior to CA observing testing. A sign-off FPT is required by the installing contractors to be provided to the CA before commissioning of the systems is to be scheduled.
- 18. Work with ATC Contractor(s) to create and maintain system trending data. Analyze any functional performance trend logs and monitoring data to verify performance.
- 19. Facilitate and observe FPT demonstrations by observing each Sequence of Operation for each system being commissioned. Observe to the greatest extent possible, the following commissioning activities:
 - a. Initial equipment startup
 - b. Testing, adjusting, and balancing
 - c. ATC point-to-point component test
 - d. PFPCs
- 20. Maintain a Master deficiency and resolution log i.e., Corrective Action Logs and provide the Construction Manager/GC with written progress reports and test results.
- 21. Maintain Commissioning Pending Issues Log of any issues or concerns identified in the Construction Phase that is Design Team or Owner related.
- 22. Assist in the development of a System Manual for the below topics and assignments that is finalized during the Post-Commissioning Phase.
- 23. Provide a final commissioning report.
- 24. Coordinate and supervise required seasonal or deferred testing and deficiency corrections.
- F. Architect Professionals shall:
 - 1. Fulfill construction administration per their contract with the Architect.
 - 2. Attend the commissioning scoping meeting and selected commissioning team meetings.
 - 3. Perform normal submittal review, construction observation, as-built drawing validation, O&M Manual validation etc., as contracted.
 - 4. Provide any design narrative documentation requested by the CA.

- 5. Coordinate resolution of system deficiencies identified during commissioning, according to the contract documents.
- 6. Prepare and submit final as-built design intent documentation for inclusion in the O&M Manuals. Review and approve the O&M Manuals.
- 7. Coordinate resolution of design non-conformance and design deficiencies identified during warranty-period commissioning.
- G. Mechanical and Electrical Designers/Engineers (Construction/Acceptance Phase):
 - 1. Perform normal submittal review, construction observation, as-built drawing turnover to client along with O&M Manuals, etc., as contracted. On-site observation should be completed just prior to system start-up.
 - 2. Provide any design narrative and sequences documentation requested by the CA. The designers shall assist (along with the contractors) in clarifying the operation and control of commissioned equipment in areas where the specifications, control drawings or equipment documentation is not sufficient for writing detailed testing procedures.
 - 3. Attend commissioning scoping meetings and other selected commissioning team meetings.
 - 4. Prepare and submit the final as-built design intent and operating parameters documentation for inclusion in the O&M manuals. Review and approve the O&M manuals.
 - 5. From the Contractor's drawings, edit and update one-line diagrams developed as part of the design narrative documentation and those provided by the vendor as shop drawings for the chilled and hot water, condenser water, domestic water, steam and condensate systems; supply, return and exhaust air systems and emergency power system.
 - 6. Witness testing of all pieces of equipment and systems.
 - 7. Review the HVAC piping test and flushing procedure, sufficient to be confident that proper procedures are being followed. Notify Owner's Project Manager of any deficiencies in results or procedures.
 - 8. Review the testing and cleaning procedures sufficient to be confident that proper procedures are being followed. Notify Owner's Project Manager of any deficiencies in results or procedures.
 - 9. Witness performance testing of smoke control systems by others and all other owner contracted tests or tests by manufacturer's personnel over which the CA may not have direct control. Document these tests and include this documentation in Commissioning Record in O&M Manuals.
 - 10. Participate in the resolution of non-compliance, non-conformance and design deficiencies identified during commissioning during warranty-period commissioning.
- H. Construction Manager/GC shall:
 - 1. Champion and support the commissioning process.
 - 2. Attend commissioning coordination meetings.
 - 3. Manage the master scheduling process with regard to timing and duration of the commissioning activities, as well as manage the Commissioning Test Plan & Schedule document.
 - 4. Manage the master shop drawing log, data retrieval log, O&M Manuals, Systems Manual, and training schedule log.
 - 5. Immediately following the acceptance of each submittal and no later than 60-days from submittal acceptance, the Trade Contractor's equipment supplier shall complete the associated equipment Data Retrieval form included within Division 1 Specification as an integral part of the submission process. Included with this form shall also be the operation and maintenance requirements. In addition, the Contractor shall submit the equipment website where the O&M data is located.

AUGUST 1, 2019

Exclude, done by subs off site Exclude,	6.	The Contractor shall provide a separate area within the construction trailer for the assembly of the O&M Manuals. An all-inclusive Table of Contents shall be displayed for the Trade Contractors to highlight open items and scheduled due dates of O&M insertions. The O&M Manuals will be built on a construction progress basis and will be reflective of each equipment/system that has been accepted and installed thus being in a completed state prior to demonstration of equipment/systems to Owner. Contractor shall accepted and installed thus being in a completed state prior to demonstration of equipment/systems to Owner. Contractor shall accepted and installed thus being in a completed state prior to demonstration of equipment/systems to Owner.
done by subs off site	7.	assign a Project Coordinator to monitor this process thru to completion. The Contractor shall provide a separate area within the construction trailer for the assembly of the Systems Manual. An all-inclusive Table of Contents shall be displayed for the Trade Contractors to use to track the collection of system readiness documents.
	8.	Coordinate the completion and delivery of shop drawings, data retrieval sheet and O&M Manuals prior to system FPT demonstration to allow facility staff to reference during system education/training provided by the Contractor and monitored by the Commissioning Firm.
	9.	Ensure that Contractor correct deficiencies and make necessary adjustments to O&M Manuals and as-built drawings for applicable issues in any testing.
	10.	Coordinate and schedule all equipment and system education/training. Completion of the Operation and Maintenance Training Record at the end of this section is required by the Construction Manager/GC for all systems requiring training. The Agenda portion depicting the training and personnel to be included shall be completed two (2) months prior to training and approved by the Owner's Representative.
	11.	A Training Schedule, four (4) months prior to training being implemented, shall be developed by the Construction Manager/GC and a meeting with the CA, Owner and Owner's facility personnel shall be implemented to discuss and finalize.
	12.	Coordinate and schedule all testing compliance and maintain Test Log for pipe testing and flushing and duct testing of system distribution.
	13.	Coordinate and schedule PFPCs and notify CA at least one (1) week prior to scheduled date.
	14.	Coordinate and schedule the Trade Contractor's initial dry-run FPT demonstration and collect the sign-off FPT document.
	15.	Coordinate and schedule deferred/seasonal tests in the appropriate season. The heating system sequence shall be tested in the winter and air-conditioning sequences in the summer.
	16. 17.	Coordinate and schedule retest activities. Assemble and deliver Systems Manual (LEED EAc1) to the CA for sign-off before forwarding to the Owner.
I.	Mech	nanical (including TAB), Electrical, and BMS Contractors:
	1.	The commissioning responsibilities applicable to each of the mechanical, controls and TAB contractors are as follows (all references apply to commissioned equipment only):
	2.	Trade Contractors are as follows:
		 a. HVAC b. Testing, Adjusting and Balancing Contractor c. Sheet Metal d. Automatic Temperature Controls, Building Automation e. Electrical f. Plumbing g. Fire Protection h. Low Voltage Systems
	3.	Include and itemize the cost of commissioning in the contract price.

- 4. Require equipment manufacturer's provides self-contained building automation equipment representative to participate in the commissioning process.
- 5. Attend a commissioning scoping meeting and other commissioning coordinating meetings.
- 6. Contractors shall provide the CA with normal cut sheets and shop drawing submittals of commissioned equipment.
- 7. Provide additional requested documentation, prior to normal O&M manual submittals to the CA for the development of start-up and functional testing procedures.
 - a. Typically this will include detailed manufacturer installation and start-up, operating, troubleshooting and maintenance procedures, full details of any owner-contracted tests, fan and pump curves, full factory testing reports, if any, and full warranty information, including all responsibilities of the Owner to keep the warranty in force clearly identified. In addition, the installation, start-up and checkout materials that are actually shipped inside the equipment and the actual field checkout sheet forms to be used by the factory or field technicians shall be submitted to the CA.
 - b. The CA may request further documentation necessary for the commissioning process.
- 8. Provide a copy of the O&M Manuals and submittals of commissioned equipment, through the submittal process, to the CA for review and approval.
- 9. Prepare a preliminary schedule of MEP pipe and duct system testing, flushing and cleaning, equipment start-up and TAB start-up and completion for use by the CA.
- 10. Contractors shall assist (along with design engineers) in clarifying the operation and control of the commissioned equipment in the areas where the specifications, control drawings or equipment documentation is not sufficient for writing detailed testing procedures.
- 11. Provide assistance to the CA in preparing the specific FPT procedures. Trade contractors shall review test procedures to ensure feasibility, safety and equipment protection and provide necessary written alarm limits to be used during the tests.
- 12. Develop a full start-up plan and initial checkout plan using manufacturer's start-up procedures and the pre-functional checklists from the CA for all commissioned equipment. Submit to CA for review and approval prior to start-up.
- 13. During the start-up and initial checkout process, execute the mechanical-related portions of the pre-functional checklists for all commissioned equipment.
- 14. Perform and clearly document all completed start-up and system operational checkout procedures, providing a copy to the CA.
- 15. Address current A/E punch list items before functional testing. TAB shall be completed with discrepancies and problems remedied before the functional testing of the respective air and water related systems.
- 16. Provide skilled technicians to execute starting of equipment and to execute the FPTs. Ensure that they are available and present during the agreed upon schedules and for sufficient duration to complete the necessary tests, adjustments and problem-solving.
- 17. Provide skilled technicians to perform FPTs under the direction of the CA for commissioned systems. Assist the CA in interpreting the monitoring data as necessary.
- 18. Correct deficiencies (differences between specified and observed performance) as interpreted by the CA, CM and A/E to retest the equipment.
- 19. Prepare O&M manuals according to the Contract Documents, including clarifying and updating the original sequence of operation to as-built conditions.
- 20. Develop and deliver O&M manuals immediately after associated equipment submittal is approved. LEED Credits EAc1.
- 21. Refine and implement PFPC Test procedures and, where applicable, have equipment manufacturer participation where controls are packaged.
- 22. Contribute information required for the Current Facilities Requirements and Operations and Maintenance Plan.

- 23. Contribute to the Systems Manual following the Table of Contents provided by the CA.
- 24. Develop and implement equipment education/training compliant with Contract Documents. LEED Credits EAc1.
- 25. Prior to the system demonstrations with the Commissioning Team, perform systems dryrun FPT demonstration and submit documented results to the Commissioning Firm.
- 26. Demonstrate systems working with the Commissioning Team implementing FPTs. LEED Credits EAp1 and EAc1.
- 27. Demonstrate systems working with the Commissioning Team implementing deferred/seasonal test FPTs.
- 28. Correct all Contractor-related deficiencies identified during FPTs and retest the corrected functions with the Commissioning Team. LEED Credits EAp1 and EAc1.
- 29. Provide Systems Manual portions that pertain to your discipline to the CA.
- J. Equipment Manufacturers shall:
 - 1. Participate in the commissioning process. Participation shall include demonstration of furnished equipment operation and packaged control system functions.
 - 2. Prior to the systems demonstrations with the Commissioning Team, perform system dryrun FPTs in conjunction with the Trade Contractor.
 - 3. Demonstrate systems working with the Commissioning Team including joint automation demonstration with the ATC Contractor implementing FPTs in conjunction with the Trade Contractor.
 - 4. Demonstrate systems working with the Commissioning Team implementing deferred/seasons test FPT in conjunction with the installation subcontractor. LEED Credits EAp1 and EAc1.
 - 5. Correct all equipment deficiencies identified during FPT and retest the corrected functions with the Commissioning Team. LEED Credits EAp1 and EAc1.
- K. Testing, Adjusting, & Balancing (TAB) Firm
 - 1. Attend commissioning coordination meetings.
 - 2. Submit TAB Plan including TAB shop drawing submittal requirements (i.e., system flow diagrams with design data at pertinent test points) during the submittal phase period of the job.
 - 3. Review and comment on field coordination drawings during the mechanical-electrical field drawing coordination meetings relative to testing, adjusting and balancing.
 - 4. Participate in PFPCs completing Pre-TAB field visits.
 - 5. Complete testing, adjusting and balancing of systems.
 - 6. Participate in FPT system demonstrations.
 - 7. Provide system performance verification data for commissioned systems.

3.2 CONSTRUCTION DOCUMENTS PHASE

- A. The documentation associated with the activities in the Construction Phase of the project are as follows:
 - 1. Commissioning Meeting Minutes for documenting regularly scheduled meeting discussions, responsibilities and action agenda due dates.
 - 2. Pending Issues Log for documenting issues identified and/or commissioning activities that are directed to design issues/concerns, field visit reporting, and other issues not directly related to the seasonal and/or deferred FPTs.
 - 3. Shop Drawing Log for documenting equipment submittals and associated documents to be commissioned and associated O&M requirements.
 - 4. Commissioning Test Plan & Schedule is used to document and track the Commissioning Process by listing all systems to be commissioned, documentation to be

provided/collected during process and anticipated dates of demonstration of systems to Owner.

- 5. Manufacturer/Contractor Test Log for documenting Contract Specification test requirements by Contractor that are directly related to the systems to be commissioned.
- 6. Pre-functional Performance Tests (PFPC) for documenting Contractor required start-up compliance for systems to be commissioned.
- 7. Systems Matrix for inventorying requirement documents leading up to the FPTs of systems to be commissioned.
- 8. Commissioning Field Report documenting CAs visits and observations.
- 9. Equipment & System Training Log for documenting Contractor required training of Owner personnel.
- 10. Commissioning Trending Checklist for documenting and assisting during the start-up of systems and for continuous monitoring and measuring of building systems through the Warranty Period.
- 11. Commissioning O&M Checklist for documenting the O&M Manual Process during the Construction Phase. This checklist can be used during the FPT demonstration to ensure proper documentation control is available to the Facility Department and compliance has been met with the Contract Documents.
- 12. Functional Performance Test Narratives (FPTs) for documenting Trade Contractor required demonstration of system (s) to be commissioned.
- 13. Corrective Action Log for documenting system installation of observation deficiencies, start-up deficiencies and deficiencies noted during demonstration of systems to the Owner (FPT). Each corrective action shall require a Trade Contractor or Design Team signoff that the corrective measure has been completed. Each FPT corrective action shall require a re-test of that deficiency to demonstrate Contract Document compliance.

3.3 COMMISSIONING TEST PLAN & SCHEDULE

- A. The Commissioning Test Plan & Schedule, included within this part of the specification is a list of activities that must occur leading up to and including the FPT demonstration to the Commissioning Team. The document lists the systems and associated equipment that will be commissioned.
- B. The Contractor shall work closely with the CA to input and keep current the activities within the Commissioning Test Plan & Schedule.

3.4 CURRENT FACILITIES REQUIREMENTS AND OPERATIONS AND MAINTENANCE PLAN

- A. Prepare and maintain a current facilities requirements and operations and maintenance plan that contains the information necessary to operate the building efficiently.
- B. The plan shall include the following:
 - 1. Sequence of operations for the building;
 - 2. Building occupancy schedule;
 - 3. Equipment run-time schedules;
 - 4. Setpoints for all HVAC equipment;
 - 5. Set lighting levels throughout the building;
 - 6. Minimum outside air requirements;
 - 7. Changes in schedules or setpoints for different seasons, days of the week, and times of day;
 - 8. Systems narrative describing the mechanical and electrical systems and equipment;
 - 9. Preventive maintenance plan for building equipment described in the systems narrative; and

10. Commissioning program that includes periodic commissioning requirements, ongoing commissioning

3.5 SYSTEMS MANUAL

- A. The Contractor shall be responsible for coordination and development of the System Manual beginning immediately following the acceptance of equipment and component in the submittal phase of the project. The Manual shall also serve as the LEED Enhanced Commissioning Credit EAc1 Systems Manual. The document to be used to track the development of the Systems Manual shall be the Systems Manual Table of Content.
- B. CA shall assist the Contractor with the development of a Systems Manual for the commissioned systems. The Systems Manual provides documentation of all pertinent, system readiness checklists leading up to the FPT system demonstration.
- C. This Manual, as it pertains to the LEED compliance shall also include but not limited to the Table of Content specified in Part 1 of this specification.
- 3.6 PRE-FUNCTIONAL CHECKLIST (PFCS)
 - A. Each PFC included is the initial system ready checklist to be signed off by each applicable Trade Contractor as they complete their work on the specific piece of equipment.
 - B. In addition to the PFC checklist, the Contractor shall supplement other pertinent documents based on the System Manual's Table of Content and the Commissioning Test Plan & Schedule.

3.7 SYSTEM READINESS CHECKLISTS (OBSERVATION OF INSTALLATION)

- A. CA will perform site visits and submit Field Reports including with the Report completed associated Observation of Installation Checklists.
- B. All deficiencies from the observation of installation will be noted on a Corrective Action Log and distributed to the Commissioning Team for corrective measures. LEED Credits EAp1 and EAc1. All deficiencies noted on the Observation Checklist Corrective Action Log shall be corrected by the appropriate Trade Contractor who will then provide the completed Action Log to the Contractor and CA prior to system demonstration (FPT).
- C. The Contractor may use but must enhance the CA furnished Observation Checklists as their "static inspection" checklist to confirm the completeness of the equipment installation prior to the Design Team's own equipment punch list.
- D. In addition to the Static Inspection checklists, the Contractor's equipment manufacturer and/or service department startup technician shall also provide their own inspection/system readiness checklists for each piece of equipment.

3.8 SYSTEM TRENDING DATA

A. The Contractor shall provide system trending of specific points (i.e., discharge air temperature) for a minimum of 16 hours prior to system FPT demonstration and shall continue the trending after the system has been commissioned. During the Commissioning meetings, trending points shall be mutually agreed upon for the ATC Contractor(s) to program into the commissioning process.

B. Contractor shall work with the CA and the Owner's Facility Manager in development of trending points during the ATC shop drawing phase.

3.9 FUNCTIONAL PERFORMANCE TESTS (FPT) NARRATIVES

- A. FPTs shall be provided by the CA for each system to be commissioned. The FPTs are the process by which a system shall be demonstrated to the Owner by the Contractor with the CA facilitating the process and the Owner's O&M Group participating.
- B. A FPT narrative have been inserted behind this Section 3 and is a "draft" sample for the Contractor to see as the level of effort and time needed to demonstrate the systems to be commissioned. This document, along with other system FPTs will be finalized during the Construction Phase upon final approved sequence of operations.
- C. Once the FPTs are completed, the Owner, Design Team, and the Contractor shall review and comment. Upon receipt comments, the CA shall finalize the FPTs.
- D. Final FPTs shall be used by the Contractor to implement in a "dry run" prior to the systems FPT demonstration to the CA and the Owner. During the dry run, trending shall occur as part of this system demonstration. With each completed dry run, the Contractor shall sign the FPT document and submit it to the CA as part of the Systems Manual.
- E. After the dry run, the CA shall facilitate the FPT system demonstrations, sequence-by-sequence with the Commissioning Team.

3.10 WARRANTY PERIOD

- A. Seasonal deferred FPT system demonstrations shall be completed in the Warranty Phase by the Commissioning Team. Leading up to the FPT demonstration(s), the Owner shall be trending the associated systems to assure the equipment is functioning per the Basis of Design. If the system(s) is not maintaining trend set points, the FPT demonstration shall be delayed until the Contractor has corrected the problem.
- B. Issues such as freeze-stat signal due to cold air stratification, cooling coil moisture carry-over, etc. during the air conditioning season shall also be resolved prior to the seasonal deferred FPT demonstration.
- C. Only that part of the system requiring deferred testing shall be demonstrated (i.e., heating valve sequence during heating season).
- D. A review of the building operation within 10 months after substantial completion with O&M staff and occupants per LEED EAc1. A plan for resolution of outstanding commissioning-related issues is provided. All outstanding construction deficiencies or deficiencies identified in this post-occupancy review should be documented and corrected under manufacturer or Contractor warranties.
- E. Team Member Responsibilities
 - 1. Owner Project Manager
 - a. Maintain records of problems or concerns associated with the systems during normal operation.
 - b. Distribute Post Construction Evaluation information to other Commissioning Team members for review and comment.

- c. Coordinate and facilitate the meeting with the Commissioning Team at the 10 month mark to discuss operational problems and concerns.
- d. Oversee the revision of the OPR and BOD based on the results of the 10-month warranty meeting.
- 2. Owner Facility Manager
 - a. Maintain problems/complaints from occupants and Owner personnel regarding commissioned systems.
 - b. Participate in seasonal/deferred FPTs.
 - c. Maintain "as-commissioned" proper operation of the building systems.
 - d. Participate in 10 month Warranty meeting present the problems, issues, and concerns.
 - e. Identify warranty versus operational issues and concerns.
- 3. Commissioning Agent
 - a. Maintain Commissioning Corrective Action Log until all issues are resolved. LEED Credits EAp1 and EAc1. All updates shall be provided by the Contractor to the CA.
 - b. Facilitate seasonal/deferred FPTs.
 - c. Complete Final Commissioning Report document. LEED Credits EAp1 and EAc1.
 - d. Facilitate the update of the System Manual by Contractor per LEED Credit EAc1 -Enhanced Commissioning on any significant issues that were identified by the CA that will not be corrected and should be recorded in this System Manual.
 - e. Review of system trends.
- 4. Design Professionals
 - a. Be available to consult on the results of the seasonal/deferred FPT results.
 - b. Meet with the Commissioning Team at the 10 month mark to discuss operational problems and concerns. LEED Credits EAc1.
- 5. Construction Manager / General Contractor
 - a. Coordinate scheduling of seasonal/deferred FPTs.
 - b. Participate in 10-month Warranty meeting present the problems, issues, and concerns. LEED Credits EAc1.
 - c. Provide completed training documentation.
 - d. Update of the Systems Manual per LEED Credit EAc1 Enhanced Commissioning on any significant issues that were identified by the CA that will not be corrected and should be recorded in the Systems Manual.
 - e. Address outstanding warranty issues and tasks identified as being under the original construction contract. LEED Credits EAc1.
- 6. Trade Contractors
 - a. Be present for and conduct seasonal/deferred FPTs. LEED Credits EAp1 and EAc1.
 - b. Address outstanding warranty issues and tasks identified as being under the original construction contract. LEED Credits EAc1
 - c. Be available to meet with the Commissioning Team at the 10 month mark to discuss operational problems, issues, and concerns.

- 7. Equipment Manufacturers
 - a. Be present for and conduct seasonal/deferred FPTs.
 - b. Participation shall include demonstration of furnished equipment operation and packaged control system functions.
 - c. Address outstanding warranty issues and tasks identified as being under the original construction contract. LEED Credits EAp1 and EAc1.
 - d. Be available to meet with the Commissioning Team at the 10 month mark to discuss operational problems, issues and concerns. LEED Credits EAc1.
- 8. Testing, Adjusting & Balancing
 - a. Conduct seasonal/deferred TAB associated with FPTs.
- 3.11 FINAL COMMISSIONING REPORT
 - A. The LEED Final Commissioning Report shall contain the following and be delivered to the Owner within a reasonable time after occupancy:
 - 1. Executive Summary
 - 2. Correspondence
 - 3. Commissioning Specification
 - 4. Commissioning Test Plan & Schedule
 - 5. Submittal Log
 - 6. O&M Manuals Log
 - 7. Training Log
 - 8. Corrective Action Log
 - 9. Current Facilities Requirements and Operations and Maintenance Plan
 - 10. Systems Manual (a separate binder from the Contractor)
 - 11. Field Reports & Observation Checklists
 - 12. FPTs & Results
 - 13. Operator Handbooks (a separate binder)
 - 14. Scrubbed FPTs for Re-Commissioning
 - 15. LEED Documents
 - a. Owner's Project Requirements
 - b. Basis of Design
 - c. LEED Commissioning Certification Documents for USGBC Upload
 - B. The Construction Manager with the participating Trade Contractors shall contribute to the successful project closeout and Final Commissioning Report by providing the following documentation.
 - 1. Submission of required information for the Current Facilities Requirements and Operations and Maintenance Plan, per LEED V4 EAp1.
 - 2. Submission of the completed Systems Manual to the CA, per LEED V4 EAc1.
 - 3. Submission of the completed Corrective Action Log to the CA.
 - 4. Project Closeout documents per the project contract.

AUGUST 1, 2019

END OF SECTION

SECTION 019115

BUILDING ENCLOSURE COMMISSIONING

PART 1 - GENERAL

- 1.1 GENERAL REQUIREMENTS
 - A. The General Conditions of the Contract for Construction and the General Requirements are hereby made part of this specification. This section shall be read in conjunction with Specification Section 019113, *General Commissioning Requirements.*
 - B. Related Sections:
 - 1. Section 019113 General Commissioning Requirements
 - 2. Section 07 Thermal and Moisture Protection
 - 3. Section 08 Openings
 - C. Reference Standards:
 - 1. ASTM E2813-12: Standard Practice for Building Enclosure Commissioning
 - 2. NIBS Guideline 3: Exterior Enclosure Technical Requirements for the Commissioning Process, 2006
 - 3. ASHRAE Guideline 0: *The Commissioning Process*, 2005

1.2 SUMMARY

- A. Commissioning is the systematic process of assuring by third-party design review, testing, documentation, and training from the design through construction, acceptance, and warranty phases that new Building Exterior Enclosure Assemblies perform independently and interactively in accordance with the design intent and design documentation.
- B. The independent third-party Commissioning Agent (CxA) for this project is NV5. Building Enclosure Associates, LLC (BEA) has been retained as the building envelope commissioning subconsultant to NV5. This section relates to the work associated with the building enclosure elements being commissioned with the involvement of the Owner, Design and Construction Team and an independent third-party Commissioning Agent.
- C. The requirements of this section are intended to supplement the other specification sections. Where any discrepancies exist between what is specified herein and elsewhere, the more stringent requirements apply.
- D. Commissioning shall be used to assess the following for building enclosure elements:
 - 1. CxA to review design and execution of building enclosure assemblies for thermal and water integrity, moisture vapor control and assembly life.

- 2. Completeness and functional performance according to design intent and Owner's operational needs <u>prior</u> to occupancy,
- 3. Documented performance provided by the installed building enclosure elements, deficiencies found, and corrective actions taken,
- 4. Pertinent, useful, and organized maintenance and warranty data.
- E. The Design Teams and installing contractors retain their full contract document responsibilities in providing a finished and fully functional facility. Commissioning does not take away from or reduce these responsibilities.
- F. Commissioning requires active project team involvement and participation to deliver effective and successful results for all concerned. Project Team to provide labor and project management required to support the commissioning process.
- G. This section is intended to supplement other sections of the construction contract and shall be read in conjunction with Division 1 - General Requirements, Division 7 – Thermal and Moisture Protection and Division 8 - Openings.
- H. The Commissioning Authority directs and coordinates all commissioning activities, this section describes some but not all of the Commissioning Authorities responsibilities.
- I. The Commissioning Authority is employed by the Owner.
- J. Commissioning Tasks:
 - 1. CxA to review Design Phase Documents and provide comments to Design Team, Owner
 - 2. CxA to review Construction Phase Documents including building exterior-related submittals and shop drawings and provide comments to Design Team, Owner
 - 3. CxA to perform periodic observation of work in progress including documenting resolution of deficiencies identified through Cx process
 - 4. CxA to witness Field Testing of representative production assemblies
 - 5. CxA to perform Infrared Moisture Survey on newly completed roofing
 - 6. CxA to perform Infrared Façade Survey on newly completed facades
 - 7. CxA to complete Exterior-related commissioning documentation
 - 8. CxA to perform 10 Month Post-Commissioning Visit
 - 9. CxA to perform review of Exterior-related Project Close-Out Documents
 - 10. CxA to Issue Final Commissioning Report

1.3 SYSTEM DESCRIPTION

A. Systems to be commissioned with the involvement of the independent third-party Commissioning Agent include but are not limited to the following Exterior Assemblies and related components:

- 1. Insulation
- 2. Weather Barriers
- 3. Exterior Cladding: Masonry, Facade Panels
- 4. Roofing Assemblies and Accessories
- 5. Sheet Metal Flashing and Trim
- 6. Fenestrations: Windows, Storefronts, Curtain Wall, Etc.
- 7. Joint Sealants
- 8. Any other building exterior-related equipment and systems explicitly identified elsewhere in Contract Documents as requiring commissioning.

1.4 COMMISSIONING TEAM

- A. Commissioning Team:
 - 1. Owner's Project Manager/Representative
 - 2. Owner's Operations & Maintenance Personnel
 - 3. Design Team / Design Consultants
 - 4. General Contractor or Construction Manager (Contractor) and Installers
 - 5. Commissioning Agent (CxA)
- B. Commissioning Coordination Supervisor: The Contractor and each Installer shall assign a Commissioning Coordination Supervisor with five (5) years of experience with the coordination of disciplines of construction. The Coordinator's responsibilities include:
 - 1. Attendance at commissioning coordination meetings
 - 2. Planning and coordination of commissioning activities
 - 3. Incorporate commissioning activities into project scheduling
 - 4. Compile and submit documentation
 - 5. Communicate with Commissioning Agent
 - 6. Direct resolution and documentation of corrective actions
 - 7. Provide assistance for performance of functional performance tests directed by the Commissioning Agent and included in the project documents.
 - 8. Address corrective actions and retain Third Party Testing Agent to perform retesting
 - 9. Compile Project Warranty and Maintenance Documentation CM excludes 3rd party testing

10. Submit Commissioning Documentation

1.5 SUBMITTALS

A. Contractor and Installers shall submit the name of person(s) assigned as Commissioning Coordination Supervisor within (2) weeks of contract award. Contractor / Installer shall submit the following information for each assigned Commissioning Representative: Company Name

Name

Title

Years of Experience

Contact Information

- B. Submit a list of required submittals to the Commissioning Agent. Commissioning Agent will identify submittals relevant to systems being commissioned.
- C. The Contractor shall forward to the CxA one copy of Shop Drawings and Product Data concurrent with distribution to the A/E.
- D. CxA shall review and provide comments to the Owner and A/E within seven (7) business days, who will then review and incorporate the CxA's comments at their discretion and return to the Contractor. The Contractor shall then copy CxA with the reviewed submittal with A/E submittal review stamp.
- E. Submittal review by Commissioning Agent will provide insight to the appropriateness of the proposed system to the project conditions and detailing issues that should be resolved. Review will be performed for design intent only and will not include a review of the following issues: verification of dimensions, coordination between trades and/or documents, and other aspects of existing conditions, warranties, building code compliance, energy code compliance, sequencing, value engineering and/or constructability.
- F. Factory/Laboratory Test Reports The Contractor shall provide any factory or laboratory testing documentation or certified test reports required by the specifications. These shall be provided prior to acceptance and installation of the specific item.
- G. Testing Agency Reports: Provide all documentation of work of independent testing agencies required by the specification. These shall be provided prior to acceptance by A/E and installation.
- H. Master Construction Schedule: Incorporate all commissioning milestones into the Master Construction Schedule. Provide monthly schedule updates.
- I. Submit a copy of Construction Meeting Minutes, Requests for Information (RFI), Design Team Supplemental Instructions (ASI), Requests for Proposals (RP), Change Orders (CO), etc. to Commissioning Agent for Record.
- J. Action Item Response: Respond to Action Items to which CxA team members assign the Contractor responsibility within 10 business days of issue.

- 1.6 INSTALLATION GUIDELINES, TEST DATA, MAINTENANCE MANUALS AND WARRANTIES
 - A. Refer to individual sections for maintenance manual and warranty requirements.
 - B. In addition to the submittal requirements of individual sections, submit one digital copy of the manufacturers' installation guidelines, laboratory test data, maintenance manuals and warranties for the systems listed in 1.3.A above.
 - C. Product Safety/Data Manual: In addition to the requirements of individual sections, provide digital copies of a manual containing product data sheets for all products installed in the project. Manuals shall be arranged in the Division/Section CSI format as indicated in the Table of Contents of this project manual.

1.7 CONTRACTOR'S RESPONSIBILITIES

- A. Coordinate with the CxA pre-construction and construction field testing and submit laboratory and field quality control testing, field checklists and inspection reports on building enclosure construction to the CxA and Commissioning Team.
- B. Perform out of sequence work as required to facilitate field tests.
- C. Develop and maintain check lists for building enclosure assemblies.
- D. Submit maintenance data for products, assemblies, and components to the CxA as part of Submittal Review process.
- E. Provide test data, inspection reports, and certificates to CxA.
- F. Review and respond to Action Items in a timely manner (typically within 10 business days).
- G. Contractor is responsible for the cost of all re-tests and compensation of time for Architect and CxA related to all additional work necessitated by re-testing of specimens following an initial test failure.
- H. Provide input for final commissioning documentation.

PART 2 - PRODUCTS - NOT USED

PART 3 - EXECUTION

3.1 COORDINATION

- A. Assign Commissioning Representative (see 1.4 for requirements).
- B. Design Team to include Commissioning Agent on material submittals (see 1.5 for details).
- C. Contractor and Installers to review the commissioning requirements.
- D. Include commissioning activities in the master schedule.
- E. Request clarification as needed.

3.2 CONSTRUCTION PHASE

- A. Scheduling:
 - 1. Contractor to provide Commissioning Agent time line schedule for construction of various building enclosure elements including schedule for coordination meetings and any field testing of exterior components.
 - 2. Commissioning Agent to provide input into the master scheduling process with regards to timing and duration of the functional performance tests. The master scheduling process will include the functional performance tests. Location of field tests to be specified by the Design Team.

CX Agent needs to 3. provide the list of FPT's to be done Contractor and Installer through its Commissioning Coordination Supervisor shall forward to the Commissioning Agent and Project Team, a list and schedule of functional performance tests to be performed. Unless specified otherwise, provide a <u>minimum two</u> week notice to the Commissioning Agent for specified functional tests to be witnessed. See Section 3.2 through 3.6 of this section for additional information.

B. Commissioning Kick-Off Meeting:

Commissioning Agent will plan and conduct a meeting early in construction phase to review commissioning activities and responsibilities with all parties involved. Meeting will include discussing incorporating CX Schedule with the Construction Schedule, reviewing the submittal review requirements, the inspection and testing process, and developing the formal lines of communication between all parties.

Attendance will be required of all members of the Commissioning Team.

- C. Site Visits:
 - 1. Contractor responsible for providing safe and full access to Commissioning Agent, or his representative to make observations of the work in progress during the course of the project.
 - 2. Periodic site visits will be made during Construction by Commissioning Agent to become generally familiar with the progress and quality of the work and to determine in general if the work, when completed, will be in accordance with the contract documents. Visits will be coordinated with Owner's Project Manager and Contractor.
 - 3. The CxA will issue a Field Report to the Commissioning Team following each site visit. Field Report will contain general observations and a Deficiency Log. See 3.2 D for further information.
 - 4. Site visits will be made whenever possible, to review completed air and vapor barrier/flashings prior to installation of cladding. Commissioning Agent will inform the Owner's designated inspector for the Air Barrier of items to be inspected and reports to be provided.
 - 5. Construction observations made by Commissioning Agent will be made independently of and in addition to those observations to be performed by the Contractor, Design Team and others involved in this project.

- 6. Exhaustive or continuous on-site observations are not included. Means and Methods of Construction as well as worker safety programs and precautions are the sole responsibility of the Contractor and not part of our responsibility or control.
- D. Deficiency Log:
 - 1. Throughout the Construction Process, the CxA will maintain a Commissioning Issues Log which will enumerate deficiencies observed during field visits.
 - 2. Responses to and resolution of items included in deficiency log are required by the responsible party <u>within 10 days</u> of receipt of report. Deficiency will remain in log until resolved. Responses shall include text and photographs for each condition identified.
 - 3. Resolution of all deficiency items required for completion of project. See Part 3.7 of this specification for additional information.

3.3 OWNER'S FUNCTIONAL PERFORMANCE TESTS

- A. Functional field performance testing will be performed on representative typical building exterior assemblies to verify their conformance with Project Performance Requirements. Demonstration of successful field performance testing is required for Project Close Out.
- B. This testing is to be performed by a Third Party Independent Testing Agent retained by the Owner, unless specified otherwise.
- C. Location of field tests to be specified by Design Team and CxA.
- D. Contractor and Installer to provide personnel and equipment as required to assist the third party testing agent to perform the functional performance tests, including retesting required due to corrective actions required.
- E. Installer to reference Project Specifications for specified field testing work and request clarification from Design Team or Commissioning Agent if necessary. Contractor / Installer to review and comment on the final detailed functional performance test procedures identified. Provide feedback as to the efficiency of the procedures and possible alternate approaches to achieving the same results.
- F. Contractor and Installer through it's Commissioning Coordination Supervisor shall forward to the Commissioning Agent and Project Team, a list and schedule of functional performance tests to be performed.
- G. Unless specified otherwise, provide a minimum two week notice to the Commissioning Agent for specified functional tests to be witnessed.
- H. Test Reports by Others:

Provide Commissioning Agent full access to inspection and test reports on building enclosure elements by various agencies retained by the Contractor, Installer or Owner. Submit Contractor and Installer's Testing Agent's test reports to the Commissioning Agent, Owner and Design Team within one week of the successful completion of each test.

3.4 PRETESTING INSPECTION AND ACCEPTANCE BY INSTALLER

- A. Prior to the scheduled start of functional performance tests, Installer (s) to submit <u>Pre-Functional</u> <u>Test Statement</u> to CxA and Project Team, indicating written acceptance of completed work and confirming readiness for functional field testing.
- B. Pre-Functional Test Statement to indicate that systems installed as part of the project and scheduled to be tested are 100% complete and ready to be tested to confirm their compliance with the Project's Performance Requirements.
- C. Functional performance testing on a system shall not commence until Pre-Functional Test Statement is provided by the Installer.
- D. <u>Prior to the Commissioning Agent attending any field testing, the following requirements must be</u> met in advance:
 - 1. Installer(s) responsible for installing components to provide *Pre-Functional Test Statement* for assemblies scheduled for field testing, verifying their completion and suitability for testing. This documentation is to be distributed to the Team, including the CxA at least one week in advance of scheduled test.
 - 2. The responsible Installer is to be present for any field testing performed.
 - 3. It is recommended that Installer inform Manufacturer of assemblies being tested that testing will take place, and it is encouraged that a Manufacturer's representative be present to witness this field testing.
 - 4. Time lost and costs incurred (including cost of Commissioning Agent) due to a false start of functional performance testing because of inaccurate, incomplete, and/or untruthful field data shall be paid for by the party providing the erroneous data.

3.5 FUNCTIONAL PERFORMANCE TESTING

- A. Building enclosure elements shall be tested in accordance with the requirements of the Technical Sections for these items of work. <u>As a minimum, tests shall be performed on at least two occasions during production work.</u>
- B. Perform the following tests with associated field performance criteria in addition to any testing (laboratory or field) not listed herein, but listed in other technical specification sections.
 - 1. If laboratory testing is not performed, then the proposed curtain wall assemblies are still to comply with the referenced testing standards.
- C. All testing should be performed in accordance with the most current AAMA and ASTM and other applicable standardized Test Methods for the assembly being tested.
- D. All performance criteria to be used for the basis of field testing should be provided by the Design Team. Per the Design Team, Field Testing for Water Penetration Resistance is to be performed per the full Laboratory Test Pressure differential, without the field reduction allowed by the Test Methods.
- E. Field Test locations to be determined by Design Team and CxA. Additional testing may be performed at the discretion of the Owner/OPM and Design Team.

- F. Provide input into the master scheduling process with regards to timing and duration of the functional performance tests. The master scheduling process will include the functional performance tests.
- G. Review and comment on the final detailed functional performance test procedures identified by the Commissioning Agent based on the system shop drawings and submittals. Provide feedback as to the efficiency of the procedures and possible alternate approaches to achieving the same results.
- H. Provide personnel and equipment as required to assist the third party testing agent to perform the functional performance tests, including retesting required due to corrective actions required.
- I. Building enclosure assemblies shall be tested by a Third Party Independent Testing Agency retained by the Owner in accordance with the requirements of the Technical Sections for these items of work.

The following is a series of functional testing to be performed by the Owner's Third Party Testing Agency and <u>witnessed by the Commissioning Agent</u>:

1. Building Exterior Assemblies:

Functional Field Testing of representative building exterior assemblies should be performed in accordance with the Project Specifications at a minimum during the following stages of construction:

a. <u>Mock-Up Assemblies:</u>

Field testing should be performed as soon as possible after initial installation of the assemblies, either on a mock-up or at no later than 25% completion. If failure occurs, additional testing to be performed to determine source of failure and no additional installation should occur until mock-up assemblies meet the Project Performance Requirements as demonstrated through successful field testing.

b. <u>Production Assemblies:</u>

Field testing should be performed on representative exterior assemblies as indicated in the table below. Test specimens shall consist of different fenestration configurations/types during each test, unless indicated as acceptable by CxA in advance. Locations of field tests to be selected by Design Team.

The intent of testing is to verify that the installed assemblies meet Project Performance Requirements.

If failure occurs, additional testing to be performed to determine source of failure. Testing to continue until successful field testing demonstrates compliance with the Project Performance Requirements.

c. Curtain Wall field testing for air infiltration and water penetration resistance (ASTM E783, E1105) is required to be performed on a minimum of 1 test per unique curtain wall type / application. This field testing shall also include 1 test performed at each unique transition between the curtain wall and adjacent air barrier transition systems.

AUGUST 1, 2019

Component	Test Method		
	i cot metrod	Quantity	Frequency
	Qualitative Testing: ASTM E1186	1 assembly	25% Completion (STEM)
Air / Vapor Barrier	Quantitative Testing: ASTM E783	1 assembly	25% Completion (STEM)
	Adhesion Testing: ASTM D4541	1 assembly	25% Completion (STEM)
	Adhesion Testing: ASTM D4541	Prior to 25%, 1 additional time after 50% Completion	25 & 50% Completion (Tappan, STEM)
Joint Sealants	Field Adhesion Pull Test: ASTM C1521	Per Test Method. Minimum 10 test locations per first 1,000 linear feet of	25% Completion, Throughout course of project.
Firesafing Owner if r	and Firestopping equired.	ioint length 1 test per 1,000 linear feet or 1 test per elevation after that.	Jappan, STEM)
	Air Infiltration & Water	1 assembly	25% of Completion (Tappan)
	Penetration: ASTM E783, ASTM	1 assembly	Mock-up (STEM)
	E1105, AAMA 503	1 assembly	75% of Completion (STEM)
Curtain Wall		1 assembly	50% of Completion (Tappan)
Curtain wall	Water Penetration:	1 assembly	Mock-up (STEM)
	AAMA 501.2	2 assemblies	50% of Completion (STEM)
		2 assemblies	75% of Completion (STEM)
	Qualitative Air Leakage: ASTM E1186	Min. 1 test per unique air barrier transition	
Note: 1 assemb	oly = min. 100 sf or entire fene	estration within wall opening	
Functional Tes	sting performed by CxA:		
Completed Building Exterior	Infrared Thermal Survey – ASTM C1060	Entire New Façade of STEM Wing Only	Following Completion, performed subject to weather requirements
Roofing	Infrared Moisture Survey – ASTM C1153	Entire New Flat Roof Assembly: Tappan Addition, STEM Wing	Following Completion, performed subject to weather requirements

d. <u>Required minimum scope of functional field testing indicated in the following table:</u>

J. Deviations from Standard Test Methods:

If the Testing Agent anticipates deviating from the standard test methods for any assemblies, including those methods indicated in this specification, the deviations are to be indicated in

writing and submitted for review to the CxA and Commissioning Team at least <u>3 days</u> in advance of scheduled testing.

Any deviations from the standardized test methods indicated in this specification are to be agreed to by all parties involved, including the OPM, Design Team/Engineer, Contractor/Installer and CxA prior to the testing being performed.

K. Partial Fenestration Test Specimens:

Due to the length and width of some of the fenestration assemblies included in this project, there may be issues in constructing a test chamber to comply with requirements specified by AAMA and ASTM - a test chamber that is able to encapsulate, and introduce a test pressure differential on the <u>entire</u> assembly.

To accommodate these conditions, some of the field testing performed on this project may be performed on a partial assembly/specimen as a deviation to these test methods, with prior approval by CxA in advance.

1. This partial test specimen may consist of a portion of the fenestration with a minimum size of 100 sf or shall consist of a width of at least 2 vertical mullions and extend at least 2 horizontal mullions in height, including either or both the sill and head of the assembly.

assume during construction mobilization

- 2. With this partial test specimen configuration, air infiltration readings taken during this test may not be representative of the entire installed assembly and should be taken for reference only and not for measurement of conformance with project performance requirements.
- L. Contractor responsible for providing personnel and equipment as required to assist the following seasonally deferred functional performance tests <u>performed by the Commissioning Agent:</u>
 - 1. Moisture Survey of Newly Completed Roofing at Teppen and STEM Wing
 - 2. Thermal Survey of Newly Completed Façade Areas at STEM Wing

3.6 FUNCTIONAL PERFORMANCE TEST FAILURE

- A. If failure occurs during field testing, the following steps are to be taken:
 - 1. Investigatory work shall be performed as necessary by the responsible Installer or Manufacturer to identify source of failure.
 - 2. The Installer or Manufacturer is to identify a course of remedial work, which is to be approved by the Owner and Design Team prior to being performed. Course of remedial work is to be performed on the assembly that has experienced failure. Upon completion of the remedial work, re-testing is to be performed at the responsible party's expense until successful results are achieved.
 - 3. Following completion of successful field testing, all similar assemblies are to be reviewed by the Installer and/or Manufacturer and those with similar issues are to be identified. The approved course of remedial work is to be performed on <u>at least one other</u> assembly and this assembly is to be field tested.

- 4. <u>For every failed assembly, at least one additional assembly is to be tested</u>. Additional testing beyond this requirement may be performed at the request of the Owner and Design Team.
- 5. Upon completion of successful field testing of additional assemblies, the approved course of remedial work is to be performed on all similar assemblies. The course of inspection and remedial work, and locations of this work performed are to be documented for Record in writing and with photographs by the Installer / Manufacturer as a minimum.

3.7 CORRECTIVE ACTIONS

- A. Installer or Manufacturer to respond in writing to and perform corrective actions for resolution of deficiencies found during all periods of construction and testing. Responses shall be provided <u>within 2 weeks</u> following documentation of deficiency. Responses shall include a description and photograph of the remedial work performed.
- B. Corrective work and retesting shall continue until all deficiencies identified have been corrected to the satisfaction of the Owner.
- C. Additional costs associated with the need to retest a system, including cost of Commissioning Agent, become eligible for being paid for by the party or parties responsible for the need for further retesting. There will be no charges to the Owner for retest of systems that do not pass the functional performance requirements during commissioning testing.

3.8 WARRANTY AND CLOSE OUT DOCUMENTS

- A. CxA to prepare building exterior Systems Manual as part of the Close Out phase of the project. CxA to receive copies of Close Out Documents, including Operation and Maintenance Documents, Warranties and other Record Documentation concurrent with submission to the Design Team of Record for Review.
- B. CxA to perform review of items for compliance with requirements identified in Contract Documents. Documents submitted for close out to be included in Building Exterior Systems Manual submitted at conclusion of the project / commissioning process.

3.9 POST COMMISSIONING

- A. The Commissioning Agent will perform a post commissioning warranty review of newly completed exterior work ten months after substantial completion. This visit will include a visual review of the building envelope to identify issues of concern with the performance of the building envelope elements and repair work required.
- B. This review will be documented in a Field Report distributed to Project Team. Any deficiencies identified during post commissioning review are to be remediated by responsible Contractor.
- C. Commissioning Agent to assist with planning the satisfactory resolution of warranty problems and committing the necessary resources to follow through with achieving the activities planned. Complete any unfinished performance verification.

3.10 PROJECT COMPLETION

A. Following completion of review of Close Out Documents and Post Commissioning visit, and resolution of any deficiencies identified during all phases, the Commissioning Agent may proceed with their Close Out of the Project.

- B. Upon completion of the Commissioning activities, a Commissioning Report will be generated documenting the Commissioning Process from Design through the Post Commissioning Phases. Copies of all documents generated by the CxA and building exterior related items generated by Others during these phases will be included in the Report.
- C. The Commissioning Report will include the following:
 - 1. Comments made by Commissioning Team on Design Phase Documents and Action taken by Design Team;
 - 2. Review comments made by Commissioning Team on Submittals and Shop Drawings and action taken by Design/Construction Team;
 - 3. BEA Field and Functional Test Reports and Deficiency Resolution Log;
 - 4. Functional Test Reports by Others;
 - 5. Building Enclosure Product Warranties and other Close Out Documents;
 - 6. Cumulative Punchlist and resolution of same;
 - 7. Post Completion Field Report and documented resolution of any deficiencies;
 - 8. Letter of compliance, assuming all non-compliance items are addressed.

END OF SECTION

SKANSKA

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT GC: CONSTRUCTION GENERAL CONDITIONS

See attached worksheets

Skanska USA Building Inc Brookline High School Improvements GC Staffing Projection - 06.02.19 Updated per GMP Negotiation

		Jan-20	Feb-20	Mar-20	Apr-20	May-20	Jun-20	Jul-20	Aug-20	Sep-20	Oct-20	Nov-20	Dec-20	Jan-21	Feb-21	Mar-21	Apr-21	May-21	Jun-21	Jul-21	Aug-21	Sep-21	Oct-21	Nov-21	Dec-21	Jan-22	Feb-22	Mar-22	Apr-22	Proje Bu
anneville	Account Mngr																									_				\$
raft	Project Executive			0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.25	0.25	0.25	0.25	0.25	0.25				\$
	Senior PM			1	1	1	1																							\$
ulligan	Senior PM			1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0.5	0.5	0.5	0.25		!	\$
Landry	EHS Manager			1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0.5						!	Ş
	Scheduling BIM Coordination			0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1			+				Ş
	Accountant			0.4	0.4	0.2	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	1	1		0.5	0.25]	ç
		-		1	1 0.2	1	1	1	Ŧ	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1		0.5	0.25		°,
Swartz	Accountant			0.5 0.2	0.2]	, ,
Sweeting	Accountant	ł		0.2																0.4	0.4									Ş
y MacLeod	Permitting														0.1	0.1	0.1			0.1	0.1	0.1				+]	Ş
,	CX Support (Cypress)																	0.05	0.1	0.1	0.1	0.05	0.05			+			!	Ş
	CX Support (STEM)														0.1	0.1	0.1	0.05	0.05										!	\$
n Daly	Administrator			1	1	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5			!	\$
Simon ©	Project Manager			1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0.5								!	\$
/lelanson ©	APM			1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0.5	0.5							\$
Roche ©	MEP PE			1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1							\$
e Coop 1 - Evan ©	Intern			0.325	0.325	0.325	0.325																							\$
Papastephanou ©	Superintendent			1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0.5										\$
te Perera ©	A Super			1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0.5									\$
Pugh (A)	Proiect Manager			1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0.5				Ś
Swetz (A)	Project Engineer			1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1			ŝ
t Koenig (50% A 50% H	.,			1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0.5				Ś
e Coop 2 - Troy Deluca				1	1	1	1	1	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5				Ś
	MEP PF			1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1				Ś
	APM			1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0.5				i c
	Cost Engineer			±	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0.5				,
Gear (A&C)	Sr Super	-		4	1	1	1	1	1	1	1		1	4	4		4	4	4		1	4				+				,
		ł		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1						Ş.
Farrrar (A) Villiams (A)	Superintendent A Super			1 1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1					è
	Monthly Budget	ş -	\$ -			\$ 282,567	\$ 280,736	\$ 385.533 \$	254,645 \$	\$ 254,522	\$ 254,439 \$	240.984 \$	361,476	\$ 240.984 :	\$ 245,201 \$	242,600 \$	5 249,878 \$	247,683 \$	373,137 \$	240,743	\$ 210,628 \$	191.384	\$ 183,214 \$	\$ 122,963	\$ 184.444	\$ 99,302 \$	20,275 \$	3,215	\$.	\$
	Cumulative Budget																						\$ 5.320.560	\$ 5,443,523					\$ 5,750,760	<u> </u>
	Cumulative Budget	\$ -	ş -	\$ 288,813	\$ 580,206	\$ 862,774	\$ 1,143,510	\$ 1,529,043 \$	1,783,688 \$	\$ 2,038,210	\$ 2,292,648 \$	2,533,632 \$	2,895,108	\$ 3,136,092	\$ 3,381,294 \$	3,623,894 \$	\$ 3,873,772 \$	4,121,455 \$	4,494,592 \$	4,735,335	\$ 4,945,962 \$	5,137,346	\$ 5,320,560 \$	\$ 5,443,523	\$ 5,627,967	\$ 5,727,269 \$	5,747,544 \$	5,750,760	\$ 5,7	50,760

\$ 478,790 \$ 9,154,000

GC Non-labor Forecast Total

Skanska USA Building, Inc Brookline High School Improvements GC Table A Projections

	o Date	Jan-20 Feb-20	1 1		May-20			Aug-20		Oct-20		ec-20 Jan-2			-	May-21 J		ul-21 Aug				Dec-21	Jan-22	Jan-22 Mar-22	Apr-22 Total	
an Northrop			30	30	30		30	30		30	30	30	30 30	30	30	30	30	30	30		30 30	30			660	
1 Lanneville			30	30	30	30	30	30	30	30	30	30	30 30	30	30	30	30	30	30	30	30 30	30			660	
Craft																									0	
er Roche																									0	
o Mulligan																									0	
othy Landry			325	325	325	325	325	325	325	325	325	325	325 325	325	325	325	325	325	325	325 3	25 325	325			7150	
rk Pener			60	60	60	60	60	60	60	60	60	60	60 60	60	60		60	60	60		60 60	60			1320	
tt Emond			60	60	60		60	60	60	60	60	60	60 60		60		60	60	60		60 60	60			1320	
			60	60				60		60									60		60 60	60				
ha Lee			60	60	60	60	60	60	60	60	60	60	60 60	60	60	60	60	60	60	60	60 60	60			1320	
a Swartz																									0	
nne Sweeting																									0	
y MacLeod																									0	
ikiet																									0	
ie Reynolds																									0	
e Stallions																									0	
/ Groves			325	325	325	325	325	325	325	325	325	325	325 325	325	325	325	325	325	325						5850	
e Simon ©			325																						5850	
				325	325		325			325	325		325 325		325		325		325	_						
Velanson ©			325	325	325	325	325	325	325	325	325	325	325 325	325	325	325	325	325	325						5850	
Roche ©																									0	
e Coop 1 - Evan ©																									0	
e Papastephanou ©				[[_				T							T			0	
tte Perera ©	-				-																				0	
Pugh (A)			325	325	325	325	325	325	325	325	325	325	325 325	325	325	325	325	325	325	325 3	25 325	325	325	325	7800	
Swetz (A)		1																					-		0	
ert Koenig (50% A 50% H)			325	325	325	325	325	325	325	325	325	325	325 325	325	325	325	325	325	325	325 3	25 325	325	325	325	7800	
			525	525	323	525	525	525	525	525	525	323	525 525	525	323	525	525	525	525	525 3	23 323	525	525	525	/800	
e Coop 2 - TBD																									0	
an Moore (A)			325	325	325		325			325	325		325 325		325		325				25 325	325	325	325	7800	
se Lunde (A)			325	325	325	325	325	325	325	325	325	325	325 325	325	325	325	325	325	325	325 3	25 325	325	325	325	7800	
e Gear (A)																									0	
e Williams (A)																									0	
(D-3rd Floor)																									0	
er (D-3rd Floor)																									0	
(B-Tappan)																									0	
													-												0	
er (B-Tappan)																									0	
/e Haney																									0	
e Donovan																									0	
ph Dowgiert																									0	
e Zeppieri			30	30	30	30	30	30	30	30	30	30	30 30	30	30	30	30	30	30	30	30 30				630	
e Ellis			30	30	30	30	30	30	30	30	30	30	30 30	30	30	30	30	30	30	30	30 30				630	
is Gary			30	30	30	30	30	30	30	30	30	30	30 30	30	30	30	30	30	30	30	30 30				630	
d Watts			30	30	30		30			30	30	30	30 30		30		30	30	30		30 30				630	
k Moore			120	120	120		120			120	120		120 120		120		120	120	120		30 30				2250	
			30					30		30		30							30		30 30				630	
ie Walsh				30	30		30		30		30		30 30		30		30	30								
rt Zulps			30	30	30		30	30	30	30	30	30	30 30		30		30	30	30		30 30				630	
Mahoney			30	30	30	30	30	30	30	30	30	30	30 30	30	30	30	30	30	30	30	30 30				630	
b Schreib																									0	
c Contrado																									0	
Tormey																1									0	67840 Parking
COSTS To Date	11,868																								11868	79708 Parking
	,000		+ +																		+ +					
le A Items																									0	
Itants (Firesafing, Mold Hygenist, Temp Engineer)			5000																						5000	
er Rent	30697	10500	10500	10500	10500	10500	10500	10500	10500	10500	10500	10500 10	500 10500	10500	10500	10500	10500	10500 1	.0500 10	500 105	00 10500	10500	10500	10500	262500	
ge Rent		300 300	300	300	300	300	300	300		300	300		300 300		300		300	300	300	300 3	300 300				6900	
e Furn. & Equipment	34288	200 200		200	200		200			200	200		200 200		200		200				00 200	200			4800	
age & Delivery	54200	150 150					150			150	150		150 200		150		150				.50 150		150		3750	
																						120	120			
s/Reprographics	13040	2000 2000	2000				2000	2000	2000	2000	2000	2000 2	2000 2000	2000	2000		2000	2000	2000 2	000 20	UU				44000	
ing Off/Safety Week		0		2000	4000		2000									4000									12000	
tionSite	4486	0	I T		Т		Т				-				Т						- T	T			0	
GE	160	100 100	100	100	100	100	100	100	100	100	100	100	100 100	100	100	100	100	100	100	100 1	.00 100	100			2400	
S	1630	100																								
KING WATER	1498	400 400	400	400	400	400	400	400	400	400	400	400	100 400	400	400	400	400	400	400	100 4	00 400	400			0000	
		400 400					400			400	400		400 400		400		400				400	400			9600	
MACHINES	3005	1400 1400					1400			1400			400 1400		1400						00 1400	1400			33600	
TAID/Safety	142	1000 1000	1000	1000	1000	1000	1000	1000	1000	1000	1000	1000 1	1000 1000	1000	1000	1000	1000	1000	1000 1	000 10	1000	1000			24000	
TY TRAINING	682	100 100			100		100			100	100		LOO 100		100		100				.00 100	100			2400	
COSTS To Date	89,628																									410950 Table
	,		<u> </u>																						<u> </u>	89,628 A CTD
						<u>├</u>																			<u> </u>	
		1	1	1		1							1										1	1	1 1	\$500,578 A Tota
				1		-	1	1														ų.	1			

SKANSKA

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT GR: CONSTRUCTION GENERAL REQUIREMENTS

See attached worksheets

Skanska USA Building Brookline High School General Requirements

SUMMARY GENERAL + PROJECTS A and C GMP RESUBMISSION: 7/10/2020

Phase/Category		Original GMP Submission 3/13/2020	Revised Estimated Value	% Discount for GMP applied to all items equally within category	Revised GMP Value
Cost To Date					
(February 2020 Requisition Total Completed)		\$1,286,914	\$1,286,914		\$1,286,914
Forecasted GR Vendor Costs					
GENERAL		\$1,546,030	\$1,414,630	10%	\$1,273,167
Project A: 111 Cypress		\$1,037,905	\$1,037,905	10%	\$934,115
Project C: STEM		\$644,990	\$644,990	10%	\$580,491
Project F: Deferred Maint.		\$35,490	\$35,490		\$35,490
Forecasted Direct Costs to be Assigned to BP					
GENERAL		\$137,000	\$187,000		\$187,000
Project A: 111 Cypress		\$1,265,000	\$1,195,000		\$1,195,000
Project C: STEM		\$721,000	\$621,000		\$621,000
Project F: Deferred Maint.		\$0	\$0		\$0
Forecasted Craft Labor					
Union Laborer		\$2,052,697	\$2,052,697	5%	\$1,950,062
Construction Waste Management		(\$1,606,122)	(\$1,606,122)		(\$1,606,122)
Union Carpenter		\$364,759	\$364,759	5%	\$346,521
	TOTAL	\$7,485,663	\$7,234,263		\$6,803,638

Skanska USA Building Brookline High School General Requirements GMP RESUBMISSION: 7/10/2020

	2020												2021												2022			
Phase	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	
PROJECTED SCHEDULE																												
Project A: 111 Cypress																												
Project C: STEM																												
Project F: Deferred Maintenance (Elevators Only)																												
Closeout																												

Markand and the second sec		Cost to Date													2021										202		Uni	its	Unit Cost	Lump Sum Value	Total Estimated Value	Revised Value with 10% Reduction	Notes
Alternational problem Alternatin problem Alternational problem			Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb I	vlar Aj	or N	lay Ju	in Jul	Aug	a Sep	Oct	Nov D	ec Jar	n Feb Ma	r						
Schedule <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>0</td> <td>)</td> <td>\$0</td> <td>\$500,000</td> <td>\$500,000</td> <td>\$450,000</td> <td>OWNER ALLOWANCE. Electric and gas, temporary</td>																											0)	\$0	\$500,000	\$500,000	\$450,000	OWNER ALLOWANCE. Electric and gas, temporary
Alt Als Als Als Als Als Als Als Als Als Als	rees Winter Conditions & snow/ice removal			0.5	1	1								1	1	1	1 1											5	\$500	\$0	\$3,750	\$3 375	
Sinter state Sin					1	1	1	1	1	1	1	1	1	1	1	1	1 1		1	1	1	1	1	1	1 1								
Watch Wa				0.5	1	1	1	1	1	1	1	1	1	1	1	1	1 1		1 1	l 1	1	1	1										
Standard </td <td>Temp fencing, enclosure, walk, barricade, stair Firefight equipment</td> <td></td> <td>25</td> <td>50</td> <td></td> <td></td> <td></td> <td></td> <td></td>	Temp fencing, enclosure, walk, barricade, stair Firefight equipment																										25	50					
And Andread Solution <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>0</td><td>)</td><td></td><td></td><td></td><td></td><td></td></t<>																											0)					
Amo <td< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>0</td><td>)</td><td></td><td></td><td></td><td></td><td></td></td<>																											0)					
martic mar																											0)	+-	20			
minimize minimize <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>0</td><td>)</td><td></td><td></td><td></td><td></td><td></td></t<>																											0)					
Substranting Sub	Interior Carpentry																										0)	\$0	\$5,000	\$5,000	\$4,500	······
Machana Mach																											0)					
And and and and and and and and and and a				0.5	1	1	1	1	1	1	1	1	1	1	1	1	1 1		1	1 1	1	1	1	1	1 1		0)					
mathem mat	Sentery Suppres			0.5	-	1	1			1	1	1	1	-		· ·							-				23.		\$2.50	30	\$5,075	\$5,200	
Second state Second state <th< td=""><td>Phone / Internet</td><td></td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1 1</td><td>L</td><td>1 1</td><td>l 1</td><td>1</td><td>1</td><td>1</td><td>1 :</td><td>1 1</td><td></td><td>25</td><td>5</td><td>\$550</td><td>\$2,500</td><td>\$16,250</td><td>\$14,625</td><td>accommodate 20 staff. Install + Remove + Monthly.</td></th<>	Phone / Internet		1	1	1	1	1	1	1	1	1	1	1	1	1	1	1 1	L	1 1	l 1	1	1	1	1 :	1 1		25	5	\$550	\$2,500	\$16,250	\$14,625	accommodate 20 staff. Install + Remove + Monthly.
Mathematic Mathematic	Office Supplies			0.5	1	1	1	1	1	1	1	1	1	1	1	1	1 1		1 1	1 1	1	1	1	1	1 1		23.	.5	\$1,500	\$0	\$35,250	\$31,725	Increased \$500 to \$1500 based on CTD
Augustim A																																	
Approximate Approximate				1	1	1	1	1	1	1	1	1	1	1	1	1	1 1		1 1	l 1	1	1	1	1	1 1				*-				
And and a bit of																													+				
And matrix And matrix																																	
in single (s) in single (s)<	-				1	1	1	1	1							1				l 1	1		1							+-			
Accimants Sector Sector <td></td> <td></td> <td></td> <td></td> <td>1</td> <td>1 1</td> <td></td> <td>1 1</td> <td>l 1</td> <td>1</td> <td>1</td> <td>1</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>*-</td> <td></td> <td></td> <td></td>					1	1	1	1	1	1	1	1	1	1	1	1	1 1		1 1	l 1	1	1	1							*-			
Action Action																											0)					
Andenomingen Image: Single	Archiving Fees																										0)	\$0	\$17,550	\$17,550	\$15,795	.013% of \$135,000,000
membra improvision membra	Check Processing Fees																										0)	\$0	\$0	\$0	\$0	\$10MM based on new rate. Apply to \$135MM. Adjust by factor of 3 due to quantity of bid packages. \$2,000 per \$10MM historic cost. Based on \$130MM
in a field in a field i <td>Precon Survey</td> <td></td> <td>0</td> <td>)</td> <td>\$0</td> <td>\$26,780</td> <td>\$26,780</td> <td>\$24,102</td> <td>interior surveys.</td>	Precon Survey																										0)	\$0	\$26,780	\$26,780	\$24,102	interior surveys.
COD COD Signing Cond Signing Signing </td <td>NFPA 241 Plans</td> <td></td> <td>0</td> <td>)</td> <td>\$0</td> <td>\$20,000</td> <td>\$20,000</td> <td>\$18,000</td> <td></td>	NFPA 241 Plans																										0)	\$0	\$20,000	\$20,000	\$18,000	
bit <	CORI Supplies				1	1	1	1	1	1	1	1	1	1	1	1	1 1		1 1	l 1	1	1	1				20	0	\$100	\$4,000	\$6,000	\$5,400	
Prefer dariable of the second of																											0)					
AEPs AEPs I <td></td> <td></td> <td></td> <td>0.5</td> <td>1</td> <td>1 1</td> <td></td> <td>1 1</td> <td>1 1</td> <td>1</td> <td>1</td> <td>1</td> <td></td> <td></td> <td></td> <td>0</td> <td>)</td> <td>*-</td> <td></td> <td></td> <td></td> <td></td>				0.5	1	1	1	1	1	1	1	1	1	1	1	1	1 1		1 1	1 1	1	1	1				0)	*-				
Image: Control in the state of the stat				0.5	-	-					-				•	· · · ·																	
Math A nor a Account ALLOWANCE Image: All a series and a series	2 way radios																										0)	\$0	\$5,000	\$5,000	\$4,500	Line added 7/9/19. Was listed on other sub project sheets as being on general, but it was not.
number of or rales: number of orales: number of orales:																											0)	\$0	\$0			
Anomenic generic Graph New relia for the																											0)		20			By Owner
SUBGROAL SO																																. ,	
Pest Control Pest Control <th< td=""><td>Answering Service for CMP SUBTOTA</td><td>AL \$0</td><td></td><td></td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1</td><td>1 1</td><td></td><td>1 1</td><td>. 1</td><td>1</td><td>1</td><td>1</td><td></td><td></td><td></td><td>20</td><td>U</td><td>\$150</td><td></td><td></td><td></td><td></td></th<>	Answering Service for CMP SUBTOTA	AL \$0			1	1	1	1	1	1	1	1	1	1	1	1	1 1		1 1	. 1	1	1	1				20	U	\$150				
Strets Sweeping 1 <th1< th=""> 1 1</th1<>																											0)	\$0	\$37,000	\$37,000	\$37,000	\$34,850 moved from sub jobs. Added \$2150 to deal with insurance issue with original low bidder.
SUBTOTAL \$0 \$187,000	Street Sweeping				1	1	1	1	1	1	1	1	1	1	1	1	1 1		1 1	l 1	1	1	1				20	0	\$15,400	\$0	\$100,000	\$100,000	Reduced to \$100,000 Allowance. Had previously carried 22 days per month, half day at \$700 per half day.
	Temporary Humidification / De-humidification Allowance																										0)	\$0	\$0	\$50,000	\$50,000	Owner Allowance
	SUBTOTA	AL \$0																												SUBTOTAL	\$187,000	\$187,000	
GRAND TOTAL GENERAL \$0,601.630 \$1,460,167	GRAND TOTAL GENERAL															_								_							L \$1,601,630	\$1,460,167	

Skanska USA Building Brookline High School General Requirements GMP RESUBMISSION: 7/10/2020

PROJECT: Project A: 111 Cypress

	2020												2021												2022			
Phase	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	
PROJECTED SCHEDULE																												
Project A: 111 Cypress																												
Project C: STEM																												
Project F: Deferred Maintenance (Elevators Only)																												
Closeout																												

	Cost to Date 2020)									2021											20	022			Units	Unit Co	st Lump S Valu		Total Estimated Value	Revised Value with 10% Reduction	Notes
Description	Jan	Feb	Mar Apr	May	Jun Ju	ıl Au	ıg Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct N	lov D	Dec Ja	an F	eb Ma	ar							
tems from Table A																																
Construction Equipment and Tools (Small Tools)		1	1 1	1	1 1	L 1	. 1	1	1	1	1	1	1	1	1	1	1	1	1	1						21	\$3,800	\$0		\$79,800	\$71,820	\$3800 from GFE. Verify against current expenditures
Winter Conditions & snow/ice removal		1	1 1							1	1	1	1	1												8	\$6,000	\$0		\$48,000	\$43,200	To supplement areas not bought in site scope
Snow Removal from Roof Areas										1	1	1	1	1												5	\$5,000	\$0		\$25,000	\$22,500	
Debris and Trash Removal (Union Labor Foreman)																										0	\$0	\$0		\$0	\$0	Carried on separate worksheet
Flagman / Traffic Control																										0	\$0	\$0		\$0	\$0	See police detail allowance
Dust Control					1	ı 1	. 1	1	1	1	1	1	1	1	1	1	1	1	1	1						16	\$500	\$0		\$8,000	\$7,200	Greensweep and dust control tools and supplies
Trash chutes and dumpsters																										0	\$0	\$0		\$0	\$0	
Dumpsters	3	4	4 6	6	6 8	8 8	8	8	8	8	8	8	8	12	12	12	12	12	12	12	2					187	\$765	\$0		\$143,055	\$128,750	
Trash Chutes Staging for Access to Trash Chutes								1	1	1	1	1	1	1	1	1	1									0	\$0 \$1,000	\$35,0 \$10,0		\$35,000 \$21,000	\$31,500 \$18,900	For building set backs
Temp Toilets	8	6	8 8	8	8 8	3 8	8	8	8	8	8	8	8	8	8	8	8	8	8	6	2					11	\$1,000	\$10,0	00	\$26,100	\$23,490	For building set backs
Project Signage		1	1 1		1 1		1	1	1	1	1	1	1	1	1	1	1	1	1	1						21	\$100	\$0		\$2,100	\$1,890	
Safety railings, nets, ladders (Union Carpenter)																										0	\$0	\$0		\$0	\$0	Carried on separate worksheet
Firefight equipment		2	2 2	2	2 2	2 2	2	2	2	2	2	2	2	2	2	2	2	2	2	2						42	\$250	\$0 \$0		\$10,500 \$0	\$9,450 \$0	FE's and stands
Security guards Police Details - ALLOWANCE	1	2	2 2	1.5	1.5 1.	51.	5 1.5	1.5	1.5	1.5	1	1	1	1	1	1	1	1	1	1						0 29	\$14,40	90		\$0 \$417,600	\$0 \$375,840	Excluded ALLOWANCE \$50 per hour, assume 10 hour day with 2OT, plus \$5 per hour admin fee from Town.
Other Items																										0	\$0	\$0		\$0	\$0	TOWN.
Surveying and Layout	1	1	1 1	1	1 1	1	1	1	1	1	1	1	1	1	1	1	1									19	\$2,000	\$0		\$38,000	\$34,200	
Air quality during construction. Enclosures, fans, air machines										1	1	1	1	1	1	1	1	1	1	1						11	\$1,000	\$0		\$11,000	\$9,900	
Fire Watch (Hotwork) Fire Alarm Impairment ALLOWANCE																				20						0 20	\$550 \$550	\$0 \$0		\$0 \$11,000	\$0 \$9,900	Bought with Trades ALLOWANCE. \$500 per day plug in and out plus admin fee
Construction Materials (Temporary)	0.5	1	1 1	1	1 1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1						21.5	\$2,500	\$0		\$53,750	\$48,375	plus autimi tee
Overhead wire protection - ALLOWANCE																										0	\$0			\$0	\$0	See utility allowance above
Overhead wire protection MBTA - ALLOWANCE																										0	\$0	\$60,0		\$60,000	\$54,000	Line Protection
Hoisting Street permits / Rentals				1	1 1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1						18	\$1,000	\$0 \$0		\$18,000 \$0	\$16,200 \$0	By Owner
MBTA Force Account ALLOWANCE																										0	\$0	\$0 \$0		\$0	\$0	By Owner
Street Sweeping																										0	\$0	\$0		\$0	\$0	See General Tab
Mock Up Support																										0	\$0	\$30,0		\$30,000	\$27,000	Fencing, E&B, demolition, landscape restoration
SUBTOTA	L \$0																											SUBTO	TAL	\$1,037,905	\$934,115	
Direct Cost to be Assigned to Bid Packages																																
Temporary Heating and Cooling		1	1 1							1	1	1	1	1												8	\$2,500	\$0		\$20,000	\$20,000	GR support of work by trades
Temporary Enclosures		1	1 1							1	1	1	1	1												8	\$15,00	\$0		\$120,000	\$120,000	
Temp fencing, enclosure, walk, barricade, stair																			1	1						2	\$5,000			\$35,000	\$35,000	Lump for adjustments to fence set up by demo sub
OH Protection (Sidewalks) Tappan Temporary Scaffold Stairs																										200	\$150 \$25,00	\$0 \$0		\$30,000 \$25,000	\$30,000 \$25,000	200LF on Tappan only. NIC at Cypress
I emporary Scattold Stairs Tempoary Protection of Windows and Snap Cover Comeback																										1	\$25,00	\$0 \$60,0		\$25,000 \$60,000	\$25,000 \$60,000	
Tarping For Masonry Winter Work																										0	\$0	\$250,0		\$250,000	\$250,000	
Tarping For Building Winter Work (Curtainwall Openings)																										0	\$0	\$150,0		\$150,000	\$150,000	
Heat for Masonry Winter Work																										0	\$0	\$100,0		\$100,000	\$100,000	
Heat for Building Winter Work Boiler Watch																										0	\$0	\$100,0 \$0		\$100,000 \$0	\$100,000 \$0	Bu Oumor
Boller Watch Elevator Operater (Final 3 Months)																										0	\$0 \$0	\$0 \$140,0		\$0 \$140,000	\$0 \$140,000	By Owner \$140 per hour
Floor Flashing / Grinding																										0	\$0	\$80,0		\$80,000	\$80,000	\$1.5 per SF over entire building
Temporary rain leaders																										0	\$0	\$20,0		\$20,000	\$20,000	
Cafeteria Stair Scaffold Dance Floor																										0	\$0	\$50,0		\$50,000	\$50,000	
Cypress St Water Barrier Upgrades SUBTOTA	L \$0																									0	\$0	\$15,0 SUBTO		\$15,000 \$1,195,000	\$15,000 \$1,195,000	
SUBIOIA	r 30																											UBUC	1714	\$1,153,000	\$1,133,000	
Subtotal Project Requirements	\$0																													\$2,232,905	\$2,129,115	

Skanska USA Building Brookline High School General Requirements GMP RESUBMISSION: 7/10/2020

PROJECT: Project C: STEM

	2020												2021												2022		
Phase	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27
PROJECTED SCHEDULE																											
Project A: 111 Cypress																											
Project C: STEM																											
Project F: Deferred Maintenance (Elevators Only)																											
Closeout																											

	Cost to Date 2020	20											202	-1								2022		Units	Unit Cost	Lump Sum Value	Total Estimated Value	Revised Value with 10% Reduction	Notes
Description	Jan	n Fe	b Mi	lar /	Apr I	May	Jun	Jul	Aug	Sep	Oct	Nov I	Dec Jan	i Feb	Ma	r Apr	r May	Jun	Jul	Aug	Sep Oct Nov De	ec Jan Fet	b Mar						
Items from Table A																													
Construction Equipment and Tools (Small Tools)	0.5	5 1		1	1		1	1	1	1	1	1	1 1	1		1								15.5	\$3.800	\$0	\$58,900	\$53,010	\$3800 from GFE. Verify against current
						1	1	1	1	1	1														. ,	*-			expenditures
Winter Conditions & snow/ice removal	0.5	5 1	. 1	1	1								1 1	1	1	1								8.5	\$6,000	\$0	\$51,000	\$45,900	To supplement areas not bought in site scope
Snow Removal From Roof																								0	\$5,000	\$0	\$0	\$0	
Debris and Trash Removal (Union Labor Foreman) Flagman / Traffic Control																								0	\$13,000 \$0	\$0 \$0	\$0 \$0	\$0 \$0	Carried on a separate worksheet See Police Detail Allowance
•																								0		+-	*-		
Dust Control			1	1	1	1	1	1	1	1	1	1	1 1	1	1	1								14	\$500	\$0	\$7,000	\$6,300	Greensweep and dust control tools and supplie
Trash chutes and dumpsters Dumpsters		6		c		<i>,</i>	0	0	0	0			8 8											0	\$0 \$765	\$0 \$0	\$0 \$88,740	\$0 \$79,866	
Trash Chutes	4	0		0	0	0	0	0	0	0	0	•	0 0	0	•	0								0	\$705	\$35,000	\$35,000	\$31,500	
Staging for Access to Trash Chutes																								0	\$0	\$0	\$0	\$0	
Temp Toilets	8	8	8	8	8	8	8	8	8	8	8	8	8 8	8	8	8								128	\$150	\$0	\$19,200	\$17,280	
Project Signage		1	. 1	1	1	1	1	1	1	1	1	1	1 1	1	1	1								15	\$100	\$0	\$1,500	\$1,350	
Safety railings, nets, ladders (Union Carpenter)		-		_		-	_	_	2	-				_	_	_								0	\$14,733	\$0	\$0	\$0	Carried on a separate worksheet
Firefight equipment Security guards		2	2	2	2	2	2	2	2	2	2	2	2 2	2	2	2								30	\$250 \$0	\$0 \$0	\$7,500 \$0	\$6,750 \$0	FE's and stands Excluded
security guards																								0	\$U	30	30	30	ALLOWANCE \$50 per hour, assume 10 hour
Police Details - ALLOWANCE	0.75	5 1	1	1	1	1	1	1	1	1	1	1	1 1	1	0.5	0.5								14.75		\$0	\$212,400	\$191,160	day with 2OT, plus \$5 per hour admin fee from Town.
Other Items																								0	\$0	\$0	\$0	\$0	
Surveying and Layout	1	1	. 1	1	1	1	1	1	1	1	1	1	1 1	1	1	1								16	\$1,500	\$0	\$24,000	\$21,600	
Air quality during construction. Enclosures, fans, air machines						1	1	1	1	1	1	1	1 1	1	1	1								12	\$1,000	\$0	\$12,000	\$10,800	
Fire Watch (Hotwork) ALLOWANCE																								0	\$550	\$0	\$0	\$0	Bought with Trades
Fire Alarm Impairment ALLOWANCE										5	5	5	5 5	5	5	20								55	\$550	\$0	\$30,250	\$27,225	ALLOWANCE. \$500 per day plug in and out plus admin fee
Construction Materials (Temporary)		1	. 1	1	1	1	1	1	1	1	1	1	1 1	1	1	1								15	\$2,500	\$0	\$37,500	\$33,750	
Overhead wire protection / relocation																								0		\$0	\$0	\$0	See utility allowance above
Hoisting		1	. 1	1	1	1	1	1	1	1	1	1	1 1	1	1	1								15	\$1,000 \$0	\$0 \$0	\$15,000 \$0	\$13,500	Pu Querra
Street permits / Rentals																								0	\$0 \$0	\$0 \$0	50 50	\$0 \$0	By Owner
Barn Doors Loading Zones																								0	\$0	\$15,000	\$15,000	\$13,500	
Mock Up Support																								0	\$0	\$30,000	\$30,000	\$27,000	Fencing, E&B, demolition, landscape restoration
SUBTOT	TAL \$0																									SUBTOTAL	\$644,990	\$580,491	
Direct Cost to be Assigned to Bid Packages																													
Temporary Heating and Cooling		1	. 1	1	1								1 1	1	1	1								8	\$2,500	\$0	\$20,000	\$20,000	GR support of work by trades
Temporary Enclosures			1		1								1 1											8	\$15,000	\$0	\$120,000	\$120,000	
Temp fencing, enclosure, walk, barricade, stair															1	1								2	\$5,000	\$15,000	\$25,000	\$25,000	For adjustments to fence set up by demo sub
OH Protection (Sidewalks)																								0	\$350	\$0	\$0	\$0	
Temporary Scaffold Stairs																								0	\$0	\$11,000	\$11,000	\$11,000	
Tarping For Masonry Winter Work																								0	\$0	\$75,000	\$75,000	\$75,000	
Tarping For Building Winter Work (Curtainwall Openings)																								0	\$0	\$0	\$0	\$0	
Tempoary Protection of Windows and Snap Cover Comeback Heat for Masonry Winter Work																								0	\$0 \$0	\$60,000 \$50,000	\$60,000 \$50,000	\$60,000 \$50,000	
Heat for Building Winter Work																								0	\$0 \$0	\$20,000	\$20,000	\$20,000	
Elevator Operater (Final 3 Months)																								0	\$0	\$120,000	\$120,000	\$120,000	
Foundation Waterproofing Protection																								0	\$0	\$10,000	\$10,000	\$10,000	
Floor Flashing / Grinding																								0	\$0	\$50,000	\$50,000	\$50,000	\$1.5 per SF over entire building
Temporary Walkway Phasing																								0	\$0	\$30,000	\$30,000	\$30,000	
Boiler Watch Temporary rain leaders																								0	\$0 \$0	\$0 \$0	\$0 \$0	\$0 \$0	Assumed not req'd. Use campus HW
Selective Demolition (Unpurchased Scope)																								0	\$0 \$0	\$0 \$0	\$30,000	\$30,000	
Subtol	TAL \$0																								**	SUBTOTAL	\$621,000	\$621,000	
Subtotal Project Requirements	\$0																										\$1,265,990	\$1,201,491	

Skanska USA Building Brookline High School General Requirements GMP RESUBMISSION: 7/10/2020

PROJECT: Project F: Deferred Maint. Elevator Refurbishment Only

	2020												2021												2022			
Phase	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	
PROJECTED SCHEDULE																												
Project A: 111 Cypress																												
Project C: STEM																												
Project F: Deferred Maintenance (Elevators Only)																												
Closeout																												

	Cost to Date	2020							20	21								2022			Units	Unit Cost	Lump Sum Value	Total Estimated Value	l Notes
Description		Jan Feb	Mar A	Apr May	Jun	Jul Aug	Sep Oc	t Nov	Dec Ja	n Feb	Mar Ap	or May	y Jun	Jul	Aug Sep Oct	t Nov	Dec	Jan	Feb Ma	ar					
tems from Table A																									
Construction Equipment and Tools (Small Tools)					1	1 1							1	1	1						6	\$500	\$0	\$3,000	
Temporary Enclosures																					0	\$15,000	\$15,000	\$15,000	Included in Elev. RTA
Debris and Trash Removal (Union Labor Foreman)																					0	\$13,000	\$0	\$0	See separate spreadsheet
Dust Control					1	1 1							1	1	1						6	\$50	\$0	\$300	Greensweep and dust control tools and supplies
Dumpsters					1	1 1							1	1	1						6	\$765	\$0	\$4,590	
Femp Toilets					1	1 1							1	1	1						6	\$150	\$0	\$900	
Project Signage					1	1 1							1	1	1						6	\$100	\$0	\$600	
Safety railings, nets, ladders (Union Carpenter)																					0	\$14,733	\$0	\$0	See separate spreadsheet
irefight equipment					1	1 1							1	1	1						6	\$250	\$0	\$1,500	FE's and stands
Security guards																					0	\$0	\$0	\$0	Excluded
Police Details																					0	\$13,200	\$6,600	\$6,600	12 deliveries at \$550 each
Other Items																					0	\$0	\$0	\$0	
ire Alarm Impairment ALLOWANCE																					0	\$500	\$0	\$0	Bought with trades
Jtility consumption																					0	\$0	\$0	\$0	See utility allowance above
Construction Materials (Temporary)					1	1 1							1	1	1						6	\$500	\$0	\$3,000	
SU	BTOTAL \$0																						SUBTOTAL	\$35,490	
Direct Cost to be Assigned to Bid Packages																									
																					0	\$0	\$0	\$0	
su	BTOTAL \$0																						SUBTOTAL	\$0	
Subtotal Project Requirements	\$0																							\$35,490	

Skanska USA Building Brookline High School General Requirements GMP RESUBMISSION: 7/10/2020

FORECAST FOR CRAFT LABOR

			40.00	40.00	40.00	40.0) 40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00	40.00					
ABORERS/CARPENT	TERS	Wks	4.33	4.33	4.33	4.3	<mark>3 4.33</mark>	4.33	4.33	4.33	4.33	4.33	4.33	4.33	4.33	4.33	4.33	4.33	4.33	4.33	4.33	4.33	4.33	4.33	4.33	4.33				r
Position	Рау Туре	Hourly Cost	Jan-20	Feb-20	Mar-20	Apr-20	May-20	Jun-20	Jul-20	Aug-20	Sep-20	Oct-20	Nov-20	Dec-20	Jan-21	Feb-21	Mar-21	Apr-21	May-21	Jun-21	Jul-21	Aug-21	Sep-21	Oct-21	Nov-21	Dec-21	Total	Estimated Value	Revised Value with 5% Reduction	Variance
oor Foreman Cypress	Regular	\$ 85.00		0.25	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	\$	327,565	\$ 311,186	<u> </u>
	Overtime	\$ 109.00		0.06	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	\$	105,013	\$ 99,763	
	Double Time	\$ 136.00																									\$	-	\$-	
ly Cleaning Cypress (#1)	Regular	\$ 79.00				1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0		Ś	273,656	\$ 259,973	<u> </u>
if cleaning efficient (in 1)	Overtime	\$ 104.00				0.25			0.25	0.25	0.25	0.25		0.25	0.25			0.25	0.25			0.25	0.25	0.25	0.25		Ś	90.064		
	Double Time	\$ 128.00				0.23	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.20	0.25		\$	-	\$ -	
														-																
ily Cleaning Cypress (#2)	Regular	\$ 79.00														1.0		1.0	1.0	-	-	1.0	1.0	1.0	1.0		Ş	136,828	\$ 129,987	───
	Overtime Double Time	\$ 104.00 \$ 128.00														0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25		\$	45,032	\$ 42,780 \$ -	<u> </u>
	bouble fille	÷ 120100																									, , , , , , , , , , , , , , , , , , ,		÷	
ward Cypress/STEM	Regular	\$ 79.00																									\$	-	\$-	
	Overtime	\$ 104.00		0.06	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25			\$	91,190	\$ 86,630	
	Double Time	\$ 128.00																									\$	-	\$-	L
oor Foreman STEM	Regular	\$ 85.00		0.25	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0							Ś	239,233	\$ 227,271	
	Overtime	\$ 109.00		0.06	0.25			0.25	0.25	0.25	0.25	0.25		0.25	0.25	0.25	0.25	0.25	0.25								\$	76,695	\$ 72,860	
	Double Time	\$ 136.00																									\$	-	\$ -	
ily Cleaning STEM (#1)	Regular	\$ 79.00								1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0								ć	136.828	\$ 129.987	
ny cleaning STEIVI (#1)	Overtime	\$ 104.00								0.25	0.25	0.25	-	0.25	0.25	0.25	0.25	0.25	0.25								ې د	45,032	.,	<u> </u>
		\$ 128.00								0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25								\$	-	\$ -	<u> </u>
ily Cleaning STEM (#2)	Regular	\$ 79.00					1.0	1.0	1.0	1.0	1.0	1.0	-	1.0	1.0	1.0	-	1.0	1.0								\$	177,876		
	Overtime Double Time	\$ 104.00 \$ 128.00		├			0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25								\$	58,542	\$ 55,615 \$ -	
		\$ 128.00																									Ş	-	<u>ې</u> -	
ily Cleaning STEM (#3)	Regular	\$ 79.00		1			1									1.00	1.00	1.00	1.00								\$	54,731	\$ 51,995	
	Overtime	\$ 104.00														0.25	0.25	0.25	0.25								\$	18,013	\$ 17,112	
	Double Time	\$ 128.00																									\$		\$-	
rpenter Foreman	Regular	\$ 104.00		0.25	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0			Ś	364,759	\$ 346,521	
ve Daniels		\$ 135.00		0.23	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0			Ś	-	\$ -	<u> </u>
		\$ 169.00					1						1														\$	-	\$ -	<u> </u>
																													•	
			-	15,350	61,399	79,585	97,771	97,771	97,771	115,957	115,957	115,957	115,957	115,957	115,957	152,329	152,329	152,329	152,329	97,771	78,330	78,330	78,330	78,330	55,814	19,442	\$	2,241,056	\$ 2,129,004	
						-		-		-		-		-		-	-							-						

ESTIMATED	COST OF DIVERSIO						
Laborer and	Steward						
15 diversion	s Fri 10pm - Sun 10	pm					
Fri night	8hrs OT	8	109	872			
Sat	16hrs OT	16	109	1744			
Sun	24hrs DT	24	136	3264	Diversions	Lab & Stew	
				5880	15	2	176400

Assumed cost of 15 Diversions	\$176,400	\$167,580
Total (Incl Div) Deduct Const Wate Mangment	\$ 2,417,456	\$ 2,296,584



Date: 7/10/2020

Project # 1318014

Prime Contract Change Order Number 007

Skanska USA Building Inc.

To Contractor: Skanska USA Building Inc.

Brookline High School

The Contract is hereby revised by the following items:

GMP Schedule Adjustment

AR	CE	Description	Amount
100.001	009	GMP Schedule Adjustment	\$ 1,064,634.00

This Change Order includes adjusted Contract Time and General Conditions / General Requirements costs only as outlined below:

• STEM Wing Addition ("Stem")

o Revised interim completion date as described in enclosed Exhibit D ("Stem Interim Completion Date").

o General Conditions and General Requirements costs for the 10 week extension from April __ through July 7, 2021 in the amount of \$1,016,524.00.

o Excludes any Subcontractor costs or claims associated with the Stem Interim Completion Date, as those will be handled separately and on a case by case basis.

o Excludes any costs (General Conditions, General Requirements, Subcontractor or other costs) associated with COVID-19 or other pandemics.

• 111 Cypress St

o Revised Substantial Completion Date as described in enclosed Exhibit D.

o Excludes Subcontractor costs or claims associated with the revised Substantial Completion Date, as those will be handled separately and on a case by case basis.

o Excludes any costs (General Conditions, General Requirements, Subcontractor or other costs) in connection with the Revised Substantial Completion Date or with COVID-19 or other pandemics. The GMP includes an Owner's Pandemic Allowance for those costs.

• MBTA

o Revised interim completion date as described in enclosed Exhibit D ("MBTA Interim Completion Date").

o Excludes Subcontractor costs or claims associated with the MBTA Interim Completion Date, as those will be handled separately and on a case by case basis.

o Excludes any costs (General Conditions, General Requirements, Subcontractor or other costs) associated with COVID-19 or other pandemics. The GMP includes an Owner's Pandemic Allowance for those costs.

Neither the adjustments to the Contract Price nor the Contract Time upon which this PCCO is based contemplates any project delays, suspensions, disruptions, cost escalations or other impacts caused, directly or indirectly, by the Pandemic (as defined in the GMP), as such cost adjustment to the Contract Sum and GMP shall be reconciled in accordance with the Owner Pandemic Allowance. Skanska further reserves all rights to request adjustment of the Contract Time as a result of the Pandemic Standards and in connection with this PCCO. Skanska will make every reasonable effort to provide the required documentation and notice in accordance with this Contract, however, Skanska may not be able to meet the contractual deadlines due to circumstances outside of Skanska's control.

Printed on: 7/8/2020

Page 1 of 1



_Authorization Request

Skanska USA Building Inc.

1318014 - Brookline High School

115 Greenough Street, Brookline, MA 02445

1318014	Brookline High School				
Authorization Requ	iest: 100.001				Date: 7/10/2020
To:		From:			
Town of I	Brookline		Skanska USA Buildin	g Inc.	
			Tel: (617) 574-1400	Fax: (617) 574-1399	
Description					Status
GMP Schedule Adjust	nent				Open
-		-			

Reference	Required By	Amt Req	Days Req
	7/14/2020	\$1,064,634.00	

Notes

This Change Order includes adjusted Contract Time and General Conditions / General Requirements costs only as outlined below:

STEM Wing Addition ("Stem")

o Revised interim completion date as described in enclosed Exhibit D ("Stem Interim Completion Date").

o General Conditions and General Requirements costs for the 10 week extension from April __ through July 7, 2021 in the amount of \$1,016,524.00.

o Excludes any Subcontractor costs or claims associated with the Stem Interim Completion Date, as those will be handled separately and on a case by case basis.

o Excludes any costs (General Conditions, General Requirements, Subcontractor or other costs) associated with COVID-19 or other pandemics.

• 111 Cypress St

o Revised Substantial Completion Date as described in enclosed Exhibit D.

o Excludes Subcontractor costs or claims associated with the revised Substantial Completion Date, as those will be handled separately and on a case by case basis. o Excludes any costs (General Conditions, General Requirements, Subcontractor or other costs) in connection with the Revised Substantial Completion Date or with

COVID-19 or other pandemics. The GMP includes an Owner's Pandemic Allowance for those costs.

• MBTA

o Revised interim completion date as described in enclosed Exhibit D ("MBTA Interim Completion Date").

o Excludes Subcontractor costs or claims associated with the MBTA Interim Completion Date, as those will be handled separately and on a case by case basis. o Excludes any costs (General Conditions, General Requirements, Subcontractor or other costs) associated with COVID-19 or other pandemics. The GMP includes an Owner's Pandemic Allowance for those costs.

Neither the adjustments to the Contract Price nor the Contract Time upon which this AR is based contemplates any project delays, suspensions, disruptions, cost escalations or other impacts caused, directly or indirectly, by the Pandemic (as defined in the GMP), as such cost adjustment to the Contract Sum and GMP shall be reconciled in accordance with the Owner Pandemic Allowance. Skanska further reserves all rights to request adjustment of the Contract Time as a result of the Pandemic Standards and in connection with this AR. Skanska will make every reasonable effort to provide the required documentation and notice in accordance with this Contract, however, Skanska may not be able to meet the contractual deadlines due to circumstances outside of Skanska's control.

CE No	Date	Description	CE Category	CE Reason	Days Req
009	6/11/2020	GMP Schedule Adjustment	Owner	Change Condition	
Item No	Company		Item Description		Amt Prop
001			GMP Schedule Adjustment - GENERAL CONDITIONS		\$227,575.00
002			GMP Schedule Adjustment - GENERAL REQUIREMENTS		\$750,892.00
			Daga 202 of 277		

003	Railroad Insurance		\$711.00
Level 001	Change Order OH & P		\$48,923.00
Level 002	SDI		\$0.00
Level 003	Builder's Risk		\$2,740.00
Level 004	CCIP		\$26,021.00
Level 005	Skanska Bond		\$7,772.00
		CE #009 Total	\$1,064,634.00
		AR #100.001 Total:	\$1,064,634.00

Printed on: 7/8/2020

Page 2 of 2

Skanska USA Building Inc.

Change Request #

AR 100.001

To: Ray Masak Project Manager 333 Washington Street, 6th Floor Brookline, MA 02445 7/10/2020 Project #: 1318014 Project: Brookline High School Expansion Project

Description:	Proposed Amount
GMP Schedule Adjustment	
	Amount
Construction Manager Costs (Line 5)	\$978,467
Subcontractor and/or Trade Contractor Costs (Line 8)	\$0
Overhead & Profit (Line 6 + Line 9)	\$48,923
Subcontractor Default Insurance (Line 11)	\$0
Builder's Risk Insurance (Line 12)	\$2,740
CCIP (Line 13)	\$26,021
Skanska Bond (Line 14)	\$7,772
Railroad Insurance Policy (Line 15)	\$711
Total :	\$1,064,634

Type: Schedule Impact: Overtime: Notes:

The date of substantial completion will be November 15, 2021, Refer to enclosed Exhibit D. Project OT (Is / $\frac{15 \text{ Not}}{15 \text{ Not}}$) Required

This Change Order includes adjusted Contract Time and General Conditions / General Requirements costs only as outlined below:

STEM Wing Addition ("Stem")

o Revised interim completion date as described in enclosed Exhibit D ("Stem Interim Completion Date").

Lump Sum

o General Conditions and General Requirements costs for the 10 week extension from April through July 7, 2021 in the amount of \$1,016,524.00.

o Excludes any Subcontractor costs or claims associated with the Stem Interim Completion Date, as those will be handled separately and on a case by case basis.

o Excludes any costs (General Conditions, General Requirements, Subcontractor or other costs) associated with COVID-19 or other pandemics.

111 Cypress St

o Revised Substantial Completion Date as described in enclosed Exhibit D.

o Excludes Subcontractor costs or claims associated with the revised Substantial Completion Date, as those will be handled separately and on a case by case basis. o Excludes any costs (General Conditions, General Requirements, Subcontractor or other costs) in connection with the Revised Substantial Completion Date or with COVID-19 or other pandemics. The GMP includes an Owner's Pandemic Allowance for those costs. • MBTA

o Revised interim completion date as described in enclosed Exhibit D ("MBTA Interim Completion Date").

o Excludes Subcontractor costs or claims associated with the MBTA Interim Completion Date, as those will be handled separately and on a case by case basis. o Excludes any costs (General Conditions, General Requirements, Subcontractor or other costs) associated with COVID-19 or other pandemics. The GMP includes an Owner's Pandemic Allowance for those costs.

Neither the adjustments to the Contract Price nor the Contract Time upon which this AR is based contemplates any project delays, suspensions, disruptions, cost escalations or other impacts caused, directly or indirectly, by the Pandemic (as defined in the GMP), as such cost adjustment to the Contract Sum and GMP shall be reconciled in accordance with the Owner Pandemic Allowance. Skanska further reserves all rights to request adjustment of the Contract Time as a result of the Pandemic Standards and in connection with this AR. Skanska will make every reasonable effort to provide the required documentation and notice in accordance with this Contract, however, Skanska may not be able to meet the contractual deadlines due to circumstances outside of Skanska's control.

Ω		
Well	July 14, 2020	
Skanska USA Building Inc.	Date:	
Ourse tely	July 14, 2020	

Town of Brookline or Hill International (on behalf of the Town of Brookline) Date:

Owner authorizes Skanska USA Building Inc. to issue Subcontract Change Orders associated with this scope and confirms availability of funds for payment of the same.

William Rawn Associates

Date:

July 13, 2020

cc: Hill: Andy Felix WRA: Andy Jonic Skanska: Rob Mulligan, Peter Roche, Jim Craft CE File: CE # 009

PROJECT NAME:	Brookline High School	PROJECT NO.	1318014	CM: Skanska USA Building Inc.					
PCO NUMBER:	009	PCO DESCRIPTION:							
PCO DATE:	7/10/2020			GMP Schedule Adjustment					
SKA PCO NUMBER:	009								
	CONSTRUCTION MANAGER CHANGE REQUEST SUMMARY								

CONSTRUCTION MANAGER CHANGE REQUEST SUMMARY

1. LABOR: CONSTRUCTION MANAGER'S SELF-PERFORMED WORK

		Regular Hours	Overtime (1.5x)	Double Time (2x)		be taken from the R r its approval by the	ate Approval Sheet, CM.		
Trade	Classification	Worked	Hours Worked	Hours Worked	Regular Time Rate		Double Time Rate		Total Labor Cost
					(Cost/hour)	(Cost/Hour)	(Cost/Hour)		
General Conditions	See attached worksheet								\$227,575.00
General Requirements	See attached worksheet								\$750,892.00
									\$0.00
									\$0.00
									\$0.00
									\$0.00
									\$0.00
								TOTAL LABOR COST	\$978,467

2. MATERIALS: CONSTRUCTION MANAGER'S SELF PERFORMED WORK
Material Description Quantity Cost per Unit Total Unit See attached worksheet \$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$0.00 TOTAL MATERIALS COST

PROJECT NAME:	Brookline High School	PROJECT NO.	1318014	CM:	Skanska USA Building Inc.		
PCO NUMBER:	009	PCO DESCRIPTION:					
PCO DATE:	7/10/2020			GMP Sch	edule Adjustment		
SKA PCO NUMBER:	009						
		CONSTRUCTION MANAGER CHANGE	REQUEST SUMMARY				
3. EQUIPMENT: CONS	TRUCTION MANAGER'S SELF PERF	Equipment Description		Qty	Unit Cost Per	Unit	Total
See attached workshe	et	4		~ /	each		\$0
							\$0
L					TOTAL EC	UIPMENT COST:	\$0
4. WISC. LOWP SUMP	SERVICES PROVIDED TO CONSTRU	CTION MANAGER (POLICE DETAIL, UTILIT Description of Mi	iscellaneous Lump Sum Service				Total
See attached workshe	et						\$0
				TOTAL	MISC. LUMP SUM SERVICES CO	DST:	\$0 \$0
5. SUBTOTAL COSTS F	OR CONSTRUCTION MANAGER LI	NE ITEMS 1., 2., 3., AND 4.			SUBTOT	AL:	\$978,467
(Line 1, 2, 3, & 4)							<i>terei</i> ,
6. OVERHEAD AND PR	OFIT OF CONSTRUCTION MANAG	ER LINE ITEM 5:			10% X Line 5:		\$0
	permitted 10% of total actual cos						
7. TOTAL OF LINES 5.8	6 FOR CONSTRUCTION MANAGE	R:		то	TAL COST OF WORK SELF-PERF	FORMED BY C.M.	\$978,467
	DRK PERFORMED BY TRADE / SUB Total for Subcontractors	CONTRACTORS: \$0	Refer to attached summary of trades / s	ubcontractor pricing	I		\$0
	Total for Trade Contractors	\$0					
					5%	l	¢ 40,022,25
9. OVERHEAD AND PR	OFIT FOR TRADE / SUBCONTRAC	IOR WORK:			5%		\$48,923.35
10. SUBTOTAL LINES 7	., 8., AND 9.						\$1,027,390
11. SUBCONTRACTOR	DEFAULT INSURANCE (SDI)			Subcontractors only	1.35% x ITEM 8	a:	\$0
12. BUILDER'S RISK IN	SURANCE				0.28% x ITEM 5	& 8	\$2,740
13.CCIP					2.65% x ITEMS	(16-6-9-13-14-15)	\$26,021
14. Skanska Bond					0.73% x ITEM 1	16	\$7,772
15. Railroad Protectiv	e Policy				0.0668% x ITEM 1	16	\$711
16. Grand Total							\$1,064,634

SUBCONTRACTORS	Amount	TRADE CONTRACTORS	Amo	
1	\$ -	1	\$	
2	\$ -	2	\$	
3	\$ -	3	\$	
4	\$ -	4	\$	
5	\$ -	5	\$	
6	\$ -	6	\$	
7	\$-	7	\$	
8	\$-	8	\$	
9	\$-	9	\$	
10	\$ -	10	\$	
TOTAL	\$ -	TOTAL	\$	

Town of Brookline Brookline High School Expansion Project | Project A and B EXHIBIT D: CONTRACT TIME

The Date of Substantial Completion for the Project prior to this Amendment is:	October 8, 2021
This Amendment revises the Contract duration by (Calendar Days):	39
The revised Date of Substantial Completion is:	November 15, 2021*

*Excludes Subcontractor costs or claims associated with the revised Substantial Completion Date, as those will be handled separately and on a case by case basis. Excludes any costs (General Conditions, General Requirements, Subcontractor or other costs) in connection with the Revised Substantial Completion Date or with COVID-19 or other pandemics. The GMP includes an Owner's Pandemic Allowance for those costs.

- 1. The above Date of Substantial Completion is based on Project A: 111 Cypress St. The anticipated interim project completion dates for other subprojects are outline below, but do not represent Substantial Completion Dates as outlined in the Owner Construction Manager Agreement.
 - a. Project C STEM Wing: July 7, 2021
 - b. MBTA Platform: December 10, 2021
- 2. Refer to attached Project Schedules
 - a. Project A: 111 Cypress St. Data Date: 06-Jun-20 / Run Date: 11-Jun-20
 - b. Project C: STEM Addition. Data Date: 06-Jun-20 / Run Date: 10-Jun-20

okline High School - Project A - 06Jun20 R1 Schedule Update - 1318014-CR - B27 ity ID Activity Name					Schedule		Data Date: 06-Jun-20 / Run Date: 09-Jul-20 09:07			
nty ID	ACTIVITY NAME	Remaining Duration	Start	Finish	2020	2)21	2022		
		Baradon			Jun Jul Aug Sep Oct Nov Dec			Jan Feb Mar		
rookline H	ligh School - Project A - 06Jun20 R1 Schedule Update									
Executive S									- 1 1	
EXEC-1065	Bid Period	28	04-Mar-19 A	16-Jul-20	Bid Period			1	1	
EXEC-1070	Construction Project A - 111 Cypress Building	360	24-Jun-19A	15-Nov-21			Cons	truction Project	A - 111 Cypres	s Building
Work Order	r Milestones							I I		
EXEC-1060	Last Day for Tappan & Cypress Temporary Power Line Relocation	0		05-Jun-20 A	♦ Last Day for Tappan & Cypress 1	emporary Power Line Relocat	on	 		÷÷
EXEC-1100	Last Day for Cypress Building Permanent Power	0		16-Jun-20	♦ Last Day for Cypress Building I	ermanent Power		1	 	
EXEC-1110	Last Day for Cypress Building New Gas Service	0		16-Jun-20	◆ Last Day for Cypress Building I	New Gas Service			1	
EXEC-1150	Last Day for Cypress Building New Fire, Water & Sewer	0		16-Jun-20	◆ Last Day for Cypress Building I	vew Fire, Water & Sewer		1		
EXEC-1140	Last Day for Cypress Building New Telecom Service	0		29-Sep-21			Last Day for	Dypress Building	g New Telecom	Service
BHS Acade	mic Calendar					+				÷
	April Break - 2020	0	20 Apr 20 A	24 Apr 20 A	l Drahle 2020			1	- 	
BHS-1040			20-Apr-20 A	•	I Break - 2020				1	
BHS-1050	Last Day of School - 2019/2020	0		22-Jun-20* 03-Sep-20*	 Last Day of School - 2019/202 First Day of Scho 			1 	1	
BHS-1060	First Day of School - 2020/2021 December Break - 2020		25 Dec 20*	•		December Break - 2020		i	 	
BHS-1070		8	25-Dec-20*	01-Jan-21*	<u>+</u>				, ,	÷
BHS-1080 BHS-1090	February Break - 2021 April Break - 2021	5	15-Feb-21*	19-Feb-21* 23-Apr-21*		 February Break - 2 April Bre 	1	Ì	1	
	•		19-Apr-21*			1 1 1 1	I I		1	
BHS-1100	Last Day of School - 20202021	0		22-Jun-21*		•	Last Day of School - 2020202		1	
BHS-1110	First Day of School - 2021/2022	0		02-Sep-21*			First Day of School	ol - 2021/2022	1 1 1	
Design / Pre	econstruction Phase								 	
GMP						1		I I		
PRE-1180	Review & Execute - GMP	20	16-Mar-20 A	06-Jul-20	Review & Execute - GMP				1	
PRE-1190	Agreement Executed - GMP	0		06-Jul-20	Agreement Executed - GMI	4		I I	1	I I I I I I I I I I I I I I I I I I I
Schedule Im	nnacts			,					1 1 1	
								1		
	tion Support Limitations					Į				
IMP-1462	Impact - MBTA Operation Support Limitations	0			Impact - MBTA Operation Suppo	1 1		1		
IMP-1482	Impact - Remobilize to Site after MBTA Support Suspension	0	05-Jun-20 A	05-Jun-20 A	Impact - Remobilize to Site after	VIBIA Support Suspension			1	
-	Union Work Suspension			1				1	1 1 1	1 I 1 I 1 I
IMP-1472	Impact - Carpenters' Union Work Suspension & Remobilization to Site	0	06-Apr-20 A	24-Apr-20 A	act - Carpenters' Union Work Suspe	nsion & Remobilization to Site			1 1 1	
FB-081 - Exte	erior Mockup Revisions							' 	, , ,	
IMP-1492	Impact - FB-081 - Exterior Mockup Revisions	0	09-Apr-20 A	23-Apr-20 A	act - FB-081 - Exterior Mockup Revi	sions				
MBTA Work								1	1 1	
Procurement									1	
Procurement								1	1	
	ard MBTA Platform							1		
CWP MBTA						J	++	L		
	Submit, Approve, Fab & Deliver - MBTA Platform	172	07-Nov-19A	16-Feb-21	-	Submit Approve E	b & Deliver - MBTA Platform		- 2 2	
MBTA-1260 MBTA-1260		0			epare & Submit - CWP MBTA Platfo			1 	1	
MBTA-1260 MBTA-1265	•	23	01-May-20 A					1	1	
MBTA Platfor		23	51-11/ay-20 A	03-34-20				1	1 	
Tactile Warn								 		
BLHA-890		Ο	03-Apr-20 A	22_Apr-20 A	pare & Submit - Tactile Warning Strip	R1	1 I 1 I 1 I		1	
BLHA-090 BLHA-900	Review & Approve - Tactile Warning Strip_R1	10	23-Apr-20 A	•	Review & Approve - Tactile War	. .		1 	1	
BLHA-900 BLHA-910		20		20-Jul-20	Fab & Deliver - Tactile Wa		1 I 1 I 1 I	1	1	1 I 1 I 1 I
		20	22-Jun-20	20-Jul-20				1	1	
Helical Piles BLHA-0240		10		10 Jun 20	Fab & Deliver - Helical Piles		· · · · · · · · · · · · · · · · · · ·			
		10	08-Jun-20	19-Jun-20				1	, 1 1	
	Test Program	•	00 4 00 4	00 4 00 1		non DO		İ	 	
) Prepare & Submit - Helical Pile Test Program_R0	0	•	· ·	pare & Submit - Helical Pile Test Pro			1	1 1	
BLHA-1030		0	•		eview & Approve - Helical Pile Test I			I	1	
BLHA-1010	Prepare & Submit - Helical Pile Test Program_R1	0	11-May-20 A	27-May-20 A	Prepare & Submit - Helical Pile Tes	ar Program_R1		I	1	
Domainin	ng Level of Effort Remaining Work					Two Months Drier				
			Page 1 of 27		TASK filter: Uncompleted Activities		ornaration			
Actual Le	evel of Effort Critical Remaining Work					© Oracle C		SK	ANS	КА
							1			
Actual Wo	'ork 🔶 🔶 Milestone			1						

	- Project A - 06Jun20 R1 Schedule Update - 1318014-CR - B27	Domoinin	Chart		I Schedule			Data Date: 06-Jun-20 / Run Date	. 05-001-20 05.07
ID	Activity Name	Remaining Duration	Start	Finish	2020		2021	2022	
		Duration						ec Jan Feb Mar Apr May Jun Jul	Aug Sep Oct N
BLHA-1020	Review & Approve - Helical Pile Test Program_R1	0	28-May-20 A	05-Jun-20 A					
	Fab & Deliver - Helical Pile Test Pile & Equipment	2	08-Jun-20	09-Jun-20	Fab & Deliver - Helical Pile Tes	t Pile & Equipment			1
	Complete Test Pile and Reports	3	10-Jun-20	12-Jun-20	Complete Test Pile and Repor				
Canopy Struct									1
BLHA-0250	Prepare & Submit - Canopy Structures_R0	18	18-May-20 A	01-Jul-20	Prepare & Submit - Canop	Structures R0			1
BLHA-0260	Review & Approve - Canopy Structures_R0	20	02-Jul-20	30-Jul-20	Review & Approve - C				
BLHA-0200 BLHA-0262	Prepare & Submit - Canopy Structures_R1	20 E		06-Aug-20	Prepare & Submit - C			i i i i i i i i i i i i i i i i i i i	1
		5	31-Jul-20						1
BLHA-0264	Review & Approve - Canopy Structures_R1	20	07-Aug-20	03-Sep-20		ve - Canopy Structures_R1			
	Fab & Deliver - Canopy Structures	85	04-Sep-20	11-Jan-21		Fab & Deliver - Canopy	Structures		1
Misc Metal Rai			1						·
BLHA-0280	Prepare & Submit - Misc Metal Railings_R0	21	08-Jun-20	07-Jul-20	Prepare & Submit - Misc I				
BLHA-0290	Review & Approve - Misc Metal Railings_R0	20	08-Jul-20	04-Aug-20	Review & Approve -	1 1			1
BLHA-0292	Prepare & Submit - Misc Metal Railings_R1	5	05-Aug-20	11-Aug-20	Prepare & Submit -	Misc Metal Railings_R1			
BLHA-0294	Review & Approve - Misc Metal Railings_R1	20	12-Aug-20	09-Sep-20	Review & Appr	ove - Misc Metal Railings_R1			1
BLHA-0300	Fab & Deliver - Misc Metal Railings	65	10-Sep-20	15-Dec-20		Fab & Deliver - Misc Metal R	ailings		1
Security Equip			· ·		11	-1		······································	
BLHA-0340	Prepare & Submit - Security Equipment_R0	21	06-May-20 A	07-Jul-20	Prepare & Submit - Secur	ity Equipment R0			
BLHA-0350	Review & Approve - Security Equipment_R0	20	08-Jul-20	04-Aug-20	Review & Approve -	, , , _ ,			
BLHA-0352	Prepare & Submit - Security Equipment_R1	5	05-Aug-20	11-Aug-20	Prepare & Submit -				-
BLHA-0354	Review & Approve - Security Equipment_R1	20	12-Aug-20	09-Sep-20		ove - Security Equipment_R1			
		65	10-Sep-20	· ·					
	Fab & Deliver - Security Equipment	05	10-Sep-20	15-Dec-20		Fab & Deliver - Security Equi	priient		
PA/VMS Equip		40		40.1.00					1
BLHA-0370	Prepare & Submit - PA/VMS Equipment_R0	10	26-May-20 A		Prepare & Submit - PA/VMS				
BLHA-0380	Review & Approve - PA/VMS Equipment_R0	20	22-Jun-20	20-Jul-20	Review & Approve - PA				
BLHA-0382	Prepare & Submit - PA/VMS Equipment_R1	5	21-Jul-20	27-Jul-20	Prepare & Submit - PA				
BLHA-0384	Review & Approve - PA/VMS Equipment_R1	20	28-Jul-20	24-Aug-20	Review & Approv	PA/VMS Equipment_R1			
BLHA-0390	Fab & Deliver - PA/VMS Equipment	85	25-Aug-20	29-Dec-20		Fab & Deliver - PA/VMS Ec	quipment		
Slab Reinforce	ement								
BLHA-0400	Prepare & Submit - Slab Reinforcement_R0	0	06-Apr-20 A	28-Apr-20 A	pare & Submit - Slab Reinforceme	nt R0			
BLHA-0410	Review & Approve - Slab Reinforcement_R0	0	29-Apr-20 A	07-May-20 A	eview & Approve - Slab Reinforcer	nent R0			
BLHA-0412	Prepare & Submit - Slab Reinforcement_R1	5	08-May-20 A		Prepare & Submit - Slab Reinf			· · · · · · · · · · · · · · · · · · ·	
BLHA-0414	Review & Approve - Slab Reinforcement_R1	20	15-Jun-20	13-Jul-20	Review & Approve - Slab				
	Fab & Deliver - Slab Reinforcement	45	14-Jul-20	15-Sep-20	Fab & Deliver				
	1		14-001-20	10-000-20					
Lighting Equi		04	00 100 20	07 1.1 20					
BLHA-0430	Prepare & Submit - Lighting Equipment_R0	21	08-Jun-20	07-Jul-20	Prepare & Submit - Lightir				
BLHA-0440	Review & Approve - Lighting Equipment_R0	20	08-Jul-20	04-Aug-20	Review & Approve - 1				
BLHA-0442	Prepare & Submit - Lighting Equipment_R1	5	05-Aug-20	11-Aug-20	Prepare & Submit -	T - · · · · -			
BLHA-0444	Review & Approve - Lighting Equipment_R1	20	12-Aug-20	09-Sep-20	Review & Appr	ove - Lighting Equipment_R1			
BLHA-0450	Fab & Deliver - Lighting Equipment	65	10-Sep-20	15-Dec-20		Fab & Deliver - Lighting Equi	pment		
Permanent Ru	bber Rail Crossing				<u> </u>				,
BLHA-930	Review & Approve - Permanent Rubber Rail Crossing_R0	0	02-Apr-20 A	22-Apr-20 A	iew & Approve - Permanent Rubbe	r Rail Crossing_R0			
BLHA-940	Fab & Deliver - Permanent Rubber Rail Crossing	25	08-Jun-20	13-Jul-20	Fab & Deliver - Permane	nt Rubber Rail Crossing			1
Wayfinding Si			-	-	1				1
BLHA-0460	Prepare & Submit - Wayfinding Signage_R0	21	08-Jun-20	07-Jul-20	Prepare & Submit - Wa yfi	nding Signage RÓ			
BLHA-0470	Review & Approve - Wayfinding Signage_R0	20	08-Jul-20	04-Aug-20	Review & Approve - 1				1
BLHA-0610	Prepare & Submit - Wayfinding Signage_R1	5	05-Aug-20	11-Aug-20	Prepare & Submit -				
BLHA-0620	Review & Approve - Wayfinding Signage_R1	20	12-Aug-20	09-Sep-20		ove - Wayfinding Signage_R1			
		20	-	09-3ep-20 08-Oct-20		g Signage Mock-up			1
BLHA-0760	Wayfinding Signage Mock-up		10-Sep-20			- 1 1 -	atinding Cianana		1
BLHA-0480	Fab & Deliver - Wayfinding Signage	85	09-Oct-20	16-Feb-21		Fab & Deliver - W	ayinnung signage		
onstruction					.	·			
MBTA -1190	Perform Phase 1 Work - Close Limits of Existing Platform/Temp Platform/Crossings/Reloca	5	25-Sep-19 A	12-Jun-20	Perform Phase 1 Work - Clos	e Limits of Existing Platform/Te	mp Platform/Crossings/Reloca	ite Fare Ticketing/Etc.	1
Phase 1 - Close	Limits of Existing Platform/Temp Platform/Crossings/Relocation of Furnishings								1
General									
						•	1		
Remaining L	Level of Effort Remaining Work		Page 2 of 27		TASK filter: Uncompleted Activitie	s Two Months Prior.			
•	l of Effort Critical Remaining Work		<u> </u>				Corporation	SKANSK	^
ACIDALLEVE						0 0 1000			
Actual Level									

vity ID	ol - Project A - 06Jun20 R1 Schedule Update - 1318014-CR - B27 Activity Name	Remaining	Start	Detailed Finish	
		Duration	Start	1 111511	2020 2021 2022
					Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct N
BLHS-1010	Phase 1 - Refeed Existing Platform Systems	29	05-Feb-20 A	17-Jul-20	Phase 1 - Refeed Existing Platform Systems
BLHS-0065	Install Hi-rail Temporary Gate and Fencing	5	08-Jun-20*	12-Jun-20	Install Hi-rail Temporary Gate and Fencing
BLHS-0120	Phase 1 - Install Buried Ductbanks below New Building	10	22-Jun-20	06-Jul-20	Phase 1 - Install Buried Ductbanks below New Building
BLHS-3240	Phase 1 - Pull Wire at Buried Ductbanks below New Building	5	07-Jul-20	13-Jul-20	Phase 1 - Pull Wire at Buried Ductbanks below New Building
BLHS-0050	Phase 1 - Cut-Over Bungalows (Weekend)	2	18-Jul-20	19-Jul-20	Phase 1 - Cut-Over Bungalows (Weekend)
BLHS-1020	Phase 1 - Demo Asphalt Platforms & Furnishings	5	20-Jul-20	24-Jul-20	Phase 1 - Demo Asphalt Platforms & Furnishings
Phase 3 - Build	New Platform East and Temporary Extension				
Construction					
BLHS-1030	Phase 3 - De-Energize/Remove Existing MBTA Systems	10	06-Jun-20	15-Jun-20	Phase 3 - De-Energize/Remove Existing MBTA Systems
BLHS-1040	Phase 3 - Excavate and Rough Grade for Piles	7	08-Jun-20	14-Jun-20	Phase 3 - Excavate and Rough Grade for Piles
BLHS-1060	Phase 3 - Demo Platform Asphalt	7	08-Jun-20	14-Jun-20	Phase 3 - Demo Platform Asphalt
BLHS-1045	Phase 3 - Install Helical Piles	9	20-Jun-20	28-Jun-20	Phase 3 - Install Helical Piles
BLHS-0075	Completion BHS Over-Build	0		21-Jun-20	Completion BHS Over-Build
BLHS-1070	Phase 3 - Install CIP Knee Walls	10	29-Jun-20	13-Jul-20	Phase 3 - Install CIP Knee Walls
BLHS-1115	Phase 3 - Install Rubber Rail Tiles	5	14-Jul-20	20-Jul-20	Phase 3 - Install Rubber Rail Tiles
BLHS-1080	Phase 3 - Backfill and Compact Platform Slab Base	10	21-Jul-20	03-Aug-20	Phase 3 - Backfill and Compact Platform Slab Base
BLHS-1090	Phase 3 - Form/Reinforce CIP Platform Slabs w/Haunch	25	04-Aug-20	08-Sep-20	Phase 3 - Form/Reinforce CIP Platform Slabs w/Haunch
BLHS-1091	Phase 3 - Place CIP Platform Slabs w/Haunch (Primary) - Weekend	20	12-Sep-20	13-Sep-20	Phase 3 - Place CIP Platform Slabs w/Haunch (Primary) - Weekend
BLHS-1092	Phase 3 - Place CIP Platform Slabs w/Haunch (Secondary) - Weekend	2	19-Sep-20	20-Sep-20	Phase 3 - Place CIP Platform Slabs w/Haunch (Secondary) - Weekend
BLHS-1130	Phase 3 - Pave Temporary Ramps at West Pedestrian Crossing	2	21-Sep-20	22-Sep-20	Phase 3 - Pave Temporary Ramps at West Pedestrian Crossing
BLHS-1100	Phase 3 - Install CIP Egress Ramp on Inbound Platform	10	21-Sep-20 21-Sep-20	02-Oct-20	Phase 3 - Install CIP Egress Ramp on Inbound Platform
BLHS-1095	Phase 3 - F/R/P Light Pole and Sign Pedestals	15	21-Sep-20 21-Sep-20	02-Oct-20	Phase 3 - F/R/P Light Pole and Sign Pedestals
			-		
BLHS-1120	Phase 3 - Install Tactile Warning Panels	15	21-Sep-20	09-Oct-20	Phase 3 - Inistall Tactile Warning Panels
BLHS-1050	Phase 3 - Pave Platform Extension - Weekends	2	26-Sep-20	27-Sep-20	I Phase 3 - Pave Platform Extension - Weekends
BLHS-1105	Phase 3 - Establish Egress Path Through 111 Cypress Site (By Others)	5	05-Oct-20	09-Oct-20	Phase 3 - Establish Egress Path Through 111 Cypress Site (By Others)
BLHS-1200	Phase 3 - Install Phase 4 Temporary Signage	10	13-Oct-20	26-Oct-20	Phase 3 Install Phase 4 Temporary Signage
BLHS-1140	Phase 3 - Install Platform Furnishings	40	13-Oct-20	10-Dec-20	Phase 3 - Install Platform Furnishings
BLHS-1190	Phase 3 - Establish Pedestrian Access for Phase 3 Platform	5	04-Dec-20	10-Dec-20	Phase 3 - Establish Pedestrian Access for Phase 3 Platform
BLHS-1180	Phase 3 - Install Railing - South Egress Ramp	5	16-Dec-20	22-Dec-20	Phase 3 - Install Railing - South Egress Ramp
BLHS-1110	Phase 3 - Install Phase 3 Light Poles - Weekends	2	19-Dec-20	20-Dec-20	Phase 3 - Install Phase 3 Light Poles - Weekends
BLHS-1170	Phase 3 - Install VMS, PA, Security System	40	30-Dec-20	26-Feb-21	Phase 3 - Install VMS, PA, Security System
BLHS-1205	Phase 3 - Testing, Commissioning and Inspections of Station Systems	10	01-Mar-21	12-Mar-21	Phase 3 - Testing, Commissioning and Inspections of Station Systems
BLHS-1210	Phase 3 - Platform Put in Service	1	15-Mar-21	15-Mar-21	I Phase 3 - Platform Put in Service
Phase 4 - Demo	D Existing West Platform & Build New Platform West				
Demolition					
BLHS-2000	Phase 4 - De-Energize/Remove Existing MBTA Systems	10	15-Mar-21	26-Mar-21	Phase 4 - De-Energize/Remove Existing MBTA Systems
BLHS-2010	Phase 4 - Demo Platform Furnishings	3	29-Mar-21	31-Mar-21	Phase 4 - Demo Platform Furnishings
Construction					
Station					
BLHS-2015	Phase 4 - Excavate and Rough Grade for Piles	5	01-Apr-21	07-Apr-21	Phase 4 - Excavate and Rough Grade for Piles
BLHS-2020	Phase 4 - Install Helical Piles	20	08-Apr-21	06-May-21	Phase 4 - Install Helical Piles
BLHS-2090	Phase 4 - Install Rubber Rail Tiles	5	07-May-21	13-May-21	Phase 4 - Install Rubber Rail Tiles
BLHS-2050	Phase 4 - Backfill and Compact Platform Slab Base	15	14-May-21	04-Jun-21	Phase 4 - Backfill and Compact Platform Slab Base
BLHS-2060	Phase 4 - Form/Reinforce CIP Platform Slabs w/Haunch	25	07-Jun-21	12-Jul-21	Phase 4 - Form/Reinforce CIP Platform Slabs w/Haunch
BLHS-2080	Phase 4 - Form/Reinforce CIP Ramps	10	13-Jul-21	26-Jul-21	Phase 4 - Form/Reinforce CIP Ramps
BLHS-2062	Phase 4 - Place CIP Platform Slabs w/Haunch (Primary) - Weekend	2	17-Jul-21	18-Jul-21	Phase 4 - Place CIP Platform Slabs w/Haunch (Primary) - Weekend
BLHS-2064	Phase 4 - Place CIP Platform Slabs w/Haunch (Secondary) - Weekend	2	24-Jul-21	25-Jul-21	Phase 4 + Place CIP Platform Slabs w/Haunch (Secondary) - Weekend
BLHS-2066	Phase 4 - F/R/P Light Pole and Sign Pedestals	5	24-Jul-21	30-Jul-21	Phase 4- F/R/P Light Pole and Sign Pedestals
BLHS-2110	Phase 4 - Install Tactile Warning Panels	15	26-Jul-21	13-Aug-21	 Phase 4 - Introl Light Fole and Sight Folestals Phase 4 - Install Tactile Warning Panels
BLHS-2110 BLHS-2082		2		-	Phase 4 - Place CIP Ramps - Weekend
	Phase 4 - Place CIP Ramps - Weekend		27-Jul-21	28-Jul-21	
BLHS-2085	Phase 4 - Install Permanent Grade Crossing - Weekend	2	29-Jul-21	30-Jul-21	Phase 4 - Install Permahent Grade Crossing - Weekend
BLHS-2070	Phase 4 - Install Stone Landscaping Beyond Platform	5	29-Jul-21	04-Aug-21	Phase 4 - Install Stone Landscaping Beyond Platform
BLHS-2120	Phase 4 - Canopies - Weekend	6	31-Jul-21	15-Aug-21	Phase 4 - Canopies - Weekend

Actual Work

Critical Remaining Work Milestone

TASK filter: Uncompleted Activities Two Months Prior. © Oracle Corporation

Page 333 of 377

×	pol - Project A - 06Jun20 R1 Schedule Update - 1318014-CR - B27				d Schedule			6-Jun-20 / Run Date: 09-Jul-20 09:07
vity ID	Activity Name	Remaining Duration	Start	Finish	2020 202	21		2022
		Duration			Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun		Dec Jan Feb Ma	
BLHS-2100	Phase 4 - Install Phase 4 Light Poles	2	02-Aug-21	03-Aug-21		Phase 4 - Install Ph		
BLHS-2180		10	02-Aug-21	13-Aug-21		Phase 4 - Install F		
BLHS-2160	Phase 4 - Install VMS, PA, AFC, Security System	35	02-Aug-21	20-Sep-21				C, Security System
BLHS-2125	Phase 4 - Canopy Roofs - Weekends	4	21-Aug-21	29-Aug-21		Phase 4 - Can		
BLHS-2230	Phase 4 - Install VMS, PA, AF C, Security System on Canopy	3	30-Aug-21	01-Sep-21				Security System on Canopy
BLHS-2130	Phase 4 - Install Platform Furnishings	10	30-Aug-21	13-Sep-21			stall Platform Furr	
		10	-	04-Oct-21				sioning and Inspections of Station System
BLHS-2245		10	21-Sep-21				-	
BLHS-2250		1	05-Oct-21	05-Oct-21		Phase 4	- Platform Put Into	Service
	o Temp. Extension, Connect East & West Platforms				.	 		
Demolition		I . I						
BLHS-3000	Phase 5 - Setup Stage 5	1	06-Oct-21	06-Oct-21		1	- Setup Stage 5	
BLHS-3010	Phase 5 - Demo Temp Asphalt / Ramps / Crossings - Weekends	6	09-Oct-21	24-Oct-21		Phase	e 5 - Demo Temp	Asphalt / Ramps / Crossings - Weekends
Construction								
Station								
BLHS-3020	Phase 5 - Excavate & Expose Piles	5	12-Oct-21	18-Oct-21		Phase	5 - Excavate & E	kpose Piles
BLHS-3085	Phase 5 - Install Rubber Rail Tiles	5	19-Oct-21	25-Oct-21		Phas	e 5 ⁺ Install Rubbe	r Rail Tiles
BLHS-3030	Phase 5 - Install CIP Knee Walls	10	19-Oct-21	01-Nov-21			se 5 - Install CIP ł	
BLHS-3090		2	23-Oct-21	24-Oct-21				Landscaping Beyond Platform - Weekend
BLHS-3040	Phase 5 - Backfill and Compact Platform Slab Base - Weekends	2	02-Nov-21	03-Nov-21				Compact Platform Slab Base - Weekend
BLHS-3050	Phase 5 - Form and Reinforce CIP Platform Slabs w/Haunch - Weekends (OD: 10 to 4)	4	06-Nov-21	14-Nov-21				Reinforce CIP Platform Slabs w/Haunch
BLHS-3060	Phase 5 - Place CIP Platform - Weekends	2	20-Nov-21	21-Nov-21				P Platform - Weekends
		5		30-Nov-21			1	Tactile Warning Panels
BLHS-3080	Phase 5 - Install Tactile Warning Panels	-	22-Nov-21					
BLHS-2170		12	22-Nov-21	09-Dec-21		1		I Railing - Outbound Knee Wall
BLHS-3160		1	10-Dec-21	10-Dec-21	·····	i 	Phase 5 - Entir	e Station Open
	struct West Parking Lot Following Demob							
Parking Lot								
BLHS-2190	Phase 6 - Demo Existing Parking Lot	10	13-Dec-21*	27-Dec-21				emo Existing Parking Lot
BLHS-2200	Phase 6 - Relocate BHS Dumpster & Electrical	10	28-Dec-21	11-Jan-22			📕 Phase 6 -	Relocate BHS Dumpster & Electrical
BLHS-2220	Phase 6 - Adjust DMH & Replace Granite Curb	10	28-Dec-21	11-Jan-22			Phase 6 -	Adjust DMH & Replace Granite Curb
BLHS-2240	Phase 6 - Grade / Pave / Paint Parking Lot	20	12-Jan-22	09-Feb-22		·	Phas	e 6 - Grade / Pave / Paint Parking Lot
Punchlist / Tes	sting & Balancing / Commissioning						l I	
INSP-1040	MBTA Interim Completion Date	0		10-Dec-21*			MBTA Interim C	ompletion Date
INSP-1050	MBTA Interim Final Completion Date	0		09-Feb-22*				A Interim Final Completion Date
Procuremen								
					······		 	
Design Assist								
Curtain Wall De	lesign Assist						l	
PRO-7390	Prepare & Submit Shop Drawings - Curtain Wal (FB-016.1)	5	02-Mar-20 A	12-Jun-20	Prepare & Submit Shop Drawings - Curtain Wall (FB-016.1)			
PRO-7400	Review & Approve Shop Drawings - Curtain Wall(FB-016.1)	10	02-Mar-20 A	26-Jun-20	Review & Approve Shop Drawings - Curtain Wall(FB-016.1)		l I	
PRO-1440	Review & Approve Shop Drawings - Curtain Wall (Round 2)	10	11-Mar-20 A					
PRO-1460	Fab & Available for Delivery - Curtain Wall	30	02-Apr-20 A			 I I	<u>-</u>	· · · · · · · · · · · · · · · · · · ·
Early Bid Pack				· ····g 0				
-						1		
Elevators	Eab 9 Available for Delivery Elevators	47	04 4 00 4	10 4				
PRO-1910	Fab & Available for Delivery - Elevators	47	21-Apr-20 A	12-Aug-20	Fab & Available for Delivery - Elevators			
Structural Stee						· · · · · · · · · · · · · · · · · · ·		
PRO-1680	Fab & Available for Delivery - Structural Steel	0			Fab & Available for Delivery - Structural Steel			
PRO-1270	MBTA Reviews - Structural Steel/Precast Steel CW P	0	24-Jan-20 A	03-Jun-20 A	MBTA Reviews - Structural Steel Precast Steel CW P			
Remaining Pro	ocurement Post CDs (Trade Contractors)							
Plumbing (Tra	de Contractor)							
PRO-4720	Subcontractor Issue Submittals - Plumbing Fixtures	0	19-Dec-19 A	04-Mav-20 A	bcontractor Issue Submittals - Plumbing Fixtures			
PRO-4710	A/E Review & Approve Submittals - Plumbing Fixtures	15	05-Mar-20 A		A/E Review & Approve Submittals - Plumbing Fixtures			
PRO-4750	Fab/Deliver Equipment - Plumbing Domestic Water Heater	50	08-Jun-20	17-Aug-20	Fab/Deliver Equipment - Plumbing Domestic Water H	Heater		
PRO-4750	Fab/Deliver Equipment - Plumbing Domestic Water Heater	30	29-Jun-20	10-Aug-20	Fab/Deliver Equipment - Plumbing Fixtures			
		30	29-Juii-20	10-Aug-20				
Fire Protection	n (Trade Contractor)					1	1	
Remaining	g Level of Effort Remaining Work		Page 4 of 27	,	TASK filter: Uncompleted Activities Two Months Prior.			
Actual Lev	vel of Effort Critical Remaining Work		-		© Oracle Co	rporation	CV	
Actual Wo							DK	ANSKA
		1						

PRO-4680 / VAC (Trade Con PRO-5040 \$ PRO-4790 \$ PRO-4840 \$ PRO-4940 \$	Activity Name A/E Review & Approve Submittals - Fire Protection Piping	Remaining Duration	Start	Finish	2020	2021	2022
VAC (Trade Con PRO-5040 \$ PRO-4790 \$ PRO-4840 \$ PRO-4940 \$		Duration					
VAC (Trade Con PRO-5040 \$ PRO-4790 \$ PRO-4840 \$ PRO-4940 \$					Liun Jul Aug Sen Oct Nov Dec	Llan Feb Mar Apr May Jun Jul Aug Sep Oct Nov [Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct
VAC (Trade Con PRO-5040 \$ PRO-4790 \$ PRO-4840 \$ PRO-4940 \$		0	06-Apr-20 A	08-Apr-20 A	view & Approve Submittals - Fire Pi		
PRO-5040 \$ PRO-4790 \$ PRO-4840 \$ PRO-4940 \$				007 pr 2071			
PRO-4790 \$ PRO-4840 \$ PRO-4940 \$	Subcontractor Issue Submittals - HVAC AHUs	0	19-Dec-19 A	28-Apr-20 A	pcontractor Issue Submittals - HVAC	AHUS	
PRO-4840 SPRO-4940 S	Subcontractor Issue Submittals - HVAC Ductwork	5	19-Dec-19 A	•	Subcontractor Issue Submittals		
PRO-4940 S	Subcontractor Issue Submittals - HVAC Exhaust Fans	5	19-Dec-19 A		Subcontractor Issue Submittals		
		5					
	Subcontractor Issue Submittals - HVAC VAVs	5	19-Dec-19 A		Subcontractor Issue Submittals	·	
	A/E Review & Approve Submittals - HVAC Ductwork	15	18-Mar-20 A		A/E Review & Approve Sub		
	Fab/Deliver Equipment - HVAC AHUs	30	19-Mar-20 A	20-Jul-20	Fab/Deliver Equipment -		
	Fab/Deliver Equipment - HVAC Air Cooled Chiller	35	19-Mar-20 A	27-Jul-20	Fab/Deliver Equipment		
	A/E Review & Approve Submittals - HVAC Exhaust Fans	8	01-Apr-20 A		A/E Review & Approve Subm		
	A/E Review & Approve Submittals - HVAC VAVs	14	03-Apr-20 A	02-Jul-20	A/E Review & Approve Subi		
	A/E Review & Approve Submittals - HVAC FCUs	0	06-Apr-20 A		view & Approve Submittals - HVAC		
	Fab/Deliver Equipment - HVAC FCUs	40	08-Jun-20	03-Aug-20	Fab/Deliver Equipmen		
PRO-2210 F	Fab/Deliver Equipment - HVAC Boilers	50	08-Jun-20	17-Aug-20	Fab/Deliver Equipm		
PRO-4870 F	Fab/Deliver Equipment - HVAC Pumps	50	08-Jun-20	17-Aug-20	Fab/Deliver Equipm		
PRO-4820 F	Fab/Deliver Equipment - HVAC Exhaust Fans	30	25-Jun-20	06-Aug-20	Fab/Deliver Equipmer	t - HVAC Exhaust Fans	
PRO-4920 F	Fab/Deliver Equipment - HVAC VAVs	50	06-Jul-20	14-Sep-20	Fab/Deliver Eq	uipment - HVAC VAVs	
ectrical & Comr	munications (Trade Contractor)						
PRO-2280 \$	Subcontractor Issue Submittals - Electrical Interior Lighting	0	22-Nov-19 A	27-Apr-20 A	pcontractor Issue Submittals - Elect	rical Interior Lighting	
PRO-2300	A/E Review & Approve Submittals - Electrical Interior Lighting	0	13-Apr-20 A	20-May-20 A	A/E Review & Approve Submittals -	Electrical Interior Lighting	
PRO-7470 F	Resubit R1- Electrical Interior Lighting	5	21-May-20 A	12-Jun-20	Resubit R1- Electrical Interior L	ighting	
PRO-2340 F	Fab/Deliver Equipment - Electrical Switchgear	75	08-Jun-20	22-Sep-20	Fab/Deliver E	quipment - Electrical Switchgear	
	A/E Review & Approve Reubmittals R1 - Electrical Interior Lighting	15	15-Jun-20	06-Jul-20		ibmittals R1 - Electrical Interior Lighting	
	Fab/Deliver Equipment - Interior Lighting	65	07-Jul-20	06-Oct-20		Equipment - Interior Lighting	
asonry (Trade C							
	Subcontractor Issue Initial Shop Drawings - Masonry	15	19-Dec-19 A	26-Jun-20	Subcontractor Issue Initial SI	non Drawings - Masonry	
	A/E Review & Approve Submittals - Masonry (Brick/Stone Samples)	0			Review & Approve Submittals - Ma	· · · · · · · · · · · · · · · · · · ·	
	Subcontractor Issue Submittals - Masonry (Brick Samples) per FB-078R1	0	06-Apr-20 A		contractor Issue Submittals - Masor		
	A/E Review & Approve Submittals - Masonry (Brick Samples) per FB-078R1	0					
	Fab & Available for Delivery - Masonry (Brick/Stone)	80	08-Jun-20	29-Sep-20		ble for Delivery - Masonry (Brick/Stone)	
	A/E Review & Approve Initial Shop Drawings - Masonry	15	29-Jun-20	20-Jul-20	A/E Review & Approve Ir		
	etals & Ornamental Iron (Trade Contractor)	15	29-501-20	20-30-20			
	Subcontractor Issue Submittals - Misc. Metals Stair 1	2	10 Ech 20 A	10 Jun 20	Subcontractor Issue Submittals	Miss Motols Stair 1	
	Subcontractor Issue Submittals - Misc. Metals Stair 1	10	13-Feb-20 A		Subcontractor Issue Submitta		
		10					
	Subcontractor Issue Submittals - Misc. Metals Stair 3	10	17-Feb-20 A		Subcontractor Issue Submitta		
	Subcontractor Issue Submittals - Misc. Metals Stair 6	0	20-Feb-20 A	•	bcontractor Issue Submittals - Misc		
	Subcontractor Issue Submittals - Misc. Metals Stair 5	0	20-Feb-20 A		Bubcontractor Issue Submittals - Mi		
	Subcontractor Issue Submittals - Misc. Metals Stair 7	10	25-Feb-20 A		Subcontractor Issue Submitta		
	A/E Review & Approve Submittals - Misc. Metals Lintels	0	16-Mar-20 A	-	VE Review & Approve Submittals - M		
	A/E Review & Approve Submittals - Misc. Metals Stair 1	10	19-Mar-20 A		A/E Review & Approve Subm		
	A/E Review & Approve Submittals - Misc. Metals Stair 2	10	15-Apr-20 A	06-Jul-20	A/E Review & Approve Sub		
	A/E Review & Approve Submittals - Misc. Metals Stair 7	10	17-Apr-20 A	06-Jul-20	A/E Review & Approve Sub		
	A/E Review & Approve Submittals - Misc. Metals Stair 3	10	28-Apr-20 A	06-Jul-20	A/E Review & Approve Sub		
	A/E Review & Approve Submittals - Misc. Metals Stair 6	10	30-Apr-20 A				
	A/E Review & Approve Submittals - Misc. Metals Stair 5	5	14-May-20 A	12-Jun-20	A/E Review & Approve Submitt		
PRO-2470 F	Fab & Available for Delivery - Misc. Metals Lintels	10	08-Jun-20	19-Jun-20	Fab & Available for Delivery - I	Misc. Metals Lintels	
PRO-5615 F	Fab & Available for Delivery - Misc. Metals Stair 5	25	15-Jun-20	20-Jul-20	Fab & Available for Delive	ery - Misc. Metals Stair 5	
PRO-5620 F	Fab & Available for Delivery - Misc. Metals Stair 6	25	22-Jun-20	27-Jul-20	Fab & Available for Deliv	very - Misc. Metals Stair 6	
PRO-2480 F	Fab & Available for Delivery - Misc. Metals Stair 1	25	25-Jun-20	30-Jul-20	Fab & Available for Del	ivery - Misc. Metals Stair 1	
PRO-2500 F	Fab & Available for Delivery - Misc. Metals Stair 2	25	07-Jul-20	10-Aug-20	Fab & Available for D	elivery - Misc. Metals Stair 2	
	Fab & Available for Delivery - Misc. Metals Stair 7	25	07-Jul-20	10-Aug-20		elivery - Misc. Metals Stair 7	
	Fab & Available for Delivery - Misc. Metals Stair 3	30	07-Jul-20	17-Aug-20		Delivery - Misc. Metals Stair 3	
	Caulking (Trade Contractor)	,					
						·	· · · · · · · · · · · · · · · · · · ·
Remaining Le	evel of Effort Remaining Work					Two Months Drier	
•	-		Page 5 of 27		TASK filter: Uncompleted Activities		
 Actual Level c 						© Oracle Corporation	SKANSKA
Actual Work	 Milestone 						

	roject A - 06Jun20 R1 Schedule Update - 1318014-CR - B27				Schedule		Data Date: 06-Jun-20 / Run Date: 09-Jul-20 09:07
ty ID Act	tivity Name	Remaining Duration	Start	Finish	2020	2021	2022
		Duration				c Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec	
PRO-2540 Sub	bcontractor Issue Submittals - Building AVB & Caulking	10	18-Mar-20 A	19-Jun-20	Subcontractor Issue Submit		
PRO-2550 A/E	E Review & Approve Submittals - Building AVB & Caulking	15	19-Mar-20 A	13-Jul-20	📕 📩 A/E Review & Approve \$	ubmittals - Building AVB & Caulking	
	b & Available for Delivery - Building AVB & Caulking	20	26-Mar-20 A		Fab & Available for Del		
Roofing & Flashing							
	bcontractor Issue Submittals - Membrane Roofing	0	06-Apr-20 A	13-Apr-20 A	potractor Issue Submittals - Memb	rahe Roofing	
	bcontractor Issue Submittals - Roofing Metal Flashing & Trim	0	06-Apr-20 A	•	contractor Issue Submittals - Roo		
	E Review & Approve Submittals - Membrane Roofing	5	13-Apr-20 A	•	A/E Review & Approve Subm		
	E Review & Approve Submittals - Roofing Metal Flashing & Trim	5	24-Apr-20 A			ttals - Roofing Metal Flashing & Trim	
	b & Available for Delivery - Membrane Roofing	20	15-Jun-20	13-Jul-20	Fab & Available for Deliv	· · · · · · · · · · · · · · · · · · ·	
	b & Available for Delivery - Roofing Metal Flashing & Trim	25	15-Jun-20	20-Jul-20		/ery - Roofing Metal Flashing & Trim	
		23	13-301-20	20-30-20			
	zing (Trade Contractor)	0	04 4	04 May 00 A			
	bcontractor Issue Submittals - Interior Glass	0		•	bcontractor Issue Submittals - Int		
	E Review & Approve Submittals - Interior Glass	5	04-May-20 A		A/E Review & Approve Subm		······
	bcontractor Issue Submittals - Interior Glass Mirrors	19	05-May-20 A	02-Jul-20			i i i
	b & Available for Delivery - Interior Glass	40	15-Jun-20	10-Aug-20		Delivery - Interior Glass	
	E Review & Approve Submittals - Interior Glass Mirrors	15	06-Jul-20	24-Jul-20		Submittals - Interior Glass Mirrors	
	b & Available for Delivery - Interior Glass Mirrors	25	27-Jul-20	28-Aug-20	Fab & Available	or Delivery - Interior Glass Mirrors	
Tile (Trade Contract	•				.	<u> </u>	i
PRO-2750 Sub	bcontractor Issue Submittals - Ceramic Tile	20	22-Jan-20 A	06-Jul-20	Subcontractor Issue Sub	nittals - Ceramic Tile	
PRO-2760 A/E	E Review & Approve Submittals - Ceramic Tile	15	07-Jul-20	27-Jul-20	A/E Review & Approv	Submittals - Ceramic Tile	i i i
PRO-2770 Fat	b & Available for Delivery - Ceramic Tile	50	28-Jul-20	06-Oct-20	Fab & Ava	ilable for Delivery - Ceramic Tile	
Terrazzo (Trade Con	ntractor)						i i i
	bcontractor Issue Submittals - Terrazzo	20	24-Feb-20 A	06-Jul-20	Subcontractor Issue Sub	nittals - Terrazzo	
PRO-5300 A/E	E Review & Approve Submittals - Terrazzo	15	25-Feb-20 A	27-Jul-20	A/E Review & Approv	Submittals - Terrazzo	
	b & Available for Delivery - Terrazzo	30	28-Jul-20	08-Sep-20	Fab & Availabl		
	File (Trade Contractor)	,					
	bcontractor Issue Submittals - ACT	0	02-Mar-20 A	29-May-20 A	Subcontractor Issue Submittals	- ACT	
	bcontractor Issue Submittals - Acoustical Metal Panels	20	02-Mar-20 A	06-Jul-20		nittals - Acoustical Metal Panels	
	E Review & Approve Submittals - ACT	10	03-Mar-20 A		A/E Review & Approve Subr	q	
	E Review & Approve Submittals - Acoustical Metal Panels	15	03-Mar-20 A	27-Jul-20		Submittals - Acoustical Metal Panels	
	••						
	b & Available for Delivery - ACT	15	22-Jun-20	13-Jul-20	Fab & Available for Deliv		
	b & Available for Delivery - Acoustical Metal Panels	50	28-Jul-20	06-Oct-20	Fab & Ava	ilable for Delivery - Acoustica I Métal Panels	
Resilient Flooring (T							
	bcontractor Issue Submittals - Resilient Flooring	0	,	y	Subcontractor Issue Submittals		
	E Review & Approve Submittals - Resilient Flooring	8	26-May-20 A		A/E Review & Approve Subn	-	
	b & Available for Delivery - Resilient Flooring	30	18-Jun-20	30-Jul-20	Fab & Available for D	eliγery - Resilient Flooring	
Painting (Trade Con	•						
PRO-2930 Sub	bcontractor Issue Submittals - Painting	15	30-Mar-20 A	26-Jun-20	Subcontractor Issue Subm	ttals - Painting	
PRO-2940 A/E	E Review & Approve Submittals - Painting	15	29-Jun-20	20-Jul-20	A/E Review & Approve	Submittals - Painting	
PRO-2950 Fab	b & Available for Delivery - Painting	10	21-Jul-20	03-Aug-20	Fab & Available for E	elivery - Painting	
Remaining Procure	ement Post CDs (Subcontractors)						
Carpentry & Drywall							
	E Review & Approve Submittals - Carpentry & Drywall Exterior Cold Formed Metal Framir	0	30-Mar-20 A	21-Apr-20 A	Review & Approve Submittals - Ca	rpentry & Drywall Exterior Cold Formed Metal Framing	
	b & Available for Delivery - Carpentry & Drywall Exterior Cold Formed Metal Framing	5	22-Apr-20 A	•		Carpentry & Drywall Exterior Cold Formed Metal Framing	
	bcontractor Issue Submittals - White Box Vibration/Sound Isolation	20	08-Jun-20	06-Jul-20		nittals - White Box Vibration/Sound Isolation	
	bcontractor Issue Submittals - While Box Vibration/Sound Isolation bcontractor Issue Submittals - Carpentry & Drywall Non-Structural Metal Framing	20	08-Jun-20	13-Jul-20		mitals - Carpentry & Drywall Noh-Structural Metal Framing	
	E Review & Approve Submittals - White Box Vibration/Sound Isolation	15	07-Jul-20	27-Jul-20		: Submittals - White Box Vibration/Sound Isolation	
	E Review & Approve Submittals - Carpentry & Drywall Non-Structural Metal Framing	15	14-Jul-20	03-Aug-20		e Submittals - Carpentry & Drywall Non-Structural Metal Frami	"IY
	b & Available for Delivery - White Box Vibration/Sound Isolation	40	28-Jul-20	22-Sep-20		ble for Delivery - White Box Vibration/Sound Isolation	
	b & Available for Delivery - Carpentry & Drywall Non-Structural Metal Framing	10	04-Aug-20	17-Aug-20	Fab & Available fo	Delivery - Carpentry & Drywall Non-Structural Metal Framing	
Spray Fireproofing							
PRO-3120 Ow	vner Review/Approve RTA - Spray Fireproofing	0		•	wner Review/Approve RTA - Spra		
PRO-6700 Tow	wn Building Commission Approves Contract - Spray Fireproofing	0	12-May-20 A	12-May-20 A	own Building Commission Approv	es Contract - Spray Fireproofing	
Remaining Level	l of Effort Remaining Work		Page 6 of 27		TASK filter: Uncompleted Activiti	es Two Months Prior.	
Actual Level of E	Effort Critical Remaining Work					© Oracle Corporation	SKANSKA
Actual Work	♦ Milestone						ANCHANC

<u> </u>	nool - Project A - 06Jun20 R1 Schedule Update - 1318014-CR - B27			Detailed				Data Date: 06-Jun-20 /	Run Date: 09-Jul-20 09:07
ty ID	Activity Name	Remaining	Start	Finish	2020	2021			2022
		Duration				Jan Feb Mar Apr May Jun Jul Aug	Sep Oct Nov Dec .	Jan Feb Mar Apr May	
PRO-3130	Award Contract - Spray Fireproofing	0	13-May-20 A	13-May-20 A	Award Contract - Spray Fireproofing			[·[· · [· ·+· [···-]	
PRO-3140	Execute Contract - Spray Fireproofing	3	14-May-20 A		Execute Contract - Spray Fireproo	ofina			
PRO-3150	Subcontractor Issue Submittals - Spray Fireproofing	2	19-May-20 A		Subcontractor Issue Submittals	-			
PRO-3160	A/E Review & Approve Submittals - Spray Fireproofing	10	10-Jun-20	23-Jun-20	A/E Review & Approve Submitta			1	
PRO-3170	Fab & Available for Delivery - Spray Fireproofing	3	24-Jun-20	26-Jun-20	Fab & Available for Delivery - S				
	es And Hard ware	5	24-0011-20	20-0011-20	T ab a Available for Delivery - O				
PRO-3190	Owner Review/Approve RTA - Doors, Frames & Hardware	0	24-Eeb-20 A	07-May-20 A	wner Review/Approve RTA - Doors, F	rames & Hardware		1	
PRO-6710	Town Building Commission Approves Contract - Doors, Frames & Hardware	0		•	fown Building Commission Approves C			1	
PRO-3200	Award Contract - Doors, Frames & Hardware	0	,	,	Award Contract - Doors, Frames & Ha				
PRO-3200	Subcontractor Issue Submittals - Interior Wood Doors	20	13-May-20 A	06-Jul-20	Subcontractor Issue Submitta				
PRO-3220	Subcontractor Issue Submittals - Door Hardware	20	14-May-20 A	06-Jul-20	Subcontractor Issue Submitta				
			-						
PRO-3240	Subcontractor Issue Submittals - HM Door Frames	20	14-May-20 A	06-Jul-20	Subcontractor Issue Submitta				
PRO-3250	Subcontractor Issue Submittals - HM Doors	20	14-May-20 A	06-Jul-20	Subcontractor Issue Submitta	1 1			
PRO-3210	Execute Contract - Doors, Frames & Hardware	5	14-May-20 A	12-Jun-20	Execute Contract - Doors, Frame	· · · · ·			
PRO-3260	A/E Review & Approve Submittals - Interior Wood Doors	15	07-Jul-20	27-Jul-20	A/E Review & Approve Su				·
PRO-3270	A/E Review & Approve Submittals - Door Hardware	15	07-Jul-20	27-Jul-20	A/E Review & Approve Su				
PRO-3280	A/E Review & Approve Submittals - HM Door Frames	15	07-Jul-20	27-Jul-20	A/E Review & Approve Su	1 I I			
PRO-3290	A/E Review & Approve Submittals - HM Doors	15	07-Jul-20	27-Jul-20	A/E Review & Approve Su	1 1			
PRO-3300	Fab & Available for Delivery - HM Door Frames	25	28-Jul-20	31-Aug-20		Delivery - HM Door Frames			
PRO-3330	Fab & Available for Delivery - HM Doors	50	28-Jul-20	06-Oct-20	Fab & Availabl	le for Delivery - HM Doors			
PRO-3310	Fab & Available for Delivery - Interior Wood Doors	65	28-Jul-20	28-Oct-20		ailable for Delivery - Interior Wood Doors	3		
PRO-3320	Fab & Available for Delivery - Door Hardware	65	28-Jul-20	28-Oct-20	Fab & Ava	ailable for Delivery - Door Hardware			
Millwork & Fi	inish Carpentry								
PRO-3350	Owner Review/Approve RTA - Millwork & Finish Carpentry	0	25-Feb-20 A	07-May-20 A	wner Review/Approve RTA - Millwork	& Finish Carpentry		1	
PRO-3660	Owner Review/Approve RTA for Fab, Furnish & Install - Millwork & Finish Carpentry	20	25-Feb-20 A	06-Jul-20	Owner Review/Approve RTA	for Fab, Furnish & Install - Millwork & F	inish Carpentry		
PRO-6720	Town Building Commission Approves Contract - Millwork & Finish CarpentrySubmittals & Sl	0	12-May-20 A	12-May-20 A	own Building Commission Approves C	Contract - Millwork & Finish CarpentrySu	Ibmittals & Shops Only	/ (Submittals & Shops C	Inly
PRO-3360	Award Contract - Millwork & Finish Carpentry (Submittals & Shops Only)	0	12-May-20 A	13-May-20 A	Award Contract - Millwork & Finish Car	rpentry (Submittals & Shops Only)			
PRO-3370	Execute Contract - Millwork & Finish Carpentry (Submittals & Shops Only)	0	13-May-20 A	13-May-20 A	Execute Contract - Millwork & Finish C	arpentry (Submittals & Shops Only)		1	
PRO-3380	Subcontractor Issue Submittals - Millwork Display Cases	20	14-May-20 A	-	Subcontractor Issue Submitta				
PRO-3390	Subcontractor Issue Submittals - Millwork Wood Benches	20	14-May-20 A	06-Jul-20	Subcontractor Issue Submitta				
PRO-3400	Subcontractor Issue Submittals - Millwork Countertops	20	14-May-20 A	06-Jul-20	Subcontractor Issue Submitta	als - Millwork Countertops			·
PRO-3410	Subcontractor Issue Submittals - Millwork Wood Veneer Casework	20	14-May-20 A	06-Jul-20		als - Millwork Wood Veneer Casework			
PRO-3420	Subcontractor Issue Submittals - Millwork Plastic Laminate Casework	20	14-May-20 A		- I I I	als - Millwork Plastic Laminate Casewor	k	1	
PRO-3430	A/E Review & Approve Submittals - Millwork Display Cases	15	07-Jul-20	27-Jul-20		Ibmittals - Millwork Display Cases			
PRO-3440	A/E Review & Approve Submittals - Millwork Wood Benches	15	07-Jul-20	27-Jul-20		Ibmittals - Millwork Wood Benches			
PRO-3450	A/E Review & Approve Submittals - Millwork Countertops	15	07-Jul-20	27-Jul-20	A/E Review & Approve Su				·
PRO-3460	A/E Review & Approve Submittals - Millwork Wood Veneer Cas ework	15	07-Jul-20	27-Jul-20		ibmittals - Millwork Wood Veneer Casev	vork	1	
PRO-3470	A/E Review & Approve Submittals - Millwork Plastic Laminate Casework	15	07-Jul-20	27-Jul-20		bmittals - Millwork Plastic Laminate Cas	1		
PRO-3480	Fab & Available for Delivery - Millwork Display Cases	35	28-Jul-20	15-Sep-20		or Delivery - Millwork Display Cases	Sework		
PRO-3490						or Delivery - Millwork Wood Benches			
PRO-3490 PRO-3500	Fab & Available for Delivery - Millwork Wood Veneer Casework	35	28-Jul-20	15-Sep-20	+		owork		·
	Fab & Available for Delivery - Millwork Wood Veneer Casework	35	28-Jul-20	15-Sep-20		or Delivery - Millwork Wood Veneer Cas or Delivery - Millwork Plastic Laminate C			
PRO-3510	Fab & Available for Delivery - Millwork Plastic Laminate Casework	35	28-Jul-20	15-Sep-20			asework	- 	
PRO-3520	Fab & Available for Delivery - Millwork Countertops	40	28-Jul-20	22-Sep-20		for Delivery - Millwork Countertops		- - - -	
Lab Casewor		2		07.14					
PRO-7170	Owner Review/Approve RTA - Lab Casework	0			wner Review/Approve RTA - Lab Case				·
PRO-7410	Owner Review/Approve RTA for Fab, Furnish & Install - Lab Casework	20	25-Feb-20 A			for Fab, Furnish & Install - Lab Casewo	ſΚ		
PRO-7220	Town Building Commission Approves Contract - Lab Casework	0			own Building Commission Approves C				
PRO-7150	Execute Contract - Lab Casework (Submittals & Shops Only)	0	-	-	Execute Contract - Lab Casework (Sul				
PRO-7160	Award Contract - Lab Casework (Submittals & Shops Only)	0	13-May-20 A		Award Contract - Lab Casework (Subr				
PRO-7200	Subcontractor Issue Submittals - Lab Casework	20	14-May-20 A	06-Jul-20	Subcontractor Issue Submitta				·
PRO-7190	A/E Review & Approve Submittals - Lab Casework	15	07-Jul-20	27-Jul-20	A/E Review & Approve Su	i i		1 1 1	
PRO-7180	Fab & Available for Delivery - Lab Casework	35	28-Jul-20	15-Sep-20	Fab & Available fo	or Delivery - Lab Casework		- - - -	
Food Service	e Equipment								
Remainin	ng Level of Effort Remaining Work		Page 7 of 27		TASK filter: Uncompleted Activities T	wo Months Prior.			
Actual Le	evel of Effort Critical Remaining Work					© Oracle Corporation		SKAN	CVA
Actual W	/ork ♦ ♦ Milestone					-		NANC	JNA
							1		

)	bol - Project A - 06Jun20 R1 Schedule Update - 1318014-CR - B27 Activity Name	Remaining	Start	Finish	
		Duration	Start	1 111311	2020 2021 2022
					Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oc
RO-3540	Owner Review/Approve RTA - Food Service Equipment	0			wner Review/Approve RTA - Food Service Equipment
RO-7420	Owner Review/Approve RTA for Fab, Furnish & Install - Food Service Equipment	20	25-Feb-20 A		Owner Review/Approve RTA for Fab, Furnish & Install - Food Service Equipment
PRO-6740	Town Building Commission Approves Contract - Food Service Equipment	0		•	own Building Commission Approves Contract - Food Service Equipment
RO-3550	Award Contract - Food Service Equipment	0			Award Contract - Food Service Equipment
PRO-3560	Execute Contract - Food Service Equipment	0	,	,	Execute Contract - Food Service Equipment
RO-3570	Subcontractor Issue Submittals - Food Service Equipment	20	14-May-20 A	06-Jul-20	
RO-3580	Subcontractor Issue Submittals - Wak-In Cooler/Freezer	20	14-May-20 A	06-Jul-20	↓ 4
PRO-3590	Subcontractor Issue Submittals - Hood System (Make Up Air Exhaust)	20	14-May-20 A	06-Jul-20	Subcontractor Issue Submittals - Hood System (Make Up Air Exhaust)
PRO-3600	A/E Review & Approve Submittals - Food Service Equipment	15	07-Jul-20	27-Jul-20	A/E Review & Approve Submittals - Food Service Equipment
RO-3610	A/E Review & Approve Submittals - Walk-In Cooler/Freezer	15	07-Jul-20	27-Jul-20	A/E Review & Approve Submittals - Walk-In Cooler/Freezer
RO-3620	A/E Review & Approve Submittals - Hood System (Make Up Air Exhaust)	15	07-Jul-20	27-Jul-20	A/E Review & Approve Submittals - Hood System (Make Up Air Exhaust)
PRO-3630	Fab & Available for Delivery - Hood System (Make Up Air Exhaust)	65	28-Jul-20	28-Oct-20	Fab & Available for Delivery - Hood System (Make Up Air Exhaust)
RO-3640	Fab & Available for Delivery - Food Service Equipment	65	28-Jul-20	28-Oct-20	Fab & Available for Delivery - Food Service Equipment
RO-3650	Fab & Available for Delivery - Walk-In Cooler/Freezer	65	28-Jul-20	28-Oct-20	Fab & Available for Delivery - Walk-In Cooler/Freezer
	ors & Fire Shutters				
RO-5410	Owner Review/Approve RTA - Overhead Doors & Fire Shutters	20	26-Feb-20 A	06-Jul-20	Owner Review/Approve RTA - Overhead Doors & Fire Shutters
RO-6770	Town Building Commission Approves Contract - Overhead Doors & Fire Shutters	1	14-Jul-20	14-Jul-20	I Town Building Commission Approves Contract - Overhead Doors & Fire Shutters
RO-5400	Award Contract - Overhead Doors & Fire Shutters	2	14-Jul-20	16-Jul-20	Award Contract - Overhead Doors & Fire Shutters
RO-5390	Execute Contract - Overhead Doors & Fire Shutters	5	16-Jul-20	23-Jul-20	Execute Contract - Overhead Doors & Fire Shutters
PRO-3700	Subcontractor Issue Submittals - Loading Dock Equipment	20	23-Jul-20	20-Aug-20	Subcontractor Issue Submittals - Loading Dock Equipment
PRO-5440	Subcontractor Issue Submittals - Overhead Doors	20	23-Jul-20	20-Aug-20	Subcontractor Issue Submittals - Overhead Doors
PRO-7430	Subcontractor Issue Submittals - Interior Sectional Doors	20	23-Jul-20	20-Aug-20	Subcontractor Issue Submittals - Interior Sectional Doors
PRO-3710	A/E Review & Approve Submittals - Loading Dock Equipment	15	20-Aug-20	11-Sep-20	A/E Review & Approve Submittals - Loading Dock Equipment
PRO-5430	A/E Review & Approve Submittals - Overhead Doors	15	20-Aug-20	11-Sep-20	A/E Review & Approve Submittals - Overhead Doors
PRO-7440	A/E Review & Approve Submittals - Interior Sectional Doors	15	20-Aug-20	11-Sep-20	A/E Review & Approve Submittals - Interior Sectional Doors
RO-3720	Fab & Available for Delivery - Loading Dock Equipment	50	11-Sep-20	24-Nov-20	Fab & Available for Delivery - Loading Dock Equipment
PRO-5420	Fab & Available for Delivery - Overhead Doors	65	11-Sep-20	17-Dec-20	Fab & Available for Delivery - Overhead Doors
PRO-7450	Fab & Available for Delivery - Interior Sectional Doors	65	11-Sep-20	17-Dec-20	Fab & Available for Delivery - Interior Sectional Doors
ooxy Floorin	Ig				
RO-3810	Owner Review/Approve RTA - Epoxy Flooring	20	11-Feb-20 A	06-Jul-20	Owner Review/Approve RTA - Epoxy Flooring
RO-6810	Town Building Commission Approves Contract - Epoxy Flooring	1	14-Jul-20	14-Jul-20	I Town Building Commission Approves Contract - Epoxy Flooring
RO-3820	Award Contract - Epoxy Flooring	2	14-Jul-20	16-Jul-20	Award Contract - Epoxy Flooring
PRO-3830	Execute Contract - Epoxy Flooring	5	16-Jul-20	23-Jul-20	Execute Contract - Epoxy Flooring
RO-3840	Subcontractor Issue Submittals - Epoxy Flooring	20	23-Jul-20	20-Aug-20	Subcontractor Issue Submittals - Epoxy Flooring
RO-3850	A/E Review & Approve Submittals - Epoxy Flooring	15	20-Aug-20	11-Sep-20	A/E Review & Approve Submittals - Epoxy Flooring
RO-3860	Fab & Available for Delivery - Epoxy Flooring	25	11-Sep-20	19-Oct-20	Fab & Available for Delivery - Epoxy Flooring
arpet					
RO-3880	Owner Review/Approve RTA - Carpet	25	11-Feb-20 A	13-Jul-20	Owner Review/Approve RTA - Carpet
PRO-6820	Town Building Commission Approves Contract - Carpet	1	14-Jul-20	14-Jul-20	I Town Building Commission Approves Contract - Carpet
RO-3890	Award Contract - Carpet	2	14-Jul-20	16-Jul-20	Award Contract - Carpet
PRO-3900	Execute Contract - Carpet	5	16-Jul-20	23-Jul-20	Execute Contract - Carpet
RO-3910	Subcontractor Issue Submittals - Carpet	20	23-Jul-20	20-Aug-20	Subcontractor Issue Submittals - Carpet
RO-3920	A/E Review & Approve Submittals - Carpet	15	20-Aug-20	11-Sep-20	A/E Review & Approve Submittals - Carpet
RO-3930	Fab & Available for Delivery - Carpet	25	11-Sep-20	19-Oct-20	Fab & Available for Delivery - Carpet
te Concrete	· ·	· · · · · · · · · · · · · · · · · · ·			
RO-5550	Owner Review/Approve RTA - Site Concrete	20	26-Feb-20 A	06-Jul-20	Owner Review/Approve RTA - Site Concrete
RO-6830	Town Building Commission Approves Contract - Site Concrete	1	14-Jul-20	14-Jul-20	Town Building Commission Approves Contract - Site Concrete
RO-5540	Award Contract - Site Concrete	2	14-Jul-20	16-Jul-20	Award Contract - Site Concrete
RO-5530	Execute Contract - Site Concrete	5	16-Jul-20	23-Jul-20	Execute Contract - Site Concrete
RO-5580	Subcontractor Issue Submittals - Site Concrete	15	23-Jul-20	13-Aug-20	Subcontractor Issue Submittals - Site Concrete
RO-5570	A/E Review & Approve Submittals - Site Concrete	15	13-Aug-20	03-Sep-20	A/E Review & Approve Submittals - Site Concrete
RO-5560	Fab & Available for Delivery - Site Concrete	20	03-Sep-20	02-Oct-20	Fab & Available for Delivery - Site Concrete
pecialties			00 00p 20	000020	
Remainin	g Level of Effort Remaining Work		Page 8 of 27		TASK filter: Uncompleted Activities Two Months Prior.
	vel of Effort Critical Remaining Work		Faye o UI 21		
 Actual Le Actual Wo 					© Oracle Corporation

	bol - Project A - 06Jun20 R1 Schedule Update - 1318014-CR - B27	Domainina	Ctort		I Schedule				/ Run Date: 09-Jul-20	09.07
D	Activity Name	Remaining Duration	Start	Finish	2020	20	21		2022	
		Duration			Jun Jul Aug Sep Oct Nov Dec Ja			v Dec Jan Feb Mar Apr Ma		Oct N
PRO-4090	Owner Review/Approve RTA - Specialties	20	26-Feb-20 A	06-Jul-20	Owner Review/Approve RTA -					
PRO-6840	Town Building Commission Approves Contract - Specialties	1	14-Jul-20	14-Jul-20	Town Building Commission Application	proves Contract - Specialtie	es			
PRO-4100	Award Contract - Specialties	2	14-Jul-20	16-Jul-20	Award Contract - Specialties					
PRO-4110	Execute Contract - Specialties	5	16-Jul-20	23-Jul-20	Execute Contract - Specialti	I I				
PRO-4120	Subcontractor Issue Submittals - Specialties	20	23-Jul-20	20-Aug-20	Subcontractor Issue Su					
PRO-4130	A/E Review & Approve Submittals - Specialties	15	20-Aug-20	11-Sep-20		ove Submittals - Specialties				
PRO-4140	Fab & Available for Delivery - Specialities	30	11-Sep-20	26-Oct-20		ble for Delivery - Specialities	, I			
			11-Sep-20	20-001-20		ible for Delivery - Specialities				
udio Visual		00					r . r			
PRO-7460	Owner Review/Approve RTA for Fab, Furnish & Install - Audio Visual	20	25-Feb-20 A		Owner Review/Approve RTA fo		Idio visuai			
PRO-7250	Owner Review/Approve RTA - Audio Visual	0	26-Feb-20 A		wner Review/Approve RTA - Audio Vis					
PRO-7300	Town Building Commission Approves Contract - Audio Visual	0	-	•	own Building Commission Approves Co					
PRO-7230	Execute Contract - Audio Visual (Partial)	0			Execute Contract - Audio Visual (Partial)					
PRO-7240	Award Contract - Audio Visual (Partial)	0	13-May-20 A	13-May-20 A	Award Contract - Audio Visual (Partial)					
PRO-7280	Subcontractor Issue Submittals - Audio Visual	20	14-May-20 A	06-Jul-20	Subcontractor Issue Submittals	s - Audio Visual				
PRO-7270	A/E Review & Approve Submittals - Audio Visual	15	07-Jul-20	27-Jul-20	A/E Review & Approve Sub	mittals - Audio Visual	 			
PRO-7260	Fab & Available for Delivery - Audio Visual	60	28-Jul-20	21-Oct-20	Fab & Availal	ole for Delivery - Audio Visua	al			
perable Parti		,								
PRO-6970	Owner Review/Approve RTA - Operable Partitions	20	25-Feb-20 A	06-Jul-20	Owner Review/Approve RTA -	Operable Partitions				
PRO-7020	Town Building Commission Approves Contract - Operable Partitions	1	14-Jul-20	14-Jul-20	I Town Building Commission Ar	• • •	Partitions			
PRO-6960	Award Contract - Operable Partitions	2	14-Jul-20	16-Jul-20	Award Contract - Operable P					¦
PRO-6950	Execute Contract - Operable Partitions	5	14-Jul-20 16-Jul-20	23-Jul-20	Execute Contract - Operable P					
PRO-7000	Subcontractor Issue Submittals - Operable Partitions	20	23-Jul-20	20-Aug-20	Subcontractor Issue Su	í I	1			
PRO-6990	A/E Review & Approve Submittals - Operable Partitions	15	20-Aug-20	11-Sep-20		ove Submittals - Operable P	1			
PRO-6980	Fab & Available for Delivery - Operable Partitions	60	11-Sep-20	10-Dec-20	Fab	& Available for Delivery - Op	erable Partitions			
tage Equipm										
PRO-4230	Owner Review/Approve RTA - Stage Equipment	20	27-Feb-20 A	06-Jul-20	Owner Review/Approve RTA -	Stage Equipment				
PRO-6850	Town Building Commission Approves Contract - Stage Equipment	1	14-Jul-20	14-Jul-20	I Town Building Commission Appendix 1	proves Contract - Stage Ed	uipment			
PRO-4240	Award Contract - Stage Equipment	2	14-Jul-20	16-Jul-20	Award Contract - Stage Equip	oment				
PRO-4250	Execute Contract - Stage Equipment	5	16-Jul-20	23-Jul-20	Execute Contract - Stage Education	1 1				
PRO-4260	Subcontractor Issue Submittals - Stage Equipment	20	23-Jul-20	20-Aug-20	Subcontractor Issue Su		¹ 1 1			
PRO-4270	A/E Review & Approve Submittals - Stage Equipment	15	20-Aug-20	11-Sep-20		ove Submittals - Stage Equip				
PRO-4280	Fab & Available for Delivery - Stage Equipment	65	11-Sep-20	17-Dec-20		& Available for Delivery - S	1			
heater Drape		00	11 000 20	11 000 20						
		20	26 Eab 20 A	06 101 20		Stage Equipment				
PRO-7330	Owner Review/Approve RTA - Stage Equipment	20	26-Feb-20 A	06-Jul-20	Owner Review/Approve RTA-					
PRO-7380	Town Building Commission Approves Contract - Theater Draperies	1	14-Jul-20	14-Jul-20	I Town Building Commission Ap	-	Draperies			
PRO-7320	Award Contract - Theater Draperies	2	14-Jul-20	16-Jul-20	Award Contract - Theater Dra	· · · ·				
PRO-7310	Execute Contract - Theater Draperies	5	16-Jul-20	23-Jul-20	Execute Contract - Theater	· · · ·				
PRO-7360	Subcontractor Issue Submittals - Theater Draperies	20	23-Jul-20	20-Aug-20	Subcontractor Issue Su	ubmittals - Theater Draperie	S			
PRO-7350	A/E Review & Approve Submittals - Theater Draperies	15	20-Aug-20	11-Sep-20	A/E Review & Appro	ove Submittals - Theater Dra	aperies		· · · · · · · · · · · · · · · · · · ·	
PRO-7340	Fab & Available for Delivery - Theater Draperies	65	11-Sep-20	17-Dec-20	Fat	o & Available for Delivery - T	heater Draperies			
/indow Treat	ments									
PRO-4370	Owner Review/Approve RTA - Window Treatments	20	26-Feb-20 A	06-Jul-20	Owner Review/Approve RTA -	Window Treatments				
PRO-6860	Town Building Commission Approves Contract - Window Treatments	1	14-Jul-20	14-Jul-20	I Town Building Commission Ar	1 1	Treatments			
PRO-4380	Award Contract - Window Treatments	2	14-Jul-20	16-Jul-20	Award Contract - Window Tre					
PRO-4390	Execute Contract - Window Treatments	5	16-Jul-20	23-Jul-20	Execute Contract - Window					
PRO-4400	Subcontractor Issue Submittals - Window Treatments	20	23-Jul-20	20-Aug-20	Subcontractor Issue St		nts			
PRO-4400	A/E Review & Approve Submittals - Window Treatments	15	20-Aug-20	20-Aug-20 11-Sep-20		ove Submittals - Window Treatment	1			
						1 1	1			
PRO-4420	Fab & Available for Delivery - Window Treatments	20	11-Sep-20	09-Oct-20		e for Delivery - Window Trea	unents			
ignage					<u></u>					
PRO-4440	Owner Review/Approve RTA - Signage	20	26-Feb-20 A	06-Jul-20	Owner Review/Approve RTA-					
PRO-6880	Town Building Commission Approves Contract - Signage	1	14-Jul-20	14-Jul-20	I Town Building Commission Ap	proves Contract - Signage				
PRO-4450	Award Contract - Signage	2	14-Jul-20	16-Jul-20	Award Contract - Signage					
PRO-4460	Execute Contract - Signage	5	16-Jul-20	23-Jul-20	Execute Contract - Signage		- 			
Remaining	g Level of Effort Remaining Work		Page 9 of 27		TASK filter: Uncompleted Activities Tw	o Months Prior.				
Actual Lev	vel of Effort Critical Remaining Work		-		·	© Oracle Co	orporation	CVAN		
Actual Wo							-	SKAN	IJKA	
							1			

	ol - Project A - 06Jun20 R1 Schedule Update - 1318014-CR - B27		<u> </u>		Schedule		Data Date: 06-Jun-20 / Ru	1 Date: 09-Jui-20 09:0
D	Activity Name	Remaining	Start	Finish	2020	2021		2022
		Duration				Jan Feb Mar Apr May Jun Jul Aug Sep Oct No		
PRO-4470	Subcontractor Issue Submittals - Signage	20	23-Jul-20	20-Aug-20	Subcontractor Issu	* * * * * * * * * * * * *		
PRO-4480	A/E Review & Approve Submittals - Signage	15	20-Aug-20	11-Sep-20		oprove Submittals - Signage		
PRO-4490	Fab & Available for Delivery - Signage	30	11-Sep-20	26-Oct-20		vailable for Delivery - Signage		
andscaping	T ab & Available for Delivery - Oighage	50	11-0cp-20	20-001-20				
PRO-4020	Owner Review/Approve RTA - Landscaping	20	25-Feb-20 A	06-Jul-20	Owner Review/Approve R1			
		20		l				
PRO-6890	Town Building Commission Approves Contract - Landscaping	1	14-Jul-20	14-Jul-20		Approves Contract - Landscaping		
PRO-4030	Award Contract - Landscaping	2	14-Jul-20	16-Jul-20	Award Contract - Landsc			
PRO-4040	Execute Contract - Landscaping	5	16-Jul-20	23-Jul-20	Execute Contract - Land			
PRO-4050	Subcontractor Issue Submittals - Landscaping	15	23-Jul-20	13-Aug-20	Subcontractor Issue			
PRO-4060	A/E Review & Approve Submittals - Landscaping	15	13-Aug-20	03-Sep-20		prove Submittals - Landscaping		
PRO-4070	Fab & Available for Delivery - Landscaping	50	03-Sep-20	17-Nov-20	Fab	& Available for Delivery - Landscaping	·	-++
nal Cleaning								
PRO-4510	Owner Review/Approve RTA - Final Cleaning	20	26-Feb-20 A	06-Jul-20	Owner Review/Approve R1	A - Final Cleaning		
PRO-6900	Town Building Commission Approves Contract - Signage	1	14-Jul-20	14-Jul-20	I Town Building Commission	Approves Contract - Signage		
PRO-4520	Award Contract - Final Cleaning	2	14-Jul-20	16-Jul-20	Award Contract - Final Cl	eaning		
PRO-4530	Execute Contract - Final Cleaning	5	16-Jul-20	23-Jul-20	Execute Contract - Final	Cleaning		
PRO-4540	Subcontractor Issue Submittals - Final Cleaning	20	23-Jul-20	20-Aug-20	Subcontractor Issue	e Submittals - Final Cleaning	·	
PRO-4550	A/E Review & Approve Submittals - Final Cleaning	15	20-Aug-20	11-Sep-20		prove Submittals - Final Cleaning		
PRO-4560	Fab & Available for Delivery - Final Cleaning	10	11-Sep-20	25-Sep-20		le for Delivery - Final Cleaning		
ockups								
terior Facad	de					· · · · · · · · · · · · · · · · · · ·	·	· · · · · · · · · · · · · · · · · · ·
rocurement								
/IOCK-1150	Prepare & Submit - Granite - Exterior Mockup	0	02-Mar-20 A	18-May-20 A	Prepare & Submit - Granite - Exterio	or Mockup		
/IOCK-1180	Prepare & Submit - Brick - Exterior Mockup	0	02-Mar-20 A	18-May-20 A	Prepare & Submit - Brick - Exterior	Mockup		
/IOCK-1260	Prepare & Submit - Roofing - Exterior Mockup	0	02-Mar-20 A	02-Jun-20 A	Prepare & Submit - Roofing - Exte	erior Mockup		
/IOCK-1070	Review & Approve - Sheathing - Exterior Mockup	0	20-Mar-20 A	13-Apr-20 A	w & Approve - Sheathing - Exterior	Mockup		
/IOCK-1510	Fab & Available for Delivery - Metal Panels - Exterior Mockup	0	23-Mar-20 A		Available for Delivery - Metal Panel			
/IOCK-1230	Prepare & Submit - JK Glass Exterior Sealants - Exterior Mockup	0	24-Apr-20 A		pare & Submit - JK Glass Exterior S			
/OCK-1240	Review & Approve - JK Glass Exterior Sealants - Exterior Mockup	0	24-Apr-20 A	•	iew & Approve - JK Glass Exterior S			
/OCK-1010	Review & Approve - Framing - Exterior Mockup	5	24-Apr-20 A	· ·	Review & Approve - Framing -			
/OCK-1210	Prepare & Submit - Masonry Exterior Sealants - Exterior Mockup	5	24-Apr-20 A		Prepare & Submit - Masonry Ex	1 1 1		
/IOCK-1080	Fab & Available for Delivery - Sheathing - Exterior Mockup	0	•		Fab & Available for Delivery - Sheat			
/OCK-1160		0		-	Review & Approve - Granite - Ex	-		
	Review & Approve - Granite - Exterior Mockup Review & Approve - Brick - Exterior Mockup	0	-					
/OCK-1190		0		02-Jun-20 A				
10CK-1200	Fab & Available for Delivery - Brick - Exterior Mockup	0	03-Jun-20 A		Fab & Available for Delivery - Brid			
/IOCK-1170	Fab & Available for Delivery - Granite - Exterior Mockup	/	03-Jun-20 A	16-Jun-20	Fab & Available for Delivery - C			
/OCK-1270	Review & Approve - Roofing - Exterior Mockup	7	03-Jun-20 A	16-Jun-20	Review & Approve - Roofing -			
/IOCK-1320	Pre-Installation Meeting - Exterior Mockup	1	08-Jun-20*	08-Jun-20	I_Pre-Installation Meeting - Exterio			
/IOCK-1250	Fab & Available for Delivery - JK Glass Exterior Sealants - Exterior Mockup	10	08-Jun-20	19-Jun-20		K Glass Exterior Sealants - Exterior Mockup		
/IOCK-1020	Fab & Available for Delivery - Framing - Exterior Mockup	5	15-Jun-20	19-Jun-20	Fab & Available for Delivery - F			
/IOCK-1220	Review & Approve - Masonry Exterior Sealants - Exterior Mockup	10	15-Jun-20	26-Jun-20	Review & Approve - Masonry	Exterior Sealants - Exterior Mockup		
/IOCK-1280	Fab & Available for Delivery - Roofing - Exterior Mockup	5	17-Jun-20	23-Jun-20	Fab & Available for Delivery -	Roofing - Exterior Mockup		
/IOCK-1225	Fab & Available for Delivery - Masonry Exterior Sealants - Exterior Mockup	10	29-Jun-20	13-Jul-20	Fab & Available for Deliver	y - Masonry Exterior Sealants - Exterior Mockup		
onstruction								
/IOCK-1330	Install Perimeter Fence - Exterior Mockup	1	22-Jun-20	22-Jun-20	I Install Perimeter Fence - Exte	rior Mockup		
/OCK-1340	FRP & Strip Concrete Anchor Pad - Exterior Mockup	5	23-Jun-20	29-Jun-20	FRP & Strip Concrete Ancho			
10CK-1350	Install LGMF & Bracing - Exterior Mockup	2	30-Jun-20	01-Jul-20	Install LGMF & Bracing - Ex			
10CK-1370	Install Sheathing - Exterior Mockup	1	02-Jul-20	02-Jul-20	I Install Sheathing - Exterior N			
10CK-1380	Install AVB - Exterior Mockup	2	02-Jul-20	07-Jul-20	Install AVB - Exterior Mock			
IOCK-1380	Install Thermal Insulation - Exterior Mockup	1	08-Jul-20	07-Jul-20 08-Jul-20	I Install Thermal Insulation -			
		1						
/OCK-1400	Install Curtain Wall Frames - Exterior Mock up	2	09-Jul-20	10-Jul-20	I Install Curtain Wall Frames		·	
/OCK-1410	Install Exterior Glazing Frames - Exterior Mockup	1	13-Jul-20	13-Jul-20	I Install Exterior Glazing Fra			
/IOCK-1420	Install Punch Windows Frames - Exterior Mockup	1	14-Jul-20	14-Jul-20	I Install Punch Windows Fr	ames - Exterior Mockup		
Remaining	g Level of Effort Remaining Work		Dago 10 of 07	.	TASK filtor: Lincompleted Activities	Two Months Brier		
-	-		Page 10 of 27		TASK filter: Uncompleted Activities			
 Actual Lev 	-					© Oracle Corporation	SKANS	ΚΔ
Actual Wo	ork							
					e 340 of 377			

	ol - Project A - 06Jun20 R1 Schedule Update - 1318014-CR - B27				Schedule				Jun-20 / Run Date: 09-J	Jui-20 09:07
rity ID	Activity Name	Remaining Duration	Start	Finish	2020	202	1		2022	
		Duration			Jun Jul Aug Sep Oct Nov Dec Jan Feb Ma			Oct Nov Dec Jan Feb Mari		Sep Oct Nov I
MOCK-1430	Install Exterior Glazing - Exterior Mockup	1	15-Jul-20	15-Jul-20	I Install Exterior Glazing - Exterior Mockur					
MOCK-1520	Install Metal Panels - Exterior Mockup	1	15-Jul-20	15-Jul-20	I Install Metal Panels - Exterior Mockup					
MOCK-1440	Install Granite Base - Exterior Mockup	1	16-Jul-20	16-Jul-20	I Install Granite Base - Exterior Mockup					
MOCK-1450	Install Brick - Exterior Mockup	5	17-Jul-20	23-Jul-20	Install Brick - Exterior Mockup	- L				
MOCK-1460	Washdown Brick - Exterior Mockup	1	24-Jul-20	24-Jul-20	Washdown Brick - Exterior Mock up					
MOCK-1400	Install Exterior Sealents & Control Joints - Exterior Mockup	1	27-Jul-20	27-Jul-20	I Install Exterior Sealents & Control Join	ta Extorior Mooku	n			
MOCK-1470 MOCK-1480	•	2		27-Jul-20 29-Jul-20	Install Roofing - Exterior Mockup	IS - EXIENDI WOCKU	þ	i i		
	Install Roofing - Exterior Mockup	_	28-Jul-20			nian Maraluun				1
MOCK-1490	Architect Review & Approve - Exterior Mockup	15	30-Jul-20	19-Aug-20	Architect Review & Approve - Exte	rior москир		·		
Construction	n Summary									
SUM-1120	Summary - Temp Platform Work	5	25-Sep-19 A	12-Jun-20	\$ummary - Temp Platform Work					
SUM-1100	Summary - Sitework & Foundations at MBTA D Line Area	15	12-Oct-19A	26-Jun-20	Summary - Sitework & Foundations at MBT	A D Line Area				
SUM-1050	Summary - Lower Level Slab on Grade	50	14-Apr-20 A	17-Aug-20	Summary - Lower Level Slab on G	rade				
SUM-1040	Summary - Erect Steel & Precast Structure alongside & over MBTA D Line Tracks (Weeke	6	06-Jun-20	21-Jun-20	Summary - Erect Steel & Precast Structure	1 1	BTA D Line T	Fracks (Weekends)		
SUM-1010	Summary - Erect Structural Steel	43	22-Jun-20	20-Aug-20	Summary - Erect Structural Steel					
SUM-1020	Summary - Detail & Deck Structural Steel	60	22-Jun-20	15-Sep-20	Summary - Detail & Deck Stru	ictural Steel				
SUM-1020	Summary - Prep & Place Slabs on Deck	35	04-Aug-20	22-Sep-20	Summary - Prep & Place Sla					
SUM-1050	Summary - Spray Fireproofing	23	15-Sep-20	16-Oct-20	Summary - Spray Firepr	1				
					Summary - Spray Filepi	-	Architacture	of Dough in		
SUM-1080	Summary - MEP & Architectural Rough-in	117	22-Sep-20	15-Mar-21		Summary - MEP 8				
SUM-1070	Summary - Exterior Facade	124	22-Sep-20	24-Mar-21		Summary - Exter	ior Facade			
INT-1080	Summary - Interior Drywall & Finishes	160	18-Mar-21	03-Nov-21				Summary - Interior Dry	wall & Finishes	1
INT-1110	Summary - Building Temp Tight	0		24-Mar-21		Summary - Build	ing Temp Tig	1		1
INT-1090	Summary - Final Inspections & C of O	52	31-Aug-21	15-Nov-21				Summary - Final Insp	1	
INT-1150	Summary - Owner Install FF&E	10	27-Sep-21	08-Oct-21				Summary - Owner Install FF	&E	
INT-1140	Summary - MEP Commissioning	60	30-Sep-21	29-Dec-21				Summary - M	EP Commissioning	
INT-1100	Summary - Substantial Completion - Project A: 111 Cypress Street	0		15-Nov-21				Summary - Substantia	al Completion - Project A:	111 Cypress St
MEP Coordin	nation									
_										
Lower Level SI				1						
MEP-3010	Review & Approve MEPs - LL Underground	0	03-Apr-20 A	29-Apr-20 A	view & Approve MEPs - LL Underground					
Lower Level										
MEP-3020	Coordinate MEPs - LL	5	23-Jan-20 A	12-Jun-20	Coordinate MEPs - LL					
MEP-3030	Review & Approve MEPs - LL	5	15-Jun-20	19-Jun-20	Review & Approve MEPs - LL					
MEP-3040	Fab & Deliver - Duct & Pipe - LL	15	07-Jul-20	27-Jul-20	🔲 Fab & Deliver - Duct & Pipe - LL					
Level 1										
MEP-3050	Coordinate MEPs - L1	8	27-Feb-20 A	17-Jun-20	Coordinate MEPs - L1					
MEP-3060	Review & Approve MEPs - L1	5	18-Jun-20	24-Jun-20	Review & Approve MEPs - L1					
MEP-3070	Fab & Deliver - Duct & Pipe - L1	15	25-Jun-20	16-Jul-20	Fab & Deliver - Duct & Pipe - L1					
		15	23-Jun-20	10-Jul-20	Fab & Deliver - Duct & Fipe - LT					
Level 2										
MEP-3080	Coordinate MEPs - L2	10	05-Mar-20 A		Coordinate MEPs - L2			.j		
MEP-3090	Review & Approve MEPs - L2	5	22-Jun-20	26-Jun-20	Review & Approve MEPs - L2					
MEP-3100	Fab & Deliver - Duct & Pipe - L2	15	29-Jun-20	20-Jul-20	🔲 🖬 Fab & Deliver - Duct & Pipe - L2					
Level 3										
MEP-3110	Coordinate MEPs - L3	15	09-Apr-20 A	26-Jun-20	Coordinate MEPs - L3			i i		
MEP-3120	Review & Approve MEPs - L3	5	29-Jun-20	06-Jul-20	Review & Approve MEPs - L3					
MEP-3130	Fab & Deliver - Duct & Pipe - L3	15	07-Jul-20	27-Jul-20	Fab & Deliver - Duct & Pipe - L3	$-\frac{1}{r} - \cdots - \frac{1}{r} - \cdots - \frac{1}{r} - \frac{1}{$				
Level 4		10	07-00F20	21-00-20						
		00	40.14 00.4	40 1 1 00						
MEP-3140	Coordinate MEPs - L4	28	18-May-20 A	16-Jul-20	Coordinate MEPs - L4					
MEP-3150	Review & Approve MEPs - L4	5	17-Jul-20	23-Jul-20	Review & Approve MEPs - L4					
MEP-3160	Fab & Deliver - Duct & Pipe - L4	15	24-Jul-20	13-Aug-20	🔲 Fab & Deliver - Duct & Pipe - L4					
Construction										
Sitework & For										
Sitework & Fou	vrana Ct L at)								1	1
Sitework & Fou South (111 Cyp	press St Lot)									
South (111 Cyp							1		L.	1
South (111 Cyp Remaining	Level of Effort Remaining Work		Page 11 of 27		TASK filter: Uncompleted Activities Two Months I					1
South (111 Cyp	Level of Effort Remaining Work		Page 11 of 27		TASK filter: Uncompleted Activities Two Months I	Prior. © Oracle Corp	poration	CV	ANSKA	1

Page 341 of 377

	ect A - 06Jun20 R1 Schedule Update - 1318014-CR - B27				d Schedule		Data D	ate: 06-Jun-20 / Run Dat	e: 09-Jul-20 09:07
Activity ID Activity	ty Name	Remaining Duration	Start	Finish	2020	2021		2022	
		Duration				c Jan Feb Mar Apr May Jun Jul Aug Sep	Oct Nov Dec Jan Fe		Aug Sep Oct Nov [
FOUND-1070 Cure &	& Backfill Foundations - South	20	02-Apr-20 A	06-Jul-20	Cure & Backfill Foundation				
Foundation Walls							I I		
FOUND-1760 Water	rproof Foundation Walls - South	0	16-Mar-20 A	07-Apr-20 A	proof Foundation Walls - South			++ 1 1 1 1 1	
	fill Foundation Walls - South	0	23-Mar-20 A		fill Foundation Walls - South				
FOUND-1450 Final O		0	02-Apr-20 A		ure Perimeter Wals				
North (MBTA Area)				, ·					
FOUND-1810 FRP F	Piers, Spread Footings & Pile Cap (CL 1 to 3) - North	5	04-Mar-20 A	12-Jun-20	FRP Piers, Spread Footings &	Pile Cap (CL 1 to 3) - North			
	blete FRP Grade Beam at CL B at OCS Portal - North	1	16-Mar-20 A	1	Complete FRP Grade Beam at		·	++ I I I I	
· · ·	Foundation Walls (Pour 2) - North	1	18-Mar-20 A		FRP Foundation Walls (Pour 2)				
	Foundation Walls (Pour 3) - North	1	18-Mar-20 A		FRP Foundation Walls (Pour 3)				
	& Strip Walls at Elevator Pit Area - North	1	18-Mar-20 A	17-Jun-20	FRP & Strip Walls at Elevator				
	Foundation Walls (Pour 4) - North	5	15-Jun-20	19-Jun-20	FRP Foundation Walls (Pour				
	Foundation Walls (Pour 5) - North	5	15-Jun-20	19-Jun-20	FRP Foundation Walls (Pour				
	rproof/Damproof Foundation Walls - North	10	15-Jun-20	26-Jun-20	Waterproof/Damproof Foun				
	rproof Walls at Elevator Pit Area - North	5	18-Jun-20	24-Jun-20	Waterproof Walls at Elevator				
FOUND-1060 Cure F		5	22-Jun-20	26-Jun-20	Cure Foundations - North		1		
FOUND-1730 Backfi	fill Foundation Walls - North	10	22-Jun-20	06-Jul-20	Backfill Foundation Wals -	North			
FOUND-1100 FRP S		15	29-Jun-20	20-Jul-20	FRP Stairs - North	······································	 		
Structure				20 00. 20					
North (MBTA D Line Ar							1		
Level 1									
	I Crane Mats & Mobilize Crane - North	0	04- Jun-20 A	05-Jun-20 A	I Install Crane Mats & Mobilize Cr	ahe - North			
	Steel along Tracks CL D - North (Weekend Work)	2	06-Jun-20	07-Jun-20	Erect Steel along Tracks CL D		·		i
	, Bolt-up & Plumb Steel along Tracks CL D - North (Weekday)	2	08-Jun-20	07-Jun-20		ong Tracks CL D - North (Weekday)			
STRUCT-1280 Erect		5	10-Jun-20	14-Jun-20	Erect Steel - North (Seq 1)	Sing Tracks CE D - North (Weekday)			1
STRUCT-1200 Set Pr		5	15-Jun-20	14-Jun-20	Set Precast Crane - South				
	Precast over Tracks - L1 - North (Weekend Work)	2	20-Jun-20	21-Jun-20	Erect Precast over Tracks	1 North (Weekend Work)			
	Perimter Curb - L1 - North	5	02-Jul-20	09-Jul-20	FRP Perimter Curb - L1 -	- +			
	& Place Topping Slab (Weekend Work) - L1 - North	2	25-Jul-20	26-Jul-20		Slab (Weekend Work) - L1 - North			
Level 3 to Roof	a Flace Topping Slab (Weekend Work) - LT - North	2	20-JUF20	20-Jul-20					
	Structural Steel over Tracks Sequences 2 to 5 - L3 & Canopy - North (Weekend Wo	6	22-Jun-20	27-Jun-20	Erect Structural Steel over 7	Fracks Sequences 2 to 5 - L3 & Canopy - North	(Weekend Work)		1 1 1
	& Deck Structural Steel Sequence 2 to 5 - L3 & Canopy - North (Weekend Work)	10	22-Jun-20	01-Jul-20		eel Sequence 2 to 5 - L3 & Canopy - North (Wee	· /		
South (111 Cypress St		10	22-3011-20	01-Jul-20		eel Sequence 2 to 5 - L5 & Canopy - North (Wee			
Level 1	Structural Steel - L1 - South	0	29-Jun-20	09-Jul-20	Erect Structural Steel - L1	South			
	& Deck Steel - L1 - South	17	10-Jul-20	03-Aug-20	Detail & Deck Steel - L				
	& Place Slab on Deck - L1 - South	5			Prep & Place Slab or		l I		
· · · ·			04-Aug-20	10-Aug-20	■ Frep & Place Slab of			· · · · · · · · · · · · · · · · · · ·	
	Perimeter Curbs - L1- South	5	11-Aug-20	17-Aug-20		bs - LT- South			
Level 2	Structural Steel 1.2. South	0	10 101 20	47 101 20					
	Structural Steel - L2 - South	17	10-Jul-20	17-Jul-20	Erect Structural Steel - L				
	& Deck Steel - L2 - South	17	20-Jul-20	11-Aug-20	Detail & Deck Steel -				1 1 1
	& Place Slab on Deck - L2 - South	5	12-Aug-20	18-Aug-20	Prep & Place Slab o	טשכע ווכע - L∠ - South		· · · · · · · · · · · · · · · · · · ·	
Level 3	Structural Steel - L3 - South	40	00 101 00	05 4					
		13	20-Jul-20	05-Aug-20	Erect Structural Steel				
	& Deck Steel - L3 - South	17	06-Aug-20	28-Aug-20	Detail & Deck Ste				
	& Place Slab on Deck - L3 - South	5	31-Aug-20	04-Sep-20	Prep & Place Sla	ab on Deck - L3 - South			
Level 4		-	00.4	40.4			·		
	Structural Steel - L4 - South	5	06-Aug-20	12-Aug-20	Erect Structural Stee				
	& Deck Steel - L4 - South	17	13-Aug-20	04-Sep-20	Detail & Deck St				
	& Place Slab on Deck - L4 - South	5	08-Sep-20	14-Sep-20	Prep & Place S	Slab on Deck - L4 - South			
Roof		-	40.1.55	00.1					
	Structural Steel - Roof - South	6	13-Aug-20	20-Aug-20	Erect Structural St		·	·	
STRUCT-1180 Detail	& Deck Steel - Roof - South	17	21-Aug-20	15-Sep-20	Detail & Deck	Steel - Root - South		 	1
Remaining Level of	-		Page 12 of 27	,	TASK filter: Uncompleted Activities				_
Actual Level of Effo	ort Critical Remaining Work					© Oracle Corporation	G	SKANSK	Δ
Actual Work	♦ Milestone								
				Pad	e 342 of 377				

ity ID	ol - Project A - 06Jun20 R1 Schedule Update - 1318014-CR - B27 Activity Name	Remaining	Start	Finish	Schedule			Data Date: 06-Jun-20 / F		2.01
ity iD	Addition of the second s	Duration	otart	1 111011	2020		2021		2022	
	00 Prep & Place Slab on Deck - Roof - South	5	16-Sep-20	22-Sep-20	Jun Jul Aug Sep Oct Nov Dec	Slab on Deck - Roof - South	n Jul Aug Sep Oct Nov Dec	Jan [Feb] Mar Apr [May]		ct [No
Misc. Metal St		5	10-3ep-20	22-3ep-20						
STAIR-1000	Install - Stair 1	5	31-Jul-20	06-Aug-20	Install - Stair 1					
STAIR-1000 STAIR-1010	Install - Stair 1	20		08-Sep-20	Install - Stair 2					
			11-Aug-20	· · ·						
STAIR-1020	Install - Stair 3	20	25-Aug-20	22-Sep-20	Install - Stair	1				
STAIR-1030	Install - Stairs 6/7	20	09-Sep-20	06-Oct-20	Install - Sta	1				
STAIR-1040	Install - Stairs 4/5	5	07-Oct-20	14-Oct-20	Install - St	airs 4/5				
Slab on Grade										
Lower Level		_								
SOG-1000	Excavate & Install Underslab Utilities - Lower Level	1	14-Apr-20 A		Excavate & Install Underslab I					
SOG-1010	Prep & Place Slab on Grade - Lower Level	10	04-Aug-20	17-Aug-20	Prep & Place Slab c	n Grade - Lower Level				
Layout & Insta										
L1-3000	Layout & Install Top Track - L1	5	19-Aug-20	25-Aug-20	Layout & Install To					
L1-3010	Layout & Install Top Track - L2	5	08-Sep-20	14-Sep-20	Layout & Instal					
L1-3020	Layout & Install Top Track - L3	5	15-Sep-20	21-Sep-20	Layout & Insta					
L1-3030	Layout & Install Top Track - L4	5	23-Sep-20	29-Sep-20		tall Top Track - L4				
L1-3040	Layout & Install Top Track - Garden Level	5	30-Sep-20	06-Oct-20	Layout & In	stall Top Track - Garden Leve				
Spray Firepro	ofing									
SPF-1000	Spray Fireproof - L1	5	08-Sep-20	14-Sep-20	Spray Fireproo	f - L1				
SPF-1010	Spray Fireproof - L2	5	15-Sep-20	21-Sep-20	Spray Firepro	of - L2				
SPF-1020	Spray Fireproof - L3	5	22-Sep-20	28-Sep-20	Spray Firepr	oof - L3				
SPF-1030	Spray Fireproof - L4	5	02-Oct-20	08-Oct-20	Spray Fire	proof - L4				
SPF-1040	Spray Fireproof - Garden Level	5	09-Oct-20	16-Oct-20	Spray Fire	eproof - Garden Level				
Roofing										
RF-1000	Temp-in Roofs	15	23-Sep-20	14-Oct-20	Temp-in F	Roofs		r		
RF-1010	Set & Connect Roof Top Equipment	20	23-Sep-20	21-Oct-20		nnect Roof Top Equipment				
RF-1020	Install Roof Screens	20	22-Oct-20	19-Nov-20		all Roof Screens				
RF-1030	Install Permanent Roof - Roof Level	15	20-Nov-20	14-Dec-20		Install Permanent Roof - Roof	Level			
RF-1040	Install Permanent Roof (Following Staging Removal) - L3	15	29-Apr-21	19-May-21			all Permanent Roof (Following S	taging Removal) - L3		
Exterior Faca		,,		, ,						
EXT-1000	Frame Exterior Walls	71	22-Sep-20	06-Jan-21		Frame Exterior Walls				
EXT-105	Sheath Exterior Walls	60	13-Oct-20	11-Jan-21		Sheath Exterior Walls				
EXT-1010	AVB Exterior Walls	57	27-Oct-20			AVB Exterior Walls				
EXT-1040	Install Curtain Wal	90	10-Nov-20	24-Mar-21			Wal			
EXT-1020	Stage Exterior Walls	83	28-Dec-20	27-Apr-21			Exterior Walls			
EXT-1020	Install Stone & Brick / Washdown / Remove Staging	77	07-Jan-21	28-Apr-21			Stone & Brick / Washdown / Ren	ove Staging		
EXT-1050	Building Temp Tight	0	0.00	24-Mar-21		Building Tem	- I			
	(CL C.7 to PP)			2111101 21						
E-1000	Frame Exterior Walls & Canopy - East Elevation	24	22-Sep-20	26-Oct-20	Frame I	Exterior Walls & Canopy - East	Elevation			
E-1010	Sheath Exterior Walls & Canopy - East Elevation	15	13-Oct-20	02-Nov-20		Exterior Walls & Canopy - Ea		L		
E-1010	Install AVB - East Elevation	10	27-Oct-20	02-Nov-20		AVB - East Elevation				
E-1030	Prep Openings for Curtain Wall - East Elevation	10	03-Nov-20	17-Nov-20		Openings for Curtain Wall - E	ast Elevation			
E-1040	Install Curtain Wal - East Elevation	31	10-Nov-20	28-Dec-20		Install Curtain Wal - East E				
E-1040	Install Staging - East Elevation	20	07-Dec-20	05-Jan-21		Install Staging - East Eleva				
E-1050	Install Stone - East Elevation	18	23-Dec-20	20-Jan-21	1	Install Stone - East Elev				
E-1000	Install Brick - East Elevation	24	07-Jan-21	10-Feb-21	1	Install Brick - East E				
E-1070	Washdown Masonry - East Elevation	10	03-Feb-21	17-Feb-21		Washdown Mason	1 1			
E-1090	Remove Staging - East Elevation	10	10-Feb-21	24-Feb-21		Remove Staging				
E-1090	Caulk Facade - East Elevation	11	25-Feb-21	11-Mar-21						
	on (CL 10 to 18)		20-1 60-21		.			, 		
S-1000	Frame Exterior Walls - South Elevation	17	19-Oct-20	10-Nov-20	Eram	e Exterior Walls - South Elevat	idn			
S-1000	Sheath Exterior Walls - South Elevation	10	04-Nov-20	18-Nov-20		ath Exterior Walls - South Elev	1			
S-1010 S-1020	Install AVB - South Elevation	6	18-Nov-20	25-Nov-20		aul Exterior wars - South Elevation				
			10-1107-20	23-1007-20			<u> </u>	i i		
Remaining	g Level of Effort Remaining Work		Page 13 of 27	7	TASK filter: Uncompleted Activities	s Two Months Prior.				
Actual Lev	vel of Effort Critical Remaining Work					© Oracle (Corporation	SKANS	SKV	
Actual Wo	ork									

-	ool - Project A - 06Jun20 R1 Schedule Update - 1318014-CR - B27		<u> </u>	Detailed S	chedule Data Date: 06-Jun-20 / Run Date: 09-Jul-20 09:07
ity ID	Activity Name	Remaining Duration	Start	Finish	2020 2021 2022
		Daradon		T.	Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov
S-1030	Prep Openings for Curtain Wall - South Elevation	5	30-Nov-20	04-Dec-20	Prep Openings for Curtain Wall - South Elevation
S-1040	Install Curtain Wal - South Elevation	8	29-Dec-20	08-Jan-21	Install Curtain Wal - South Elevation
S-1050	Install Staging - South Elevation	5	11-Jan-21	15-Jan-21	Install Staging - South Elevation
S-1060	Install Stone - South Elevation	15	21-Jan-21	10-Feb-21	Install Stone - South Elevation
S-1070	Install Brick - South Elevation	20	04-Feb-21	04-Mar-21	Install Brick - South Elevation
S-1080	Washdown Masonry - South Elevation	5	04-Mar-21	10-Mar-21	Washdown Masonry - South Elevation
S-1090	Remove Staging - South Elevation	3	11-Mar-21	15-Mar-21	Remove Staging - South Elevation
S-1100	Caulk Facade - South Elevation	7	16-Mar-21	24-Mar-21	Caulk Facade - South Elevation
	on (CL C.7 to P)	-			
W-1000	Frame Exterior Walls - West Elevation	36	02-Nov-20	24-Dec-20	Frame Exterior Walls - West Elevation
W-1010	Sheath Exterior Walls - West Elevation	17	09-Dec-20	04-Jan-21	Sheath Exterior Walls - West Elevation
W-1020	Install AVB - West Elevation	19	16-Dec-20	13-Jan-21	Install AVB - West Elevation
W-1020	Prep Openings for Curtain Wall - West Elevation	15	30-Dec-20	21-Jan-21	Prep Openings for Curtain Wall - West Elevation
W-1030 W-1040	Install Curtain Wall - West Elevation	23	11-Jan-21	11-Feb-21	Install Curtain Wall - West Elevation
		-			
W-1050	Install Staging - West Elevation	20	26-Jan-21	23-Feb-21	Install Staging - West Elevation
W-1060	Install Stone - West Elevation	5	11-Feb-21	18-Feb-21	Install Stone - West Elevation
W-1070	Install Brick - West Elevation	36	23-Feb-21	13-Apr-21	Install Brick - West Elevation
W-1080	Washdown Masonry - West Elevation	10	06-Apr-21	20-Apr-21	🔲 Washdown Masonry - West Elevation
W-1090	Remove Staging - West Elevation	10	13-Apr-21	27-Apr-21	Remove Staging - West Elevation
W-1100	Caulk Facade - West Elevation	19	28-Apr-21	24-May-21	Caulk Facade - West Elevation
North Elevation	on (CL 2.6 to 6.4)				
N-1000	Frame Exterior Walls - North Elevation	7	28-Dec-20	06-Jan-21	Frame Exterior Walls - North Elevation
N-1010	Sheath Exterior Walls - North Elevation	5	05-Jan-21	11-Jan-21	Sheath Exterior Walls - North Elevation
N-1020	Install AVB - North Elevation	5	14-Jan-21	21-Jan-21	Install AVB - North Elevation
N-1030	Prep Openings for Curtain Wall - North Elevation	3	22-Jan-21	26-Jan-21	Prep Openings for Curtain Wall - North Elevation
N-1040	Install Curtain Wal - North Elevation	10	02-Feb-21	16-Feb-21	Install Curtain Wal - North Elevation
N-1050	Install Staging - North Elevation	5	17-Feb-21	23-Feb-21	Install Staging - North Elevation
N-1070	Install Brick - North Elevation	10	07-Apr-21	21-Apr-21	
N-1080	Washdown Masonry - North Elevation	3	22-Apr-21	26-Apr-21	Washdown Masonry - North Elevation
N-1080	Remove Staging - North Elevation	2	27-Apr-21	28-Apr-21	Remove Staging - North Elevation
N-1090	Caulk Facade - North Elevation	3	•	20-Apr-21 27-May-21	Caulk Facade - North Elevation
		3	25-May-21	27-1viay-21	
	t Elevation (CL D to B)	-		00.0.00	
CE-1110	Install & Adjust Metal Relieving Angle at Perimeter Curb - Cafeteria East Elevation	5	22-Sep-20		Install & Adjust Metal Relieving Angle at Perimeter Curb - Cafeteria East Elevation
CE-1000	Frame Canopy - Cafeteria East Elevation	10	27-Oct-20	09-Nov-20	Frame Canopy - Cafeteria East Elevation
CE-1010	Sheath Canopy - Cafeteria East Elevation	10	10-Nov-20	24-Nov-20	Sheath Canopy - Cafeteria East Elevation
CE-1020	Install AVB - Cafeteria East Elevation	10	18-Nov-20	03-Dec-20	Install AVB - Cafeteria East Elevation
CE-1030	Prep Openings & Install Starter Sill for Curtain Wall - Cafeteria East Elevation	10	25-Nov-20	10-Dec-20	Prep Openings & Install Starter Sill for Curtain Wal - Cafeteria East Elevation
CE-1040	Install Curtain Wal - Cafeteria East Elevation	10	04-Dec-20	17-Dec-20	Install Curtain Wal - Cafeteria East Elevation
CE-1050	Install Staging - Cafeteria East Elevation	5	18-Dec-20	24-Dec-20	Install Staging - Cafeteria East Elevation
CE-1060	Install Stone - Cafeteria East Elevation	10	28-Dec-20	11-Jan-21	Install Stone - Cafeteria East Elevation
CE-1080	Washdown Masonry - Cafeteria East Elevation	4	12-Jan-21	15-Jan-21	Washdown Masonry - Cafeteria East Elevation
CE-1120	Install Metal Panel System at Canopy - Cafeteria East Elevation	10	19-Jan-21	01-Feb-21	Install Metal Panel System at Canopy - Cafeteria East Elevation
CE-1090	Remove Staging - Cafeteria East Elevation	5	02-Feb-21	08-Feb-21	Remove Staging - Cafeteria East Elevation
CE-1100	Caulk Facade - Cafeteria East Elevation	5	09-Feb-21	16-Feb-21	Caulk Facade - Cafeteria East Elevation
	th Elevation (CL 1 to 17.2)				
CN-1110	Install & Adjust Metal Relieving Angle at Perimeter Curb - Cafeteria North Elevation	15	29-Sep-20	20-Oct-20	Install & Adjust Metal Relieving Angle at Perimeter Curb - Cafeteria North Elevation
CN-1100	Frame Canopy - Cafeteria North Elevation	20	10-Nov-20	10-Dec-20	Frame Canopy - Cafeteria North Elevation
CN-1000 CN-1010		20			
	Sheath Canopy - Cafeteria North Elevation		25-Nov-20	24-Dec-20	Sheath Canopy - Cafeteria North Elevation
CN-1020	Install AVB - Cafeteria North Elevation	15	11-Dec-20	04-Jan-21	Install AVB - Cafeteria North Elevation
CN-1030	Prep Openings & Install Starter Sill for Curtain Wall - Cafeteria North Elevation	15	17-Dec-20	08-Jan-21	Prep Openings & Install Starter Sill for Curtain Wal - Cafeteria North Elevation
CN-1040	Install Curtain Wal - Cafeteria North Elevation	45	24-Dec-20	02-Mar-21	Install Curtain Wall - Cafeteria North Elevation
CN-1050	Install Staging - Cafeteria North Elevation	10	24-Feb-21	09-Mar-21	Install Staging - Cafeteria North Elevation
CN-1060	Install Stone along CL B - Cafeteria North Elevation	11	03-Mar-21	17-Mar-21	Install Stone along CL B - Cafeteria North Elevation
— Devertisie	ig Level of Effort Remaining Work		Page 14 of 27	, -	TASK filter: Uncompleted Activities Two Months Prior.
Remainin					
	evel of Effort Critical Remaining Work				© Oracle Corporation

Remaining Level of Effort Remaining Work	Page 14 of 27	TASK filter: Uncompleted Activities Two Months Prior.
Actual Level of Effort Critical Remaining Work		© Oracle Corporation
Actual Work		
	Pad	e 344 of 377

	ool - Project A - 06Jun20 R1 Schedule Update - 1318014-CR - B27		011	Detailed	d Schedule Data Date: 06-Jun-20 / Run Date: 09-Jul-20 09:07
y ID	Activity Name	Remaining Duration	Start	Finish	2020 2021 2022
		Duration			Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct I
CN-1065	Install Stone along Porch - Cafeteria North Elevation	10	18-Mar-21	31-Mar-21	Install Stone along Porch - Cafeteria North Elevation
CN-1080	Washdown Masonry - Cafeteria North Elevation	4	01-Apr-21	06-Apr-21	Washdown Masonry - Cafeteria North Elevation
CN-1170	Remove Staging for Masonry - Cafeteria North Elevation	5	07-Apr-21	13-Apr-21	Remove Staging for Masohry - Cafeteria North Elevation
CN-1180	Install Staging for Upper Canopy - Cafeteria North Elevation	10	09-Apr-21	23-Apr-21	Install Staging for Upper Canopy - Cafeteria North Elevation
CN-1120	Install Metal Panel System at Upper Canopy - Cafeteria North Elevation	20	26-Apr-21	21-May-21	Install Metal Panel System at Upper Canopy - Cafeteria North Elevation
CN-1090	Remove Staging for Upper Canopy - Cafeteria North Elevation	5	24-May-21	28-May-21	Remove Staging for Upper Canopy - Cafeteria North Elevation
CN-1160	Frame & Sheath Lower Canopy - Cafeteria North Elevation	5	01-Jun-21	07-Jun-21	Frame & Sheath Lower Canopy - Cafeteria North Elevation
CN-1150	Install Metal Panel System at Lower Canopy - Cafeteria North Elevation	5	08-Jun-21	14-Jun-21	Install Metal Panel System at Lower Canopy - Cafeteria North Elevation
CN-1100	Caulk Facade - Cafeteria North Elevation	5	15-Jun-21	21-Jun-21	Caulk Facade - Cafeteria North Elevation
CN-1190	Waterproof Porch - Cafetera North Elevation	10	22-Jun-21	06-Jul-21	🔲 Waterproof Porch - Cafetera North Elevation
CN-1130	Install Granite Treads - Cafetera North Elevation	15	07-Jul-21	27-Jul-21	Install Granite Treads - Cafetera North Elevation
CN-1200	Install Granite Pavers - Cafetera North Elevation	10	28-Jul-21	10-Aug-21	Install Granite Pavers - Cafetera North Elevation
CN-1140	Install Metal Railings - Cafetera North Elevation	15	11-Aug-21	31-Aug-21	Install Metal Railings - Cafetera North Elevation
Cafeteria West	t Elevation (CL A.5 to D)				
CW-1000	Frame Canopy - Cafeteria West Elevation	5	11-Dec-20	17-Dec-20	Frame Canopy - Cafeteria West Elevation
CW-1010	Sheath Canopy - Cafeteria West Elevation	5	28-Dec-20	04-Jan-21	Sheath Canopy - Cafeteria West Elevation
CW-1020	Install AVB - Cafeteria West Elevation	5	05-Jan-21	11-Jan-21	Install AVB - Cafeteria West Elevation
CW-1030	Prep Openings & Install Starter Sill for Curtain Wall - Cafeteria West Elevation	5	12-Jan-21	19-Jan-21	Prep Openings & Install Starter Sill for Curtain Wal - Cafeteria West Elevation
CW-1046	Install Curtain Wallover Tracks - Cafeteria West Elevation (Weekend 1)	2	20-Feb-21	21-Feb-21	Install Curtain Wall over Tracks - Cafeteria West Elevation (Weekend 1)
CW-1210	Install Curtain Wallover Tracks - Cafeteria West Elevation (Weekend 2)	2	27-Feb-21	28-Feb-21	Install Curtain Wal over Tracks - Cafeteria West Elevation (Weekend 2)
CW-1040	Install Curtain Wal - Cafeteria West Elevation including White Box (Weekday)	16	03-Mar-21	24-Mar-21	Install Curtain Wal - Cafeteria West Elevation including White Box (Weekday)
CW-1060	Install Stone - Cafeteria West Elevation	2	01-Apr-21	02-Apr-21	I Install Stone - Cafeteria West Elevation
CW-1080	Washdown Masonry - Cafeteria West Elevation	1	05-Apr-21	05-Apr-21	I Washdown Masonry - Cafeeria West Elevation
CW-1180	Install Staging for Upper Canopy - Cafeteria West Elevation	2	26-Apr-21	27-Apr-21	I Install Staging for Upper Canopy - Cafeteria West Elevation
CW-1120	Install Metal Panel System at Upper Canopy - Cafeteria West Elevation	5	24-May-21	28-May-21	
CW-1090	Remove Staging for Upper Canopy - Cafeteria West Elevation	2	01-Jun-21	02-Jun-21	Remove Staging for Upper Canopy - Cafeteria West Elevation
levators	Remove staging for opper sanopy - saletena west Elevation	2	01-0411-21	02-0011-21	
ELEV-1000	Build Elevator Shafts - South	20	15-Oct-20	12-Nov-20	Duild Floyater Chafte, Couth
	Install Elevators - South	60	13-Nov-20	12-N0V-20 11-Feb-21	Build Elevator Shafts - South
ELEV-1010 ELEV-1020	Build Elevator Shaft - North	10	13-1NOV-20 18-Mar-21	31-Mar-21	Build Elevator Shaft - North
		60			
ELEV-1030	Install Elevators - North	60	01-Apr-21	25-Jun-21	Install Elevators - North
MEP Systems		· · - · ·			
MEP-1500	Build Wals - Garden Level Mechanical & Electrical Rooms	15	19-Oct-20	06-Nov-20	+ +
MEP-1510	FRP Equipment Pads - Garden Level Mechanical & Electrical Rooms	5	09-Nov-20	16-Nov-20	FRP Equipment Pads - Garden Level Mechanical & Electrical Rooms
Hot Water					
Garden Leve		1 1			
MEP-2050	Rig & Set Boilers (B-1/2/3) & Expansion Tank (ET-2) - Hot Water System	2	17-Nov-20	18-Nov-20	
MEP-3350	Install Mechanical Piping to Boilers (B-1/2/3) & Expansion Tank (ET-2) - Hot Water System	20	19-Nov-20	18-Dec-20	Install Mechanical Piping to Boilers (B-1/2/3) & Expansion Tank (ET-2) - Hot Water System
MEP-3400	Install Electrical Conduits & Wiring to Boilers (B-1/2/3) & Expansion Tank (ET-2) - Hot Wate	15	21-Dec-20	12-Jan-21	Install Electrical Conduits & Wiring to Boilers (B-1/2/3) & Expansion Tank (ET-2) - Hot Water System
MEP-3360	Install Controls Wiring to Boilers (B-1/2/3) & Expansion Tank (ET-2) - Hot Water System	10	13-Jan-21	27-Jan-21	Install Controls Wiring to Boilers (B-1/2/3) & Expansion Tank (ET-2) - Hot Water System
MEP-3370	Fill, Flush & Treat Piping - Hot Water System	5	28-Jan-21	03-Feb-21	Fill, Flush & Treat Piping - Hot Water System
MEP-3380	Insulate Piping - Hot Water System	20	04-Feb-21	04-Mar-21	Insulate Piping - Hot Water System
MEP-3390	Start-up & Test - Hot Water System	15	17-Feb-21	09-Mar-21	Start-up & Test - Hot Water System
Chilled Water					
Roof					
MEP-2000	Rig & Set Chiller (CH-1) at Roof - Chilled Water System	2	23-Sep-20	24-Sep-20	
MEP-2010	Install Mechanical Piping to Chiller (CH-1) - Chilled Water System	20	25-Sep-20	23-Oct-20	Install Mechanical Piping to Chiller (CH-1) - Chilled Water System
MEP-2020	Install Electrical Conduits & Wiring to Chiller (CH-1) - Chilled Water System	15	26-Oct-20	16-Nov-20	Install Electrical Conduits & Wiring to Chiller (CH-1) - Chilled Water System
MEP-2030	Install Controls Wiring to Chiller (CH-1) - Chilled Water System	10	17-Nov-20	02-Dec-20	Install Controls Wiring to Chiller (CH-1) - Chilled Water System
Garden Level					
MEP-2040	Rig & Set Chilled Water Pumps (GCHWP-1/2/3) & Expansion Tank (ET-1) - Chilled Water 5	2	19-Nov-20	20-Nov-20	■ Rig & Set Chilled Water Pumps (GCHWP-1/2/3) & Expansion Tank (ET-1) - Chilled Water System
MEP-3200	Rig & Set Gycol Feed System (GFT-1) - Chilled Water System	2	23-Nov-20	24-Nov-20	
MEP-3170	Install Mechanical Piping to Chilled Water Pumps (GCHW P-1/2/3) & Expansion Tank (ET-1	20	07-Dec-20	05-Jan-21	Install Mechanical Piping to Chilled Water Pumps (GCHWP-1/2/3) & Expansion Tank (ET-1) - Chilled Water Sys
Remaining	g Level of Effort Remaining Work		Page 15 of 27	7 1	TASK filter: Uncompleted Activities Two Months Prior.
	-				
Actual Lev	Vel of Effort Critical Remaining Work			1	
Actual Lev					© Oracle Corporation



ity ID	ol - Project A - 06Jun20 R1 Schedule Update - 1318014-CR - B27 Activity Name	Remaining	Start	Detailed S	Debug D	
LY ID		Remaining Duration	Start	Pinish	2020 2021	2022
					lun Jul [Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Ja	
MEP-3180	Install Electrical Conduits & Wiring to Chilled Water Pumps (GCHWP-1/2/3) & Expansion Ti	15	29-Dec-20	20-Jan-21	Install Electrical Conduits & Wiring to Chilled Water Pumps	
MEP-3210	Install Mechanical Piping to Glycol Feed System (GFT-1) - Chilled Water System	5	06-Jan-21	12-Jan-21	Install Mechanical Piping to Glycol Feed System (GFT-1) - C	
MEP-3220	Install Electrical Conduits & Wiring to System (GFT-1) - Chilled Water System	5	21-Jan-21	27-Jan-21	Install Electrical Conduits & Wiring to System (GFT-1) - C	1 - 1
MEP-3190	Install Controls Wiring to Chilled Water Pumps (GCHW P-1/2/3) & Expansion Tank (ET-1) -	10	21-Jan-21	03-Feb-21	Install Controls Wiring to Chilled Water Pumps (GCHW F	
MEP-3230	Install Controls Wiring to Gycol Feed System (GFT-1) - Chilled Water System	5	04-Feb-21	10-Feb-21	Install Controls Wiring to Gycol Feed System (GFT-1) -	Chilled Water System
MEP-3320	Fill, Flush & Treat Piping - Chilled Water System	5	11-Feb-21	18-Feb-21	Fill, Flush & Treat Piping - Chilled Water System	
MEP-3330	Insulate Piping - Chilled Water System	20	19-Feb-21	18-Mar-21	Insulate Piping + Chilled Water System	
MEP-3340	Start-up & Test - Chiled Water System	15	05-Mar-21	25-Mar-21	Start-up & Test - Chiled Water System	
Air Handiling						
Garden Level						
AHU-3 (Kitch	nen) & AHU-4 (Cafe/Servery)					
MEP-2060	Rig & Set - AHU-3 (Kitchen) & AHU-4 (Cafe/Servery)	2	25-Nov-20	30-Nov-20	Rig & Set - AHU-3 (Kitchen) & AHU-4 (Cafe/Servery)	
MEP-2070	Install Ductwork Connections - AHU-3 (Kitchen) & AHU-4 (Cafe/Servery)	15	11-Dec-20	04-Jan-21	Install Ductwork Connections - AHU-3 (Kitchen) & AHU-4 (C	
MEP-3410	Install Mechanical Piping Connections - AHU-3 (Kitchen) & AHU-4 (Cafe/Servery)	15	28-Dec-20	19-Jan-21	Install Mechanical Piping Connections - AHU-3 (Kitchen)	
MEP-3420	Install Electrical Conduits & Wiring - AHU-3 (Kitchen) & AHU-4 (Cafe/Servery)	15	12-Jan-21	02-Feb-21	Install Electrical Conduits & Wiring - AHU-3 (Kitchen) & A	
MEP-3430	Install Controls Wiring - AHU-3 (Kitchen) & AHU-4 (Cafe/Servery)	10	03-Feb-21	17-Feb-21	Install Controls Wiring - AHU-3 (Kitchen) & AHU-4 (C	
MEP-3440	Start-up & Test - AHU-3 (Kitchen) & AHU-4 (Cafe/Servery)	5	16-Apr-21	23-Apr-21	Start-up & Test - AHU-3 (Kitchen) & AHU-4	(Cafe/Servery)
Roof						
AHU-5 (Class	s Northeast) & AHU-6 (Class Northwest)					
MEP-3450	Rig & Set - AHU-5 (Class Northeast) & AHU-6 (Class Northwest)	1	25-Sep-20	25-Sep-20	I Rig & Set - AHU-5 (Class Northeast) & AHU-6 (Class Northwest)	
MEP-3460	Install Ductwork Connections - AHU-5 (Class Northeast) & AHU-6 (Class Northwest)	15	28-Sep-20	19-Oct-20	Install Ductwork Connections - AHU-5 (Class Northeast) & AHU-6 (Class	Northwest)
MEP-3470	Install Mechanical Piping Connections - AHU-5 (Class Northeast) & AHU-6 (Class Northwe	15	13-Oct-20	02-Nov-20	Install Mechanical Piping Connections - AHU-5 (Class Northeast) & AHU	J-6 (Class Northwest)
MEP-3480	Install Electrical Conduits & Wiring - AHU-5 (Class Northeast) & AHU-6 (Class Northwest)	15	27-Oct-20	17-Nov-20	Install Electrical Conduits & Wiring - AHU-5 (Class Northeast) & AHU	6 (Class Northwest)
MEP-3490	Install Controls Wiring - AHU-5 (Class Northeast) & AHU-6 (Class Northwest)	10	18-Nov-20	03-Dec-20	Install Controls Wiring - AHU-5 (Class Northeast) & AHU-6 (Class	Northwest)
MEP-3500	Start-up & Test - AHU-5 (Class Northeast) & AHU-6 (Class Northwest)	5	26-Mar-21	01-Apr-21	Start-up & Test - AHU-5 (Class Northeast) & A	HU-6 (Class Northwest)
AHU-7 (Class	s Southeast) & AHU-8 (Class South)					
MEP-3510	Rig & Set - AHU-7 (Class Southeast) & AHU-8 (Class South)	1	28-Sep-20	28-Sep-20	Rig & Set - AHU-7 (Class Southeast) & AHU-8 (Class South)	
MEP-3520	Install Ductwork Connections - AHU-7 (Class Southeast) & AHU-8 (Class South)	15	13-Oct-20	02-Nov-20	Install Ductwork Connections - AHU-7 (Class Southeast) & AHU-8 (Class Southeast)	₃s South)
MEP-3530	Install Mechanical Piping Connections - AHU-7 (Class Southeast) & AHU-8 (Class South)	15	27-Oct-20	17-Nov-20	Install Mechanical Piping Connections - AHU-7 (Class Southeast) & A	HU-8 (Class South)
MEP-3540	Install Electrical Conduits & Wiring - AHU-7 (Class Southeast) & AHU-8 (Class South)	15	10-Nov-20	03-Dec-20	Install Electrical Conduits & Wiring - AHU-7 (Class Southeast) & Al	IU-8 (Class South)
MEP-3550	Install Controls Wiring - AHU-7 (Class Southeast) & AHU-8 (Class South)	10	04-Dec-20	17-Dec-20	Install Controls Wiring - AHU-7 (Class Southeast) & AHU-8 (Class Southeast)	s South)
MEP-3560	Start-up & Test - AHU-7 (Class Southeast) & AHU-8 (Class South)	5	02-Apr-21	08-Apr-21	Start-up & Test - AHU-7 (Class Southeast) &	AHU-8 (Class South)
AHU-1 (White	e Box) & AHU-2 (Library)		· · · ·			
MEP-3570	Rig & Set - AHU-1 (White Box) & AHU-2 (Library)	1	29-Sep-20	29-Sep-20	Rig & Set - AHU-1 (White Box) & AHU-2 (Library)	
MEP-3580	Install Ductwork Connections - AHU-1 (White Box) & AHU-2 (Library)	15	27-Oct-20	17-Nov-20	Install Ductwork Connections - AHU-1 (White Box) & AHU-2 (Library)
MEP-3590	Install Mechanical Piping Connections - AHU-1 (White Box) & AHU-2 (Library)	15	10-Nov-20	03-Dec-20	Install Mechanical Piping Connections - AHU-1 (White Box) & AHU	-2 (Library)
MEP-3600	Install Electrical Conduits & Wiring - AHU-1 (White Box) & AHU-2 (Library)	15	25-Nov-20	17-Dec-20	Install Electrical Conduits & Wiring - AHU-1 (White Box) & AHU-2	
MEP-3610	Install Controls Wiring - AHU-7 (Class Southeast) & AHU-8 (Class South)	10	18-Dec-20	04-Jan-21	Install Controls Wiring - AHU-7 (Class Southeast) & AHU-8 (
MEP-3620	Start-up & Test - AHU-7 (Class Southeast) & AHU-8 (Class South)	5	09-Apr-21	15-Apr-21	Start-up & Test - AHU-7 (Class Southeast) &	
Domestic Wate		·				
MEP-3630	Rig & Set - Domestic Water Heaters (DMH-1/2)	2	25-Nov-20	30-Nov-20	Rig & Set - Domestic Water Heaters (DMH-1/2)	
MEP-3640	Install Plumbing Connections - Domestic Water Heaters (DMH-1/2)	20	01-Dec-20	29-Dec-20	Install Plumbing Connections - Domestic Water Heaters (DMH	- 1/2)
MEP-3650	Test Piping - Domestic Water Heaters (DMH-1/2)	5	26-Feb-21	04-Mar-21	Test Piping - Domestic Water Heaters (DMH-1/2)	
MEP-3660	Insulate Piping - Domestic Water Heaters (DMH-1/2)	15	05-Mar-21	25-Mar-21	Insulate Piping - Domestic Water Heaters (DMF	⊢1/2)
Electrical		·				
Garden Level						
MEP-3240	Install Overhead Conduits & Electrical Panels - Permanent Power	15	17-Nov-20	09-Dec-20	Install Overhead Conduits & Electrical Panels - Permanent Power	
MEP-3250	Rig, Set & Assemble Switchgear - Permanent Power	10	10-Dec-20	23-Dec-20	Rig, Set & Assemble Switchgear - Permanent Power	
MEP-3290	Install Doors & Secure Room - Permanent Power	10	24-Dec-20	08-Jan-21	Install Doors & Secure Room - Permanent Power	
MEP-3260	Wire & Terminate Panels & Switchgear - Permanent Power	20	24-Dec-20	25-Jan-21	Wire & Terminate Panels & Switchgear - Permanent Pow	er
MEP-3270	Pull Conductors & Terminate - Permanent Power	5	26-Jan-21	01-Feb-21	Pull Conductors & Terminate - Permanent Power	·····
MEP-3280	Test Switchgear - Permanent Power	5	02-Feb-21	08-Feb-21	 Test Switchgear - Permanent Power 	
MEP-3300	Energize Switchgear - Permanent Power	5	09-Feb-21	16-Feb-21	 Energize Switchgear - Permanent Power 	
			00100-21	10100-21		

Actual Level
Actual Work

vel of Effort Critical Remaining Work ♦ ♦ Milestone

Page 346 of 377

© Oracle Corporation

rity ID	Activity Name	Remaining	Start	Detailed Finish				
		Duration			2020	2021	2022	
					Jun_Jul_Aug[Sep[Oct[Nov[Dec		ec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov	
MEP-3310	Permanent Power Available	0		16-Feb-21		 Permanent Power Available 		
Interiors				1				
MEP-1000	MEP & Architectural Rough-in - L1	91	22-Sep-20	04-Feb-21		MEP & Architectural Rough-in - L1		
MEP-1010	MEP & Architectural Rough-in - L2	62	06-Oct-20	07-Jan-21		MEP & Architectural Rough-in - L2		
MEP-1040	MEP & Architectural Rough-in - Garden Level	99	19-Oct-20	15-Mar-21		MEP & Architectural Rough-in - Garden Lev	el	
MEP-1020	MEP & Architectural Rough-in - L3	67	21-Oct-20	29-Jan-21		MEP & Architectural Rough-in - L3		
MEP-1030	MEP & Architectural Rough-in - L4	72	04-Nov-20	22-Feb-21		MEP & Architectural Rough-in - L4		
INT-1000	Interior Drywall & Finishes - L1	98	18-Mar-21	05-Aug-21		Interior Drywall & Fi	nishes - L1	
INT-1010	Interior Drywall & Finishes - L2	118	01-Apr-21	17-Sep-21		Interior Dryv	/all & Finishes - L2	
INT-1020	Interior Drywall & Finishes - L3	123	15-Apr-21	08-Oct-21		Interior E	0rywall & Finishes - L3	
INT-1030	Interior Drywall & Finishes - L4	128	30-Apr-21	01-Nov-21		Inter	ior Drywall & Finishes - L4	
INT-1040	Interior Drywall & Finishes - Garden Level	120	14-May-21	03-Nov-21		Inter	ior Drywall & Finishes - Garden Level	
Level 1						1		
L1-1010	Install MEP Risers - L1	10	22-Sep-20	05-Oct-20	Install MEP	Risers - L1		
L1-1000	Install Tube Steel Wall Supports - L1	5	06-Oct-20	13-Oct-20		e Steel Wall Supports - L1		
L1-1020	Rough-in Overhead Ductwork - L1	15	06-Oct-20	27-Oct-20		Overhead Ductwork - L1		
L1-1030	Rough-in Overhead Plumbing - L1	15	06-Oct-20	27-Oct-20	·	1 Overhead Plumbing - L1		
L1-1040	Rough-in Overhead Mechanical Piping - L1	15	14-Oct-20	03-Nov-20	4	in Overhead Mechanical Piping - L1		
L1-1050	Rough-in Overhead Electrical Conduit - L1	20	14-Oct-20	10-Nov-20		r-in Overhead Electrical Conduit - L1		
L1-1060	Frame Electrical Closets - L1	3	28-Oct-20	30-Oct-20		Electrical Closets - L1		
L1-1070	Rough Fire Protection - L1	10	28-Oct-20	10-Nov-20		Fire Protection - L1		
L1-1130	Install Above Ceiling Mechanical Equipment - L1	10	28-Oct-20	10-Nov-20		Above Ceiling Mechanical Equipment - L1		
L1-1130		5	02-Nov-20	06-Nov-20		& Tape Electrical Closets - L1		
	Board & Tape Electrical Closets - L1	5				e Interior Walls - L1		
L1-1090	Frame Interior Wals - L1	10	04-Nov-20	18-Nov-20				
L1-1450	Insulate Overhead Mechanical Piping & HVAC Ductwork - L1	15	04-Nov-20	25-Nov-20		ulate Overhead Mechanical Piping & HVAC Ductwork - L1		
L1-1120	Set Door Frames - L1	5	09-Nov-20	16-Nov-20		boor Frames - L1		
L1-1110	Rough-in Plumbing In-Wall - L1	10	12-Nov-20	25-Nov-20	4	ugh-in Plumbing In-Wall - L1		
L1-1100	Frame Soffits - L1	10	17-Nov-20	02-Dec-20		ame Soffits - L1		
L1-1140	Rough-in Electrical In-Wall & Pull Branch Circuits - L1	15	19-Nov-20	11-Dec-20		Rough-in Electrical In-Wall & Pull Branch Circuits - L1		
L1-1150	Rough-in Low Voltage In-Wall & Pull Wire - L1	15	19-Nov-20	11-Dec-20		ough-in Low Voltage In-Wall & Pull Wire - L1		
L1-1160	Perform Wall & Ceiling Punch List & Inspections - L1	10	11-Dec-20	24-Dec-20		Perform Wall & Ceiling Punch List & Inspections - L1		
L1-1170	Perform In-Wall Inspections with Town - L1	2	14-Dec-20	15-Dec-20		Perform In-Wall Inspections with Town - L1		
L1-1180	Install Wood Blocking - L1	5	16-Dec-20	22-Dec-20		Install Wood Blocking - L1		
L1-1330	Insulate In-Wall Piping - L1	5	16-Dec-20	22-Dec-20		Insulate In-Wall Piping - L1		
L1-1190	Board Walls & Soffits - L1	10	18-Mar-21	31-Mar-21		Board Wals & Soffits - L1		
L1-1210	Tape Walls & Soffits - L1	10	25-Mar-21	07-Apr-21		Tape Walls & Soffits - L1		
L1-3050	Field Measure & Fab Interior Glass - L1	20	25-Mar-21	22-Apr-21		Field Measure & Fab Interior Glass	L1	
L1-1220	Prime & 1st Coat walls - L1	6	08-Apr-21	15-Apr-21		Prime & 1st Coat walls - L1		
L1-1230	Install Ceiling Grid & Cut/DeviceTiles at Classrooms & Offices - L1	10	13-Apr-21	27-Apr-21		Install Ceiling Grid & Cut/DeviceTiles	at Classrooms & Offices - L1	
L1-3060	Install Wall Tile at Corridors - L1	10	13-Apr-21	27-Apr-21		Install Wal Tile at Corridors - L1		
L1-1240	Install MEP Drops at Classrooms & Offices - L1	10	21-Apr-21	04-May-21	1 : :	Install MEP Drops at Classrooms &	Offices - L1	
L1-1250	Install Storefront Frames - L1	10	28-Apr-21	11-May-21		Install Storefront Frames - L1		
L1-1260	Install Millwork at Classrooms & Offices - L1	10	05-May-21	18-May-21	1	Install Millwork at Classrooms &	Offices - L1	
L1-1440	Install Teledata Finishes & Terminations - L1	10	05-May-21	18-May-21	1	Install Teledata Finishes & Termin		
L1-1390	Install Interior Glazing - L1	10	12-May-21	25-May-21	1	Install Interior Glazing - L1		
L1-1445	Install Fintube Radiators - L1	10	12-May-21	25-May-21		Install Fintube Radiators - L1		
L1-1275	Install Simulated Wood Aluminum Ceiling Panel System - L1	15	12-May-21	02-Jun-21		Install Simulated Wood Alumin	Im Ceiling Panel System - I 1	
L1-1273	Install Ceiling Grid & Cut/DeviceTies at Corridors - L1	5	12-May-21 19-May-21	25-May-21	++	Install Ceiling Grid & Cut/Device		
L1-1270	Install Doors & Hardware - L1	5	19-May-21 19-May-21	25-May-21 25-May-21		Install Doors & Hardware - L1		
		10						
L1-1380	Install Flooring at Classrooms & Offices - L1		19-May-21	02-Jun-21		Install Flooring at Classrooms		
L1-1280	Install MEP Drops at Corridors - L1	8	26-May-21	07-Jun-21		Install MEP Drops at Corridor	S-LI	
L1-1285	Install Fintube Covers - L1	10	26-May-21	09-Jun-21	4	Install Fintube Covers - L1	· · · · · · · · · · · · · · · · · · ·	
L1-1430	Install Fire Alarm Devices - L1	5	03-Jun-21	09-Jun-21		Install Fire Alarm Devices - L		

Page 347 of 377

Actual Work

Milestone

	ool - Project A - 06Jun20 R1 Schedule Update - 1318014-CR - B27 Activity Name	Bomaining	Chart	Elmin I-	
ivity ID	Activity Name	Remaining		Finish	2020 2021 2022
		20.000			Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct N
L1-1300	Install Terrazzo at Corridors - L1	20	03-Jun-21	30-Jun-21	Install Terrazzo at Corridors - L1
L1-1360	Install Terrazzo Base at Corridors - L1	10	24-Jun-21	08-Jul-21	Install Terrazzo Base at Corridors - L1
L1-1310	Install Lockers - L1	5	09-Jul-21	15-Jul-21	Install Lockers - L1
L1-1320	Install AV - L1	5	09-Jul-21	15-Jul-21	Install AV - L1
L1-1340	Install Whiteboards & Tack Boards - L1	5	09-Jul-21	15-Jul-21	Install Whiteboards & Tack Boards - L1
L1-1350	Install Window Shades - L1	5	09-Jul-21	15-Jul-21	Install Window Shades - L1
L1-1400	Construction Cleaning - L1	5	16-Jul-21	22-Jul-21	Construction Cleaning - L1
L1-1290	Balance HVAC - L1	5	23-Jul-21	29-Jul-21	Balance ^l HVAC - L1
L1-1410	Skanska Punch List - L1	5	23-Jul-21	29-Jul-21	Skanska Punch List - L1
L1-1420	Architect Punch List - L1	5	30-Jul-21	05-Aug-21	Architect Punch List - L1
Bathrooms					
L1-1600	Board & Install Cement Board - L1 Bathrooms	5	25-Mar-21	31-Mar-21	Board & Install Cement Board - L1 Bathrooms
L1-1605	Tape & Finish - L1 Bathrooms	5	01-Apr-21	07-Apr-21	Tape & Finish - L1 Bathrooms
L1-1610	Prime Paint - L1 Bathrooms	3	01-Apr-21 08-Apr-21	12-Apr-21	Prime Paint - L1 Bathrooms
		2	•		
L1-1615	Install Counters - L1 Bathrooms Install Wall & Floor Tile - L1 Bathrooms	10	13-Apr-21	14-Apr-21	Install Counters - L1 Bathrooms
L1-1620		10	15-Apr-21	29-Apr-21	Install Wal & Floor Tile - L1 Bathrooms
L1-1625	Install Plumbing Fixtures - L1 Bathrooms	5	30-Apr-21	06-May-21	Install Plumbing Fixtures - L1 Bathrooms
L1-1630	Field Measure & Fab Mirrors - L1 Bathrooms	10	30-Apr-21	13-May-21	Field Measure & Fab Mirrors - L1 Bathrooms
L1-1635	Install Toilet Partitions - L1 Bathrooms	4	07-May-21	12-May-21	Install Toilet Partitions - L1 Bathrooms
L1-1640	Install Bathroom Accessories - L1 Bathrooms	4	13-May-21	18-May-21	Install Bathroom Accessories - L1 Bathrooms
L1-1645	Install Mirrors - L1 Bathrooms	2	19-May-21	20-May-21	Install Mirrors - L1 Bathrooms
L1-1650	Finish Paint - L1 Bathrooms	2	21-May-21	24-May-21	Finish Paint - L1 Bathrooms
White Box					
L1WB-1000	Install HSS Tube Steel - L1 White Box	5	28-Oct-20	03-Nov-20	Install HSS Tube Steel - L1 White Box
L1WB-1001	Install Rolling Staging - L1 White Box	5	19-Nov-20	25-Nov-20	Install Rolling Staging - L1 White Box
L1WB-1030	Rough-in MEPs above Sound Barrier Ceiling - L1 White Box	10	30-Nov-20	11-Dec-20	Rough-in MEPs above Sound Barrier Ceiling - L1 White Box
L1WB-1090	Frame Interior Wals - L1 White Box	5	14-Dec-20	18-Dec-20	Frame Interior Wals - L1 White Box
L1WB-1140	Rough-in Electrical In-Wall & Pull Branch Circuits - L1 White Box	5	21-Dec-20	28-Dec-20	Rough-in Electrical In-Wall & Pull Branch Circuits - L1 White Box
L1WB-1150	Rough-in Low Voltage In-Wall & Pull Wire - L1 White Box	5	21-Dec-20	28-Dec-20	■ Rough-in Low Voltage In-Wall & Pull Wire - L1 White Box
L1WB-1170	Perform In-Wall Inspections with Town - L1 White Box	2	29-Dec-20	30-Dec-20	Perform In-Wall Inspections with Town - L1 White Box
L1WB-1180	Install Wood Blocking - L1 White Box	3	31-Dec-20	05-Jan-21	Install Wood Blocking - L1 White Box
L1WB-1190	Board & Tape Walls - L1 White Box	5	01-Apr-21	07-Apr-21	Board & Tape Walls - L1 White Box
L1WB-1210	Install Hangers & Frame Sound Barrier Ceiling - L1 White Box	10	08-Apr-21	22-Apr-21	Install Hangers & Frame Sound Barrier Ceiling - L1 White Box
L1WB-1405	Board & Tape Sound Barrier Ceiling - L1 White Box	5	23-Apr-21	29-Apr-21	Board & Tape Sound Barrier Ceiling - L1 White Box
L1WB-1440	Paint Ceiling - L1 White Box	3	30-Apr-21	04-May-21	Paint Ceiling - L1 White Box
L1WB-1500	Field Measure & Fab Interior Glazing - L1 White Box	25	30-Apr-21	04-Jun-21	Field Measure & Fab Interior Glazing - L1 White Box
L1WB-1450	Install Sound Absorbing 1" Perimeter Metal Ceiling Panels - L1 White Box	5	05-May-21	11-May-21	Install Sound Absorbing 1" Perimeter Metal Ceiling Panels - L1 White Box
L1WB-1425	Install Unistrut & Steel Pipe Grid System - L1 White Box	10	12-May-21	25-May-21	Install Unistrut & Steel Pipe Grid System - L1 White Box
L1WB-1415	Rough-in HVAC Below Sound Barrier Ceiling - L1 White Box	5	26-May-21	02-Jun-21	Rough-in HVAC Below Sound Barrier Ceiling - L1 White Box
L1WB-1413	Install Electical Rough-in Below Sound Barrier Ceiling - L1 White Box	5	03-Jun-21	02-Jun-21	 Install Electical Rough-in Below Sound Barrier Ceiling - L1 White Box
L1WB-1400	Install Metal Strut Channel at Walls - L1 White Box	<u></u> Ω	10-Jun-21	21-Jun-21	Install Metal Strut Channel at Walls - L1 White Box
L1WB-1470		8	15-Jun-21	24-Jun-21	 Install Metal Stutt Chamber at Walks - L1 White Box Install Perforated Plywood Wall Panels - L1 White Box
	Install Perforated Plywood Wall Panels - L1 White Box				
L1WB-1490	Install Wood Sunshade Grille - L1 White Box	8	18-Jun-21	29-Jun-21	Install Wood Sunshade Grille - L1 White Box
L1WB-1430	Install Floor Isolators & Plywood Subfloor - L1 White Box	10	30-Jun-21	14-Jul-21	Install Floor Isolators & Plywood Subfloor - L1 White Box
L1WB-1250	Install Storefront Frames - L1 White Box	5	15-Jul-21	21-Jul-21	Install Storefront Frames - L1 White Box Duild Oraction Dictionary - L4 White Box
L1WB-1510	Build Seating Platforms - L1 White Box	15	15-Jul-21	04-Aug-21	Build Seating Platforms - L1 White Box
L1WB-1390	Install Interior Glazing - L1 White Box	3	22-Jul-21	26-Jul-21	Install Interior Glazing - L1 White Box
L1WB-1530	Install Barn Door - L1 White Box	3	05-Aug-21	09-Aug-21	Install Barn Door - L1 White Box
L1WB-1520	Install Painted 1/4" Hardboard Flooring Panels - L1 White Box	5	10-Aug-21	16-Aug-21	Install Painted 1/4" Hardboard Flooring Panels - L1 White Box
L1WB-1515	Install Light Fixtures & Electrical Finishes - L1 White Box	5	17-Aug-21	23-Aug-21	Install Light Fixtures & Electrical Finishes - L1 White Box
L1WB-1540	Install Black Sharkstooth Scrim - L1 White Box	2	24-Aug-21	25-Aug-21	Install Black Sharkstooth Scrim - L1 White Box
L1WB-1560	Install Projection Screen - L1 White Box	2	26-Aug-21	27-Aug-21	I Install Projection Screen - L1 White Box
L1WB-1590	Install AV Projectors & Speakers - L1 White Box	5	26-Aug-21	01-Sep-21	Install AV Projectors & Speakers + L1 White Box

Remaining Le	evel of Effort	Remaining Work	Page 18 of 27
Actual Level	of Effort	Critical Remaining Work	
Actual Work	•	♦ Milestone	

ivity ID	Activity Name	Remaining	g Start	Finish				
-5		Duration			2020	2021	2022	
	Install White Cyclorama - L1 White Box	2	02.000.01	07.000.01	Jun Jul Aug Sep Oct Nov Dec	Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec J Install White Cyclor		
L1WB-1570 L1WB-1550		3	02-Sep-21	07-Sep-21				
	Install Seating - L1 White Box Install Curtain - L1 White Box		08-Sep-21	10-Sep-21		Install Seating - L1		
L1WB-1580		2	13-Sep-21	14-Sep-21				
L1WB-1400	Construction Cleaning - L1 White Box	2	15-Sep-21	16-Sep-21			ning - L1 White Box	
L1WB-1410	Skanska Punch List - L1 White Box	2	17-Sep-21	20-Sep-21		Skanska Punch I		
L1WB-1420	Architect Punch List - L1 White Box	2	21-Sep-21	22-Sep-21	.	I Architect Punch I	List - L1 White Box	
Cafeteria		05		07.0.1.00	- I			
	Install Intumescent Paint at Columns - L1 Cafeteria	25	22-Sep-20	27-Oct-20		ntumescent Pairit at Columns - L1 Cafeteria		
	Install Rolling Staging - L1 Cafeteria	5	07-Dec-20	11-Dec-20		nstall Rolling Staging - L1 Cafeteria		
	Rough-in Overhead Plumbing - L1 Cafeteria	5	14-Dec-20	18-Dec-20		Rough-in Overhead Plumbing - L1 Cafeteria		
	Rough-in Overhead Ductwork - L1 Cafeteria	10	14-Dec-20	28-Dec-20		Rough-in Overhead Ductwork - L1 Cafeteria		
	Rough-in Overhead Mechanical Piping - L1 Cafeteria	10	21-Dec-20	05-Jan-21	_	Rough-in Overhead Mechanical Piping - L1 Cafeteria		
	Rough-in Overhead Electrical Conduit - L1 Cafeteria	10	29-Dec-20	12-Jan-21		Rough-in Overhead Electrical Conduit - L1 Cafeteria		
	Rough Fire Protection - L1 Cafeteria	5	06-Jan-21	12-Jan-21		Rough Fire Protection - L1 Cafeteria		
	Install Above Ceiling Mechanical Equipment - L1 Cafeteria	5	06-Jan-21	12-Jan-21		Install Above Ceiling Mechanical Equipment - L1 Cafeteria		
	Frame Interior Wals - L1 Cafeteria	5	13-Jan-21	20-Jan-21		Frame Interior Wals - L1 Cafeteria		
	Rough-in Electrical In-Wall - L1 Cafeteria	4	22-Jan-21	27-Jan-21		Rough-in Electrical In-Wall - L1 Cafeteria		
	Perform In-Wall Inspections with Town - L1 Cafeteria	2	28-Jan-21	29-Jan-21		Perform In-Wall Inspections with Town - L1 Cafeteria		
	Perform Wall & Ceiling Punch List & Inspections - L1 Cafeteria	5	29-Jan-21	04-Feb-21		Perform Wall & Ceiling Punch List & Inspections - L1 Ca	feteria	
L1CAFE-1180	Install Wood Blocking - L1 Cafeteria	2	01-Feb-21	02-Feb-21		Install Wood Blocking - L1 Cafeteria		
L1CAFE-1190	Board Wals - L1 Cafeteria	3	06-Apr-21	08-Apr-21		Board Walls - L1 Cafeteria		
L1CAFE-1210	Tape Walls & Soffits - L1 Cafeteria	3	09-Apr-21	13-Apr-21		Tape Walls & Soffits - L1 Cafeteria		
L1CAFE-1220	Prime & First Coat Paint Walls - L1 Cafeteria	3	14-Apr-21	16-Apr-21		Prime & First Coat Paint Walls - L1 Cafeteria	a	
L1CAFE-1110	Install Walls under Library Box - L1 Cafeteria	10	20-Apr-21	03-May-21		🔲 Install Wals under Library Box - L1 Cafet	eria	
L1CAFE-1475	Install Vestibule Storefront - L1 Cafeteria	10	20-Apr-21	03-May-21		Install Vestibule Storefront - L1 Cafeteria		
L1CAFE-1230	Install Ceiling Grid & Cut/DeviceTiles - L1 Cafeteria	15	20-Apr-21	10-May-21		Install Ceiling Grid & Cut/DeviceTies - L	1 Cafeteria	
	Install MEP Drops - L1 Cafeteria	15	27-Apr-21	17-May-21		Install MEP Drops - L1 Cafeteria		
L1CAFE-1485	Install Vestibule Ceiling - L1 Cafeteria	10	04-May-21	17-May-21		Instal Vestibule Ceiling - L1 Cafeteria		
	Install Fire Alarm Devices - L1 Cafeteria	5	11-May-21	17-May-21		Install Fire Alarm Devices - L1 Cafeteri	a	
L1CAFE-1455	Perform Above Ceiling Inspections & Punch List - L1 Cafeteria	5	18-May-21	24-May-21		Perform Above Ceiling Inspections &	Punch List - L1 Cafeteria	
	Install Ceiling Tile - L1 Cafeteria	8	25-May-21	04-Jun-21		Install Ceiling Tile - L1 Cafeteria		
	Remove Rolling Staging - L1 Cafeteria	5	07-Jun-21	11-Jun-21		Remove Rolling Staging - L1 Cafet	eria	
	Install Terrazzo - L1 Cafeteria	20	24-Jun-21	22-Jul-21		Install Terrazzo - L1 Cafeter		
	Install Resin Impregnated Wood Look Panels - L1 Cafeteria	10	23-Jul-21	05-Aug-21			Wood Look Panels - L1 Cafeteria	
	Install Fintube Radiators - L1 Cafeteria	10	23-Jul-21	05-Aug-21		Install Fintube Radiators		
	Install Back Painted Glass - L1 Cafeteria	10	06-Aug-21	19-Aug-21		Install Back Painted GI		
	Install Millwork - L1 Cafeteria	15	06-Aug-21	26-Aug-21		Install Millwork - L1 C		
	Install AV - L1 Cafeteria	5	20-Aug-21	26-Aug-21		Install AV - L1 Cafeter		
	Install Window Shades - L1 Cafeteria	5	27-Aug-21	02-Sep-21		□ Install Window Shad		
	Construction Cleaning - L1 Cafeteria	5	03-Sep-21	10-Sep-21		Gonstruction Clear		
	Balance HVAC - L1 Cafeteria	5	13-Sep-21	17-Sep-21		Balance HVAC + L		
	Skanska Punch List - L1 Cafeteria	5	13-Sep-21	17-Sep-21		Skanska Punch L		
	Architect Punch List - L1 Cafeteria	2	20-Sep-21	21-Sep-21		Architect Punch I		
Servery		<u> </u>	20-0ep-21	21-066-21				
-	Frame Wals - L1 Servery	5	19-Nov-20	25-Nov-20	Era	ame Wals - L1 Servery		
	Rough-in Plumbing In-Wall - L1 Servery	10	30-Nov-20	11-Dec-20		Rough-in Plumbing In-Wall - L1 Servery		
	Rough-in Electrical In-Wall - L1 Servery	5	14-Dec-20	18-Dec-20		Rough-in Electrical In-Wall - L1 Servery		
	Perform In-Wall Inspections with Town & Punch List- L1 Servery	5	29-Jan-21	04-Feb-21	-	 Perform In-Wall Inspections with Town & Punch List- L1 	Servery	
		3	29-Jan-21 05-Feb-21	04-Feb-21 09-Feb-21			Savery	
	Install Wood Blocking - L1 Servery	3				Install Wood Blocking - L1 Servery		
	Board Wals - L1 Servery		01-Apr-21	05-Apr-21	- -	Board Wals - L1 Servery		
	Tape & Finish Walls - L1 Servery	3	06-Apr-21	08-Apr-21		Tape & Finish Walls - L1 Servery		
	Prime Paint & 1st Coat Walls - L1 Servery	3	09-Apr-21	13-Apr-21		Prime Paint & 1st Coat Walls - L1 Servery		
LISERV-1080	Install Ceiling Grid & Cut/Device Tiles - L1 Servery	3	14-Apr-21	16-Apr-21		Install Ceiling Grid & Cut/Device Tiles - L1 S	ervery	

Page 349 of 377

e
Actual Level
Actual Work

Actual Level of Effort

Critical Remaining Work Milestone

TASK filter: Uncompleted Activities Two Months Prior. © Oracle Corporation

	ol - Project A - 06Jun20 R1 Schedule Update - 1318014-CR - B27			Detailed	Schedule Data Date: 06-Jun-20 / Run Date: 09-Jul-20 09:07
vity ID	Activity Name	Remaining Duration	Start	Finish	2020 2021 2022
		Duration			Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct No
L1SERV-1085	Install Simulated Wood Aluminum Ceiling Panels - L1 Servery	6	14-Apr-21	22-Apr-21	Install Simulated Wood Aluminum Ceiling Panels - L1 Servery
L1SERV-1090	Install MEP Drops at Ceiling Grid - L1 Servery	5	20-Apr-21	26-Apr-21	Install MEP Drops at Ceiling Grid - L1 Servery
L1SERV-1100	Above Ceiling Punch List - L1 Servery	5	27-Apr-21	03-May-21	Above Ceiling Punch List - L1 Servery
L1SERV-1110	Install Wall Tile - L1 Servery	10	27-Apr-21	10-May-21	🔲 Install Wal Tile - L1 Servery
L1SERV-1120	Install Epoxy Flooring - L1 Servery	3	11-May-21	13-May-21	Install Epoxy Flooring - L1 Servery
L1SERV-1130	Install Terrazzo Flooring - L1 Servery	5	14-May-21	20-May-21	Install Terrazzo Flooring - L1 Servery
L1SERV-1135	Install Overhead Garage Doros - L1 Servery	2	21-May-21	24-May-21	Install Overhead Garage Doros - L1 Servery
L1SERV-1140	Install Kitchen Equipment - L1 Servery	10	10-Aug-21	23-Aug-21	Install Kitchen Equipment - L1 Servery
	Install Plumbing Connections to Kitchen Equipment - L1 Servery	5	24-Aug-21	30-Aug-21	Install Plumbing Connections to Kitchen Equipment - L1 Servery
	Install Electrical Connections to Kitchen Equipment - L1 Servery	5	27-Aug-21	02-Sep-21	Install Electrical Connections to Kitchen Equipment - L1 Servery
	Install Ceiling Tile - L1 Servery	3	03-Sep-21	08-Sep-21	Install Ceiling Tile - L1 Servery
	Test & Balance HVAC - L1 Servery	3	09-Sep-21	13-Sep-21	Test & Balance HVAC - L1 Servery
	Startup & Test Kitchen/Servery Equipment - L1 Servery	10	09-Sep-21	22-Sep-21	Startup & Test Kitchen/Servery Equipment - L1 Servery
	Board of Health Inspections - L1 Servery	1	26-Oct-21	26-Oct-21	I Board of Health Inspections - L1 Servery
Level 2			20 001 21	20 001 21	
L2-1010	Install MEP Risers - L2	10	06-Oct-20	20-Oct-20	Install MEP Risers - L2
L2-1010	Install Tube Steel Wall Supports - L2	5	21-Oct-20	27-Oct-20	Install Tube Steel Wall Supports - L2
L2-1000	Rough-in Overhead Ductwork - L2	15	21-Oct-20 28-Oct-20	18-Nov-20	Rough-in Overhead Ductwork - L2
L2-1020	Rough-in Overhead Plumbing - L2	15	28-Oct-20	18-Nov-20	Rough-in Overhead Ductwork - L2
L2-1030		15	04-Nov-20	25-Nov-20	Rough-in Overhead Mechanical Piping - L2
	Rough-in Overhead Mechanical Piping - L2	-			Rough-in Overhead Electrical Conduit - L2
L2-1050	Rough-in Overhead Electrical Conduit - L2	20	04-Nov-20	04-Dec-20	
L2-1060	Frame Electrical Closets - L2	3	19-Nov-20	23-Nov-20	Frame Electrical Closets - L2
L2-1070	Rough Fire Protection - L2	10	19-Nov-20	04-Dec-20	Rough Fire Protection - L2
L2-1130	Install Above Ceiling Mechanical Equipment - L2	10	19-Nov-20	04-Dec-20	Install Above Ceiling Mechanical Equipment - L2
L2-1080	Board & Tape Electrical Closets - L2	5	24-Nov-20	02-Dec-20	Board & Tape Electrical Closets - L2
L2-1090	Frame Interior Wals - L2	10	30-Nov-20	11-Dec-20	Frame Interior Wals - L2
L2-1450	Insulate Overhead Mechanical Piping & HVAC Ductwork - L2	15	30-Nov-20	18-Dec-20	Insulate Overhead Mechanical Piping & HVAC Ductwork - L2
L2-1120	Set Door Frames - L2	5	03-Dec-20	09-Dec-20	Set Door Frames - L2
L2-1110	Rough-in Plumbing In-Wall - L2	10	07-Dec-20	18-Dec-20	Rough-in Plumbing In-Wall - L2
L2-1100	Frame Soffits - L2	10	10-Dec-20	23-Dec-20	Frame Soffits - L2
L2-1140	Rough-in Electrical In-Wall & Pull Branch Circuits - L2	15	14-Dec-20	05-Jan-21	Rough-in Electrical In-Wall & Pull Branch Circuits - L2
L2-1150	Rough-in Low Voltage In-Wall & Pull Wire - L2	15	14-Dec-20	05-Jan-21	Rough-in Low Voltage In-Wall & Pull Wire - L2
L2-1160	Perform Wall & Ceiling Punch List & Inspections - L2	10	05-Jan-21	19-Jan-21	Perform Wall & Ceiling Punch List & Inspections - L2
L2-1170	Perform In-Wall Inspections with Town - L2	2	06-Jan-21	07-Jan-21	Perform In-Wall Inspections with Town - L2
L2-1180	Install Wood Blocking - L2	5	08-Jan-21	14-Jan-21	Install Wood Blocking - L2
L2-1330	Insulate In-Wall Piping - L2	5	08-Jan-21	14-Jan-21	Insulate In-Wall Piping - L2
L2-1190	Board Walls & Soffits - L2	10	01-Apr-21	14-Apr-21	Board Walls & Soffits - L2
L2-1210	Tape Walls & Soffits - L2	10	08-Apr-21	22-Apr-21	Tape Walls & Soffits - L2
L2-3050	Field Measure & Fab Interior Glass - L2	20	08-Apr-21	06-May-21	Field Measure & Fab Interior Glass - L2
L2-1220	Prime & 1st Coat walls - L2	6	23-Apr-21	30-Apr-21	Prime & 1st Coat walls - L2
L2-1230	Install Ceiling Grid & Cut/DeviceTiles at Classrooms & Offices - L2	10	28-Apr-21	11-May-21	Install Ceiling Grid & Cut/DeviceTies at Classrooms & Offices - L2
L2-3060	Install Wal Tile at Corridors - L2	10	28-Apr-21	11-May-21	Install Wal Tile at Corridors - L2
L2-1240	Install MEP Drops at Classrooms & Offices - L2	10	05-May-21	18-May-21	Install MEP Drops at Classrooms & Offices - L2
L2-1250	Install Storefront Frames - L2	10	12-May-21	25-May-21	Install Storefront Frames - L2
L2-1260	Install Millwork at Classrooms & Offices - L2	10	19-May-21	02-Jun-21	Install Millwork at Classrooms & Offices - L2
L2-1440	Install Teledata Finishes & Terminations - L2	10	19-May-21	02-Jun-21	Install Teledata Finishes & Terminations - L2
L2-1390	Install Interior Glazing - L2	10	26-May-21	09-Jun-21	Install Interior Glazing - L2
L2-1445	Install Fintube Radiators - L2	10	26-May-21	09-Jun-21	Install Fintube Radiators - L2
L2-1443	Install Ceiling Grid & Cut/DeviceTiles at Corridors - L2	5	03-Jun-21	09-Jun-21	Install Ceiling Grid & Cut/DeviceTies at Corridors - L2
L2-1270	Install Doors & Hardware - L2	5	03-Jun-21	09-Jun-21	Install Doors & Hardware - L2
L2-1370	Install Doors & Hardware - L2 Install Flooring at Classrooms & Offices - L2	10	03-Jun-21	16-Jun-21	 Install Flooring at Classrooms & Offices - L2
L2-1430	Install Fire Alarm Devices - L2	5	10-Jun-21	16-Jun-21	Install Fire Alarm Devices - L2
L2-1280	Install MEP Drops at Corridors - L2	8	10-Jun-21	21-Jun-21	Install MEP Drops at Corridors - L2

Remaining Level of Effort	Remaining Work	Page 20 of 27	TASK filter: Uncompleted Activities Two Months Prior.	
Actual Level of Effort	Critical Remaining Work		© Oracle Corporation	
Actual Work \blacklozenge	♦ Milestone			
		Dee	- 250 - 4 277	

-	ool - Project A - 06Jun20 R1 Schedule Update - 1318014-CR - B27			Detailed Sche	dule Data Date: 06-Jun-20 / Run Date: 09-Jul-20 09:07
vity ID	Activity Name	Remaining Duration	Start	Finish 20	020 2021 2022
		Burduon			Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct N
L2-1285	Install Fintube Covers - L2	10	10-Jun-21	23-Jun-21	Install Fintube Covers - L2
L2-1300	Install Terrazzo at Corridors - L2	20	16-Jul-21	12-Aug-21	Install Terrazzo at Corridors - L2
L2-1360	Install Terrazzo Base at Corridors - L2	10	06-Aug-21	19-Aug-21	Install Terrazzo Base at Corridors - L2
L2-1305	Install Railings at Opening - L2	5	13-Aug-21	19-Aug-21	Install Railings at Opening - L2
L2-1310	Install Lockers - L2	5	20-Aug-21	26-Aug-21	Install Lockers - L2
L2-1320	Install AV - L2	5	20-Aug-21	26-Aug-21	Install AV - L2
L2-1340	Install Whiteboards & Tack Boards - L2	5	20-Aug-21	26-Aug-21	Install Whiteboards & Tack Boards - L2
L2-1350	Install Window Shades - L2	5	20-Aug-21	26-Aug-21	Install Window Shades - L2
L2-1400	Construction Cleaning - L2	5	27-Aug-21	02-Sep-21	Construction Cleaning - L2
L2-1290	Balance HVAC - L2	5	03-Sep-21	10-Sep-21	Balance HVAC - L2
L2-1410	Skanska Punch List - L2	5	03-Sep-21	10-Sep-21	Skanska Punch List - L2
L2-1420	Architect Punch List - L2	5	13-Sep-21	17-Sep-21	Architect Punch List - L2
Bathrooms					
L2-1600	Board & Install Cement Board - L2 Bathrooms	5	01-Apr-21	07-Apr-21	Board & Install Cement Board - L2 Bathrooms
L2-1605	Tape & Finish - L2 Bathrooms	5	08-Apr-21	14-Apr-21	Tape & Finish - L2 Bathrooms
L2-1610	Prime Paint - L2 Bathrooms	3	15-Apr-21	20-Apr-21	Prime Paint - L2 Bathrooms
L2-1615	Install Counters - L2 Bathrooms	2	21-Apr-21	22-Apr-21	I Install Counters - L2 Bathrooms
L2-1620	Install Wall & Floor Tile - L2 Bathrooms	10	30-Apr-21	13-May-21	Install Wal & Floor Tile - L2 Bathrooms
L2-1625	Install Plumbing Fixtures - L2 Bathrooms	5	14-May-21	20-May-21	Install Plumbing Fixtures - L2 Bathrooms
L2-1630	Field Measure & Fab Mirrors - L2 Bathrooms	10	14-May-21	27-May-21	Field Measure & Fab Mirrors - L2 Bathrooms
L2-1635	Install Toilet Partitions - L2 Bathrooms	4	21-May-21	26-May-21	Install Toilet Partitions - L2 Bathrooms
L2-1640	Install Bathroom Accessories - L2 Bathrooms	4	27-May-21	02-Jun-21	Install Bathroom Accessories - L2 Bathrooms
L2-1645	Install Mirrors - L2 Bathrooms	2	03-Jun-21	02-Jun-21	Install Mirrors - L2 Bathrooms
L2-1645	Finish Paint - L2 Bathrooms	2	03-Jun-21 07-Jun-21	04-Jun-21	Finish Paint - L2 Bathrooms
	Filish Paint - LZ Bath Ooms	2	07-Jun-21	00-JUII-21	I FINISH Paint - LZ Baunooms
	Frame Coffin 1.2 Library	10	24 Dec 20	00 lan 01	
L2LIB-1000	Frame Soffits - L2 Library		24-Dec-20	08-Jan-21	Frame Soffits - L2 Library
L2LIB-1010	Install MEP Drops at Soffits - L2 Library	10	11-Jan-21	25-Jan-21	Install MEP Drops at Soffits - L2 Library
L2LIB-1020	Board Wals & Soffits - L2 Library	5	15-Apr-21	22-Apr-21	Board Walls & Soffits - L2 Library
L2LIB-1030	Drywall & Tape Walls & Soffits - L2 Library	5	23-Apr-21	29-Apr-21	Drywall & Tape Walls & Soffits - L2 Library
L2LIB-1050	Prime & 1st Coat Wals & Soffits - L2 Library	5	30-Apr-21	06-May-21	Prime & 1st Coat Walls & Soffits - L2 Library
L2LIB-1040	Field & Measure & Fab Interior Glazing - L2 Library	25	30-Apr-21	04-Jun-21	Field & Measure & Fab Interior Glazing - L2 Library
L2LIB-1060	Install Ceiling Grid & Cut/DeviceTiles - L2 Library	5	07-May-21	13-May-21	□ Install Ceiling Grid & Cut/DeviceTiles - L2 Library
L2LIB-1070	Install MEP Drops at Ceiling Grid - L2 Library	6	14-May-21	21-May-21	Install MEP Drops at Ceiling Grid - L2 Library
L2LIB-1080	Above Ceiling Punch List - L2 Library	5	24-May-21	28-May-21	Above Ceiling Punch List - L2 Library
L2LIB-1090	Install Storefronts - L2 Library	10	07-Jun-21	18-Jun-21	Install Storefronts - L2 Library
L2LIB-1100	Install Interior Glazing - L2 Library	5	21-Jun-21	25-Jun-21	Install Interior Glazing - L2 Library
L2LIB-1105	Install Ceiling Tiles - L2 Library	5	21-Jun-21	25-Jun-21	Install Ceiling Tiles - L2 Library
L2LIB-1210	Install Fintube Radiators - L2 Library	5	28-Jun-21	05-Jul-21	Install Fintube Radiators - L2 Library
L2LIB-1220	Install Electrical Finishes & Hanging Light Fixtures - L2 Library	5	28-Jun-21	05-Jul-21	Install Electrical Finishes & Hanging Light Fixtures - L2 Library
L2LIB-1120	Intall Guardrail in Front of Glass - L2 Library	10	28-Jun-21	12-Jul-21	🔲 Intall Guardrail in Front of Glass - L2 Library
L2LIB-1110	Install Millwork & Shelving - L2 Library	5	13-Jul-21	19-Jul-21	Install Millwork & Shelving - L2 Library
L2LIB-1130	Install Plumbing Fixtures at Library Office - L2 Library	1	20-Jul-21	20-Jul-21	I Install Plumbing Fixtures at Library Office - L2 Library
L2LIB-1230	Install Custom Millwork Barndoor with Glass Panel - L2 Library	3	20-Jul-21	22-Jul-21	Install Custom Millwork Barndoor with Glass Panel - L2 Library
L2LIB-1140	Install Flooring & Base - L2 Library	5	23-Jul-21	29-Jul-21	Install Flooring & Base - L2 Library
L2LIB-1150	Install Fintube Radiator Covers - L2 Library	5	30-Jul-21	05-Aug-21	Install Fintube Radiator Covers - L2 Library
L2LIB-1400	Construction Cleaning - L2 Library	2	06-Aug-21	09-Aug-21	Construction Cleaning - L2 Library
L2LIB-1410	Skanska Punch List - L2 Library	2	10-Aug-21	11-Aug-21	Skanska Punch List - L2 Library
L2LIB-1420	Architect Punch List - L2 Library	2	12-Aug-21	13-Aug-21	Architect Punch List - L2 Library
Level 3		,,		<u> </u>	
L3-1005	Install Intumescent Paint at Physics Classrooms - L3	25	29-Sep-20	03-Nov-20	Install Intumescent Paint at Physics Classrooms - L3
L3-1010	Install MEP Risers - L3	10	21-Oct-20	03-Nov-20	Install MEP Risers - L3
L3-1000	Install Tube Steel Wall Supports - L3	5	04-Nov-20	10-Nov-20	Install Tube Steel Wall Supports - L3
L0-1000		5	54-1107-20	10-1107-20	

 Remaining Level of Effort		Remaining Work	Page 21 of 27	TASK filter: Uncompleted Activities Two Months Prior.	
Actual Level of Effort		Critical Remaining Work		© Oracle Corporation	1
Actual Work	•	♦ Milestone			
			Pac	e 351 of 377	

	hool - Project A - 06Jun20 R1 Schedule Update - 1318014-CR - B27	Demoiring	Ctart	Detailed	Schedule Data Date: 06-Jun-20 / Run Date: 09-Jul-20 09:07
tivity ID	Activity Name	Remaining Duration	Start	Finish	2020 2021 2022
					Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov
L3-1030	Rough-in Overhead Plumbing - L3	15	19-Nov-20	11-Dec-20	Rough-in Overhead Plumbing - L3
L3-1040	Rough-in Overhead Mechanical Piping - L3	15	30-Nov-20	18-Dec-20	Rough-in Overhead Mechanical Piping - L3
L3-1050	Rough-in Overhead Electrical Conduit - L3	20	30-Nov-20	28-Dec-20	Rough-in Overhead Electrical Conduit - L3
L3-1060	Frame Electrical Closets - L3	3	14-Dec-20	16-Dec-20	Frame Electrical Closets - L3
L3-1070	Rough Fire Protection - L3	10	14-Dec-20	28-Dec-20	Rough Fire Protection - L3
L3-1130	Install Above Ceiling Mechanical Equipment - L3	10	14-Dec-20	28-Dec-20	Install Above Ceiling Mechanical Equipment - L3
L3-1080	Board & Tape Electrical Closets - L3	5	17-Dec-20	23-Dec-20	Board & Tape Electrical Closets - L3
L3-1090	Frame Interior Walls - L3	10	21-Dec-20	05-Jan-21	Frame Interior Walls - L3
L3-1450	Insulate Overhead Mechanical Piping & HVAC Ductwork - L3	15	21-Dec-20	12-Jan-21	Insulate Overhead Mechanical Piping & HVAC Ductwork - L3
L3-1120	Set Door Frames - L3	5	24-Dec-20	31-Dec-20	Set Door Frames - L3
L3-1110	Rough-in Plumbing In-Wall - L3	10	29-Dec-20	12-Jan-21	Rough-in Plumbing In-Wall - L3
L3-1100	Frame Soffits - L3	10	04-Jan-21	15-Jan-21	Frame Soffits - L3
L3-1140	Rough-in Electrical In-Wall & Pull Branch Circuits - L3	15	06-Jan-21	27-Jan-21	Rough-in Electrical In-Wall & Pull Branch Circuits - L3
L3-1150	Rough-in Low Voltage In-Wall & Pull Wire - L3	15	06-Jan-21	27-Jan-21	Rough-in Low Voltage In-Wall & Pull Wire - L3
L3-1160	Perform Wall & Ceiling Punch List & Inspections - L3	10	27-Jan-21	09-Feb-21	Perform Wall & Ceiling Punch List & Inspections - L3
L3-1170	Perform In-Wall Inspections with Town - L3	2	28-Jan-21	29-Jan-21	Perform In-Wall Inspections with Town - L3
L3-1180	Install Wood Blocking - L3	5	01-Feb-21	05-Feb-21	Install Wood Blocking - L3
L3-1330	Insulate In-Wall Piping - L3	5	01-Feb-21	05-Feb-21	Insulate In-Wall Piping - L3
L3-1335	Install Steel Tube Grid at Physics Classrooms - L3	20	18-Mar-21	14-Apr-21	Install Steel Tube Grid at Physics Classrooms - L3
L3-1190	Board Wals & Soffits - L3	10	15-Apr-21	29-Apr-21	Board Wals & Soffits - L3
L3-1210	Tape Walls & Soffits - L3	10	23-Apr-21	06-May-21	Tape Walls & Soffits - 43
L3-3050	Field Measure & Fab Interior Glass - L3	20	23-Apr-21	20-May-21	Field Measure & Fab Interior Glass - L3
L3-1220	Prime & 1st Coat walls - L3	6	07-May-21	14-May-21	Prime & 1st Coat walls - L3
L3-1220	Install Ceiling Grid & Cut/DeviceTiles at Classrooms & Offices - L3	10	12-May-21	25-May-21	Install Ceiling Grid & Cut/DeviceTies at Classrooms & Offices - L3
L3-3060	Install Wall Tile at Corridors - L3	10	12-May-21	25-May-21	Install Wal Tile at Corridors - L3
L3-1240	Install MEP Drops at Classrooms & Offices - L3	10	12-May-21	02-Jun-21	Install MEP Drops at Classrooms & Offices - L3
			•		Install Storefront Frames - L3
L3-1250 L3-1260	Install Storefront Frames - L3 Install Millwork at Classrooms & Offices - L3	10 10	26-May-21	09-Jun-21 16-Jun-21	Install Storeront Franes - L3
			03-Jun-21		Install Teledata Finishes & Terminations - L3
L3-1440	Install Teledata Finishes & Terminations - L3	10	03-Jun-21	16-Jun-21	Install Laboratory Casework at Classrooms - L3
L3-3070	Install Laboratory Casework at Classrooms - L3	10	03-Jun-21	16-Jun-21	
L3-1390	Install Interior Glazing - L3	10	10-Jun-21	23-Jun-21	Install Interior Glazing - L3
L3-1445	Install Fintube Radiators - L3	10	10-Jun-21	23-Jun-21	Install Fintube Radiators - L3
L3-1270	Install Ceiling Grid & Cut/DeviceTiles at Corridors - L3	5	17-Jun-21	23-Jun-21	Install Ceiling Grid & Cut/DeviceTies at Corridors - L3
L3-1370	Install Doors & Hardware - L3	5	17-Jun-21	23-Jun-21	Install Doors & Hardware - L3
L3-1380	Install Flooring at Classrooms & Offices - L3	10	17-Jun-21	30-Jun-21	Install Flooring at Classrooms & Offices - L3
L3-1375	Install Garage Doors at Physics Classrooms - L3	3	24-Jun-21	28-Jun-21	Install Garage Doors at Physics Classrooms - L3
L3-1430	Install Fire Alarm Devices - L3	5	24-Jun-21	30-Jun-21	Install Fire Alarm Devices - L3
L3-1280	Install MEP Drops at Corridors - L3	8	24-Jun-21	06-Jul-21	Install MEP Drops at Corridors - L3
L3-1285	Install Fintube Covers - L3	10	24-Jun-21	08-Jul-21	Install Fintube Covers - L3
L3-1300	Install Terrazzo at Corridors - L3	20	06-Aug-21	02-Sep-21	Install Terrazzo at Corridors - L3
L3-1360	Install Terrazzo Base at Corridors - L3	10	27-Aug-21	10-Sep-21	Install Terrazzo Base at Corridors - L3
L3-1310	Install Lockers - L3	5	13-Sep-21	17-Sep-21	Install Lockers + L3
L3-1320	Install AV - L3	5	13-Sep-21	17-Sep-21	Install AV - L3
L3-1340	Install Whiteboards & Tack Boards - L3	5	13-Sep-21	17-Sep-21	Install Whiteboards & Tack Boards - L3
L3-1350	Install Window Shades - L3	5	13-Sep-21	17-Sep-21	Install Window Shades - L3
L3-1400	Construction Cleaning - L3	5	20-Sep-21	24-Sep-21	Construction Cleaning - L3
L3-1290	Balance HVAC - L3	5	27-Sep-21	01-Oct-21	Balance HVAC - L3
L3-1410	Skanska Punch List - L3	5	27-Sep-21	01-Oct-21	Skanska Purich List - L3
L3-1420	Architect Punch List - L3	5	04-Oct-21	08-Oct-21	Architect Punch List - L3
Bathrooms					
L3-1600	Board & Install Cement Board - L3 Bathrooms	5	15-Apr-21	22-Apr-21	Board & Install Cement Board - L3 Bathrooms
L3-1605	Tape & Finish - L3 Bathrooms	5	23-Apr-21	29-Apr-21	Tape & Finish - L3 Bathrooms
L3-1610	Prime Paint - L3 Bathrooms	3	30-Apr-21	04-May-21	Prime Paint - L3 Bathrooms

Remaining Level of Effort	Remaining Work	Page 22 of 27	TASK filter: Uncompleted Activities Two Months Prior.
Actual Level of Effort	Critical Remaining Work		© Oracle Corporation
Actual Work	♦ Milestone		
		Pad	e 352 of 377

	hool - Project A - 06Jun20 R1 Schedule Update - 1318014-CR - B27			Detailed	Schedule Data Date: 06-Jun-20 / Run Date: 09-Jul-20 09:07
tivity ID	Activity Name	Remaining Duration	Start	Finish	2020 2021 2022
10.4045					Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov
L3-1615	Install Counters - L3 Bathrooms	2	05-May-21	06-May-21	I Install Counters - L3 Bathrooms
L3-1620	Install Wal & Floor Tile - L3 Bathrooms	10	14-May-21	27-May-21	Install Wal & Floor Tile - L3 Bathrooms
L3-1625	Install Plumbing Fixtures - L3 Bathrooms	5	28-May-21	04-Jun-21	Install Plumbing Fixtures - L3 Bathrooms
L3-1630	Field Measure & Fab Mirrors - L3 Bathrooms	10	28-May-21	11-Jun-21	Field Measure & Fab Mirrors - L3 Bathrooms
L3-1635	Install Toilet Partitions - L3 Bathrooms	4	07-Jun-21	10-Jun-21	Install Toilet Partitions - L3 Bathrooms
L3-1640	Install Bathroom Accessories - L3 Bathrooms	4	11-Jun-21	16-Jun-21	Install Bathroom Accessories - L3 Bathrooms
L3-1645	Install Mirrors - L3 Bathrooms	2	17-Jun-21	18-Jun-21	Install Mirrors - L3 Bathrooms
L3-1650	Finish Paint - L3 Bathrooms	2	21-Jun-21	22-Jun-21	Finish Paint - L'3 Bathrooms
Level 4					
L4-1005	Install Intumescent Paint at Physics Classrooms - L4	25	28-Oct-20	04-Dec-20	Install Intumescent Paint at Physics Classrooms - L4
L4-1010	Install MEP Risers - L4	10	04-Nov-20	18-Nov-20	Install MEP Risers - L4
L4-1000	Install Tube Steel Wall Supports - L4	5	19-Nov-20	25-Nov-20	Install Tube Steel Wall Supports - L4
L4-1020	Rough-in Overhead Ductwork - L4	15	14-Dec-20	05-Jan-21	Rough-in Overhead Ductwork - L4
L4-1020	Rough-in Overhead Plumbing - L4	15	14-Dec-20	05-Jan-21	Rough-in Overhead Plumbing - L4
					Rough-in Overhead Plumbling - L4
L4-1040	Rough-in Overhead Mechanical Piping - L4	15	21-Dec-20	12-Jan-21	
L4-1050	Rough-in Overhead Electrical Conduit - L4	20	21-Dec-20	20-Jan-21	Rough-in Overhead Electrical Conduit - L4
L4-1060	Frame Electrical Closets - L4	3	06-Jan-21	08-Jan-21	Frame Electrical Closets - L4
L4-1070	Rough Fire Protection - L4	10	06-Jan-21	20-Jan-21	Rough Fire Protection - L4
L4-1130	Install Above Ceiling Mechanical Equipment - L4	10	06-Jan-21	20-Jan-21	Install Above Ceiling Mechanical Equipment - L4
L4-1080	Board & Tape Electrical Closets - L4	5	11-Jan-21	15-Jan-21	Board & Tape Electrical Closets - L4
L4-1090	Frame Interior Wals - L4	10	13-Jan-21	27-Jan-21	Frame Interior Wals - L4
L4-1450	Insulate Overhead Mechanical Piping & HVAC Ductwork - L4	15	13-Jan-21	03-Feb-21	Insulate Overhead Mechanical Piping & HVAC Ductwork - L4
L4-1120	Set Door Frames - L4	5	19-Jan-21	25-Jan-21	Set Door Frames - L4
L4-1110	Rough-in Plumbing In-Wall - L4	10	21-Jan-21	03-Feb-21	Rough-in Plumbing In-Wall - L4
L4-1100	Frame Soffits - L4	10	26-Jan-21	08-Feb-21	Frame Soffits - L4
L4-1140	Rough-in Electrical In-Wall & Pull Branch Circuits - L4	15	28-Jan-21	18-Feb-21	Rough-in Electrical In-Wall & Pull Branch Circuits - L4
L4-1150	Rough-in Low Voltage In-Wall & Pull Wire - L4	15	28-Jan-21	18-Feb-21	Rough-in Low Voltage In-Wall & Pull Wire - L4
L4-1160	Perform Wall & Ceiling Punch List & Inspections - L4	10	18-Feb-21	03-Mar-21	Perform Wall & Ceiling Punch List & Inspections - L4
L4-1170	Perform In-Wall Inspections with Town - L4	2	19-Feb-21	22-Feb-21	Perform In-Wall Inspections with Town - L4
L4-1180		Z	23-Feb-21	01-Mar-21	 Install Wood Blocking - L4
	Install Wood Blocking - L4	5			
L4-1330	Insulate In-Wall Piping - L4	5	23-Feb-21	01-Mar-21	Insulate In-Wall Piping - L4
L4-1335	Install Steel Tube Grid at Physics Classrooms - L4	20	08-Apr-21	06-May-21	Install Steel Tube Grid at Physics Classrooms - L4
L4-1190	Board Wals & Soffits - L4	10	30-Apr-21	13-May-21	Board Walls & Soffits - L4
L4-1210	Tape Walls & Soffits - L4	10	07-May-21	20-May-21	Tape Walls & Soffits - L4
L4-3050	Field Measure & Fab Interior Glass - L4	20	07-May-21	04-Jun-21	Field Measure & Fab Interior Glass - L4
L4-1220	Prime & 1st Coat Wals & Exposed Ceilings - L4	6	21-May-21	28-May-21	Prime & 1st Coat Wals & Exposed Ceilings - L4
L4-1230	Install Ceiling Grid & Cut/DeviceTiles at Classrooms & Offices - L4	10	26-May-21	09-Jun-21	Install Ceiling Grid & Cut/DeviceTies at Classrooms & Offices - L4
L4-3060	Install Wall Tile at Corridors - L4	10	26-May-21	09-Jun-21	Install Wal Tile at Corridors - L4
L4-1240	Install MEP Drops at Classrooms & Offices - L4	10	03-Jun-21	16-Jun-21	Install MEP Drops at Classrooms & Offices - L4
L4-1250	Install Storefront Frames - L4	10	10-Jun-21	23-Jun-21	Install Storefront Frames - L4
L4-1260	Install Millwork at Classrooms & Offices - L4	10	17-Jun-21	30-Jun-21	Install Millwork at Classrooms & Offices - L4
L4-1440	Install Teledata Finishes & Terminations - L4	10	17-Jun-21	30-Jun-21	■ Install Teledata Finishes & Terminations - L4
L4-3070	Install Laboratory Casework at Classrooms - L4	10	17-Jun-21	30-Jun-21	 Install Laboratory Casework at Classrooms - L4
L4-1390	Install Interior Glazing - L4	10	24-Jun-21	08-Jul-21	Install Interior Glazing - L4
		5			**
L4-1270	Install Ceiling Grid & Cut/DeviceTiles at Corridors - L4		01-Jul-21	08-Jul-21	Install Ceiling Grid & Cut/DeviceTiles at Corridors - L4
L4-1370	Install Doors & Hardware - L4	5	01-Jul-21	08-Jul-21	Install Doors & Hardware - L4
L4-1375	Install Garage Doors at Physics Classrooms - L3	3	09-Jul-21	13-Jul-21	Install Garage Doors at Physics Classrooms - L3
L4-1430	Install Fire Alarm Devices - L4	5	09-Jul-21	15-Jul-21	Install Fire Alarm Devices + L4
L4-1280	Install MEP Drops at Corridors - L4	8	09-Jul-21	20-Jul-21	Install MEP Drops at Corridors - L4
L4-1445	Install Fintube Radiators - L4	10	09-Jul-21	22-Jul-21	Install Fintube Radiators + L4
L4-1380	Install Flooring at Classrooms & Offices - L4	10	16-Jul-21	29-Jul-21	Install Flooring at Classrooms & Offices - L4
L4-1285	Install Fintube Covers - L4	10	23-Jul-21	05-Aug-21	Install Fintube Covers + L4
L4-1300	Install Terrazzo at Corridors - L4	20	27-Aug-21	24-Sep-21	Install Terrazzo at Corridors - L4

Remaining Level of Effort		Remaining Work	Page 23 of 27	TASK filter: Uncompleted Activities Two Months Prior.	
Actual Level of Effort		Critical Remaining Work		© Oracle Corporation	1
Actual Work	•	♦ Milestone			1
			Pad	e 353 of 377	

ivity ID	Activity Name	Remaining	Start	Detailed Finish	
		Duration	Start	FINIST	2020 2021 2022
					Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct N
L4-1360	Install Terrazzo Base at Corridors - L4	10	20-Sep-21	01-Oct-21	Install Terrazzo Base at Corridors - L4
L4-1305	Install Railings at Openings - L2	10	27-Sep-21	08-Oct-21	Install Railings at Openings - L2
L4-1310	Install Lockers - L4	5	04-Oct-21	08-Oct-21	Install Lockers - L4
L4-1320	Install AV - L4	5	04-Oct-21	08-Oct-21	InstallAV - L4
L4-1340	Install Whiteboards & Tack Boards - L4	5	04-Oct-21	08-Oct-21	Install Whiteboards & Tack Boards - L4
L4-1350	Install Window Shades - L4	5	04-Oct-21	08-Oct-21	Install Window Shades - L4
L4-1400	Construction Cleaning - L4	5	12-Oct-21	18-Oct-21	Construction Cleaning - L4
L4-1290	Balance HVAC - L4	5	19-Oct-21	25-Oct-21	Balance HVAC - L4
L4-1410	Skanska Punch List - L4	5	19-Oct-21	25-Oct-21	Skanska Punch List - L4
L4-1420	Architect Punch List - L4	5	26-Oct-21	01-Nov-21	Architect Punch List - L4
Bathrooms					
L4-1600	Board & Install Cement Board - L4 Bathrooms	5	30-Apr-21	06-May-21	Board & Install Cement Board - L4 Bathrooms
L4-1605	Tape & Finish - L4 Bathrooms	5	07-May-21	13-May-21	Tape & Finish - L4 Bathrooms
L4-1610	Prime Paint - L4 Bathrooms	3	14-May-21	18-May-21	Prime Paint - L4 Bathrooms
L4-1615	Install Counters - L4 Bathrooms	2	•	20-May-21	Install Counters - L4 Bathrooms
			19-May-21		
L4-1620	Install Wal & Floor Tile - L4 Bathrooms	10	28-May-21	11-Jun-21	Install Wal & Floor Tile - L4 Bathrooms
L4-1625	Install Plumbing Fixtures - L4 Bathrooms	5	14-Jun-21	18-Jun-21	Install Plumbing Fixtures - L4 Bathrooms
L4-1630	Field Measure & Fab Mirrors - L4 Bathrooms	10	14-Jun-21	25-Jun-21	Field Measure & Fab Mirrors + L4 Bathrooms
L4-1635	Install Toilet Partitions - L4 Bathrooms	4	21-Jun-21	24-Jun-21	Install Toilet Partitions - L4 Bathrooms
L4-1640	Install Bathroom Accessories - L4 Bathrooms	4	25-Jun-21	30-Jun-21	Install Bathroom Accessories - L4 Bathrooms
L4-1645	Install Mirrors - L4 Bathrooms	2	01-Jul-21	05-Jul-21	Install Mirrors - L4 Bathrooms
L4-1650	Finish Paint - L4 Bathrooms	2	06-Jul-21	07-Jul-21	Finish Paint - L4 Bathrooms
Garden Level					
G-1010	Install MEP Risers - Garden Level	10	19-Oct-20	30-Oct-20	Install MEP Risers - Garden Level
G-1005	Install CMU Walls - Garden Level	30	02-Nov-20	16-Dec-20	Install CMU Walls - Garden Level
G-1000	Install Tube Steel Wall Supports - Garden Level	5	17-Dec-20	23-Dec-20	Install Tube Steel Wall Supports - Garden Level
G-1020	Rough-in Overhead Ductwork - Garden Level	15	06-Jan-21	27-Jan-21	Rough-in Overhead Ductwork - Garden Level
G-1030	Rough-in Overhead Plumbing - Garden Level	15	06-Jan-21	27-Jan-21	Rough-in Overhead Plumbing - Garden Level
G-1040	Rough-in Overhead Mechanical Piping - Garden Level	15	13-Jan-21	03-Feb-21	Rough-in Overhead Mechanical Piping - Garden Level
G-1050	Rough-in Overhead Electrical Conduit - Garden Level	20	13-Jan-21	10-Feb-21	Rough-in Overhead Electrical Conduit - Garden Level
G-1060	Frame Electrical Closets - Garden Level	3	28-Jan-21	01-Feb-21	Frame Electrical Closets - Garden Level
G-1070	Rough Fire Protection - Garden Level	10	28-Jan-21	10-Feb-21	Rough Fire Protection - Garden Level
G-1130	Install Above Ceiling Mechanical Equipment - Garden Level	10	28-Jan-21	10-Feb-21	Install Above Ceiling Mechanical Equipment - Garden Level
G-1080	Board & Tape Electrical Closets - Garden Level	5	02-Feb-21	08-Feb-21	Board & Tape Electrical Closets - Garden Level
G-1090	Frame Interior Walls - Garden Level	10	04-Feb-21	18-Feb-21	Frame Interior Wals - Garden Level
G-1450	Insulate Overhead Mechanical Piping & HVAC Ductwork - Garden Level	15	04-Feb-21	25-Feb-21	Insulate Overhead Mechanical Piping & HVAC Ductwork - Garden Level
G-1120	Set Door Frames - Garden Level	5	09-Feb-21	16-Feb-21	Set Door Frames - Garden Level
G-1110	Rough-in Plumbing In-Wall - Garden Level	10	11-Feb-21	25-Feb-21	Rough-in Plumbing In-Wall - Garden Level
G-1100	Frame Soffits - Garden Level	10	17-Feb-21	02-Mar-21	Frame Soffits - Garden Level
G-1140	Rough-in Electrical In-Wall & Pull Branch Circuits - Garden Level	15	19-Feb-21	11-Mar-21	Rough-in Electrical In-Wall & Pull Branch Circuits - Garden Level
G-1150	Rough-in Low Voltage In-Wall & Pull Wire - Garden Level	15	19-Feb-21	11-Mar-21	Rough-in Low Voltage In-Wall & Pull Wire - Garden Level
G-1160	Perform Wall & Ceiling Punch List & Inspections - Garden Level	10	11-Mar-21	24-Mar-21	Perform Wall & Ceiling Punch List & Inspections - Garden Level
G-1170	Perform In-Wall Inspections with Town - Garden Level	2	12-Mar-21	15-Mar-21	Perform In-Wall Inspections with Town - Garden Level
G-1180	Install Wood Blocking - Garden Level	5	16-Mar-21	22-Mar-21	Install Wood Blocking - Garden Level
G-1330	Insulate In-Wall Piping - Garden Level	5	16-Mar-21	22-Mar-21	Insulate In-Wall Piping - Garden Level
G-1190	Board Walls & Soffits - Garden Level	5	14-May-21	20-May-21	Board Wals & Soffits - Garden Level
G-1210	Tape Walls & Soffits - Garden Level	5	21-May-21	27-May-21	Tape Walls & Soffits - Garden Level
G-3050	Field Measure & Fab Interior Glass - Garden Level	20	21-May-21 21-May-21	18-Jun-21	Field Measure & Fab Interior Glass - Garden Level
G-1220	Prime & 1st Coat walls - Garden Level	3		02-Jun-21	Prime & 1st Coat walls - Garden Level
			28-May-21		
G-1230	Install Ceiling Grid & Cut/DeviceTles at Classrooms & Offices - Garden Level	5	10-Jun-21	16-Jun-21	Install Ceiling Grid & Cut/DeviceTies at Classrooms & Offices - Garden Level
G-1240	Install MEP Drops at Classrooms & Offices - Garden Level	5	17-Jun-21	23-Jun-21	Install MEP Drops at Classrooms & Offices - Garden Level
G-1250	Install Storefront Frames - Garden Level	5	24-Jun-21	30-Jun-21	Install Storefront Frames - Garden Level
G-1440	Install Teledata Finishes & Terminations - Garden Level	5	24-Jun-21	30-Jun-21	Install Teledata Finishes & Terminations - Garden Level

Remaining Level of Effort	Remaining Work	Page 24 of 27	TASK filter: Uncompleted Activities Two Months Prior.	
Actual Level of Effort	Critical Remaining Work		© Oracle Corporation	
Actual Work \blacklozenge	♦ Milestone			
		Pad	e 354 of 377	

-	ool - Project A - 06Jun20 R1 Schedule Update - 1318014-CR - B27	Domaining	Ctort	Linich	
ity ID	Activity Name	Remaining Duration	Start	Finish	2020 2021 2022
					Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct No
G-1260	Install Millwork at Classrooms & Offices - Garden Level	5	01-Jul-21	08-Jul-21	Install Millwork at Classrooms & Offices - Garden Level
G-1370	Install Doors & Hardware - Garden Level	2	09-Jul-21	12-Jul-21	Install Doors & Hardware - Garden Level
G-1270	Install Ceiling Grid & Cut/DeviceTiles at Corridors - Garden Level	3	09-Jul-21	13-Jul-21	Install Ceiling Grid & Cut/DeviceTies at Corridors - Garden Level
G-1390	Install Interior Glazing - Garden Level	5	09-Jul-21	15-Jul-21	Install Interior Glazing - Garden Level
G-1445	Install Fintube Radiators - Garden Level	5	09-Jul-21	15-Jul-21	Install Fintube Radiators - Garden Level
G-1430	Install Fire Alarm Devices - Garden Level	3	16-Jul-21	20-Jul-21	Install Fire Alarm Devices - Garden Level
G-1280	Install MEP Drops at Corridors - Garden Level	4	21-Jul-21	26-Jul-21	Install MEP Drops at Corridors - Garden Level
G-1380	Install Flooring at Classrooms & Offices - Garden Level	4	30-Jul-21	04-Aug-21	 Install Flooring at Classrooms & Offices - Garden Level
G-1385	Install Fintube Covers - Garden Level	5			 Install Fintube Covers - Garden Level Install Fintube Covers - Garden Level
		5	05-Aug-21	11-Aug-21	
G-1300	Install Flooring at Corridors - Garden Level	5	12-Aug-21	18-Aug-21	Install Flooring at Corridors - Garden Level
G-1360	Install Base at Corridors - Garden Level	3	19-Aug-21	23-Aug-21	Install Base at Corridors - Garden Level
G-1310	Install Lockers - Garden Level	3	12-Oct-21	14-Oct-21	Install Lockers - Garden Level
G-1320	Install AV - Garden Level	3	12-Oct-21	14-Oct-21	I Install AV - Garden Lev el
G-1340	Install Whiteboards & Tack Boards - Garden Level	3	12-Oct-21	14-Oct-21	Install Whiteboards & Tack Boards - Garden Level
G-1350	Install Window Shades - Garden Level	3	12-Oct-21	14-Oct-21	Install Window Shades - Garden Level
G-1400	Construction Cleaning - Garden Level	3	15-Oct-21	19-Oct-21	Construction Cleaning - Garden Level
G-1290	Balance HVAC - Garden Level	3	20-Oct-21	22-Oct-21	Balance HVAC - Garden Level
G-1410	Skanska Punch List - Garden Level	3	20-Oct-21	22-Oct-21	Skanska Punch List - Garden Level
G-1420	Architect Punch List - Garden Level	2	02-Nov-21	03-Nov-21	Architect Punch List - Garden Level
Kitchen				1	
G-1675	Prime & First Coat Paint - Garden Level Kitchen	5	28-May-21	04-Jun-21	Prime & First Coat Paint - Garden Level Kitchen
G-1685	Install Epoxy Flooring - Garden Level Kitchen	10	07-Jun-21	18-Jun-21	Install Epoxy Flooring - Garden Level Kitchen
		5			
G-1705	Install FRP at Walls - Garden Level Kitchen	5	21-Jun-21	25-Jun-21	Install FRP at Walls - Garden Level Kitchen
G-1695	Install Walk-in Cooler/Freezer - Garden Level Kitchen	5	28-Jun-21	05-Jul-21	Install Walk-in Cooler/Freezer - Garden Level Kitchen
G-1715	Install Kitchen Hoods - Garden Level Kitchen	5	28-Jun-21*	05-Jul-21	Install Kitchen Hoods - Garden Level Kitchen
G-1725	Install Ansul System - Garden Level Kitchen	5	06-Jul-21	12-Jul-21	Install Ansul System - Garden Level Kitchen
G-1735	Install Ceiling Grid & Boarder/Device Tiles - Garden Level Kitchen	5	13-Jul-21	19-Jul-21	Install Ceiling Grid & Boarder/Device Tiles - Garden Level Kitchen
G-1745	Install MEP Drops at Celing Grid - Garden Level Kitchen	5	20-Jul-21	26-Jul-21	Install MEP Drops at Celling Grid - Garden Level Kitchen
G-1755	Above Ceiling Punch List - Garden Level Kitchen	5	27-Jul-21	02-Aug-21	Above Ceiling Punch List - Garden Level Kitchen
G-1765	Install Kitchen Equipment - Garden Level Kitchen	15	27-Jul-21	16-Aug-21	Instal Kitchen Equipment - Garden Level Kitchen
G-1775	Install Plumbing Connections to Kitchen Equipment - Garden Level Kitchen	5	17-Aug-21	23-Aug-21	Install Plumbing Connections to Kitchen Equipment - Garden Level Kitcher
G-1785	Install Electrical Connections to Kitchen Equipment - Garden Level Kitchen	5	20-Aug-21	26-Aug-21	Install Electrical Connections to Kitchen Equipment - Garden Level Kitche
G-1787	Start-up & Test Kitchen Hoods - Garden Level Kitchen	5	27-Aug-21	02-Sep-21	Start-up & Test Kitchen Hoods - Garden Level Kitchen
G-1795	Install Ceiling Tile - Garden Level Kitchen	3	03-Sep-21	08-Sep-21	Install Ceiling Tile - Garden Level Kitchen
G-1815	Startup & Test Kitchen Equipment - Garden Level Kitchen	15	09-Sep-21	29-Sep-21	Startup & Test Kitchen Equipment - Garden Level Kitchen
G-1825	Balance HVAC - Garden Level Kitchen	3	20-Oct-21	22-Oct-21	Balance HVAC - Garden Level Kitchen
G-1835	Board of Health Inspections - Garden Level Kitchen	1	25-Oct-21	25-Oct-21	Board of Health Inspections - Garden Level Kitchen
	Board of Health Inspections - Oarden Lever Nichen	I	25-001-21	23-001-21	T Doard of freakin inspections - Oarden Level Nichen
Bathrooms	Deard & Install Compart Deard - Conden Lavel Datherson	0	01 May 01	05 Mar 04	
G-1600	Board & Install Cement Board - Garden Level Bathrooms	3	21-May-21	25-May-21	Board & Install Cement Board - Garden Level Bathrooms
G-1605	Tape & Finish - Garden Level Bathrooms	3	26-May-21	28-May-21	Tape & Finish - Garden Level Bathrooms
G-1610	Prime Paint - Garden Level Bathrooms	1	01-Jun-21	01-Jun-21	I Prime Paint - Garden Level Bathrooms
G-1615	Install Counters - Garden Level Bathrooms	1	02-Jun-21	02-Jun-21	I Install Counters - Garden Level Bathrooms
G-1620	Install Wall & Floor Tile - Garden Level Bathrooms	5	14-Jun-21	18-Jun-21	Install Wal & Floor Tile - Garden Level Bathrooms
G-1625	Install Plumbing Fixtures - Garden Level Bathrooms	3	21-Jun-21	23-Jun-21	Install Plumbing Fixtures - Garden Level Bathrooms
G-1630	Field Measure & Fab Mirrors - Garden Level Bathrooms	10	21-Jun-21	05-Jul-21	Field Measure & Fab Mirrors - Garden Level Bathrooms
G-1635	Install Toilet Partitions - Garden Level Bathrooms	2	25-Jun-21	28-Jun-21	Install Toilet Partitions - Garden Level Bathrooms
G-1640	Install Bathroom Accessories - Garden Level Bathrooms	2	29-Jun-21	30-Jun-21	Install Bathroom Accessories - Garden Level Bathrooms
G-1645	Install Mirrors - Garden Level Bathrooms	1	06-Jul-21	06-Jul-21	I Install Mirror's - Garden Level Bathrooms
G-1650	Finish Paint - Garden Level Bathrooms	1	07-Jul-21	07-Jul-21	I Finish Paint - Garden Level Bathrooms
Stair Finishes					
Stair 1			44.5	40.0	
ST1-1000	Frame Wals - Stair 1	5	14-Dec-20	18-Dec-20	D Frame Wals - Stair 1
ST1-1010	Rough-in In-Wall Electric - Stair 1	3	21-Dec-20	23-Dec-20	Rough-in In-Wall Electric - Stair 1

Page 355 of 377

Actual Work

Milestone

Data Date: 06-Jun-20 / Run	Date: 09-Jul-20 09:07



-	ol - Project A - 06Jun20 R1 Schedule Update - 1318014-CR - B27				d Schedule			Data Date: 06-Jun-20 / Run D	ate. 09-Jui-20 09:07
vity ID	Activity Name	Remaining Duration	Start	Finish	2020	2	021	202	2
		Durution			Jun Jul Aug Sep Oct Nov Dec				
ST1-1020	Board Walls - Stair 1	3	15-Apr-21	20-Apr-21		Board W			
ST1-1030	Tape & Finish Walls - Stair 1	4	21-Apr-21	26-Apr-21		Tape & I	inish Walls - Stair 1		
ST1-1040	Prime Paint Walls & Stairs - Stair 1	3	27-Apr-21	29-Apr-21		Prime F	aint Walls & Stairs - Stair 1		
ST1-1050	Install Tile Walls - Stair 1	5	04-May-21	10-May-21		Instal	Tile Walls - Stair 1		
ST1-1100	Install Wood Wall Panels - Stair 1	10	11-May-21	24-May-21		📕 🔲 Inst	all Wood Wall Panels - Stair 1		
ST1-1060	Install Wall Raings - Stair 1	3	25-May-21	27-May-21		l Ins	tall Wall Raings - Stair 1		
ST1-1070	Finish Paint Stairs - Stair 1	2	28-May-21	01-Jun-21			nish Paint Stairs - Stair 1		
ST1-1090	Install Terrazzo Treads - Stair 1	5	02-Jun-21	08-Jun-21			hstall Terrazzo Treads - Stair 1		1
Stair 2									
ST2-1000	Frame Wals - Stair 2	15	21-Dec-20	12-Jan-21		Frame Wals - Stair 2			
ST2-1010	Rough-in In-Wall Electric - Stair 2	5	13-Jan-21	20-Jan-21		Rough-in In-Wall Electric	- Stair 2		
ST2-1020	Board Wals - Stair 2	10	30-Apr-21	13-May-21			Walls - Stair 2		1
ST2-1020	Tape & Finish Walls - Stair 2	10	14-May-21	27-May-21		1	be & Finish Walls - Stair 2		1 1 1
	•						rime Paint Walls & Stairs - Stair		
ST2-1040	Prime Paint Walls & Stairs - Stair 2	5	28-May-21	04-Jun-21		1	1 1	4	
ST2-1050	Install Tile Walls - Stair 2	20	07-Jun-21	05-Jul-21	4	¦	Install Tile Walls - Stair 2	. <u>.</u>	
ST2-1060	Install Wall Raings - Stair 2	10	06-Jul-21	19-Jul-21			Install Wal Raings - Stai		
ST2-1070	Paint Railings & Finish Paint Stairs - Stair 2	5	20-Jul-21	26-Jul-21			Paint Railings & Finish P	1 1 1	
ST2-1080	Install Light Fixtures - Stair 2	2	27-Jul-21	28-Jul-21			Install Light Fixtures - S		1 1 1
ST2-1090	Install Rubber Flooring - Stair 2	10	29-Jul-21	11-Aug-21			Install Rubber Floorin	g - Stair 2	
Stair 3						İ			
ST3-1000	Frame Wals - Stair 3	15	13-Jan-21	03-Feb-21		Frame Wals - Stair 3			
ST3-1010	Rough-in In-Wall Electric - Stair 3	5	04-Feb-21	10-Feb-21		Rough-in In-Wall Ele	ctric - Stair 3		
ST3-1020	Board Walls - Stair 3	10	14-May-21	27-May-21		Bo	ard Walls - Stair 3		
ST3-1030	Tape & Finish Walls - Stair 3	10	28-May-21	11-Jun-21		i 🗖 -	Tape & Finish Walls - Stair 3		
ST3-1040	Prime Paint Walls & Stairs - Stair 3	5	14-Jun-21	18-Jun-21		•	Prime Paint Walls & Stairs - St	ar 3	
ST3-1050	Install Tile Walls - Stair 3	20	06-Jul-21	02-Aug-21			Install Tile Walls - Stair		
ST3-1060	Install Wal Raings - Stair 3	10	03-Aug-21	16-Aug-21			Install Wal Raings -	1	
ST3-1000	Paint Railings & Finish Paint Stairs - Stair 3	5	17-Aug-21	23-Aug-21				ish Paint Stairs - Stair 3	
	Install Light Fixtures - Stair 3		-	-			Install Light Fixture		
ST3-1080		2	24-Aug-21	25-Aug-21					
ST3-1090	Install Rubber Flooring - Stair 3	10	26-Aug-21	09-Sep-21			Install Rubber FI	ooring - Stair 3	
Stair 6/7							~ -		
ST6/7-1000	Frame Wals - Stair 6/7	15	04-Feb-21	25-Feb-21		Frame Wals - Sta	1 1		
ST6/7-1010	Rough-in In-Wall Electric - Stair 6/7	5	26-Feb-21			Rough-in In-Wall	· ·		
ST6/7-1020	Board Walls - Stair 6/7	8	28-May-21	09-Jun-21			Board Walls - Stair 6/7		
ST6/7-1030	Tape & Finish Walls - Stair 6/7	8	10-Jun-21	21-Jun-21			Tape & Finish Walls - Stair 6/7		
ST6/7-1040	Prime Paint Walls & Stairs - Stair 6/7	4	22-Jun-21	25-Jun-21			Prime Paint Walls & Stairs - S	U	
ST6/7-1050	Install Tile Walls - Stair 6/7	15	03-Aug-21	23-Aug-21			Install Tile Walls - S	1 1	
ST6/7-1060	Install Wall Railings - Stair 6/7	8	24-Aug-21	02-Sep-21			Install Wal Raing	s - Stair 6/7	
ST6/7-1070	Paint Railings & Finish Paint Stairs - Stair 6/7	4	03-Sep-21	09-Sep-21			Paint Railings &	Finish Paint Stairs - Stair 6/7	
ST6/7-1080	Install Light Fixtures - Stair 6/7	2	10-Sep-21	13-Sep-21			Install Light Fixt	ures - Stair 6/7	- 1 1
ST6/7-1090	Install Linoleum Flooring - Stair 6/7	8	14-Sep-21	23-Sep-21			Install Linoleur	n Flooring - Stair 6/7	
General		· · · · ·							1 1 1
GEN-1000	Install Building Signage	15	27-Sep-21	18-Oct-21			install Rui	ding Signage	1
Commissioning		10	2. 000-21	10 00[-2]					
COMM-1000		00	20 500 01	20 Dec 21					
	Commission MEPs	60	30-Sep-21	29-Dec-21		 		Commission MEPs	
Hardscapes &		ii							1 1 1
EXT-6010	Remove Temp Poles from Park	9	12-Apr-21*	23-Apr-21		Remove	Temp Poles from Park		
EXT-6000	Install Hardscapes & Landscaping	80	03-Jun-21*	24-Sep-21			Install Hardsc	apes & Landscaping	
Final Testing, In	nspections & Occupancy								
Plumbing Syste	tem								1
LSI-1160	Perform Potable Water Chlorination	5	31-Aug-21	07-Sep-21			Perform Potable	Water Chlorination	<u>-</u>
LSI-1220	Issue Potable Water Chlorination Report	0	<u> </u>	07-Sep-21	1		1	ater Chlorination Report	
Water & Sewer	•								
							<u>; </u>		1
Remaining	Level of Effort Remaining Work		Page 26 of 27	7	TASK filter: Uncompleted Activities	Two Months Prior.			
Actual Leve	rel of Effort Critical Remaining Work					© Oracle C	orporation	SKANSK	
Actual Wor	-							JCANJC	
		1							

Brookline High Sch	nool - Project A - 06Jun20 R1 Schedule Update - 1318014-CR - B27			Detailed	Schedule	Data Date: 06-Jun-20 / Run Date: 09-Jul-20 (
ivity ID	Activity Name	Remaining	Start	Finish		
		Duration			2020	2021 2022
LSI-1240	Acquire GSA Permit	1	08-Sep-21	08-Sep-21		Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep O I Acquire GSA Permit
	•	<u> </u>	06-Sep-21	06-Sep-21		T Acquire GSA Permit
BDA Testing			44.004	44.0 04		
LSI-1330	Test Bi-Directional Amplifier	1	14-Sep-21	14-Sep-21		I Test Bi-Directional Amplifier
	Power System & Power Outage Testing	0		40.0 04		
LSI-1140	Ceilings, Lights & Exit Signs Complete	0		13-Sep-21		◆ ¢eilings, Lights & Exit Signs Complete
LSI-1250	Pre-test for Lights Out Testing	1	14-Sep-21	14-Sep-21		Pre-test for Lights Out Testing
LSI-1300	Correct Issues for Brookline Lights Out Testing	2	15-Sep-21	16-Sep-21		Correct Issues for Brookline Lights Out Testing
LSI-1320	Perform Lights Out Testing with Brookline	1	17-Sep-21	17-Sep-21		Perform Lights Out Testing with Brookline
Fire Alarm Sy						
LSI-1030	Test Fire Alarm - Garden Level Devices, Speakers & Duct Smokes	2	10-Sep-21	13-Sep-21		Test Fire Alarm - Garden Level Devices, Speakers & Duct Smol
LSI-1060	NFPA 72 Fire Alarm Testing	9	10-Sep-21	22-Sep-21		NFPA 72 Fire Alarm Testing
LSI-1070	Test Fire Alarm - L1 Devices, Speakers & Duct Smokes	2	14-Sep-21	15-Sep-21		Ⅰ Test Fire Alarm L1 Devices, Speakers & Duct Smokes
LSI-1090	Test Fire Alarm - L2 Devices, Speakers & Duct Smokes	2	16-Sep-21	17-Sep-21		Test Fire Alarm - L2 Devices, Speakers & Duct Smokes
LSI-1110	Test Fire Alarm - L3 Devices, Speakers & Duct Smokes	2	20-Sep-21	21-Sep-21		Test Fire Alarm - L3 Devices, Speakers & Duct Smokes
LSI-1260	Test Fire Alarm - L4 Speakers & Duct Smokes	1	22-Sep-21	22-Sep-21		I Test Fire Alarm - L4 Speakers & Duct Smokes
LSI-1370	Submit Record of Completion (ROC) to Brookline	5	24-Sep-21	30-Sep-21		Submit Record of Completion (ROC) to Brookline
LSI-1420	Brookline ROC NFPA 72 Test	3	01-Oct-21	05-Oct-21		Brookline ROC NFPA 72 Test
Elevators						
LSI-1310	Preliminary Test Elevator with Fire Alarm Recall	3	20-Sep-21	22-Sep-21		Preliminary Test Elevator with Fire Alarm Recall
LSI-1390	Complete Elevator Cleaning & Adjustment for Inspection	10	23-Sep-21	06-Oct-21		Complete Elevator Cleaning & Adjustment for Inspection
LSI-1470	Complete Phone Service to Elevators	0		06-Oct-21		Complete Phone Service to Elevators
LSI-1480	State (Mass 524) Inspection & Signoff	3	07-Oct-21	12-Oct-21		State (Mass 524) Inspection & Signoff
Fire Protection	on System					
LSI-1000	Flow Test Fire Protection System	5	14-Sep-21	20-Sep-21		Flow Test Fire Protection System
LSI-1020	Checkout Tampers & Flows	1	21-Sep-21	21-Sep-21		I Checkout Tampers & Flows
LSI-1350	Test Stand Pipe & Floor Control Valves with PRVs - Stair 2	2	22-Sep-21	23-Sep-21		Test Stand Pipe & Floor Control Valves with PRVs - Stair 2
LSI-1520	Test Stand Pipe & Floor Control Valves with PRVs - Stair 3	2	24-Sep-21	27-Sep-21		Test Stand Pipe & Floor Control Valves with PRVs - Stair 3
LSI-1450	Brookline Fire Protection Test	1	06-Oct-21	06-Oct-21		Brookline Fire Protection Test
Final Inspect	tions & C of O					
LSI-1230	Final Plumbing Signoff	1	08-Sep-21	08-Sep-21		I Final Plumbing Signoff
LSI-1340	Final Electrical Signoff	1	20-Sep-21	20-Sep-21		Final Electrical Signoff
INSP-1030	Owner Install FF&E	10	27-Sep-21	08-Oct-21		Owner Install FF&E
LSI-1490	Final Life Safety Walk-thru	2	26-Oct-21	27-Oct-21		I Final Life Safety Wak-thru
LSI-1460	Receive Final Architectural, Mechanical & Structural Affadavits	2	04-Nov-21	05-Nov-21		Receive Final Architectural, Mechanical & Structural Af
INSP-1010	Final Building Sigh Off Acquire C of O	5	08-Nov-21	15-Nov-21		■ Final Building Sigh Off Acquire C of Ø
INSP-1020	Substantial Completion - Project A: 111 Cypress Street	0	201101 21	15-Nov-21*		 Substantial Completion - Project A: 111 Cypress Stre

Remaining Level of Effort Remaining Work	Page 27 of 27	TASK filter: Uncompleted Activities Two Months Prior.
Actual Level of Effort Critical Remaining Work		© Oracle Corporation
Actual Work		
	Pac	e 357 of 377



-	nool - Project C - 06Jun20 R1 Schedule Update - 1318015-CR				iled Schedule		Data Date: 06-Jun-20 / Run Date: 09-Jul-20 08:50
ivity ID	Activity Name	Remaining Duration	Start	Finish	2020	2021	2022
		2 41 44 611			Jun Jul Aug Sep Oct Nov Dec		Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov De
Brookline H	High School - Project C - 06Jun20 R1 Schedule Update						
Executive S	Summary						
EXEC-1070	Bid Period	20	04 Mar 10 A	10 Jul 20	Bid Period		
		28	04-Mar-19 A	16-Jul-20	Bid Period	Construction Device t	Demo Deherte Mirty & Duild New CTEM Ming
EXEC-1060	Construction Project C - Demo Roberts Wing & Build New STEM Wing	270	21-Aug-19 A	07-Jul-21			Demo Roberts Wing & Build New STEM Wing
EXEC-1320	Construction Project C - Owner Install FF&E New STEM Wing	10	27-May-21	10-Jun-21		Construction Project C - Own	
EXEC-1310	Summary - STEM Interim Completion Date	0		07-Jul-21		◆ Summary - STEM Interim	
Work Order	r Milestones						
EXEC-1390	Last Day for STEM Fire, Water & Sewer Service Installation	0		30-Jun-20	 Last Day for STEM Fire, Wa 	ter & Sewer Service Installation	
BHS Acade	emic Calendar						
BHS-1050	Last Day of School - 2019/2020	0		22-Jun-20*	◆ Last Day of School - 2019/202	on	
BHS-1060	First Day of School - 2020/2021	0		03-Sep-20*	♦ First Day of School		
BHS-1070	December Break - 2020	8	25-Dec-20*	01-Jan-21*		December Break - 2020	
BHS-1080	February Break - 2021	5	15-Feb-21*	19-Feb-21*		February Break - 2021	
BHS-1090	April Break - 2021	5	19-Apr-21*	23-Apr-21*		April Break - 2021	
BHS-1100	Last Day of School - 2020/2021	0	19-Apr-21	23-Apr-21*		■ April Diear - 2021 ◆ Last Day of School - 2020/2	2021
BHS-1110	First Day of School - 2021//2022	0		02-Sep-21*		◆ Last Day of Settloor - 2020/2	
		0		02-3ep-21			1001 - 2021//2022
	econstruction Phase						
GMP (Project	t C Only)						
PRE-1180	Review & Execute - GMP	20	16-Mar-20 A	06-Jul-20	Review & Execute - GMP		
PRE-1190	Agreement Executed - GMP	0		06-Jul-20	 Agreement Executed - GMF 		
Procureme	nt	· · · · ·					
Design Assis							
	Design Assist						
PRO-1460	Fab & Available for Delivery - Curtain Wall	11	29-Jan-20 A	22-Jun-20	Fab & Available for Delivery - (Curtain vvali	
	rocurement Post CDs (Trade Contractors)				.		
	rade Contractor)						
PRO-4700	Fab/Deliver Equipment - Plumbing Fixtures	32	04-May-20 A	22-Jul-20	Fab/Deliver Equipment -	Plumbing Fixtures	
HVAC (Trade							
PRO-2200	Fab/Deliver Equipment - HVAC RTUs	18	04-Feb-20 A		Fab/Deliver Equipment - HV		
PRO-2220	Fab/Deliver Equipment - Air Cooled Chiller	50	04-Feb-20 A	17-Aug-20	Fab/Deliver Equipme	eht - Air Cooled Chiller	
PRO-4820	Fab/Deliver Equipment - HVAC Exhaust Fans	50			Fab/Deliver Equipme		
PRO-4870	Fab/Deliver Equipment - HVAC Pumps	18	07-Mar-20 A		Fab/Deliver Equipment - HV		
PRO-2190	Fab/Deliver Equipment - HVAC VRF Units	50	11-May-20 A	17-Aug-20	Fab/Deliver Equipme	ent - HVAC VRF Units	
Electrical & C	Communications (Trade Contractor)						
PRO-2320	Fab/Deliver Equipment - Interior Lighting	49	02-Apr-20 A	14-Aug-20	Fab/Deliver Equipme	nt - Interior Lighting	
Masonry (Trac	ade Contractor)						
PRO-2010	Fab & Available for Delivery - Masonry (Brick)	5	06-Jan-20 A	12-Jun-20	Eab & Available for Delivery - M	asonry (Brick)	
Building AVB	3 & Caulking (Trade Contractor)						
PRO-2560	Fab & Available for Delivery - Building AVB & Caulking	5	02-Mar-20 A	12-Jun-20	Fab & Available for Delivery - Bu	uilding AVB & Caulking	
Roofing & Fla	lashing (Trade Contractor)						
PRO-2590	Subcontractor Issue Submittals - Roofing Metal Flashing & Trim	5	18-May-20 A	12-Jun-20	Subcontractor Issue Submittals	- Roofing Metal Flashing & Trim	
PRO-2600	Subcontractor Issue Submittals - Membrane Roofing	5	18-May-20 A		Subcontractor Issue Submittals		
PRO-2610	A/E Review & Approve Submittals - Roofing Metal Flashing & Trim	0	15-Jun-20	15-Jun-20		als - Roofing Metal Flashing & Trim	
PRO-2620	A/E Review & Approve Submittals - Membrane Roofing	15	15-Jun-20	06-Jul-20	A/E Review & Approve Sub		
PRO-2640	Fab & Available for Delivery - Roofing Metal Flashing & Trim	25	15-Jun-20*	20-Jul-20		ery - Roofing Metal Flashing & Trim	
PRO-2630	Fab & Available for Delivery - Membrane Roofing	20	07-Jul-20*	03-Aug-20	Fab & Available for Del		······································
	de Contractor)						
PRO-7220	A/E Review & Approve Submittals - Painting	10	29-May-20 A	19-Jun-20	A/E Review & Approve Submit	tals - Painting	
PRO-7210	Fab & Available for Delivery - Painting	10	01-Jul-20*	15-Jul-20	Fab & Available for Deliver		
	s & Glazing (Trade Contractor)					· ·······	
PRO-2700	A/E Review & Approve Submittals - Interior Glass Mirrors	5	27-Dec-19A	12-Jun-20	Á/E Review & Approve Submitta	als - Interior Glass Mirrors	
PRO-2690	A/E Review & Approve Submittals - Interior Glass	15	08-Jun-20		A/E Review & Approve Submitte		
1110 2000				20 001-20			
Remainin	ng Level of Effort Remaining Work		Page 1 of	14	TASK filter: % Complete <100.		
Actual Le	evel of Effort Critical Remaining Work		-			© Oracle Corporation	CVANCVA
Actual W	-			Page	e 358 of 377	.	SKANSKA
				9	1	I	

-	ol - Project C - 06Jun20 R1 Schedule Update - 1318015-CR	Domaining	Start	Deta Finish	
ty ID	Activity Name	Remaining Duration	Start	FINIST	2020 2021
					Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug
PRO-2720	Fab & Available for Delivery - Interior Glass	40	01-Oct-20*	01-Dec-20	
PRO-2710	Fab & Available for Delivery - Interior Glass Mirrors	25	13-Oct-20*	17-Nov-20	Fab & Available for Delivery - Interior Glass Mirr
Tile (Trade Cor					
PRO-2760	A/E Review & Approve Submittals - Ceramic Tile	10	01-Jun-20 A	19-Jun-20	
PRO-2770	Fab & Available for Delivery - Ceramic Tile	50	22-Jun-20	31-Aug-20	Fab & Available for Delivery - Ceramic Tile
Terrazzo (Trad					
PRO-5300	A/E Review & Approve Submittals - Terrazzo	19	04-May-20 A	02-Jul-20	A/E Review & Approve Submittals - Terrazzo
PRO-5310	Fab & Available for Delivery - Terrazzo	30	06-Jul-20	14-Aug-20	Fab & Available for Delivery - Terrazzo
Acoustical Cei	ling Tile (Trade Contractor)				
PRO-2810	Subcontractor Issue Submittals - Acoustical Metal Panels	11	07-Nov-19A	22-Jun-20	
PRO-2840	Fab & Available for Delivery - ACT	1	12-May-20 A	08-Jun-20	
PRO-2830	A/E Review & Approve Submittals - Acoustical Metal Panels	15	23-Jun-20	14-Jul-20	A/E Review & Approve Submittals - Acoustical Metal Panels
PRO-2850	Fab & Available for Delivery - Acoustical Metal Panels	40	15-Jul-20	09-Sep-20	Fab & Available for Delivery - Acoustical Metal Panels
Resilient Floor	ring (Trade Contractor)				
PRO-2890	A/E Review & Approve Submittals - Resilient Flooring	10	01-Jun-20 A	19-Jun-20	A/E Review & Approve Submittals - Resilient Flooring
PRO-2900	Fab & Available for Delivery - Resilient Flooring	30	22-Jun-20	03-Aug-20	Fab & Available for Delivery - Resilient Flooring
emaining Pro	ocurement Post CDs (Subcontractors)				
	And Hardware				
PRO-3310	Fab & Available for Delivery - Interior Wood Doors	40	23-Mar-20 A	03-Aug-20	Fab & Available for Delivery - Interior Wood Doors
PRO-3320	Fab & Available for Delivery - Door Hardware	45	02-Apr-20 A	10-Aug-20	
Millwork & Fini			017.p. 2077	10 / kug _0	
PRO-3370	Execute Contract - Millwork & Finish Carpentry (Submittals & Shops Only)	5	29-May-20 A	12-Jun-20	Execute Contract - Millwork & Finish Carpentry (Submittals & Shops Only)
PRO-3380	Subcontractor Issue Submittals - Millwork Display Cases	19	29-May-20 A	02-Jul-20	Subcontractor Issue Submittals - Millwork Display Cases
PRO-3390	Subcontractor Issue Submittals - Millwork Wood Benches	19	29-May-20 A	02-Jul-20	Subcontractor Issue Submittals - Millwork Wood Benches
PRO-3400	Subcontractor Issue Submittals - Millwork Countertops	19	29-May-20 A	02-Jul-20	Subcontractor Issue Submittals - Millwork Countertops
PRO-3410	Subcontractor Issue Submittals - Millwork Wood Veneer Casework	19	29-May-20 A	02-Jul-20	Subcontractor Issue Submittals - Millwork Wood Veneer Casework
PRO-3420	Subcontractor Issue Submittals - Millwork Plastic Laminate Casework	19	29-May-20 A	02-Jul-20	Subcontractor Issue Submittals - Millwork Plastic Laminate Casework
		15	-	24-Jul-20	A/E Review & Approve Submittals - Millwork Display Cases
PRO-3430	A/E Review & Approve Submittals - Millwork Display Cases		06-Jul-20		
PRO-3440	A/E Review & Approve Submittals - Millwork Wood Benches	15	06-Jul-20	24-Jul-20	A/E Review & Approve Submittals - Millwork Wood Benches
PRO-3450	A/E Review & Approve Submittals - Millwork Countertops	15	06-Jul-20	24-Jul-20	A/E Review & Approve Submittals - Millwork Countertops
PRO-3460	A/E Review & Approve Submittals - Millwork Wood Veneer Casework	15	06-Jul-20	24-Jul-20	A/E Review & Approve Submittals - Millwork Wood Veneer Cas ewor
PRO-3470	A/E Review & Approve Submittals - Millwork Plastic Laminate Casework	15	06-Jul-20	24-Jul-20	A/E Review & Approve Submittals - Millwork Plastic Laminate Casew
PRO-3580	Building Commision Final Approval of RTA - Millwork & Finish Carpentry	1	14-Jul-20	14-Jul-20	I Building Commision Final Approval of RTA - Millwork & Finish Carpentr
PRO-3480	Fab & Available for Delivery - Millwork Display Cases	35	27-Jul-20	14-Sep-20	
PRO-3490	Fab & Available for Delivery - Millwork Wood Benches	35	27-Jul-20	14-Sep-20	
PRO-3500	Fab & Available for Delivery - Millwork Wood Veneer Casework	35	27-Jul-20	14-Sep-20	
PRO-3510	Fab & Available for Delivery - Millwork Plastic Laminate Casework	35	27-Jul-20	14-Sep-20	
PRO-3520	Fab & Available for Delivery - Millwork Countertops	40	27-Jul-20	21-Sep-20	Fab & Available for Delivery - Millwork Countertops
Laboratory Ca					
PRO-5370	Subcontractor Issue Submittals - Laboratory Casework	34	29-May-20 A	24-Jul-20	Subcontractor Issue Submittals - Laboratory Casework
PRO-5320	Execute Contract - Laboratory Casework (Submittals & Shops Only)	5	04-Jun-20 A	12-Jun-20	
PRO-5460	Building Commision Final Approval of RTA - Laboratory Casework	1	14-Jul-20	14-Jul-20	I Building Commision Final Approval of RTA - Laboratory Casework
PRO-5360	A/E Review & Approve Submittals - Laboratory Casework	15	27-Jul-20	14-Aug-20	A/E Review & Approve Submittals - Laboratory Casework
PRO-5350	Fab & Available for Delivery - Laboratory Casework	65	17-Aug-20	18-Nov-20	Fab & Available for Delivery - Laboratory Casew
Food Service E	Equipment				
PRO-3570	Subcontractor Issue Submittals - Food Service Equipment	20	01-Jun-20 A	06-Jul-20	Subcontractor Issue Submittals - Food Service Equipment
PRO-3590	Subcontractor Issue Submittals - Hood System (Make Up Air Exhaust)	20	08-Jun-20	06-Jul-20	Subcontractor Issue Submittals - Hood System (Make Up Air Exhaust)
PRO-3600	A/E Review & Approve Submittals - Food Service Equipment	15	07-Jul-20	27-Jul-20	A/E Review & Approve Submittals - Food Service Equipment
PRO-3620	A/E Review & Approve Submittals - Hood System (Make Up Air Exhaust)	15	07-Jul-20	27-Jul-20	A/E Review & Approve Submittals - Hood System (Make Up Air Exh
PRO-3610	Building Commision Final Approval of RTA - Food Service Equipment	1	14-Jul-20	14-Jul-20	I Building Commision Final Approval of RTA - Food Service Equipment
PRO-3630	Fab & Available for Delivery - Hood System (Make Up Air Exhaust)	65	28-Jul-20	28-Oct-20	
PRO-3640	Fab & Available for Delivery - Food Service Equipment	65	28-Jul-20	28-Oct-20	
	rs & Fire Shutters	, 	·		
	Subcontractor Issue Submittals - Overhead Doors & Fire Shutters	20	08-Jun-20*	06-Jul-20	Subcontractor Issue Submittals - Overhead Doors & Fire Shutters
PRO-5440					
PRO-5440	Level of Effort Remaining Work		Der- 0. f	14	TASK filter: 9/ Complete :400
PRO-5440	Level of Effort Remaining Work		Page 2 of	14	TASK filter: % Complete <100. © Oracle Corporati

Data Date: 06-Jun-20 / Run Date: 09-Jul-20 08:50 2022 123 ep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Ian --!----vork ----k ust) Air Exhaust)

SKANSKA

	ol - Project C - 06Jun20 R1 Schedule Update - 1318015-CR	Domaining	Stort	Detai				09-Jul-20 08:50
ity ID	Activity Name	Remaining	Start	Finish	2020	2021	2022	
		Duration					ep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug	Sep Oct Nov
PRO-5430	A/E Review & Approve Submittals - Overhead Doors & Fire Shutters	15	07-Jul-20	27-Jul-20		Ibmittals - Overhead Doors & Fire Shutters		• · • • •
PRO-5420	Fab & Available for Delivery - Overhead Doors & Fire Shutters	65	28-Jul-20	28-Oct-20	Fab & Av	ailable for Delivery - Overhead Doors & Fire	Shutters	
Epoxy Flooring								
PRO-3840	Subcontractor Issue Submittals - Epoxy Flooring	5	05-Feb-20 A	12-Jun-20	Subcontractor Issue Submittals -	Epoxy Elooring		
PRO-3850	A/E Review & Approve Submittals - Epoxy Flooring	10	28-Feb-20 A		A/E Review & Approve Submitt			
PRO-3860	Fab & Available for Delivery - Epoxy Flooring	25	03-Aug-20*	04-Sep-20	Fab & Available for			
Carpet		25	03-Aug-20	04-069-20		Delivery - Lpoxy r looring		
PRO-3910	Subcontractor Issue Submittals - Carpet	19	14-Jan-20 A	02-Jul-20	Subcontractor Issue Submitta	la Carpat		
PRO-3920	A/E Review & Approve Submittals - Carpet	19	06-Jul-20 A	24-Jul-20	A/E Review & Approve Su	• • •		1
PRO-3920 PRO-3930								
	Fab & Available for Delivery - Carpet	40	27-Jul-20*	21-Sep-20	Fab & Available	for Delivery - Carpet		
Site Concrete								
PRO-5950	Bid, Descope & RTA - Site Concrete (Rebid)	30	12-Jun-20*	24-Jul-20	Bid, Descope & RTA - Site			
PRO-5960	Owner Review/Approve RTA - Site Concrete (Rebid)	5	27-Jul-20	31-Jul-20	Owner Review/Approve			
PRO-6850	Building Commission Approves Contract - Site Concrete	1	11-Aug-20*	11-Aug-20		pproves Contract - Site Concrete		
PRO-5540	Award Contract - Site Concrete	2	12-Aug-20	13-Aug-20	Award Contract - Site			
PRO-5530	Execute Contract - Site Concrete	5	14-Aug-20	20-Aug-20	Execute Contract - S			
PRO-5580	Subcontractor Issue Submittals - Site Concrete	15	21-Aug-20	11-Sep-20		sue Submittals - Site Concrete		
PRO-5570	A/E Review & Approve Submittals - Site Concrete	15	14-Sep-20	02-Oct-20	A/E Review &	Approve Submittals - Site Concrete		
PRO-5560	Fab & Available for Delivery - Site Concrete	20	05-Oct-20	02-Nov-20	Fab & Av	ailable for Delivery - Site Concrete		
A/V								
PRO-7300	Subcontractor Issue Submittals - A/V	20	08-Jun-20	06-Jul-20	Subcontractor Issue Submitt	als - A/V		
PRO-7290	A/E Review & Approve Submittals - A/V	15	07-Jul-20	27-Jul-20	A/E Review & Approve Su	ıbmittals - A/V		
PRO-7330	Building Commision Final Approval of RTA - A/V	1	14-Jul-20	14-Jul-20	I Building Commision Final Ap	1 1		
PRO-7280	Fab & Available for Delivery - A/V	20	28-Jul-20	24-Aug-20	Fab & Available for D			
Specialties		20	20 001 20	217 kag 20				
PRO-4120	Subcontractor Issue Submittals - Specialties	20	31-Mar-20 A	06-Jul-20	Subcontractor Issue Submitt	als Specialties		
PRO-4120 PRO-4130	A/E Review & Approve Submittals - Specialties				A/E Review & Approve Su			
PRO-4130 PRO-4140		15	03-Apr-20 A 28-Jul-20*	27-Jul-20				
	Fab & Available for Delivery - Specialties	30	20-Jul-20	08-Sep-20	Fab & Available fo	Delivery - Specialities		
Window Treatn		4	4.4 1.1 00*	44 1-1-00				
PRO-6870	Building Commission Approves Contract - Window Treatments	1	14-Jul-20*	14-Jul-20		ves Contract - Window Treatments		
PRO-4380	Award Contract - Window Treatments	2	15-Jul-20	16-Jul-20	Award Contract - Window			
PRO-4390	Execute Contract - Window Treatments	5	17-Jul-20	23-Jul-20	Execute Contract - Windo	1 I I		
PRO-4400	Subcontractor Issue Submittals - Window Treatments	20	24-Jul-20	20-Aug-20		Submittals - Window Treatments		
PRO-4410	A/E Review & Approve Submittals - Window Treatments	15	21-Aug-20	11-Sep-20	A/E Review & Ap	prove Submittals - Window Treatments		
PRO-4420	Fab & Available for Delivery - Window Treatments	20	01-Oct-20*	29-Oct-20	Fab & Av	ailable for Delivery - Window Treatments		
Signage								
PRO-4470	Subcontractor Issue Submittals - Signage	20	08-Jun-20	06-Jul-20	Subcontractor Issue Submitt	als - Signage		
PRO-4480	A/E Review & Approve Submittals - Signage	15	07-Jul-20	27-Jul-20	🔲 A/E Review & Approve Su	ıbmittals - Signage		
PRO-4490	Fab & Available for Delivery - Signage	40	01-Sep-20*	28-Oct-20	Fab & Av	ailable for Delivery - Signage		
Landscaping								
PRO-6890	Building Commission Approves Contract - Landscaping	1	14-Jul-20*	14-Jul-20	I Building Commission Approv	ves Contract - Landscaping		
PRO-4030	Award Contract - Landscaping	2	15-Jul-20	16-Jul-20	Award Contract - Landscar			
PRO-4040	Execute Contract - Landscaping	5	17-Jul-20	23-Jul-20	Execute Contract - Lands	-		
PRO-4050	Subcontractor Issue Submittals - Landscaping	15	24-Jul-20	13-Aug-20	Subcontractor Issue S			
PRO-4050	A/E Review & Approve Submittals - Landscaping	15	14-Aug-20	03-Sep-20		ove Submittals - Landscaping		
PRO-4000	Fab & Available for Delivery - Landscaping	50	04-Sep-20*	17-Nov-20		Available for Delivery - Landscaping		
		50	0 4 -0ep-20	17-1100-20	Fab o			
Final Cleaning PRO-4510		05	21 lon 20 4	12 101 20				
	Owner Review/Approve RTA - Final Cleaning	25	31-Jan-20 A	13-Jul-20	Owner Review/Approve RT			
PRO-6900	Building Commission Approves Contract - Final Cleaning	1	14-Jul-20*	14-Jul-20		/es Contract - Final Cleaning		
PRO-4520	Award Contract - Final Cleaning	2	15-Jul-20	16-Jul-20	Award Contract - Final Clea			1
PRO-4530	Execute Contract - Final Cleaning	5	17-Jul-20	23-Jul-20	Execute Contract - Final C	-		1 1 1
PRO-4540	Subcontractor Issue Submittals - Final Cleaning	20	24-Jul-20	20-Aug-20	Subcontractor Issue			1
PRO-4550	A/E Review & Approve Submittals - Final Cleaning	15	21-Aug-20	11-Sep-20		prove Submittals - Final Cleaning		
PRO-4560	Fab & Available for Delivery - Final Cleaning	10	14-Sep-20	25-Sep-20	Fab & Available	e for Delivery - Final Cleaning		
Remaining	Level of Effort Remaining Work		Page 3 of	14	TASK filter: % Complete <100.			
•	-		raye 3 Of	14	ASK IIILEI. % CUMPIELE < 100.	© Oracle Corporation	SKANSKA	1
Actual Lev								



/ ID	Activity Name	Remaining	Start	Finish		
		Duration				
					Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug	Sep Oct Nov
ockups						
xterior Facad	le					
Procurement						
MOCK-1170	Fab & Available for Delivery - Granite/Limestone - Exterior Mockup	5	04-Feb-20 A		Fab & Available for Delivery - Granite/Limestone - Exterior Mockup	
MOCK-1140	Fab & Available for Delivery - Curtain Wall - Exterior Mockup	5	14-Feb-20 A		Fab & Available for Delivery - Curtain Wall - Exterior Mockup	
MOCK-1200	Fab & Available for Delivery - Brick - Exterior Mockup	5	24-Feb-20 A		Fab & Available for Delivery - Brick - Exterior Mockup	
MOCK-1110	Fab & Available for Delivery - AVB/Insulation - Exterior Mockup	5	02-Mar-20 A		Fab & Available for Delivery - AVB/Insulation - Exterior Mockup	
MOCK-1310 MOCK-1240	Fab & Available for Delivery - Waterproofing Exterior Sealants - Exterior Mockup Review & Approve - JK Glass Exterior Sealants - Exterior Mockup	5	02-Mar-20 A 23-Mar-20 A		Fab & Available for Delivery - Waterproofing Exterior Sealants - Exterior Mockup Review & Approve - JK Glass Exterior Sealants - Exterior Mockup	
MOCK-1240	Review & Approve - Masonry Exterior Sealants - Exterior Mockup	5	23-Mar-20 A		Review & Approve - Masonry Exterior Sealants - Exterior Mockup	
MOCK-1220	Review & Approve - HSS Steel - Exterior Mockup	4	02-Jun-20 A	11-Jun-20	Review & Approve - HSS Steel - Exterior Mockup	
MOCK-1320	Pre-Installation Meeting - Exterior Mockup	1	08-Jun-20*	08-Jun-20	I Pre-Installation Meeting - Exterior Mockup	1
MOCK-1260	Prepare & Submit - Roof Cap - Exterior Mockup	10	09-Jun-20*	22-Jun-20	Prepare & Submit - Roof Cap - Exterior Mockup	
MOCK-1050	Fab & Available for Delivery - HSS Steel - Exterior Mockup	10	12-Jun-20	25-Jun-20	■ Fab & Available for Delivery - HSS Steel - Exterior Mockup	
MOCK-1225	Fab & Available for Delivery - Masonry Exterior Sealants - Exterior Mockup	10	15-Jun-20	26-Jun-20	Fab & Available for Delivery - Masonry Exterior Sealants - Exterior Mockup	
MOCK-1250	Fab & Available for Delivery - JK Glass Exterior Sealants - Exterior Mockup	10	15-Jun-20	26-Jun-20	Fab & Available for Delivery - JK Glass Exterior Sealants - Exterior Mockup	
MOCK-1270	Review & Approve - Roof Cap - Exterior Mockup	10	23-Jun-20	07-Jul-20	🛑 Review & Approve - Roof Cap - Exterior Mockup	
MOCK-1280	Fab & Available for Delivery - Roof Cap - Exterior Mockup	5	08-Jul-20	14-Jul-20	Fab & Available for Delivery - Roof Cap - Exterior Mockup	
Construction						
MOCK-1330	Install Perimeter Fence - Exterior Mockup	1	15-Jun-20*	15-Jun-20	I Install Perimeter Fence - Exterior Mockup	
MOCK-1340	FRP & Strip Concrete Anchor Pad - Exterior Mockup	5	16-Jun-20	22-Jun-20	FRP & Strip Concrete Anchor Pad - Exterior Mockup	
MOCK-1350	Install LGMF & Bracing - Exterior Mockup	2	23-Jun-20	24-Jun-20	I Install LGMF & Bracing - Exterior Mockup	
MOCK-1360	Install Tube Steel & Relieving Angle - Exterior Mockup	1	26-Jun-20	26-Jun-20	I Install Tube Steel & Relieving Angle - Exterior Mockup	
MOCK-1370	Install Sheathing - Exterior Mockup	1	29-Jun-20	29-Jun-20	Install Sheathing - Exterior Mockup	
MOCK-1380	Install AVB - Exterior Mockup	2	30-Jun-20	01-Jul-20	Install AVB - Exterior Mockup	
MOCK-1390	Install Thermal Insulation - Exterior Mockup	1	02-Jul-20	02-Jul-20	Install Thermal Insulation - Exterior Mockup	
MOCK-1400	Install Curtain Wall Frames - Exterior Mock up	2	06-Jul-20	07-Jul-20	Install Curtain Wal Frames - Exterior Mock up	
MOCK-1410	Install Exterior Glazing Frames - Exterior Mockup	1	08-Jul-20	08-Jul-20	I Install Exterior Glazing Frames - Exterior Mockup	
MOCK-1420 MOCK-1430	Install Punch Windows Frames - Exterior Mockup Install Exterior Glazing - Exterior Mockup	1	09-Jul-20 10-Jul-20	09-Jul-20 10-Jul-20	I Install Punch Windows Frames - Exterior Mockup I Install Exterior Glazing - Exterior Mockup	1
MOCK-1430 MOCK-1440	Install Granite Base - Exterior Mockup	1	13-Jul-20	13-Jul-20	I Install Granite Base - Exterior Mockup	
MOCK-1450	Install Brick & Limestone Cornice - Exterior Mockup	5	14-Jul-20	20-Jul-20	 Install Brick & Limestone Cornice - Exterior Mockup 	
MOCK-1460	Washdown Brick - Exterior Mock up	1	21-Jul-20	21-Jul-20	I Washdown Brick - Exterior Mock up	
MOCK-1470	Install Exterior Sealents & Control Joints - Exterior Mockup	1	22-Jul-20	22-Jul-20	I Install Exterior Sealents & Control Joints - Exterior Mockup	
MOCK-1480	Install Roof & Cap - Exterior Mockup	2	23-Jul-20	24-Jul-20	I Install Roof & Cap - Exterior Mockup	
MOCK-1490	Architect Review & Approve - Exterior Mockup	15	27-Jul-20	14-Aug-20	Architect Review & Approve - Exterior Mockup	
EP Coordi	nation					
asement						
ASEMENT AEP-3040	Fab & Deliver - Duct & Pipe - Basement	10	18-Mar-20 A	19- Jun-20	Fab & Deliver - Duct & Pipe - Basement	
evel 1	Tab & Deliver - Duct & Lipe - Dasement	10	10-101ai -20 A	19-5011-20	i ab & Deliver - Duct & Lipe - Dasement	
MEP-3070	Fab & Deliver - Duct & Pipe - L1	15	01-May-20 A	26- Jun-20	Fab & Deliver - Duct & Pipe - L1	
evel 2		15	01-May-20A	20-301-20		
MEP-3090	Review & Approve MEPs - L2	2	03 Apr 20 A	00 Jun 20	Review & Approve MEPs - L2	
MEP-3100	Fab & Deliver - Duct & Pipe - L2	15	10-Jun-20		Fab & Deliver'- Duct & Pipe - L2	
evel 3		10	10 0011 20	00 0011 20		
MEP-3120	Review & Approve MEPs - L3	5	29-May-20 A	12-Jun-20	Review & Approve MEPs - L3	
MEP-3130	Fab & Deliver - Duct & Pipe - L3	15	24-Jun-20	15-Jul-20	Fab & Deliver - Duct & Pipe - L3	
	n Summary					
roject C - STE	-	-	00 N (0)	40 1 00		
SUM-1090	Summary - Sitework & Foundations	9	08-Nov-19 A		Summary - Sitework & Foundations	
SUM-1100	Summary - Erect Structural Steel	40	27-Mar-20 A	0	Summary - Erect Structural Steel	
SUM-1120	Summary - Detail & Deck Structural Steel	56	06-Apr-20 A	25-Aug-20 01-Sep-20		1
SUM-1130	Summary - Prep & Place Slabs on Deck	61	30-Api-20 A	01-Sep-20		I
Remaining	Level of Effort Remaining Work		Page 4 of	14	TASK filter: % Complete <100.	
	el of Effort Critical Remaining Work	1			© Oracle Corporation	

ity ID	I - Project C - 06Jun20 R1 Schedule Update - 1318015-CR	Dense in t	Clart	Detai			
ity ID	Activity Name	Remaining Duration	Start	Finish	2020	2021	2022
		Duration					/ Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov
SUM-1140	Summary - Level 1 Slab on Grade	25	06-Aug-20	10-Sep-20	Summary - Leve		
SUM-1150	Summary - Spray Fireproofing	18	31-Aug-20	24-Sep-20	Summary - Sp	pray Fireproofing	
SUM-1160	Summary - Exterior Facade	170	08-Sep-20	14-May-21		Summary - Exterior Facade	
SUM-1170	Summary - MEP & Architectural Rough-in	84	22-Sep-20	26-Jan-21		Summary - MEP & Architectural Rough-in	
SUM-1190	Summary - Building Temp Tight	0		14-Jan-21		Summary - Building Temp Tight	
SUM-1200	Summary - Interior Drywall & Finishes	114	15-Jan-21	29-Jun-21		Summary - Interior Dryv	vall & Finishes
SUM-1240	Summary - Final Inspections & C of O	34	19-May-21	07-Jul-21		Summary - Final Inspe	
SUM-1260	Summary - Complete Punch List	20	23-Jun-21	21-Jul-21		Summary - Complet	e Punch List
SUM-1250	Summary - STEM Interim Completion Date	0		07-Jul-21		Summary - STEM Inte	
SUM-1270	Summary - Move-in	10	08-Jul-21	21-Jul-21		Summary - Move-in	
onstruction							
				_			
Project C - STE	•						
Fire Alarm Upg	rad es						
FA-1000	Upgrade Fire Alarm System	60	27-Apr-20 A	31-Aug-20	Upgrade Fire Alar	m System	
Sitework & Fou	ndations						
Upper Founda	tions						
FOUND-1110	FRP Upper Footings & Mat Slab	4	21-May-20 A	11-Jun-20	FRP Upper Footings & Mat Slab		
FOUND-1080	FRP Upper Foundation Walls	9	01-Jun-20 A	18-Jun-20	FRP Upper Foundation Walls		
FOUND-1170	Prep Wals for Waterproofing	10	08-Jun-20	19-Jun-20	Prep Wals for Waterproofing		
FOUND-1120	Waterproof Upper Foundations	10	11-Jun-20	24-Jun-20	Waterproof Upper Foundation	15	
	Backfill Upper Foundations	5	22-Jun-20	26-Jun-20	Backfill Upper Foundations		
Structure				1			
	Erect Structural Steel	40	27-Mar-20 A	03-Aug-20	Erect Structural Steel		
	Detail & Deck Steel	56	06-Apr-20 A	0	Detail & Deck Stee		
Level 2	Detail & Deck Oteen	50	00-Api-20 A	23-Aug-20	Detail & Deck Stee		
	Mobilize Crane	2	29-Jun-20	30-Jun-20	Mobilize Crane		
	Erect Structural Steel & Precast Planks - L2				Erect Structural Steel & Pre	aget Planka I 2	
		5	01-Jul-20	08-Jul-20	++		
	Detail & Deck Steel / Grout Precast Planks - L2	20	09-Jul-20	05-Aug-20	Detail & Deck Steel / G		
	Prep & Place Slab on Deck - L2	5	06-Aug-20	12-Aug-20	Prep & Place Slab on		
	Install Relieving Angles - L2	5	06-Aug-20	12-Aug-20	Install Relieving Angle	es - L2	
Level 3		i					
	Erect Structural Steel - L3	7	09-Jul-20	17-Jul-20	Erect Structural Steel - L3	'	
	Detail & Deck Steel - L3	20	20-Jul-20	14-Aug-20	Detail & Deck Steel -		
	Prep & Place Slab on Deck - L3	5	17-Aug-20	21-Aug-20	Prep & Place Slab o		
STRUCT-1330	Install Relieving Angles - L3	5	17-Aug-20	21-Aug-20	Install Relieving Ang	les - L3	
Roof							
STRUCT-1270	Erect Structural Steel - Roof	7	20-Jul-20	28-Jul-20	Erect Structural Steel - I	Roof	
	Erect Structural Steel for Roof Screen - Roof	4	29-Jul-20	03-Aug-20	Erect Structural Steel for a steel for	or Roof Screen - Roof	
STRUCT-1280	Detail & Deck Steel - Roof	20	29-Jul-20	25-Aug-20	Detail & Deck Stee	I - Roof	
STRUCT-1190	Prep & Place Slab on Deck - Roof	5	26-Aug-20	01-Sep-20	Prep & Place Slab	on Deck - Roof	
STRUCT-1230	Install Roof Dunnage - Roof	5	02-Sep-20	09-Sep-20	Install Roof Duni	nage - Roof	
Level 1 Slab on	-						
SOG-1000	Excavate & Install Underslab Utiltites & Drainage System - L1	15	06-Aug-20	26-Aug-20	Excavate & Install	Underslab Utiltites & Drainage System - L1	
SOG-1010	Prep & Place Slab on Grade - L1	10	27-Aug-20	10-Sep-20	Prep & Place Sla		
Layout & Instal	•			· · · ·			
L1-3000	Layout & Install Top Track - L2	5	24-Aug-20	28-Aug-20	Layput & Install Top	DTrack - L2	
L1-3010	Layout & Install Top Track - Basement	2	31-Aug-20	01-Sep-20	Layout & Install To		
L1-3020	Layout & Install Top Track - L3	5	02-Sep-20	01-Sep-20	Layout & Install 1		
L1-3020	Layout & Install Top Track - L3	5	11-Sep-20	17-Sep-20	Layout & Install		
		J	11-3ep-20	17-3ep-20		1 100 11 aux - L1	
Spray Fireproof	-	-	21 Aug 00	04.0== 00			
SPF-1010	Spray Fireproof - L2	5	31-Aug-20	04-Sep-20	Spray Fireproof -		
SPF-1030	Spray Fireproof - Basement	2	08-Sep-20	09-Sep-20	Spray Fireproof		
SPF-1020	Spray Fireproof - L3	5	10-Sep-20	16-Sep-20	Spray Fireproof		
SPF-1000	Spray Fireproof - L1	5	18-Sep-20	24-Sep-20	Spray Firepro	of - L1	
D							
Remaining	-		Page 5 of	14	TASK filter: % Complete <100.		
Actual Leve	el of Effort Critical Remaining Work					© Oracle Corporation	SKANSKA
Actual Worl	k				362 of 377	l l	



ID	ool - Project C - 06Jun20 R1 Schedule Update - 1318015-CR Activity Name	Remaining	Start	Finish				
		Duration	Otdire	1 mor	2020			2021
					Jun Jul Aug Sep Oct Nov De	c Jan Feb Mar	Apr May Jun] Jul Aug S
Stairs								
ST-1000	Install - Stair 1	5	30-Jul-20	05-Aug-20	Install - Stair 1			
ST-1010	Install - Stair 2	15	06-Aug-20	26-Aug-20	Install - Stair 2			
ST-1020	Install - Stair 3	15	20-Aug-20	10-Sep-20	Install - Stair 3			
Roofing								
RF-1010	Frame & Sheath Roof Parapet	15	02-Sep-20	23-Sep-20	Frame & She			
RF-1040	Frame & Sheath Clerestory Light Monitor	10	17-Sep-20	30-Sep-20		eath Clerestory Li		
RF-1000	Temp-in Roofs / Install Roof AVB	15	24-Sep-20	15-Oct-20		Roofs / Install Roo		
RF-1050	Install Roofing at Clerestory Light Monitor	5	01-Oct-20	07-Oct-20		ing at Clerestory I		
RF-1060	Install Sill Flashing & Curtain Wall at Light Monitor	10	08-Oct-20	22-Oct-20	📕 Install Si	I Flashing & Curta	in Wa l at Ligh	t Monitor
RF-1020	Install Roof Screens	20	04-Nov-20	04-Dec-20		nstall Roof Screen	IS	
RF-1030	Install Permanent Roof - Roof Level	15	07-Dec-20	28-Dec-20		Install Perman	ent Roof - Roo	fLevel
RF-1070	Install Stair at Roof	5	29-Dec-20	05-Jan-21		Install Stair a	Roof	
RF-1080	Install Roof Pavers	5	06-Jan-21	12-Jan-21		Install Roof		
Exterior Faca								
EXT-1000	Frame Exterior Walls	45	08-Sep-20	10-Nov-20	Eram	e Exterior Walls		
EXT-105	Sheath Exterior Walls	40	23-Sep-20	19-Nov-20		ath Exterior Walls		
EXT-105 EXT-1010	AVB Exterior Walls	34	23-Sep-20 07-Oct-20	25-Nov-20		B Exterior Walls		
EXT-1010 EXT-1040	AVB Exterior Walls	58	20-Oct-20	25-Nov-20 14-Jan-21	AV	Install Curta		
						- I · · ·		
EXT-1020	Stage Exterior Walls	48	10-Nov-20	22-Jan-21		Stage Exte		
EXT-1030	Install Stone & Brick / Washdown / Remove Staging	74	03-Dec-20	22-Mar-21			Install Stone &	Brick / Wash
EXT-1050	Building Temp Tight	0		14-Jan-21		♦ Building Ten	np Tight	
North Elevat								
N-1000	Frame Exterior Walls - North Elevation	18	08-Sep-20	01-Oct-20		ior Walls - North		1
N-1010	Sheath Exterior Walls - North Elevation	12	23-Sep-20	08-Oct-20	Sheath Ext	er¦ior Walls - Nort∤	n Elevation	1
N-1020	Install AVB - North Elevation	7	07-Oct-20	16-Oct-20	Install AVI	B - North Elevatio	ו	
N-1030	Prep Openings for Curtain Wall - North Elevation	10	13-Oct-20	26-Oct-20	Prep O	penings for Curtai	n Wall - North	ev ation
N-1040	Install Curtain Wal - North Elevation	23	20-Oct-20	20-Nov-20	Inst	all Curtain Wa l - I	North Elevation	٦
N-1050	Install Staging - North Elevation	15	10-Nov-20	03-Dec-20	l Ir	nstall Staging - No	rth Elevation	
N-1060	Install Stone - North Elevation	4	25-Nov-20	02-Dec-20		stall Stone - North		
N-1070	Install Brick - North Elevation	23	04-Dec-20	07-Jan-21			North Elevation	on
N-1080	Washdown Masonry - North Elevation	10	30-Dec-20	13-Jan-21		i i	Masonry-Nor	- i
N-1090	Remove Staging - North Elevation	10	07-Jan-21	21-Jan-21		Remove \$	•	1
N-1100	Caulk Facade - North Elevation	6	22-Jan-21	29-Jan-21			cade - North E	
		0	22-Jan-21	29-Jan-21				
South & Wes		00	00.0 00	00.0+00				
S-1000	Frame Exterior Walls - South & West Elevations	26	22-Sep-20	28-Oct-20		Exterior Walls - So		i
S-1010	Sheath Exterior Wals - South & West Elevations	17	13-Oct-20	04-Nov-20		n Exterior Walls -		1
S-1020	Install AVB - South & West Elevations	12	27-Oct-20	12-Nov-20		II AVB - South & V		
S-1030	Prep Openings for Curtain Wall - South & West Elevations	10	05-Nov-20	19-Nov-20	Pre	p¦Openings for C		
S-1040	Install Curtain Wal - South & West Elevations	25	16-Nov-20	22-Dec-20		Install Curtain V		
S-1050	Install Staging - South & West Elevations	15	09-Dec-20	30-Dec-20		Install Staging	- South & Wes	st Elevations
S-1070	Install Brick - South & West Elevations	38	04-Jan-21	26-Feb-21		Insta	all Brick - Sout	h & West Ele
S-1080	Washdown Masonry - South & West Elevations	10	19-Feb-21	04-Mar-21		📙 🖬 Wa	shdown Maso	n ry - South &
S-1090	Remove Staging - South & West Elevations	10	26-Feb-21	11-Mar-21		' 🗖 R	emove Staging	g - South & W
S-1100	Caulk Facade - South & West Elevations	10	12-Mar-21	25-Mar-21			Caulk Facade	
East Elevatio			,					
E-1000	Frame Exterior Walls & Canopy - East Elevation	15	21-Oct-20	10-Nov-20	📕 Fram	e Exterior Walls	Canopy-Eas	st Elevation
E-1010	Sheath Exterior Walls & Canopy - East Elevation	10	05-Nov-20	19-Nov-20		ath Exterior Walls		1
E-1020	Install AVB - East Elevation	7	17-Nov-20	25-Nov-20		stall AVB - East Ele		
E-1020	Prep Openings for Curtain Wall - East Elevation	10	30-Nov-20	11-Dec-20		Prep Openings fo		- Fast Flovet
E-1030	Install Curtain Wall - East Elevation		11-Dec-20	14-Jan-21			in Wall - East	
		23			-			1
E-1050	Install Staging - East Elevation	5	15-Jan-21	22-Jan-21		Install Stag		1
E-1060	Install Stone - East Elevation	3	01-Mar-21	03-Mar-21	 		tall Stone - Eas	
E-1070	Install Brick - East Elevation	8	04-Mar-21	15-Mar-21		1	nstall Brick - Ea	
E-1080	Washdown Masonry - East Elevation	3	16-Mar-21	18-Mar-21		<u> </u>	Vashdown Ma	is¦onry-East
	g Level of Effort Remaining Work		Page 6 of	14	TASK filter: % Complete <100.		© Orac	cle Corporatio
					1		S Orac	
Actual W	ork	I			363 of 377			

Data Date: 06-Jun-20 / Run Date: 09-Jul-20 08:50 2022 223 ep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Ian ndown / Remove Staging - - - - - - levations ns ations West Elevations est Elevations est Elevations m lev atio n



	ol - Project C - 06Jun20 R1 Schedule Update - 1318015-CR Activity Name	Remaining	Start	Finish	iled Schedule	
		Duration	Otart	1 111311	2020 202	
E 4000					Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun 、	
E-1090	Remove Staging - East Elevation	2	19-Mar-21	22-Mar-21	Remove Staging	
E-1110	Install Metal Panels at Canopy - East Elevations	20	23-Mar-21	20-Apr-21		
E-1120	Install Metal Column Enclosures - East Elevation	10	21-Apr-21	04-May-21	Install Me	
E-1100	Caulk Facade - East Elevation	8	05-May-21	14-May-21	Caulk F	acade -
Elevators	Duild Elevater Chaft	20	05 Can 20	22 Oct 20	Duild Floupter Chaft	
ELEV-1000 ELEV-1010	Build Elevator Shaft Install Elevator	20 60	25-Sep-20 26-Oct-20	23-Oct-20 25-Jan-21	Build Elevator Shaft	
MEP Systems		00	20-001-20	25-Jan-21		
MEP-1500	Build Walls - Basement Level Mechanical & Electrical Rooms	15	10-Sep-20	30-Sep-20	Build Wals - Basement Level Mechanical & Ele	otric al E
MEP-1510	FRP Equipment Pads - Basement Level Mechanical & Electrical Rooms	5	24-Sep-20	30-Sep-20	FRP Equipment Pads - Basement Level Mecha	
Hot Water		5	24-00p-20	00-0cp-20		inical d
Basement						
MEP-3350	Rig & Set Heat Exchanger (HEX-1.1), Expansion Tanks (ET-1/2) & Pumps (HHWP-1.1/1.2)	2	01-Oct-20	02-Oct-20	Rig & Set Heat Exchanger (HEX-1.1), Expansio	on Tank
MEP-3360	Install Mechanical Piping to Exchanger (HEX-1.1), Expansion Tanks (ET-1/2) & Pumps (HH	20	01-Oct-20 05-Oct-20	02-00t-20 02-Nov-20	Install Mechanical Piping to Exchanger (H	
MEP-3410	Install Electrical to Heat Exchanger (HEX-1.1), Expansion Tanks (ET-1/2) & Pumps (HHWF	15	20-Oct-20	09-Nov-20	Install Electrical to Heat Exchanger (HE)	
MEP-3370	Install Controls Wiring to Heat Exchanger (HEX-1.1), Expansion Tanks (ET-1/2) & Pumps (10	10-Nov-20	24-Nov-20	Install Controls Wiring to Heat Exchange	
MEP-3380	Fill, Flush & Treat Piping - Hot Water System	5	25-Nov-20	03-Dec-20	 Fill, Flush & Treat Piping - Hot Wate 	•
MEP-3390	Insulate Piping - Hot Water System	20	04-Dec-20	04-Jan-21	Insulate Piping - Hot Water System	-
MEP-3400	Start-up & Test - Hot Water System	15	16-Dec-20	07-Jan-21	Start-up & Test - Hot Water S	
Chilled Water		10	10 200 20	or our Er		jotom
Roof						
MEP-2000	Rig & Set Chiller (ACC-1.1) at Roof - Chilled Water System	2	10-Sep-20	11-Sep-20	Rig & Set Chiller (ACC-1.1) at Roof - Chilled Water	Svsten
MEP-2010	Install Mechanical Piping to Chiller (ACC-1.1) - Chilled Water System	20	14-Sep-20	09-Oct-20	Install Mechanical Piping to Chiller (ACC-1.1)	-
MEP-2020	Install Electrical Conduits & Wiring to Chiller (ACC-1.1) - Chilled Water System	15	13-Oct-20	02-Nov-20	Install Electrical Conduits & Wiring to Chil	
MEP-2030	Install Controls Wiring to Chiller (ACC-1.1) - Chilled Water System	10	03-Nov-20	17-Nov-20	Instal Controls Wiring to Chiller (ACC-	
Basement						, -
MEP-2040	Rig & Set Chilled Water Pumps (CHWP-1/2/3) & Expansion Tank (ET-1) - Chilled Water Sy	2	05-Oct-20	06-Oct-20	Ⅰ Rig & Set Chilled Water Pumps (CHWP-1/2/3)	& Expa
MEP-2070	Rig & Set Gycol Feed System (GFT-1) - Chilled Water System	2	07-Oct-20	08-Oct-20	Rig & Set Gycol Feed System (GFT-1) - Chille	
MEP-3260	Install Mechanical Piping to Chilled Water Pumps (CHWP-1/2/3) & Expansion Tank (ET-1) -	20	20-Oct-20	17-Nov-20	Install Mechanical Piping to Chilled Wat	
MEP-2050	Install Electrical Conduits & Wiring to Chilled Water Pumps (CHWP-1/2/3) & Expansion Tan	15	03-Nov-20	24-Nov-20	Install Electrical Conduits & Wiring to	
MEP-2080	Install Mechanical Piping to Glycol Feed System (GFT-1) - Chilled Water System	5	18-Nov-20	24-Nov-20	Install Mechanical Piping to Glycol Fe	
MEP-2090	Install Electrical Conduits & Wiring to System (GFT-1) - Chilled Water System	5	25-Nov-20	03-Dec-20	Install Electrical Conduits & Wiring to	
MEP-2060	Install Controls Wiring to Chilled Water Pumps (CHW P-1/2/3) & Expansion Tank (ET-1) - C	10	25-Nov-20	10-Dec-20	Install Controls Wiring to Chilled W	-
MEP-2100	Install Controls Wiring to Gycol Feed System (GFT-1) - Chilled Water System	5	11-Dec-20	17-Dec-20	Install Controls Wiring to Gycol Fe	
MEP-3320	Fill, Flush & Treat Piping - Chilled Water System	5	18-Dec-20	24-Dec-20	Fill, Flush & Treat Piping - Chilled	
MEP-3330	Insulate Piping - Chilled Water System	20	28-Dec-20	26-Jan-21	Insulate Piping - Chilled W	
MEP-3340	Start-up & Test - Chiled Water System	15	07-Jan-21	28-Jan-21	Start-up & Test - Chiled M	
Air Handiling				,		-
Roof				_		
AHU-1.1 (ST	EM) & AH U-1.2 (ST EM)					
MEP-3480	Rig & Set - AHU-1.1 (STEM) & AHU-1.2 (STEM)	1	14-Sep-20	14-Sep-20	I Rig & Set - AHU-1.1 (STEM) & AHU-1.2 (STEM)	
MEP-3490	Install Ductwork Connections - AHU-1.1 (STEM) & AHU-1.2 (STEM)	15	15-Sep-20	05-Oct-20	Install Ductwork Connections - AHU-1.1 (STE	M) & AF
MEP-3500	Install Mechanical Piping Connections - AHU-1.1 (STEM) & AHU-1.2 (STEM)	15	29-Sep-20	20-Oct-20	Install Mechanical Piping Connections - AHU	J-1.1 (S
MEP-3510	Install Electrical Conduits & Wiring - AHU-1.1 (STEM) & AHU-1.2 (STEM)	15	14-Oct-20	03-Nov-20	Install Electrical Conduits & Wiring - AHU	-1.1 (ST
MEP-3520	Install Controls Wiring - AHU-1.1 (STEM) & AHU-1.2 (STEM)	10	04-Nov-20	18-Nov-20	Install Controls Wiring - AHU-1.1 (STE	M) & Al
MEP-3530	Start-up & Test - AHU-1.1 (STEM) & AHU-1.2 (STEM)	5	29-Jan-21	04-Feb-21	Start-up & Test - AHU-1.	1 (STEN
AHU-2.1 (Kit	chen)					
MEP-3540	Rig & Set - AHU-2.1 (Kitchen)	1	15-Sep-20	15-Sep-20	I Rig & Set - AHU-2.1 (Kitchen)	
MEP-3550	Install Ductwork Connections - AHU-2.1 (Kitchen)	15	29-Sep-20	20-Oct-20	Install Ductwork Connections - AHU-2.1 (Ki	tchen)
MEP-3560	Install Mechanical Piping Connections - AHU-2.1 (Kitchen)	15	14-Oct-20	03-Nov-20	Install Mechanical Piping Connections - A	
MEP-3570	Install Electrical Conduits & Wiring - AHU-2.1 (Kitchen)	15	28-Oct-20	18-Nov-20	Install Electrical Conduits & Wiring - Al-	
MEP-3580	Install Controls Wiring - AHU-2.1 (Kitchen)	10	19-Nov-20	04-Dec-20	Install Controls Wiring - AHU-2.1 (K	
MEP-3590	Start-up & Test - AHU-2.1 (Kitchen)	5	05-Feb-21	11-Feb-21	Start-up & Test - AHU-2	
Electrical				,		
Basement						
Remaining	Level of Effort Remaining Work		Dogo 7 -f	14	TASK filter: % Complete <100	
-	-		Page 7 of	14	TASK filter: % Complete <100.	Corre
 Actual Leve Actual Wor 	5			-	© Oracle 364 of 377	Corpor
	k $igodelta Milestone$			Dogo		

					Data	a Date	e: 06-	Jun-2	20 / 1	Run D)ate: ()9-Ju	I-20 C	8:50		
									20	22)23
ер	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov		lan
atio	i															
		- East					1 1 1						1 1 1			
	+	ires -	East	Eleva	ition		 									
stl	Eleva	tion		i I											I	i I
															ſ	1
	1			l I			1 1 1			1 1 1			1 1 1		I I	I I
	1 1 1			l I			1 1 1			1 1 1			1 1 1		,	1
				 			, , !								 	
ms	1			1			1 									1
ctri	cal R	ooms					1			1			1			
	1 1 1			1			1 1 1			1			1 1 1		1	
_		_											1 1 1		j	İ
	*	& Pum														
		n Tank													ļ	
	÷	anks		1									i		ľ	l I
1.1), Exp	bansic	n Iar	iks (E	=1-1/2	2)&F	umps	s (HH	WP-	1.1/1.2	2) - H	ot wa	ater S	ysten	ן ו	
				I.											1	1
							; !						; 			
				1			1			1			1		i	1
	1						, , ,						1 1 1			
															i	I
- +	- 6.40	tom					1 1 1			1			1 1 1			
	r Sys	led W	at or 0	l	 m		 								¹	L
		Syste		pyster I	11		1						1		l	1
uv	valei	Syste	;111	1 											1	
-n ⁻	Tank	(ET-1		hillod	Wato	r Sve	tom								ļ	1
/ste	1	(∟1-1) - 01		vvale	i Oys										
	+	1/2/3) & F v	nans	inn T:	ank (F		- Chi	led \A	l Jater	Svete	m				
		os (Cl		1									Svete	m	ĺ	İ
		- Chi		1					LI-I)			valer	Joysic	,,,,,	i	I
	1	Chille		1	-		1 1 1								ļ	ĺ
	1 1	P-1/2/			•		/ (FT-1) - Cl	ni l ed '	Wate	r Svst	em	 		I F	I I
	*) - Cł					<u>}</u>	/								
ter	i i	,		1			1 1 1			1 1 1			1 1 1		1	l I
1							1									
n				1												
	i 1 1															
				; 1			 			L					i	' I
	1						1						1 1 1		ſ	
				I I											I I	I I
1.2	(STE	EM)		1			1 1 1			1 1			1 1 1		,	1
	1	Ú-1.2	(STE	M)			 								1	
		J-1.2 (L			/			
	(STE														1	
Aŀ	1U-1.	2 (ST	EM)	1			 									
				Ì											j	
							1						1		i	I
che	en)			1			1 1 1			1			1 1 1		I	1
he	n)						1 1 1						1 1 1		ļ	
				I I			1 1 1						1 1 1		ľ	l
)															ļ	
				1			 									
							 			1			 			
- 1																



0	ol - Project C - 06Jun20 R1 Schedule Update - 1318015-CR	<u></u>		Detaile			Data Date: 06-Jun-20 / Run Date: 09-Jul-20 08:50		
<i>i</i> ID	Activity Name	Remaining	Start	Finish	2020	2021	2022		
		Duration		Ι Π			Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov		
MEP-2110	Install Overhead Conduits & Electrical Panels - Permanent Power	10	01-Oct-20	15-Oct-20	Install Overhead	Conduits & Electrical Panels - Permanent Power			
MEP-2120	Rig & Set Electrical Gear & Panels - Permanent Power	5	16-Oct-20	22-Oct-20	Rig & Set Election	rical Gear & Panels - Permanent Power			
MEP-3290	Install Doors & Secure Room - Permanent Power	5	23-Oct-20	29-Oct-20	Install Doors &	Secure Room - Permanent Power			
MEP-2130	Wire & Terminate Panels & Gear- Permanent Power	20	23-Oct-20	20-Nov-20	Wire & Tei	rminate Panels & Gear- Permanent Power			
MEP-3270	Pull Conductors & Terminate - Permanent Power	5	23-Nov-20	01-Dec-20		ductors & Terminate - Permanent Power			
MEP-3280	Test Switchgear - Permanent Power	5	02-Dec-20	08-Dec-20		vitchgear - Permanent Power			
MEP-3300	Energize Switchgear - Permanent Power	5	09-Dec-20	15-Dec-20		ize Switchgear - Permanent Power			
MEP-3310	Permanent Power Available	0	00 200 20	15-Dec-20		anent Power Available			
Interiors				10-000-20					
MEP-1010	MEP & Architectural Rough-in - L2	57	08-Sep-20	01-Dec-20		Architectural Rough-in - L2			
MEP-1020	MEP & Architectural Rough-in - L3	62	22-Sep-20	22-Dec-20		& Architectural Rough-in - L3			
			•			MEP & Architectural Rough-in - L1			
MEP-1000	MEP & Architectural Rough-in - L1	75	06-Oct-20	27-Jan-21					
INT-1010	Interior Drywall & Finishes - L2	84	15-Jan-21	17-May-21		Interior Drywall & Finishes - L2			
INT-1020	Interior Drywall & Finishes - L3	89	01-Feb-21	08-Jun-21		Interior Drywall & Finishes -			
INT-1000	Interior Drywall & Finishes - L1	94	16-Feb-21	29-Jun-21		Interior Drywall & Finish	es - L1		
Level 2									
L2-1010	Install MEP Risers - L2	10	08-Sep-20	21-Sep-20	Install MEP Risers -				
L2-1000	Install Tube Steel Wall Supports - L2	5	22-Sep-20	28-Sep-20	Install Tube Steel W	/all Supports - L2			
L2-1020	Rough-in Overhead Ductwork - L2	15	22-Sep-20	13-Oct-20	Rough-in Overhe	ead Ductwork - L2			
L2-1030	Rough-in Overhead Plumbing - L2	15	22-Sep-20	13-Oct-20	Rough-in Overhe	ead Plumbing - L2			
L2-1040	Rough-in Overhead Mechanical Piping - L2	15	29-Sep-20	20-Oct-20	Rough-in Øverh	nead Mechanical Piping - L2			
L2-1050	Rough-in Overhead Electrical Conduit - L2	20	29-Sep-20	27-Oct-20	Rough-in Over	rhead Electrical Conduit - L2			
L2-1060	Frame Electrical Closets - L2	3	14-Oct-20	16-Oct-20	Frame Electrical				
L2-1070	Rough Fire Protection - L2	10	14-Oct-20	27-Oct-20	📕 Rough Fire Pro				
L2-1130	Install Above Ceiling Mechanical Equipment - L2	10	14-Oct-20	27-Oct-20		Ceiling Mechanical Equipment - L2			
L2-1080	Board & Tape Electrical Closets - L2	5	19-Oct-20	23-Oct-20		Electrical Closets - L2			
L2-1080	Frame Interior Wals - L2	10	21-Oct-20	03-Nov-20	Frame Interio				
L2-1450	Insulate Overhead Mechanical Piping & HVAC Ductwork - L2	15	21-Oct-20	10-Nov-20		erhead Mechanical Piping & HVAC Ductwork - L2			
L2-1120	Set Door Frames - L2	5	26-Oct-20	30-Oct-20	Set Door Fran				
L2-1110	Rough-in Plumbing In-Wall - L2	10	28-Oct-20	10-Nov-20		umbing In-Wall - L2			
L2-1100	Frame Soffits - L2	10	02-Nov-20	16-Nov-20	Frame Soft				
L2-1140	Rough-in Electrical In-Wall & Pull Branch Circuits - L2	15	04-Nov-20	25-Nov-20		Electrical In-Wall & Pull Branch Circuits - L2			
L2-1150	Rough-in Low Voltage In-Wall & Pull Wire - L2	15	04-Nov-20	25-Nov-20		Low Voltage In-Wall & Pull Wire - L2			
L2-1160	Perform Wall & Ceiling Punch List & Inspections - L2	10	25-Nov-20	10-Dec-20		m Wall & Ceiling Punch List & Inspections + L2			
L2-1170	Perform In-Wall Inspections with Town - L2	2	30-Nov-20	01-Dec-20	Perform	In-Wall Inspections with Town - L2			
L2-1180	Install Wood Blocking - L2	5	02-Dec-20	08-Dec-20	Install V	Nood Blocking - L2			
L2-1330	Insulate In-Wall Piping - L2	5	02-Dec-20	08-Dec-20	Insulate	e In-Wall Piping - L2			
L2-1190	Board Wals & Soffits - L2	10	15-Jan-21	29-Jan-21		Board Walls & Soffits - L2			
L2-1210	Tape Walls & Soffits - L2	10	22-Jan-21	04-Feb-21	+	Tape Walls & Soffits - L2			
L2-3050	Field Measure & Fab Interior Glass - L2	20	25-Jan-21	22-Feb-21		Field Measure & Fab Interior Glass - L2			
L2-1220	Prime & 1st Coat walls - L2	6	05-Feb-21	12-Feb-21		Prime & 1st Coat walls - L2			
L2-1220	Paint Exposed Ceilings at Classrooms & Offices - L2	10	05-Feb-21	19-Feb-21		 Paint Exposed Ceilings at Classrooms & Office 	es - 1 2		
L2-1230	Install Ceiling Grid & Cut/DeviceTies at Classrooms & Offices - L2	5	10-Feb-21	17-Feb-21		 Install Ceiling Grid & Cut/DeviceTies at Classro 			
L2-1225 L2-3060	Install Celling Grid & CurDevice Les at Cassrooms & Offices - L2		10-Feb-21 10-Feb-21	24-Feb-21		 Install Celling Grid & CurDevice Les at Cassif Install Wal Tile at Corridors - L2 			
		10					10		
L2-1240	Install MEP Drops at Classrooms & Offices - L2	10	12-Feb-21	26-Feb-21		Install MEP Drops at Classrooms & Offices -	L2		
L2-1235	Install Fume Hoods - L2	5	18-Feb-21	24-Feb-21		Install Fume Hoods - L2			
L2-1250	Install Storefront Frames - L2	10	23-Feb-21	08-Mar-21		Install Storefront Frames - L2			
L2-1260	Install Millwork at Classrooms & Offices - L2	10	01-Mar-21	12-Mar-21		Install Millwork at Classrooms & Offices - L			
L2-1440	Install Teledata Finishes & Terminations - L2	10	01-Mar-21	12-Mar-21		Install Teledata Finishes & Terminations - L	2		
L2-1390	Install Interior Glazing - L2	10	02-Mar-21	15-Mar-21		Install Interior Glazing - L2			
L2-1445	Install Fintube Radiators - L2	10	05-Mar-21	18-Mar-21		Install Fintube Radiators - L2			
L2-1270	Install Ceiling Grid & Cut/Device Tiles at Corridors - L2	5	11-Mar-21	17-Mar-21		Install Ceiling Grid & Cut/Device Tiles at C	orridors - L2		
L2-1380	Install Flooring at Classrooms & Offices - L2	10	12-Mar-21	25-Mar-21		Install Flooring at Classrooms & Offices	- L2		
L2-1370	Install Doors & Hardware - L2	5	15-Mar-21	19-Mar-21		Install Doors & Hardware - L2			
L2-1305	Install Railings at Opening - L2	5	18-Mar-21	24-Mar-21		Install Railings at Opening - L2			
-	Level of Effort Remaining Work		Page 8 of	14	TASK filter: % Complete <100.				
Actual Leve	el of Effort Critical Remaining Work					© Oracle Corporation	SKANSKA		
					365 of 377				

	ject C - 06Jun20 R1 Schedule Update - 1318015-CR /ity Name	Remaining	Start	Finish	ed Schedule		Data Date: 06-Jun-20 / Run Date: 09-Jul-20 08:		
		Duration	Start		2020 Jun Jul Aug Sep Oct Nov Dec	2021 Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec	 Jan Feb Mar Apr Mav J	2022 un Jul Aug Sep Oct No	
L2-1430 Insta	all Fire Alarm Devices - L2	5	18-Mar-21	24-Mar-21		Install Fire Alarm Devices - L2			
L2-1280 Insta	all MEP Drops at Corridors - L2	8	18-Mar-21	29-Mar-21		Install MEP Drops at Corridors - L2			
L2-3070 Insta	all Laboratory Casework at Classrooms - L2	10	18-Mar-21	31-Mar-21		Install Laboratory Casework at Classrooms -	L2		
L2-1285 Insta	all Fintube Covers - L2	10	19-Mar-21	01-Apr-21		Install Fintube Covers - L2	1		
L2-3080 Insta	all Plumbing Fixtures at Classrooms & Offices - L2	10	24-Mar-21	06-Apr-21		Install Plumbing Fixtures at Classrooms & O	ffices - L2		
L2-1300 Insta	all Terrazzo at Corridors - L2	18	26-Mar-21	21-Apr-21		Install Terrazzo at Corridors - L2			
L2-1360 Insta	all Terrazzo Base at Corridors - L2	10	12-Apr-21	26-Apr-21		Install Terrazzo Base at Corridors - L2			
L2-1320 Insta	all AV - L2	5	20-Apr-21	26-Apr-21		Install AV - L2			
L2-1340 Insta	all Whiteboards & Tack Boards - L2	5	20-Apr-21	26-Apr-21		Install Whiteboards & Tack Boards - L2			
L2-1350 Insta	all Window Shades - L2	5	20-Apr-21	26-Apr-21		Install Window Shades - L2			
L2-1400 Cons	struction Cleaning - L2	5	27-Apr-21	03-May-21		Construction Cleaning - L2			
L2-1290 Balar	nce HVAC - L2	5	04-May-21	10-May-21		Balance HVAC - L2			
L2-1410 Skar	nska Punch List - L2	5	04-May-21	10-May-21		Skanska Punch List - L2			
	itect Punch List - L2	5	11-May-21	17-May-21		Architect Punch List - L2	·		
Bathrooms									
L2-1600 Boar	rd & Install Cement Board - L2 Bathrooms	5	15-Jan-21	22-Jan-21		Board & Install Cement Board - L2 Bathrooms			
	e & Finish - L2 Bathrooms	5	25-Jan-21	29-Jan-21		Tape & Finish - L2 Bathrooms			
	e Paint - L2 Bathrooms	3	01-Feb-21	03-Feb-21		Prime Paint - L2 Bathrooms			
	all Counters - L2 Bathrooms	2	04-Feb-21	05-Feb-21		Install Counters - L2 Bathrooms	·		
	all Wal & Floor Tile - L2 Bathrooms	10	08-Feb-21	22-Feb-21		Install Wal & Floor Tile - L2 Bathrooms			
	all Plumbing Fixtures - L2 Bathrooms	5	23-Feb-21	01-Mar-21		Install Plumbing Fixtures - L2 Bathrooms			
	I Measure & Fab Mirrors - L2 Bathrooms	10	23-Feb-21	08-Mar-21		Field Measure & Fab Mirrors - L2 Bathrooms			
	all Toilet Partitions - L2 Bathrooms	4	02-Mar-21	05-Mar-21		Install Toilet Partitions - L2 Bathrooms	1		
	all Bathroom Accessories - L2 Bathrooms	4	08-Mar-21	11-Mar-21		 Install Bathroom Accessories - L2 Bathrooms 			
	all Mirrors - L2 Bathrooms	2	12-Mar-21	15-Mar-21		 Install Data completes of L2 Data complete Install Mirrors - L2 Bathrooms 	1		
	sh Paint - L2 Bathrooms	2	16-Mar-21	17-Mar-21		Finish Paint - L2 Bathrooms			
IT Room 204C		2	10-11101-21	17-11101-21			1		
	all MEP Above Ceiling Rough-in - L2 IT Room 204C	3	14-Oct-20	16-Oct-20		Above Ceiling Rough-in - L2 IT Room 204C			
	ne Wals & Instal Door Frame - L2 IT Room 204C	-	14-Oct-20 19-Oct-20	20-Oct-20		Is & Install Door Frame - L2 IT Room 204C	 		
		2			1 I I I I I I I I I I I I I I I I I I I	Val Rough-in - L2 IT Room 204C			
	all In-Wal Rough-in - L2 IT Room 204C	2	21-Oct-20	22-Oct-20					
	all In-Wal Blocking - L2 IT Room 204C	1	23-Oct-20	23-Oct-20		Wall Blocking - L 2 IT Room 204C			
	rd Wals - L2 IT Room 204C	1	23-Dec-20	23-Dec-20		Board Wals - L2 IT Room 204C			
· ·	e Walls - L2 IT Room 204C	3	24-Dec-20	29-Dec-20		Tape Walls - L2 IT Room 204C	' 	· · · · · · · · · · · · · · · · · · ·	
	e & 1st Coat Paint Walls - L2 IT Room 204C	2	30-Dec-20	31-Dec-20		Prime & 1st Coat Paint Walls - L2 IT Room 204C			
	all Ceiling Grid - L2 IT Room 204C	1	04-Jan-21	04-Jan-21		I Install Ceiling Grid - L2 IT Room 204C			
	all MEP Drops at Grid - L2 IT Room 204C	2	05-Jan-21	06-Jan-21		I Install MEP Drops at Grid - L2 IT Room 204C			
	all Moisture Mitigation - L2 IT Room 204C	1	07-Jan-21	07-Jan-21		Install Moisture Mitigation - L2 IT Room 204C			
	all Flooring - L2 IT Room 204C	2	08-Jan-21	11-Jan-21		Install Flooring - L2 IT Room 204C			
	I Paint - L2 IT Room 204C	2	12-Jan-21	13-Jan-21		Final Paint - L2 IT Room 204C			
	all IT Racks & Equipment - L2 IT Room 204C	5	15-Jan-21	22-Jan-21		Install IT Racks & Equipment - L2 IT Room 204C			
	all Ceiling Tile - L2 IT Room 204C	1	25-Jan-21	25-Jan-21		Install Ceiling Tile - L2 IT Room 204C			
	struction Clean - L2 IT Room 204C	5	26-Jan-21	01-Feb-21		Construction Clean - L2 IT Room 204C			
	nce HVAC - L2 IT Room 204C	1	05-Feb-21	05-Feb-21		Balance HVAC - L2 IT Room 204C			
	nska Punch List- L2 IT Room 204C	1	08-Feb-21	08-Feb-21		I Skanska Punch List- L2 IT Room 204C	1		
	itect Punch List - L2 IT Room 204C	1	09-Feb-21	09-Feb-21		I Architect Punch List - L2 IT Room 204C			
	plete 90 Calendar Days Prior to STEM Interim Completion Date - L2 IT Room 204C	90	10-Feb-21	10-May-21		Complete 90 Calendar Days Prior to S	TEM Interim Completion Date	e - L2 IT Room 204C	
Level 3									
L3-1010 Insta	all MEP Risers - L3	10	22-Sep-20	05-Oct-20	📕 Install MEP F	Risers - L3	l 		
L3-1000 Insta	all Tube Steel Wall Supports - L3	5	06-Oct-20	13-Oct-20	Install Tube	Steel Wall Supports - L3			
L3-1020 Roug	gh-in Overhead Ductwork - L3	15	14-Oct-20	03-Nov-20	Rough-i	h Overhead Ductwork - L3			
L3-1030 Roug	gh-in Overhead Plumbing - L3	15	14-Oct-20	03-Nov-20	Rough-i	h Overhead Plumbing - L3			
L3-1040 Roug	gh-in Overhead Mechanical Piping - L3	15	21-Oct-20	10-Nov-20	Rough	n Overhead Mechanical Piping - L3	1		
	gh-in Overhead Electrical Conduit - L3	20	21-Oct-20	18-Nov-20		h-in Overhead Electrical Conduit - L3			
	ne Electrical Closets - L3	3	04-Nov-20	06-Nov-20		Electrical Closets - L3			
	gh Fire Protection - L3	10	04-Nov-20	18-Nov-20		h Fire Protection - L3			
	5					· · · ·	. '	. 1	
-	of Effort Remaining Work		Page 9 of	14	TASK filter: % Complete <100.				
Actual Level of Eff	5					© Oracle Corporation	SKAN	SKA	
Actual Work	♦ Milestone	1		Dere	366 of 377				

•	ol - Project C - 06Jun20 R1 Schedule Update - 1318015-CR		Chart		led Schedule
D	Activity Name	Remaining Duration	Start	Finish	2020 2021
		Duration			Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul
L3-1130	Install Above Ceiling Mechanical Equipment - L3	10	04-Nov-20	18-Nov-20	Instal Above Ceiling Mechanical Equipmer
L3-1080	Board & Tape Electrical Closets - L3	5	09-Nov-20	16-Nov-20	Board & Tape Electrical Closets - L3
L3-1090	Frame Interior Wals - L3	10	12-Nov-20	25-Nov-20	Frame Interior Walls - L3
L3-1450	Insulate Overhead Mechanical Piping & HVAC Ductwork - L3	15	12-Nov-20	04-Dec-20	Insulate Overhead Mechanical Piping &
L3-1120	Set Door Frames - L3	5	17-Nov-20	23-Nov-20	Set Door Frames - L3
L3-1110	Rough-in Plumbing In-Wall - L3	10	19-Nov-20	04-Dec-20	Rough-in Plumbing In-Wall - L3
L3-1100	Frame Soffits - L3	10	24-Nov-20	09-Dec-20	Frame Soffits - L3
L3-1140	Rough-in Electrical In-Wall & Pull Branch Circuits - L3	15	30-Nov-20	18-Dec-20	Rough-in Electrical In-Wall & Pull Bra
L3-1150	Rough-in Low Voltage In-Wall & Pull Wire - L3	15	30-Nov-20	18-Dec-20	Rough-in Low Voltage In-Wall & Pull \
L3-1160	Perform Wall & Ceiling Punch List & Inspections - L3	10	18-Dec-20	04-Jan-21	Perform Wall & Ceiling Punch List
L3-1170	Perform In-Wall Inspections with Town - L3	2	21-Dec-20	22-Dec-20	Perform In-Wall Inspections with Tow
L3-1180	Install Wood Blocking - L3	5	23-Dec-20	30-Dec-20	Install Wood Blocking - L3
L3-1330	Insulate In-Wall Piping - L3	5	23-Dec-20	30-Dec-20	Insulate In-Wall Piping - L3
L3-1190	Board Wals & Soffits - L3	10	01-Feb-21	12-Feb-21	Board Wals & Soffits - L3
L3-1210	Tape Walls & Soffits - L3	10	05-Feb-21	19-Feb-21	Tape Walls & Soffits - L3
L3-3050	Field Measure & Fab Interior Glass - L3	20	03-Feb-21	08-Mar-21	Field Measure & Fab Ir
L3-3050	Prime & 1st Coat walls - L3	6	22-Feb-21	01-Mar-21	Prime & 1st Coat walls -
L3-1220	Printe & Tst Coal Walls - L3 Paint Exposed Ceilings & MEPs at Classrooms & Offices - L3	10	22-Feb-21 22-Feb-21	01-Mar-21 05-Mar-21	Printe & Tst Coal waiis - Paint Exposed Ceilings
L3-1230 L3-1225	Install Ceiling Grid & Cut/DeviceTies at Classrooms & Offices - L2	5	22-Feb-21 25-Feb-21	03-Mar-21	 Paint Exposed Cellings Install Celling Grid & Cu
L3-1225 L3-3060	Install Wal Tile at Corridors - L3	10	25-Feb-21 25-Feb-21	10-Mar-21	Install Celling Grid & Cu
L3-1240	Install MEP Drops at Classrooms & Offices - L3	10	01-Mar-21	12-Mar-21	Install MEP Drops at C
L3-1235	Install Fume Hoods - L3	5	04-Mar-21	10-Mar-21	Install Fume Hoods - L
L3-1250	Install Storefront Frames - L3	10	09-Mar-21	22-Mar-21	Install Storefront Fra
L3-1260	Install Millwork at Classrooms & Offices - L3	10	15-Mar-21	26-Mar-21	Install Millwork at C
L3-1440	Install Teledata Finishes & Terminations - L3	10	15-Mar-21	26-Mar-21	Install Teledata Fini
L3-1390	Install Interior Glazing - L3	10	16-Mar-21	29-Mar-21	Install Interior Glaz
L3-1445	Install Fintube Radiators - L3	10	19-Mar-21	01-Apr-21	Install Fintube Rad
L3-1270	Install Ceiling Grid & Cut/DeviceTiles at Corridors - L3	5	25-Mar-21	31-Mar-21	Install Ceiling Grid
L3-1380	Install Flooring at Classrooms & Offices - L3	10	26-Mar-21	08-Apr-21	Install Flooring at
L3-1370	Install Doors & Hardware - L3	5	29-Mar-21	02-Apr-21	Install Doors & Ha
L3-1305	Install Railings at Opening - L3	5	01-Apr-21	07-Apr-21	Install Railings at
L3-1430	Install Fire Alarm Devices - L3	5	01-Apr-21	07-Apr-21	Install Fire Alarm
L3-1280	Install MEP Drops at Corridors - L3	8	01-Apr-21	12-Apr-21	Install MEP Drop
L3-3070	Install Laboratory Casework at Classrooms - L3	10	01-Apr-21	14-Apr-21	Install Laborator
L3-1285	Install Fintube Covers - L3	10	02-Apr-21	15-Apr-21	📕 Install Fintube C
L3-3080	Install Plumbing Fixtures at Classrooms & Offices - L3	10	07-Apr-21	21-Apr-21	📕 Install Plumbing
L3-1300	Install Terrazzo at Corridors - L3	18	16-Apr-21	12-May-21	Install Terra
L3-1360	Install Terrazzo Base at Corridors - L3	10	04-May-21	17-May-21	🔲 Install Terr
L3-1320	Install AV - L3	5	11-May-21	17-May-21	Install AV -
L3-1340	Install Whiteboards & Tack Boards - L3	5	11-May-21	17-May-21	Instal) Whi
L3-1350	Install Window Shades - L3	5	11-May-21	17-May-21	Install Win
L3-1400	Construction Cleaning - L3	5	18-May-21	24-May-21	Construc
L3-1290	Balance HVAC - L3	5	25-May-21	01-Jun-21	Balance
L3-1410	Skanska Punch List - L3	5	25-May-21	01-Jun-21	Skansk
L3-1410	Architect Punch List - L3	5	02-Jun-21	01-301-21 08-Jun-21	
Bathrooms		5	02-001-21	00.001-21	
L3-1600	Board & Install Cement Board - L3 Bathrooms	5	01-Feb-21	05-Feb-21	Board & Install Cement Boa
L3-1605	Tape & Finish - L3 Bathrooms	5	01-Feb-21 08-Feb-21	12-Feb-21	Tape & Finish - L3 Bathroo
L3-1605	Prime Paint - L3 Bathrooms	3	16-Feb-21	12-Feb-21 18-Feb-21	Prime Paint - L3 Bathroon
L3-1615	Install Counters - L3 Bathrooms	2	19-Feb-21	22-Feb-21	Install Counters - L3 Bath
L3-1620	Install Wal & Floor Tile - L3 Bathrooms	10	23-Feb-21	08-Mar-21	Install Wal & Floor Tile
L3-1625	Install Plumbing Fixtures - L3 Bathrooms	5	09-Mar-21	15-Mar-21	Install Plumbing Fixtu
L3-1630	Field Measure & Fab Mirrors - L3 Bathrooms	10	09-Mar-21	22-Mar-21	Field Measure & Fa
L3-1635	Install Toilet Partitions - L3 Bathrooms	4	16-Mar-21	19-Mar-21	Install Toilet Partition
L3-1640	Install Bathroom Accessories - L3 Bathrooms	4	22-Mar-21	25-Mar-21	Install Bathroom Ac
-	Level of Effort Remaining Work		Page 10 o	f 14	TASK filter: % Complete <100. © Oracle Co

Data Date: 06-Jun-20 / Run Date: 09-Jul-20 08:50 2022)23 ep[Oct|Nov]Dec]Jan]Feb[Mar]Apr]May]Jun]Jul]Aug]Sep]Oct]Nov]Dec[lan] Ductwork - L3 cuits-L3 ctions-L3 lass - L3 at Classrooms & Offices - L3 Tiles at Classrooms & Offices - L2 _3 ms & Offices - L3 3 ns & Offices - L3 erminations - L3 L3 İ eviceTiles at Corridors - L3 oms & Offices - L3 L3 - L3 - Ľ3 ridors - L3 vork at Classrooms - L3 L3 s at Classrooms & Offices - L3 orridors - L3 se at Corridors - L\$ & Tack Boards - L3 ides - L3 aning - L3 L3 n List - L3 ch List - L3 athrooms throoms Bathrooms s - L3 Bathrooms athrooms es - L3 Bathrooms

SKANSKA

y ID	Activity Name	Remaining	Start	Finish	
y ID		Duration	Sidiri	1 11 11511	2020 2021
L3-1645	Install Mirrors - L3 Bathrooms	2	26-Mar-21	29-Mar-21	Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Install Mirrors - L3 Bathrooms
L3-1650	Finish Paint - L3 Bathrooms	2	30-Mar-21	31-Mar-21	Finish Paint - L3 Bathrooms
Level 1		2	30-1viai - 2 1	51-1vidi-21	
L1-1010	Install MEP Risers - L1	10	06-Oct-20	20-Oct-20	Install MEP Risers - L1
L1-1000	Install Tube Steel Wall Supports - L1	5	21-Oct-20	27-Oct-20	Install Tube Steel Wall Supports - L1
L1-1020	Rough-in Overhead Ductwork - L1	15	04-Nov-20	25-Nov-20	Rough-in Overhead Ductwork - L1
L1-1030	Rough-in Overhead Plumbing - L1	15	04-Nov-20	25-Nov-20	Rough-in Overhead Plumbing - L1
L1-1040	Rough-in Overhead Mechanical Piping - L1	15	12-Nov-20	04-Dec-20	Rough-in Overhead Mechanical Piping - L1
L1-1050	Rough-in Overhead Electrical Conduit - L1	20	12-Nov-20	11-Dec-20	Rough-in Overhead Electrical Conduit - L1
L1-1060	Frame Electrical Closets - L1	3	30-Nov-20	02-Dec-20	Frame Electrical Closets - L1
L1-1070	Rough Fire Protection - L1	10	30-Nov-20	11-Dec-20	Rough Fire Protection - L1
L1-1130	Install Above Ceiling Mechanical Equipment - L1	10	30-Nov-20	11-Dec-20	Install Above Ceiling Mechanical Equipment - L1
L1-1080	Board & Tape Electrical Closets - L1	5	03-Dec-20	09-Dec-20	Board & Tape Electrical Closets - L1
L1-1090	Frame Interior Wals - L1	10	07-Dec-20	18-Dec-20	Frame Interior Wals - L1
L1-1450	Insulate Overhead Mechanical Piping & HVAC Ductwork - L1	15	07-Dec-20	28-Dec-20	Insulate Overhead Mechanical Piping & HVA
L1-1120	Set Door Frames - L1	5	10-Dec-20	16-Dec-20	Set Door Frames - L1
L1-1110	Rough-in Plumbing In-Wall - L1	10	14-Dec-20	28-Dec-20	Rough-in Plumbing In-Wall - L1
L1-1100	Frame Soffits - L1	10	17-Dec-20	31-Dec-20	Frame Soffits - L1
L1-1140	Rough-in Electrical In-Wall & Pull Branch Circuits - L1	15	21-Dec-20	12-Jan-21	Rough-in Electrical In-Wall & Pull Branch C
L1-1150	Rough-in Low Voltage In-Wall & Pull Wire - L1	15	21-Dec-20	12-Jan-21	Rough-in Low Voltage In-Wall & Pull Wire
L1-1160	Perform Wall & Ceiling Punch List & Inspections - L1	10	12-Jan-21	26-Jan-21	Perform Wall & Ceiling Punch List & Ins
L1-1170	Perform In-Wall Inspections with Town - L1	2	13-Jan-21	14-Jan-21	I Perform In-Wall Inspections with Town - L
_1-1180	Install Wood Blocking - L1	5	15-Jan-21	22-Jan-21	Install Wood Blocking - L1
_1-1330	Insulate In-Wall Piping - L1	5	15-Jan-21	22-Jan-21	Insulate In-Wall Piping - L1
_1-1190	Board Walls & Soffits - L1	10	16-Feb-21	01-Mar-21	Board Wals & Soffits - L1
L1-1210	Tape Walls & Soffits - L1	10	22-Feb-21	05-Mar-21	Tape Walls & Soffits - L1
L1-3050	Field Measure & Fab Interior Glass - L1	20	23-Feb-21	22-Mar-21	Field Measure & Fab Interior (
L1-1230	Paint Exposed Ceiling at Makerspace - L1	3	08-Mar-21	10-Mar-21	Paint Exposed Ceiling at Makers
1-1220	Prime & 1st Coat Wals - L1	6	08-Mar-21	15-Mar-21	Prime & 1st Coat Wals - L1
_1-1225	Install Ceiling Grid & Cut/DeviceTies at Classrooms & Offices - L1	5	11-Mar-21	17-Mar-21	Install Ceiling Grid & Cut/Device
.1-1333	Install Unistrut Grid at Makerspace - L1	5	11-Mar-21	17-Mar-21	Install Unistrut Grid at Makersp
.1-3060	Install Wal Tile at Corridors - L1	10	11-Mar-21	24-Mar-21	Install Wall Tile at Corridors -
_1-1240 _1-3070	Install MEP Drops at Classrooms & Offices - L1 Install Overhead Garage Doors - L1	5	15-Mar-21 18-Mar-21	26-Mar-21 24-Mar-21	Install MEP Drops at Classro
_1-3070	Install Storefront Frames - L1	10	23-Mar-21	05-Apr-21	Install Overhead Galage Doo
_1-1230 _1-1440	Install Teledata Finishes & Terminations - L1	10	29-Mar-21	09-Apr-21	Install Stoler on Frances - I
.1-1260	Install Millwork at Classrooms & Offices - L1	10	30-Mar-21	12-Apr-21	Install Millwork at Classroo
L1-1390	Install Interior Glazing - L1	10	30-Mar-21	12-Apr-21	Install Interior Glazing - L1
L1-1445	Install Fintube Radiators - L1	10	05-Apr-21	16-Apr-21	Install Fintube Radiators -
L1-1275	Install Simulated Wood Aluminum Ceiling Panel System - L1	20	06-Apr-21	04-May-21	Install Simulated Wood
L1-1270	Install Ceiling Grid & Cut/DeviceTies at Corridors - L1	5	09-Apr-21	15-Apr-21	■ Install Ceiling Grid & Cut/E
L1-1380	Install Flooring at Classrooms & Offices - L1	10	12-Apr-21	26-Apr-21	Install Flooring at Classr
L1-1370	Install Doors & Hardware - L1	5	13-Apr-21	20-Apr-21	Install Doors & Hardware
L1-1280	Install MEP Drops at Corridors - L1	15	16-Apr-21	07-May-21	Install MEP Drops at C
L1-1285	Install Fintube Covers - L1	10	20-Apr-21	03-May-21	Install Fintube Covers
L1-1430	Install Fire Alarm Devices - L1	5	05-May-21	11-May-21	Install Fire Alarm Dev
L1-1300	Install Terrazzo at Corridors - L1	18	10-May-21	03-Jun-21	Install Terrazzo at
L1-1360	Install Terrazzo Base at Corridors - L1	10	25-May-21	08-Jun-21	📕 Install Terrazzo E
L1-1320	Install AV - L1	5	02-Jun-21	08-Jun-21	Install AV - L1
L1-1340	Install Whiteboards & Tack Boards - L1	5	02-Jun-21	08-Jun-21	Install Whiteboar
L1-1350	Install Window Shades - L1	5	02-Jun-21	08-Jun-21	Install Window S
L1-1400	Construction Cleaning - L1	5	09-Jun-21	15-Jun-21	Construction C
L1-1290	Balance HVAC - L1	5	16-Jun-21	22-Jun-21	Balance HVAC
L1-1410	Skanska Punch List - L1	5	16-Jun-21	22-Jun-21	Skanska Pun
L1-1420	Architect Punch List - L1	5	23-Jun-21	29-Jun-21	Architect Pur
 Remaining Actual Lev Actual Wo 	-		Page 11 of		TASK filter: % Complete <100. © Oracle Corporation 368 of 377

Data Date: 06-Jun-20 / Run Date: 09-Jul-20 08:50 2022 |23 ep | Oct |Nov | Dec | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | Ian AC Ductwork - L1 Circuits - L1 e - L1 spections - L1 L1 Glass - L1 rspace - L1 iceTiles at Classrooms & Offices - L1 space - L1 - Ľ1 rooms & Offices - L1 oors - L1 L1 & Terminations - L1 ooms & Offices - L1 _1 ¦ s - Ļ1 od Aluminum Ceiling Panel System - L1 t/DeviceTiles at Corridors - L1 srooms & Offices - L1 re - L1 Corridors - L1 s - L1 vices - L1 at Corridors - L1 Base at Corridors - L1 ards & Tack Boards - L1 Shades - L1 Cleaning - L1 AC - L1 nch List - L1 un¢h List - L1

SKANSKA

-	ol - Project C - 06Jun20 R1 Schedule Update - 1318015-CR	Demoint 1	Otor!		ed Schedule			Data Date: 06-Jun-20 / Run Date: 09-Jul-20 08:50			
/ ID	Activity Name	Remaining Duration	Start	Finish	2020)21		2022		
					Jun Jul Aug Sep Oct Nov Dec Jan Fel	eb[Mar Apr May]Jun	Jul Aug Sep Oct Nov De	c Jan Feb Mar	Apr May Jun Jul Au	g Sep Oct Nov	
Bathrooms											
L1-1600	Board & Install Cement Board - L1 Bathrooms	5	16-Feb-21	22-Feb-21		1	ent Board - L1 Bathrooms				
L1-1605	Tape & Finish - L1 Bathrooms	5	23-Feb-21	01-Mar-21		Tape & Finish - L1		 			
L1-1610	Prime Paint - L1 Bathrooms	3	02-Mar-21	04-Mar-21		Prime Paint - L1 B		1			
L1-1615	Install Counters - L1 Bathrooms	2	05-Mar-21	08-Mar-21		Install Counters -		1			
L1-1620	Install Wal & Floor Tile - L1 Bathrooms	10	09-Mar-21	22-Mar-21			oor Tile - L1 Bathrooms		1 I 1 I 1 I		
L1-1625	Install Plumbing Fixtures - L1 Bathrooms	5	23-Mar-21	29-Mar-21			ig Fixtures - L1 Bathrooms				
L1-1630	Field Measure & Fab Mirrors - L1 Bathrooms	10	23-Mar-21	05-Apr-21			e & Fab Mirrors - L1 Bathroon	าร' -	' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' '		
L1-1635	Install Toilet Partitions - L1 Bathrooms	4	30-Mar-21	02-Apr-21			Partitions - L1 Bathrooms				
L1-1640	Install Bathroom Accessories - L1 Bathrooms	4	05-Apr-21	08-Apr-21			oom Accessories - L1 Bathroo	ms			
L1-1645	Install Mirrors - L1 Bathrooms	2	09-Apr-21	12-Apr-21			rs - L1 Bathrooms				
L1-1650	Finish Paint - L1 Bathrooms	2	13-Apr-21	14-Apr-21		Finish Pain	t - L1 Bathrooms	Ì			
Servery						· · · · · · · · · · · · · · · · · · ·	 				
L1KIT-1000	Frame Wals - L1 Kitchen	5	21-Dec-20	28-Dec-20		Wals - L1 Kitchen		Ì			
L1KIT-1010		10	29-Dec-20	12-Jan-21		gh-in Plumbing In-Wall		1			
L1KIT-1020		5	13-Jan-21	20-Jan-21		ugh-in Electrical In-Wa					
L1KIT-1030	Perform In-Wall Inspections with Town & Punch List - L1 Kitchen	5	21-Jan-21	27-Jan-21		-	ons with Town & Punch List - I	1 Kitchen			
L1KIT-1040	Install Wood Blocking - L1 Kitchen	3	28-Jan-21	01-Feb-21		nstall Wood Blocking -			, , , , , , , , , , , , , , , , , , ,		
L1KIT-1050	Board Wals - L1 Kitchen	3	25-Feb-21	01-Mar-21		Board Walls - L1 K		1			
L1KIT-1060	Tape & Finish Walls - L1 Kitchen	3	02-Mar-21	04-Mar-21		Tape & Finish Wal					
L1KIT-1070		3	05-Mar-21	09-Mar-21			Coat Walls - L1 Kitchen				
L1KIT-1845		5	10-Mar-21	16-Mar-21			s Reinforced Panels - L1 Kitch				
L1KIT-1080	Install Ceiling Grid & Cut/Device Tiles - L1 Kitchen	3	17-Mar-21	19-Mar-21			rid & Cut/Device Tiles - L1 Kitc	hện	· · · · · · · · · · · · · · · · · · ·		
L1KIT-1855		5	17-Mar-21	23-Mar-21			Cooler/Freezer - L1 Kitchen				
L1KIT-1085	Install Simulated Wood Aluminum Ceiling Panels - L1 Kitchen	6	22-Mar-21	29-Mar-21			ed Wood Aluminum Ceiling Par				
L1KIT-1090	Install MEP Drops at Ceiling Grid - L1 Kitchen	5	25-Mar-21	31-Mar-21		1	rops at Ceiling Grid - L1 Kitche	n			
L1KIT-1100		5	01-Apr-21	07-Apr-21			g Punch List - L1 Kitchen	1			
L1KIT-1110		10	01-Apr-21	14-Apr-21			Tile - L1 Kitchen	. 	; !		
L1KIT-1120		3	15-Apr-21	20-Apr-21			xy Flooring - L1 Kitchen	1			
L1KIT-1130	0	5	21-Apr-21	27-Apr-21			rrazzo Flooring - L1 Kitchen				
L1KIT-1135		2	28-Apr-21	29-Apr-21			verhead Garage Doros - L1 Ki				
L1KIT-1140		10	30-Apr-21	13-May-21		1	Kitchen Equipment - L1 Kitche	1			
L1KIT-1775		5	14-May-21	20-May-21			Il Plumbing Connections to Kite				
L1KIT-1785	Install Electrical Connections to Kitchen Equipment - L1 Kitchen	5	19-May-21	25-May-21			all Electrical Connections to Kit	chen Equipment	L1 Kitchen		
L1KIT-1795		3	26-May-21				all Ceiling Tile - L1 Kitchen				
L1KIT-1815	· · · · · · · · · · · · · · · · · · ·	10	26-May-21	09-Jun-21			tartup & Test Kitchen/Kitchen I		tchen		
L1KIT-1825		3	01-Jun-21	03-Jun-21		1	st & Balance HVAC - L1 Kitche				
L1KIT-1835		1	10-Jun-21	10-Jun-21	·····		oard of Health Inspections - L	Kitchen	i 		
Stair Finishes											
Stair 1	Energy Mills Obtin 4		04 Nov 00	40 Nov 00		Otain 4		1			
ST1-1000	Frame Wals - Stair 1	5	04-Nov-20	10-Nov-20	Frame Wals - S						
ST1-1010	Rough-in In-Wall Electric - Stair 1	3	12-Nov-20	16-Nov-20		/all Electric - Stair 1					
ST1-1020	Board Walls - Stair 1	3	01-Feb-21	03-Feb-21		Board Walls - Stair 1			, , , , , , , , , , , , , , , , , , ,		
ST1-1030	Tape & Finish Walls - Stair 1	4	04-Feb-21	09-Feb-21		Tape & Finish Walls -					
ST1-1040	Prime Paint Walls & Stairs - Stair 1	3	10-Feb-21	12-Feb-21		Prime Paint Walls & S					
ST1-1050	Install Tile Walls - Stair 1	5	16-Feb-21	22-Feb-21		Install Tile Walls - S	-				
ST1-1100	Install Wood Wall Panels - Stair 1	10	23-Feb-21	08-Mar-21		Install Wood Wall					
ST1-1060	Install Wal Raings - Stair 1	3	09-Mar-21	11-Mar-21		Install Wal Rain	F		i 		
ST1-1070	Finish Paint Stairs - Stair 1	2	12-Mar-21	15-Mar-21		Finish Paint Stai					
ST1-1090	Install Terrazzo Treads - Stair 1	5	16-Mar-21	22-Mar-21		Install Terrazzo	Treads - Stair 1				
Stair 2		10	40.11 00			04-1-10					
ST2-1000	Frame Wals - Stair 2	10	12-Nov-20	25-Nov-20	Frame Wals	1					
ST2-1010	Rough-in In-Wall Electric - Stair 2	5	30-Nov-20	04-Dec-20	· · · · · · · · · · · · · · · · · · ·	n-Wall Electric - Stair 2			, , , , , , , , , , , , , , , , , , ,		
ST2-1020	Board Walls - Stair 2	10	08-Feb-21	22-Feb-21		Board Walls - Stair					
ST2-1030	Tape & Finish Walls - Stair 2	10	23-Feb-21	08-Mar-21		Tape & Finish Wa	his - Stair 2			1	
Remaining	Level of Effort Remaining Work		Page 12 c	of 14	TASK filter: % Complete <100.						
Actual Lev	vel of Effort Critical Remaining Work		-			© Orac	e Corporation	CL	/ANCV/		
Actual Wo	-			Page 3	69 of 377			21	(ANSK/		
					1						



ID	Activity Name	Remaining	Start	Finish		
		Duration	Start	1 111311	2020 2021	2022
					lun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Se	p Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov
ST2-1040	Prime Paint Walls & Stairs - Stair 2	5	09-Mar-21	15-Mar-21	Prime Paint Walls & Stairs - S	air 2
ST2-1050	Install Tile Walls - Stair 2	15	16-Mar-21	05-Apr-21	Install Tile Walls - Stair 2	
ST2-1060	Install Wal Railings - Stair 2	5	06-Apr-21	12-Apr-21	Install Wal Raings - Stai	
ST2-1070	Paint Railings & Finish Paint Stairs - Stair 2	5	13-Apr-21	20-Apr-21	Paint Railings & Finish F	Paint Stairs - Stair 2
ST2-1080	Install Light Fixtures - Stair 2	2	21-Apr-21	22-Apr-21	I Install Light Fixtures - S	
ST2-1090	Install Terrazo Treads - Stair 2	10	23-Apr-21	06-May-21	Install Terrazo Tread	
Stair 3		10	2070121			
ST3-1000	Frame Wals - Stair 3	10	30-Nov-20	11-Dec-20	Frame Walls - Stair 3	
ST3-1000	Rough-in In-Wall Electric - Stair 3	5	14-Dec-20	18-Dec-20	Rough-in In-Wall Electric - Stair 3	
ST3-1020	Board Wals - Stair 3	10	23-Feb-21	08-Mar-21	Board Walls - Stair 3	
ST3-1030	Tape & Finish Walls - Stair 3	10	09-Mar-21	22-Mar-21	Tape & Finish Walls - Stair 3	
ST3-1040	Prime Paint Walls & Stairs - Stair 3	5	23-Mar-21	29-Mar-21	Prime Paint Walls & Stairs -	
ST3-1060	Install Wal Railings - Stair 3	10	30-Mar-21	12-Apr-21	📕 Install Wal Raings - Stai	r 3
ST3-1070	Paint Railings & Finish Paint Stairs - Stair 3	5	13-Apr-21	20-Apr-21	Paint Railings & Finish F	
ST3-1080	Install Light Fixtures - Stair 3	2	21-Apr-21	22-Apr-21	Install Light Fixtures - S	tair 3
ST3-1090	Seal Concrete Floor - Stair 3	5	07-May-21	13-May-21	Seal Concrete Floor	- Stair 3
lardscapes &	Landscaping			·		
5500	Install Hardscapes & Landscaping	45	16-Apr-21	21-Jun-21	Install Hards	capes & Landscaping
General				1		
GEN-1000	Install Building Signage	15	20-May-21	10-Jun-21	Install Building	Signage
Commissionin						
COMM-1000	-	60	10-Jun-21	02-Sep-21		Commission MEPs
		00	10-3011-21	02-3ep-21		
-	Inspections & Occupancy					
Plumbing Sys						
LSI-1160	Perform Potable Water Chlorination	5	21-May-21	27-May-21	Perform Potable	
LSI-1220	Issue Potable Water Chlorination Report	0		27-May-21	♦ Issue Potable Wa	ter Chlorination Report
Water & Sewe	er System					
LSI-1240	Acquire GSA Permit	1	28-May-21	28-May-21	I Acquire GSA Per	mit
Emergency P	Power System & Power Outage Testing					
LSI-1140	Ceilings, Lights & Exit Signs Complete	0		28-May-21	♦ Ceilings, Lights 8	Exit Signs Complete
LSI-1250	Pre-test for Lights Out Testing	1	01-Jun-21	01-Jun-21	I Pre-test for Ligh	s Out Testing
LSI-1300	Correct Issues for Brookline Lights Out Testing	2	02-Jun-21	03-Jun-21		or Brookline Lights Out Testing
LSI-1320	Perform Lights Out Testing with Brookline	1	04-Jun-21	04-Jun-21		Dut Testing with Brookline
Fire Alarm Sy		•	01001121	or our Er		
LSI-1030	Test Fire Alarm - Basement Level Devices, Speakers & Duct Smokes	2	12-May-21	13-May-21	I Test Fire Alarm Ba	sement Level Devices, Speakers & Duct Smokes
	· · · · · · · · · · · · · · · · · · ·					
LSI-1060	NFPA 72 Fire Alarm Testing	21	12-May-21	10-Jun-21		
LSI-1070	Test Fire Alarm - L1 Devices, Speakers & Duct Smokes	2	14-May-21	17-May-21		Devices, Speakers & Duct Smokes
LSI-1090	Test Fire Alarm - L2 Devices, Speakers & Duct Smokes	2	18-May-21	19-May-21	!	2 Devices, Speakers & Duct Smokes
LSI-1110	Test Fire Alarm - L3 Devices, Speakers & Duct Smokes	2	20-May-21	21-May-21		3 Devices, Speakers & Duct Smokes
LSI-1370	Submit Record of Completion (ROC) to Brookline	5	11-Jun-21	17-Jun-21	Submit Recor	d of Completion (ROC) to Brookline
LSI-1420	Brookline ROC NFPA 72 Test	3	18-Jun-21	22-Jun-21	Brookline RC	OC NFPA 72 Test
Elevators						
LSI-1310	Preliminary Test Elevator with Fire Alarm Recall	3	19-May-21	21-May-21	Preliminary Test E	evator with Fire Alarm Recall
LSI-1390	Complete Elevator Cleaning & Adjustment for Inspection	10	24-May-21	07-Jun-21		tor Cleaning & Adjustment for Inspection
LSI-1470	Complete Phone Service to Elevators	0	- ,	07-Jun-21		e Service to Elevators
LSI-1480	State (Mass 524) Inspection & Signoff	3	08-Jun-21	10-Jun-21		4) Inspection & Signoff
Fire Protectio		0	00 001121	10 0011 21		
	•	5	01 Jun 21	07 Jun 21	Elow Tost Eiro	Protoction System
LSI-1000	Flow Test Fire Protection System	5	01-Jun-21	07-Jun-21	Flow Test Fire	
LSI-1020	Checkout Tampers & Flows	1	08-Jun-21	08-Jun-21		
LSI-1350	Test Stand Pipe & Floor Control Valves with PRVs - Stair 2	2	09-Jun-21	10-Jun-21		e & Floor Control Valves with PRVs - Stair 2
LSI-1520	Test Stand Pipe & Floor Control Valves with PRVs - Stair 3	2	11-Jun-21	14-Jun-21		e & Floor Control Valves with PRVs - Stair 3
LSI-1450	Brookline Fire Protection Test	1	23-Jun-21	23-Jun-21	I Brookline Fir	e ₽rotection Test
Final Inspecti	ions & C of O					
INSP-1050	Owner Install FF&E	10	27-May-21	10-Jun-21	Owner Install F	F&E
LSI-1230	Final Plumbing Signoff	1	28-May-21	28-May-21	Final Plumbing Si	
			,			
Remaining	g Level of Effort Remaining Work		Page 13 o	f 14	TASK filter: % Complete <100.	
 Actual Lev 	vel of Effort Critical Remaining Work				© Oracle Corporation	SKANSKA



Brookline High Scho	ool - Project C - 06Jun20 R1 Schedule Update - 1318015-CR			Deta	led Schedule		Data Date: 06-Jun-20 / Run Date: 09-Jul-20 08:50
Activity ID	Activity Name	Remaining Duration	Start	Finish	2020 Jun Jul Aug Sep Oct Nov Dec	2021 Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec	2022 2 Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec la
LSI-1340	Final Electrical Signoff	1	07-Jun-21	07-Jun-21		I Final Electrical Signoff	
INSP-1030	Complete Punch List	20	23-Jun-21	21-Jul-21		Complete Punch List	
LSI-1490	Final Life Safety Wak-thru	2	24-Jun-21	25-Jun-21		Final Life Safety Walk-thru	
LSI-1460	Receive Final Architectural, Mechanical & Structural Affadavits	2	28-Jun-21	29-Jun-21		Receive Final Architectural, M	echanical & Structural Affadavits
INSP-1010	Final Building Sigh Off Acquire C of O	5	30-Jun-21	07-Jul-21		Final Building Sigh Off Acquir	e C of O
INSP-1020	STEM Interim Completion Date	0		07-Jul-21*		STEM Interim Completion Date	te
INSP-1040	Move-in to New STEM Wing	10	08-Jul-21	21-Jul-21		Move-in to New STEM Wi	ng

Remaining Level of Effort Remaining Work	Page 14 of 14	TASK filter: % Complete <100.
Actual Level of Effort Critical Remaining Work		© Oracle Corporation
Actual Work Milestone	Page 37	1 of 377

Data Date: 06- lun-20 /	Run Date: 09-Jul-20 08:50
Data Date. 00-Juli-20 /	Run Dale. 09-Jui-20 00.50



Skanska USA Building Inc Brookline High School Improvements

Name	Position/Role	Hourly Billing Rate	Month 1	Month 2	Month 3	Project Final Budget	
					2 weeks		
Dan Lanneville	Account Mngr					\$-	
Jim Craft	Project Executive		0.175	0.04375		\$ 6,941	
Peter Roche	Senior PM		0.35	0.0875		\$ 9,398	
Rob Mulligan	Senior PM		0.35	0.0875		\$ 10,743	
Timothy Landry	EHS Manager		0.35	0.0875		\$ 5,076	
Mark Pener	Scheduling		0.07	0.0175		\$ 2,276	
Matt Emond	BIM Coordination		0.07	0.0175		\$ 1,602	
Anna Lee	Accountant		0.35	0.0875		\$ 5,463	
Lauren Daly	Administrator		0.175	0.04375		\$ 2,278	
Jamie Simon ©	Project Manager		1	1	0.5	\$ 39,637	
Tom Melanson ©	APM		1	1	0.5	\$ 26,021	
Chris Roche ©	MEP PE		1	1	0.5	\$ 19,643	
Office Coop 1 - Evan ©	Intern		0.35	0.0875		\$ 3,006	
Steve Papastephanou ©	Superintendent		1	1	0.5	\$ 44,345	
Brigitte Perera ©	A Super		1	1	0.5	\$ 22,543	
Mike Pugh (A)	Project Manager					\$-	
Paul Swetz (A)	Project Engineer					\$-	
Robert Koenig (50% A 50% H)	Senior PM					\$-	
Office Coop 2 - Troy Deluca	Intern		0.35	0.0875		\$ 2,260	
Nathan Moore (A)	MEP PE					\$-	
Connor Hennessey	APM					\$-	
Steve Brown	Cost Engineer		0.35	0.0875		\$ 5,886	
Mike Gear (A&C)	Sr Super		0.35	0.0875		\$ 9,573	
Adam Farrrar (A)	Superintendent					\$-	
Assist Super (A)	A Super					\$-	
		Monthly Budget	\$ 112,479	\$ 73,777	\$ 30,438	\$ 216,694	

Subtotal of GC Labor Fore	Subtotal of GC Labor Forecast (Above)							
GC Non-labor Forecast (Nex	: Worksheet)	\$	10,881					
Total	Total	\$	227,575					

GC Table A Projections

PARKING PROJECTION	Month 1		Month 2		Month 3		Total	
						2 weeks		
Bryan Northrop								
Dan Lanneville								
Jim Craft								
Peter Roche								
Rob Mulligan					-			
Timothy Landry	\$	114	\$	28			\$	14
Mark Pener	\$	21	\$	5			\$	2
Matt Emond	\$	21	\$	5			\$	2
Anna Lee	\$	21	\$	5			\$	2
Lauren Daly	\$	114	\$	28			\$	14
Jamie Simon ©	\$	325	\$	325	\$	163	\$	65
Tom Melanson ©	\$	325	\$	325	\$	163	\$	65
Chris Roche ©			\$	-	\$	-	\$	-
Office Coop 1 - Evan ©			\$	-	\$	-	\$	-
Steve Papastephanou ©			\$	-	\$	-	\$	-
Brigitte Perera ©			\$	-	\$	-	\$	-
Mike Pugh (A)			\$	-	\$	-	\$	-
Paul Swetz (A)			\$	-	\$	-	\$	-
Robert Koenig (50% A 50% H)			\$	-	\$	-	\$	-
Office Coop 2 - TBD			\$	-	\$	-	\$	-
Nathan Moore (A)			\$	-	\$	-	\$	-
Assist PM (A)			\$	-	\$	-	\$	-
Mike Gear (A)			\$	-	\$	-	\$	-
Assist Super (A)			\$	-	\$	-	\$	-
Marc Contrado			\$	-	\$	-	\$	-
Jose Tormey			\$	-	\$	-	\$	-
Table A Items			\$	-	\$	-		
Consultants (Firesafing, Mold Hygienist, Temp Engineer	0		ې \$		ې \$			
	Ĺ,	2.675			Ş	-	ć	7.00
Trailer Rent	Ş	3,675		3,675			\$	7,35
Storage Rent	\$	105	\$	105			\$	21
Office Furn. & Equipment	\$	-	\$	-			\$	-
Postage & Delivery	\$	53	\$	13			\$	6
Prints/Reprographics	\$	-	\$	-			\$	-
Topping Off/Safety Week							\$	-
StructionSite	\$	-	\$	-			\$	-
MILEAGE	\$	-	\$	-			\$	-
DRINKING WATER	\$	140	\$	35			\$	17
COPY MACHINES	\$	490	\$	490			\$	98
FIRST AID/Safety	\$	350	\$	88			\$	43
SAFETY TRAINING	\$	-	\$	-			\$	-
TOTAL		5,753	-	5,128	\$	325	\$	10,88
		Month 1		Month 2		Month 3		Total

SUMMARY GENERAL + PROJECT C General Requirements for Schedule Update PCCO 007

Phase/Category	CHANGE CONDITION - PROJECT C
Forecasted GR Vendor Costs	
GENERAL	\$252,096
Project C: STEM	\$59,750
Forecasted Direct Costs to be Assigned to BP	
GENERAL	\$548
Project C: STEM	\$251,000
Forecasted Craft Labor	
Union Laborer	\$168,221
Union Carpenter	\$19,277
TOTAL	\$750,892

General Requirements for Schedule Update PCCO 007 PROJECT: General (All)

				Units	Unit Cost	Lump Sum Value	Total Estimated Value	Notes
Description	Month 1	Month 2	Month 3				Value	
Items from Table A			2 weeks					
Temporary and Permanent Utility Costs, backcharges and connection								OWNER ALLOWANCE. Electric and gas, temporary
fees				0	\$0	\$250,000	\$250,000	and permanent.
Winter Conditions & snow/ice removal				0	\$500	\$0	\$0	
Misc. Supplies	0.35	0.1875		0.5375	\$250	\$0	\$134	
Project Signage				0	\$100	\$0	\$0	
Temp fencing, enclosure, walk, barricade, stair Firefight equipment				0	\$45 \$0	\$0 \$0	\$0 \$0	
Security guards				0	\$0	\$0 \$0	\$0	Excluded
Police Details				0	\$0	\$0	\$0	
Offices (Rental in GC's)				0	\$0	\$0	\$0	In GC's
Set up				0	\$0	\$0	\$0	
Dismantle				0	\$0	\$0	\$0	
Interior Carpentry				0 0	\$0 \$0	\$0 \$0	\$0 \$0	
Sitework and Enabling Demobilization and Restoration				0	\$0 \$0	\$0 \$0	\$0 \$0	
Sanitary Supplies	0.35	0.1875		0.5375	\$0 \$250	\$0 \$0	\$134	
						-	* ·	
Phone / Internet	0.35	0.1875		0.5375	\$550	\$0	\$296	
Office Councilies	0.25	0.1075		0.5275	£1.500	to.	£00C	
Office Supplies Computer and Software	0.35	0.1875		0.5375 0	\$1,500 \$3,000	\$0 \$0	\$806 \$0	
Subsidence (Meals)	0.35	0.1875		0.5375	\$0	\$0	\$0	
Topping Off				0	\$10,000	\$0	\$0	
Recognition / Team Building				0	\$10,000	\$0	\$0	
Public Communications /Advertising	0.35	0.1875		0.5375	\$100	\$0	\$54	
-								
Progress Photos Laser Scanning	0.35	0.1875		0.5375 0	\$500 \$0	\$0 \$0	\$269 \$0	Allowance, not defined in specs. Excluded
Technology Fee				0	\$0 \$0	\$0 \$0	\$0 \$0	0.15%
Archiving Fees				0	\$0	\$0	\$0	0.01%
Check Processing Fees				0	\$0	\$0	\$0	Removed from GMP per Hill request
Precon Survey				0	\$0	\$0	\$0	
NFPA 241 Plans				0	\$0	\$0	\$0	
	0.25	0.4075						
CORI Supplies Control Survey	0.35	0.1875		0.5375 0	\$100 \$0	\$0 \$0	\$54 \$0	
Surveying and Layout				0	\$0 \$0	\$0 \$0	\$0 \$0	
PPE for staff and visitors	0.35	0.1875		0.5375	\$500	\$0	\$269	
AED's				0	\$3,000	\$0	\$0	
2 way radios				0	\$0	\$0	\$0	
Street permits / Rentals				0	\$0	\$0	\$0	By Owner
MBTA Force Account ALLOWANCE				0	\$0 \$0	\$0 \$0	\$0	By Owner
Fuel for Generator for Trailers				0	\$0	\$0 \$0	\$0	
Answering Service for CMP	0.35	0.1875		0.5375	\$150	\$0	\$81	
SUBTOTAL						SUBTOTAL	\$252,096	
Direct Cost to be Assigned to Bid Packages								
Pest Control	0.35	0.1875		0.5375	\$1,020	\$0	\$548	
Street Sweeping				0	\$15,400	\$0	\$0	See GMP for Owner Allowance
Pandemic PPE, Construction Material and GR Labor				0	\$25,000	\$0	\$0	\$25,000 unit cost is based on \$18,500 union labor
Pandemic PPE, Construction Material and GR Labor SUBTOTAL				U	৶᠘₯₢∠ঽড়	SUBTOTAL	\$0 \$548	and \$6,500 misc. vendor invoices and supplies.
GRAND TOTAL GENERAL					GRA	ND TOTAL GENERAL	\$252,645	

General Requirements for Schedule Update PCCO 007 PROJECT: Project C: STEM

				Units	Unit Cost	Lump Sum Value	Total Estimated Value	Notes
Description	Month 1	Month 2	Month 3 2 weeks					
Items from Table A								
Construction Equipment and Tools (Small Tools)	1	1	0.5	2.5	\$3,800	\$0	\$9,500	
Winter Conditions & snow/ice removal				0	\$6,000	\$0	\$0	
Snow Removal From Roof				0	\$5,000	\$0	\$0	
Debris and Trash Removal (Union Labor Foreman) Flagman / Traffic Control				0	\$13,000 \$0	\$0 \$0	\$0 \$0	Carried on a separate worksheet See Police Detail Allowance
			0.5					
Dust Control	1	1	0.5	2.5	\$500	\$0	\$1,250	Greensweep and dust control tools and supplies
Trash chutes and dumpsters				0 0	\$0 \$765	\$0 \$0	\$0 \$0	
Dumpsters Trash Chutes				0	\$765	\$0 \$0	\$0 \$0	
Staging for Access to Trash Chutes				0	\$0	\$0	\$0	
Temp Toilets	8	8	4	20	\$150	\$0	\$3,000	
Project Signage				0	\$100	\$0	\$0	
Safety railings, nets, ladders (Union Carpenter)				0	\$14,733	\$0	\$0	Carried on a separate worksheet
Firefight equipment	2	2	1	5	\$250	\$0	\$1,250	FE's and stands
Security guards				0	\$0	\$0	\$0	Excluded
Police Details - ALLOWANCE	1	1	0.5	2.5	\$14,400	\$0	\$36,000	ALLOWANCE \$50 per hour, assume 10 hour day with 20T, plus \$5 per hour admin fee from Town.
Other Items				0	\$0	\$0	\$0	
Surveying and Layout				0	\$1,500	\$0	\$0	
Air quality during construction. Enclosures, fans, air machines				0	\$1,000	\$0	\$0	
Fire Watch (Hotwork) ALLOWANCE				0	\$550	\$0	\$0	Bought with Trades
Fire Alarm Impairment ALLOWANCE				0	\$550	\$0	\$0	ALLOWANCE. \$500 per day plug in and out plus admin fee
Construction Materials (Temporary)	1	1	0.5	2.5	\$2,500	\$0	\$6,250	
Overhead wire protection / relocation				0		\$0	\$0	See utility allowance above
Hoisting	1	1	0.5	2.5	\$1,000	\$0	\$2,500	
Street permits / Rentals				0	\$0	\$0	\$0	By Owner
Barn Doors Loading Zones				0 0	\$0 \$0	\$0 \$0	\$0 \$0	
Mock Up Support				0	\$0	\$0	\$0	
SUBTOTAL				0	\$ 0	SUBTOTAL	\$59,750	
JODICITZ						JODICIAL	4357,50	
Direct Cost to be Assigned to Bid Packages								
Temporary Heating and Cooling				0	\$2,500	\$0	\$0	
Temporary Enclosures				0	\$15,000	\$0	\$0	
Temp fencing, enclosure, walk, barricade, stair	1	1	0.5	2.5	\$5,000	\$0	\$12,500	Rentals
OH Protection (Sidewalks)				0	\$350	\$0	\$0	
Temporary Scaffold Stairs	1	1	0.5	2.5	\$1,000	\$0	\$2,500	Rentals
Tarping For Masonry Winter Work				0	\$0	\$0	\$0	Included in GMP
Tarping For Building Winter Work (Curtainwall Openings)				0 0	\$0 \$0	\$0 \$0	\$0 \$0	
Temporary Protection of Windows and Snap Cover Comeback Heat for Masonry Winter Work				0	\$0	\$0 \$0	\$0 \$0	Included in GMP
Heat for Building Winter Work				0	\$0 \$0	\$0	\$0	Included in GMP
Elevator Operator (Final 3 Months)				0	\$0	\$0	\$0	
Foundation Waterproofing Protection				0	\$0	\$0	\$0	
Floor Flashing / Grinding				0	\$0	\$0	\$0	
Temporary Walkway Phasing				0	\$0	\$0	\$0	
Boiler Watch				0	\$0	\$0	\$0	Assumed not req'd. Use campus HW
Temporary rain leaders Selective Demolition (Unpurchased Scope)				0	\$0 \$0	\$0 \$0	\$0 \$0	
Selective Demolition (Unpurchased Scope) Winter tarping due to schedule impacts				U	φU	\$0 \$61,000	\$0 \$61,000	\$75K carried in lines above
Winter taiping due to schedule impacts Winter heating equipment due to schedule impacts						\$105,000	\$105,000	\$20K carried in lines above
Supplementary Heaters for Façade Work due to schedule impacts						\$0	\$0	\$50K carried in lines above
Fuel for winter heating due to schedule impacts						\$0	\$0	Carried on General Tab, Utility consumption
Temporary Heating Plan Revisions SUBTOTAL						\$0 SUBTOTAL	\$70,000 \$251,000	allowance. Moved from STEM
SUBIOIAL						JUDIUIAL	¥231,000	
Subtotal Project Requirements							\$310,750	

General Requirements for Schedule Update PCCO 007 FORECAST FOR CRAFT LABOR PROJECT: Project C: STEM

				40.00	40.00	40.00		
LABORERS/CARPENTERS			Wks	4.33	4.33	4.33		
Position	Рау Туре	Но	ourly Cost	Month 1	Month 2	Month 3	Total Estimated Value	
		4					•	
Steward Cypress/ STEM	Regular	\$	80.00	1.00	1.00	0.50	\$ -	
	Overtime	\$	105.00	1.00	1.00	0.50	\$ 45,465	
	Double Time	\$	129.00				\$-	
Labor Foreman STEM	Regular	\$	86.00	1.0	1.0	0.50	\$ 37,238	
	Overtime	\$	110.00	0.25	0.25	0.13	\$ 11,908	
	Double Time	\$	137.00				\$ -	
Daily Cleaning STEM (#1)	Regular	\$	80.00	1.0	1.0	0.50	\$ 34,640	
	Overtime	\$	105.00	0.25	0.25	0.13	\$ 11,366	
	Double Time	\$	129.00	0.23	0.23	0.15	\$ -	
Daily Cleaning STEM (#2)	Regular	\$	80.00		1.0	0.50	\$ 20,784	
	Overtime	\$	105.00		0.25	0.13	\$ 6,820	
	Double Time	\$	129.00		0.23	0.15	\$ -	
Daily Cleaning STEM (#3)	Regular	\$	80.00				\$ -	
	Overtime	\$	105.00				\$ -	
	Double Time	\$	129.00				\$ -	
Corportor Foromon	Degular	\$	106.00	0.25	0.35	0.25	\$ 19,277	
Carpenter Foreman	Regular			0.35	0.35	0.35		
Dave Daniels	Overtime Double Time	\$ \$	137.00 171.00				\$ - \$ -	
		\$	171.00				\$ -	
		-		62,672	81,075	43,750	\$ 187,498	