

Town Of Brookline

Contract Coding Approval Form

Department: BUILDING / DPW

Vendor Name : Cassidy Corp

Vendor Number : 59710 Amount of Contract \$ \$44,175

Contract # : PW 25-09

Purpose of Contact:

	Description:
	repave passageway abutting Driscoll School

Coding:

Org #	Org Name *	Acct #	Acct Name	Amount
2594C210	6C0002		Driscoll	\$44,175

* For "K" or "C" accounts, please call it "CIP", preceded by your Dept (e.g., 4909K001 would be "DPW CIP").

Department Head: _____ Date _____

Comptroller and Purchasing Approvals

Funds Available / Codes Correct _____
Comptroller
Date Approved by Comptroller

Complies with Appropriate Procurement Law _____
(MGL ch 149, ch 30 30M, or ch 30B)
Purchasing
Date Approved by Purchasing

FORM FOR GENERAL BID

THIS SECTION MUST BE FILLED OUT

I. CONTRACTOR INFORMATION

NAME OF COMPANY: CASSIDY CORP
ADDRESS: 53 FONDI ROAD
CITY/ST/ZIP: HAVERHILL, MA 01832
TELEPHONE: 866-978-9788 FAX: _____
EMAIL: DAN.DAMBRO@CASSIDYCORP.COM
SS NO.OR FID NO.: 900065873
PERSON BIDDING: DAN D'AMBROSIO 781-454-8521
TITLE: VICE PRESIDENT

BID PRICING SHEET

See Attached Bid Pricing Sheet

GRAND TOTAL:	\$ <u>44,175.00</u>
---------------------	----------------------------



FORM OF AGREEMENT
CONTRACT SIGNATURES

CONTRACTOR'S AUTHORIZED SIGNATORY:

The undersigned parties have signed or identified all parts of these documents; this contract being itself signed in these counterparts.

Daniel V. Ambrosio Daniel V. Ambrosio
SIGNATURE
Vice President 11-25-2024
TITLE DATE

BUILDING COMMISSION AUTHORIZED SIGNATORY:

<u></u> _____ Nathan Peck C7FD8E0A35E1495...	<u></u> _____ Brooke Duskin D40FEFDC1FA4BC...	_____ _____ _____
----------------------------------------------------------------------------------------------------------------------------------------	-----------------------------------------------------------------------------------------------------------------------------------------	-------------------------

SCHOOL COMMITTEE AUTHORIZED SIGNATORY:

_____	_____	_____
_____	_____	_____
_____	_____	_____

TOWN OF BROOKLINE SELECT BOARD AUTHORIZED SIGNATORY:

_____	_____	_____
_____	_____	_____

APPROVAL OF COMMISSIONER OF PUBLIC WORKS


The undersigned hereby approves this contract as to matters of form:

_____	_____
SIGNATURE	DATE

CERTIFICATION OF COMPTROLLER:

The undersigned hereby certifies, pursuant to M.G.L. c. 44, p. 31C, that an appropriation in the amount of this contract has been made and is available therefore. The undersigned hereby further certifies that an officer or agent of the Town of Brookline has been authorized to execute this contract and to approve all requisitions and change orders.

_____	_____
SIGNATURE	DATE
_____	_____
TITLE	DATE



Erin Chute
Commissioner
Daniel Murph, PE
Director

TOWN OF BROOKLINE
Massachusetts

DEPARTMENT OF PUBLIC WORKS
Engineering & Transportation Division
November 13, 2024

Request for Quotation

DRISCOLL SCHOOL- RECONSTRUCTION OF PASSAAGEWAY

Issue Date: November 13, 2024

Quote #: PW-25-09

Department: Public Works

Quote Due Date: Monday, November 18, 2024 @ 4:00 p.m.

Quotation is requested for goods and services listed on the attached *Quotation Form and Scope of Work* for the Passageway abutting Driscoll School, 725 Washington Street, Brookline, MA 02446 under the management of the Brookline Department of Public Works.

Please return quotation to:

Robert Kefalas, DPW
Town of Brookline
333 Washington Street
Brookline, MA 02445
Phone: 617-730-2316 fax: 617-713-3727
Email: rkefalas@brooklinema.gov

The following items are to be completed by the bidder and returned together with the completed *Quotation Form and Scope of Work*.

Quotation Date:	11-18-2024
Key Contact:	Dan D'Ambrosio (781-454-0521)
Company Name:	Cassidy Corp
Address:	53 Ford Road Haverhill, MA 01832
Email:	dan.dambrosio@cassidycorp.com
Telephone #:	866-978-9788
Authorized Signature:	Daniel D'Ambrosio

Sincerely,

Robert Kefalas
Project Engineer

Scope of Work

Driscoll School - Reconstruction of Passageway

PW/25-09

The purpose of this Contract is to:

Excavate the bituminous asphalt passageway along Driscoll School as shown on the plan and as directed by the engineer

Remove all excess and unsuitable materials, as determined by the engineer, which shall become the Contractor's property.

Adjust all structures as directed by the engineer

Add DGCS as directed by the engineer.

Re-grade and compact stabilized base.

Install two (2) inches of Bituminous Concrete Binder Course and one and a half (1 ½) inches of Bituminous Concrete Wearing Surface.

All quantities are approximate and are to be used only for comparison of Bids.

A site visit is strongly recommended. To schedule a site visit contact Robert Kefalas, rkefalas@brooklinema.gov. Site visit times will be arranged with each interested company at a mutually agreed time during normal business hours.

General Bidders must demonstrate expertise in similar construction and a record of completing projects on time and within budget. Bidders must have completed 3 municipal projects, of similar nature, in the last five (5) years. References shall be provided with bids to verify the bidder's experience record.

The Commissioner of Public Works reserves the right to increase or decrease quantities, as needed, to meet budget constraints. The Town will award the Contract to the lowest, responsible, qualified bidder, as determined by the Commissioner of Public Works.

Working hours will be Monday through Friday from 7:00 a.m. to 5 p.m.

SW-1

PW25-09 Quotation Form for Reconstruction of Passageway at Driscoll School
 Issue Date 13-Nov-24
 Department Public Works Engineering Division
 See attached Scope of Work, Specification, and Plan

Bid Pricing Sheet

Item Number	Contract Quantity	Description	Unit	Bid Unit Price	Bid Total
129.100	575	Bituminous Concrete Excavation @	Sqyare Yard	\$ 35 ⁰⁰	\$ 20,125 ⁰⁰
220.000	2	Structure Adjusted, E.C.C. @	Each	\$ 1,500 ⁰⁰	\$ 3,000 ⁰⁰
402.100	80	Dense Graded Crushed Stone for subbase @	Ton	\$ 50 ⁰⁰	\$ 4,000 ⁰⁰
702.100	110	Hot Mix Asphalt Pavement @	Ton	\$ 155 ⁰⁰	\$ 17,050 ⁰⁰
Forty Four thousand one hundred seventy five dollars TOTAL BID (written in Words) Zero cents				\$ 44,175 ⁰⁰	

Key Contact	Don D'Ambrosio (981-454-8521)
Company Name	Cassidy Corp
Phone Number	866-978-9788
Address	53 Ford Road - Haverhill, MA 01832
Email	don.dambrosio@cassidycorp.com
Authorized Signature	Daniel V. Ambrosio 11-18-2024

11/13/2024

S:\Contracts FY 2025\PW-25-09 Driscoll School Paving Passageway\PW 25-09 bid sheet

SECTION 129

BITUMINOUS CONCRETE EXCAVATION

DESCRIPTION

129.20 General

The Bituminous Concrete surface where shown on the plans or as directed by the Engineer, shall be broken up, excavated to the proposed grades, and the excavated material removed from the site to a Contractor-furnished disposal area.

CONSTRUCTION METHODS

129.60 General

Under the classification of Bituminous Concrete Excavation, the Contractor shall cut, break up, and remove the broken up material from the site to a Contractor-furnished disposal area. The edges of all excavated areas shall be cut on straight lines with vertical faces of sufficient depth to afford a butt joint of a minimum depth of one (1) inch wearing surface, or to a deeper depth if so directed by the Engineer. The cutting of all edges shall be by means of a power saw or as by such means as the Engineer shall direct. The excavated area shall then be reshaped and thoroughly compacted to the lines and grades as shown on the plans or as directed by the Engineer. The depth of Bituminous Concrete Excavation shall include the depth required to place the D.G.C.S. subbase in areas that will receive new bituminous concrete surfacing as directed by the Engineer and as shown on the Drawings.

COMPENSATION

129.80 Method of Measurement

Where the existing pavement is cut, broken up and excavated, the excavated material removed, and the subgrade reshaped and compacted the Bituminous Concrete Excavated area will be measured in square yards.

129.81 Basis of Payment

All cutting, breaking up, excavation, removal of excavated material, reshaping and the compaction of subgrade will be paid for at the contract unit price per square yard of Bituminous Concrete excavation, which price shall include full compensation for all labor and equipment necessary to complete the work in a satisfactory manner.

129.82 Payment Item

129.10	Bituminous Concrete Excavation	Square Yard
	SS-1	

SECTION 220

ADJUSTMENT, REBUILDING AND REMODELING

OF DRAINAGE STRUCTURES

DESCRIPTION

220.20 GENERAL

This work shall consist of removing, replacing and adjusting the masonry and castings of present structures, as required, to conform to newly proposed line and grade changes; to change type of structure, or changes in type of castings; to remodel or adjust Bradley Head basins, all in accordance with this specification and in close conformity with the line and grades shown on the plan or established by the Engineer.

CONSTRUCTION METHODS

220.60 GENERAL

Prior to "Cold-Planing" the castings may be removed, a steel plate shall be placed on the existing masonry structure and bituminous concrete binder (pneumatically compacted) shall be placed to the existing pavement grade. If the castings are not removed and plated, then they shall be ramped with Hot Mix Asphalt immediately after the "Cold-Planing" process.

Prior to "Pulverization/Asphalt Reclamation" the castings shall be removed and the masonry structures shall be removed to a depth of Fifteen (15) inches or more below the existing pavement. A steel plate shall be placed on the existing masonry structure. Gravel and three (3) inches of bituminous concrete binder (pneumatically compacted) shall be placed to the existing pavement grade.

After Cold-Planning and/or after placing the binder course during the Reclamation process, the steel plate shall be removed, the masonry replaced and the casting set to conform to the newly proposed line and grade.

Hot Mix Asphalt (binder), thoroughly compacted, shall be placed around all castings adjusted as shown on the plan or as directed by the Engineer. Compensation for each payment item shall include payment for the HMA binder used in backfilling.

The Contractor will be held responsible for keeping all catch basins, manholes, and sewer and drain pipes within the work site free from all construction debris. Prior to placing the Bituminous Concrete Wearing Surface, the portion of completed work shall be thoroughly cleaned and the open ends of any pipe or structure securely blocked or stoppered in such a manner as to prevent the entrance into the pipe or structure of any dirt, rubbish or other foreign matter. No structure shall be accepted until it has been thoroughly inspected by the Engineer and found to comply with the above-specified requirements.

Should the Town's Public Works Department have to remove any construction debris from catch basins, manholes, or sewer and drain pipes, the Contractor will be charged for these Town services.

220.61 Protection of work

The present castings shall be carefully removed. They shall be satisfactorily stored until they are required for use or until they are transported and stacked by the Contractor at the Water and Sewer Division Storage Yard, 815 Newton St., (Transfer Station). If new castings are needed, they may be picked up at the same yard.

COMPENSATION

220.81 Basis of Payment

The cost of removing, transporting, stacking and picking up and loading new castings by the Contractor shall be included in the contract unit price under the respective payment item for catch basins, and manholes adjusted and change in type, excluding cost of castings (E.C.C.), and Bradley Head basins remodeled. New castings will be furnished and delivered to Dean Road by the Town Water and Sewer Division. Adjustment of Sanitary and Drainage Structures shall include replacing broken and substandard castings with new castings furnished by the Town of Brookline.

The cost of plating and back filling with gravel and bituminous concrete binder shall be included in the contract unit price under the respective payment item. HMA for backfilling adjusted, new, and removed and reset structures shall be included within each respective payment item.

Bradley Head basins remodeled will be paid for at the contract unit price each for Bradley Head Remodeled. The price will constitute full compensation for the excavation of all materials encountered (except rock;) removal and disposal of the granite top and cover casting at a Contractor furnished disposal area; the removal of existing masonry as directed by the Engineer; the construction of new masonry; setting Town furnished castings including all labor and equipment required.

Bradley Head basins adjusted will be paid for at the contract unit price each for Bradley Head adjusted, including removing the granite top, removing and replacing up to two (2) vertical feet of masonry, and resetting the granite top to the lines and grades specified. Also included in this unit price is all bituminous concrete collars; all backfilling and compaction; all tools, labor, materials, steel rails if required, equipment and incidental work necessary to complete the work as specified.

220.82 Payment Items

220.0	Structure Adjusted, E.C.C.	Each
-------	----------------------------	------

SECTION 402

DENSE GRADED CRUSHED STONE FOR SUB-BASE

COMPENSATION

402.81 Basis of Payment.

Delete subsection and add the following:

Dense graded crushed stone for sub-base will be paid for at the contract unit price per ton complete in place.

402.82 Payment Items

Add the following:

402.1 Dense Graded Crushed Stone for Sub-base

Ton

